

**UP-GRADATION OF MONOTECHNIC INSTITUTE TO THE LEVEL OF POLYTECHNIC
(ADD 2-TECHNOLOGIES TEXTILE WEAVING AT SECTOR 51-1, KORANGI, KARACHI)**

[REMAINING WORK] BILL OF QUANTITIES

(Civil Works)

Sindh Schedule of Rates 2012

S.NO	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	IMPORTED EARTH FILL Filling, watering and ramming earth under floor with new earth (excavated from outside) lead upto one chain and lift upto 5 feet. (Page No. 4, Item No. 22)	10,112.00	%OCft	3,630.00	36,706.56
2	SUPPLY OF RIVER / PIT Supply of clean / screened (river or pit) sand within 5 chains including removal of top crust of earth or over burden and royalty to the Government or cost to the Private Owner. (Page No. 6, Item No. 36)	10,112.00	%Cft	420.00	42,470.40
	Add: extra lead 6 mile (referred from carriage of materials schedule)	10,112.00	%Cft	771.96	78,060.60
3	CC BRICK STONE BALLAST Cement Concrete brick stone ballast 1½" to 2" gauge (ratio 1:4:8) (Page No. 10, Item No. 19-c)	2,528.06	%Cft	9,416.28	238,049.21
4	TILES Laying floor of approved with glazed / porcelain tile ¾" thick in white cement 1:2 over ¾" thick cement mortar 1:2. complete. (Page No. 42, Item No. 24)	6,560.00	%Sft	27,678.86	1,815,733.22
5	FINISH FLOORING Providing and laying 3" thick topping cement concrete (1:2:4) including surface finishing and dividing into panels. (Page No. 41, Item No. 16-c)	5,060.00	%Sft	4,411.82	223,238.09
6	CHEMICAL POLISHING Applying chemical polishing on existing mosaic / marble flooring / dado including cleaning, grinding with carborandum stone / sand paper and applying chemical polish as per requirement. (Page No. 48, Item No. 70)	33,965.00	P.Sft	36.60	1,243,119.00

**UP-GRADATION OF MONOTECHNIC INSTITUTE TO THE LEVEL OF POLYTECHNIC
(ADD 2-TECHNOLOGIES TEXTILE WEAVING AT SECTOR 51-1, KORANGI, KARACHI)**

REMAINING WORK BILL OF QUANTITIES

(Civil Works)

Sindh Schedule of Rates 2012

S.NO	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
7	BITUMEN Two coats of bitumen laid hot using 34 lbs for %Sft over roof and blinded with sand at one Cft Per %Sft. (Page No. 34, Item No. 13)	32,008.00	%Sft	1,887.40	604,118.99
8	GRAFFIATO WALL COATING Providing and applying wall finish coat of Graffiato wall coating 1/16" thick in any approved colour all work to be completed as per drawing, specification and instruction of the Architect / Engineer-in-Charge.	4,517.00	Per Sft	45.00	203,265.00
Sub Total				Rs=	4,484,761.06
____ % above / below <u>except item no. 8</u>				Rs=	
Cost of Scheduled Items (Civil Work)				Rs=	