

PHONE NO: 071-9310213 FAX 9310119.

OFFICE OF THE MEDICAL SUPERINTENDENT GHULAM MUHAMMAD MAHAR
MEDICAL COLLEGE HOSPITAL SUKKUR

NO: MS/GMCHS/ SUKKUR/

2266/75

DATED: February 2016

NOTICE INVITED TENDERS.

19

Sealed bids are invited for all the interested Bidders on Standard Bidding Documents under Public Procurement Regulatory Authority Rules 2010 (Amended 2013), for the following works (List attached) with Tender Fee @ **Rs. 3000/-** and Earnest Money @ **5%** for each work / component.

1/- The intended participants can purchase the separate set of tenders on payment of tender fee / document fee for the each work with effect from **25-02-2016 to 12-03-2016** Upto **1.00 p.m.** Works un-responded will be cancelled keeping in view short span of time in close of current financial year.

2/- The tenders will be received back and opened on same date i.e. **12-03-2016** @ **2.00 P.M** in presence of tender opening / evaluation committee and bidders or their authorized representatives who will be present. If the tendered work remains un-responded or the Chairman Tender Committee is out of Head quarter the Bidding Document Will be re-issued Form **14-03-2016** and will be received back on **29-03-2016** upto **1.00 P.M** which will be opened in the presence of the participants at **2.00 P.M** on the same date.

3/- Eligibility conditions for intending participants are as under.

- i) Registration with Pakistan Engineering council in the relevant field of specialization of work & to the extent to tender amount each work
- ii) Bio-data of Engineers and Technical staff working with the firm.
- iii) Documentary evidence of work executed / works in progress and certificate of satisfactory completion of work by the employers.
- iv) List of work in progress, indicating cost of each work and copy of letter of award of work.
- v) List of machinery and equipment available with documentary evidence of its ownership certificate of Bank showing credit worthiness along with Bank statement.

4/- Registration with Income Tax Department (NTN Certificate) and copy of C.N.I.C.

5/- Undertaking of Affidavit that the firm is not involved in any litigation of abandoned any work in the department.

6/- The bidders should submit earnest money as shown against each work in shape of Call Deposit prepared from the scheduled bank in favour of the undersigned.

7/- Affidavit to the effect that the firm / contractor have not been black listed previously by any executing agency.

8/- Affidavit to the effect that all documents particulars / information furnished are true and correct.

9/- In case of firm, list of partners / Partnership Deed, giving full particulars of directors/ proprietors or others connected along with power of attorney. In case of being sole proprietors, such undertaking on affidavit be furnished.

10/- The undersigned and other competent authority reserve the right to reject any one or all the Bids as per provision of SPPRA Rules.

D.A / AS ABOVE
List of Work

MEDICAL SUPERINTENDENT
GMMMC HOSPITAL SUKKUR

1. Copy submitted to the Secretary Health Government of Sindh Karachi for kind information.
2. Copy Submitted to the Commissioner Sukkur Division Sukkur for kind information with reference to meeting held on 23-12-2015.
3. Copy forwarded to P.S to Minister Health Department Government of Sindh Karachi for information.
4. Copy forwarded to the Secretary, Information Technology Government of Sindh, Secretariat No.6@ Karachi along with copies of NIT's for favour of information and placing them on the Web site of Sindh Government Karachi for information.
5. Copy forwarded to the Director (A&F) SPPRA/3-15 Government of Sindh Public Procurement Regulatory for information, along with soft & hard copy of N.I.T. for information and placing the same on the Web site.
- ✓ 6. Copy forwarded to the Director information (Advertisement) public Relation Department Government of Sindh Block No. 96 Karachi for information, along with seven (07) Copies for information. He is requested to get the Advertisement published in leading newspapers (English, Sindh, Urdu).
7. Copy forwarded to the Executive Engineer, Provincial Building Division Sukkur, for information and publicity.
8. Copy forwarded to the Assistant Engineer, Provincial Building Division Sukkur, for information and publicity.
9. Copy to Divisional Accounts Officer.
10. Copy to Notice Board.

MEDICAL SUPERINTENDENT
GMMMC HOSPITAL SUKKUR

LIST OF WORKS

S. NO.	M&R WORK OF GMMMC HOSPITAL SUKKUR	ESTIMATED COST	COMPLETION PERIOD
	Name of Work.	Rs (M)	
1.	i) Repair of Nursing School. ii) Internal E.I of Nursing School.	7.50 0.80	04 Months
2.	i) Renovation of Mortuary ii) Internal E.I of Mortuary	5.00 0.50	04 Months
3.	Renovation of Internal & External Water Supply/ Sanitary Fitting Drainage line of outdoor, Indoor and Thalesemia Centre GMMMC Hospital Sukkur.	8.00	04 Months
4.	I) Renovation of Hostel Building NO: 2 II) Internal E.I of Hostile Building	7.00 0.80	04 Months
5.	I) Miscellaneous works (Repair of Casualty roof, remaining work of Hospital Building, Old Ultrasound Building, MRI Building, Encroached paths / Gates including Repair & Renovation of Residential Buildings) II) Internal E.I. of Hospital Allied Building	11.70 0.50	04 Months
	TOTAL.	41.8 (Millions)	


**MEDICAL SUPERINTENDENT
GMMMC HOSPITAL SUKKUR**

FOUNDED BY QUAID-I-AZAM MOHAMMAD ALI JINNAH



DAWN

University of Balochistan, Quetta

OFFICE OF THE MEDICAL SUPERINTENDENT
 GHULAM MUHAMMAD MAHAR MEDICAL COLLEGE HOSPITAL SUKKUR
 PHONE NO: 071-9310213 — FAX: 9310119

NO: MS/GMCHS/SUKKUR/2266/75

DATED: 19 February 2016

NOTICE INVITING TENDER

Sealed bids are invited from all the interested bidders on Standard Bidding Documents under Public Procurement Regulatory Authority Rules 2010 (Amended 2013) for the following works with Tender Fee at Rs. 3000/- and Earnest Money @ 5% for each work / component.

S. No.	M&R WORK OF GMMMC HOSPITAL SUKKUR	ESTIMATED COST	COMPLETION PERIOD
Name of Work		Rs (M)	
1.	i) Repair of Nursing School	7.50	04 Months
	ii) Internal E.I. of Nursing School	0.80	
2.	i) Renovation of Mortuary	5.00	04 Months
	ii) Internal E.I. of Mortuary	0.50	
3.	Renovation of Internal & External Water Supply / Sanitary Fitting, Drainage Line of Outdoor, Indoor and Thalassaemia Centre GMMMC Hospital Sukkur.	8.00	04 Months
4.	i) Renovation of Hostel Building No. 2	7.00	04 Months
	ii) Internal E.I. of Hostel Building	0.80	
5.	i) Miscellaneous works (Repair of Casualty Roof, Remaining Work of Hospital Building, Old Ultrasound Building, MRI Building, Encroached Paths / Gates Including Repair & Renovation of Residential Buildings)	11.70	04 Months
	ii) Internal E.I. of Hospital Allied Building	0.60	
TOTAL		41.8 (Millions)	

- The intending participants can purchase the separate set of tenders on payment of tender fee / document fee for the each work from 25-02-2016 to 12-03-2016 upto 1.00 p.m. Works unresponded will be cancelled keeping in view short span of time in close of current financial year.
- The tenders will be received back and opened on the same date i.e. 12-03-2016 at 2.00 P.M in presence of Tender Opening / Evaluation Committee and bidders or their authorized representatives who will be present. If the tendered work remains unresponded or the Chairman Tender Committee is out of Headquarters, the bidding document will be reissued from 14-03-2016 and will be received back on 29-03-2016 upto 1.00 P.M which will be opened in presence of the participants at 2.00 P.M on the same date.
- Eligibility conditions for intending participants are as under:-
 - Registration with Pakistan Engineering Council in the relevant field of specialization of work & to the extent to tender amount of each work
 - Bio-data of engineers and technical staff working with the firm.
 - Documentary evidence of work executed / works in progress and certificate of satisfactory completion of work by the employers.
 - List of works in progress, indicating cost of each work and copy of letter of award of work.
 - List of machineries and equipment's available with documentary evidence of its ownership, certificate of Bank showing credit worthiness along with Bank statement.
- Registration with Income Tax Department (NTN Certificate) and copy of C.N.I.C.
- Undertaking or Affidavit that the firm is not involved in any litigation or abandoned any work in the department.
- The bidders should submit earnest money as shown against each work in shape of Call Deposit prepared from the scheduled bank in favour of the undersigned.
- Affidavit to the effect that the firm / contractor has not been blacklisted previously by any executing agency.
- Affidavit to the effect that all documents / particulars / information furnished are true and correct.
- In case of firm, list of partners / Partnership Deed, giving full particulars of directors / proprietors or others connected along with power of attorney. In case of being sole proprietors, such undertaking on stamp paper be furnished.
- The undersigned and other competent authority reserve the right to reject any one or all into bids as per provision of SPPRA Rules.

MEDICAL SUPERINTENDENT
 GMMMC HOSPITAL SUKKUR

SAY NO TO CORRUPTION

ایک انسان کا کل نسل، ناپائیدگ ہے۔

INF-KRY No. 519/16

016
117, 1437



Pakistan's Chief Minister Pervez Khattar signing a memorandum of understanding with reporters after signing a memorandum of understanding

Rs460bn re against Dr

By Ishaq Tanol

KARACHI: The National Accountability Bureau filed a reference against former petroleum minister Dr A Hussain, former petroleum secretary Mohammad Ejaz Chaudhry and other an accountability court on Thursday alleged corruption of over Rs460 billion.

Dr Asim, a close aide to former president Asif Ali Zardari, has been accused of misusing his authority for getting plots allotted fraudulently and encroach upon state land for expansion of Ziauddin Hospital/Trust, illegal gas kickbacks and money laundering.

The former minister has also been accused of receiving commissions from fertiliser cartel for an "exploitative price-fixing arrangement".

Fore-
sday
ic in
sting
acred-
ndia
s of
eral
mat-
han
sted
alks



GOVERNMENT OF SINDH
 Sindh Solid Waste Management Board



اللہ تمہارا پروردگار ہے
 اللہ کے نام سے جو ہر اس امر میں ہم کام لائے

زادہ علی اکبر چیئرمین پی سی بی

برطانوی شہری بننے کی وجہ سے
 اسلام آباد (ظاہری طور پر مسلم لیگ) پاکستانی اور
 کے ایک ماہی چول نے پورنالی کے لایم جی بی

THE BRILLIANT KARACHI

جنگ

فریڈ ایڈیشن

55-023
 2016

FRIDAY FEBRUARY 26, 2016

77 روپے

77 روپے

77 روپے

ڈسٹر میڈیکل سپرنٹنڈنٹ علامہ محمد ہمدرد
 میڈیکل کالج ہسپتال سکمر
 فون نمبر 071-9310213 فیکس 9310119
 مورخہ: 19 فروری 2016م
 No.MS/GMCHS/SUKKUR/2266/75

میرٹھ میں طبی سہولتوں کی فراہمی

میرٹھ میں کاموں کے لئے ایک پروگرام کو فروغ دینے کی غرض سے (2013) کے تحت اسٹیٹ ڈیولپمنٹ اور سوشل ویلفیئر
 ٹرسٹ نے 3000 روپے اور ریجنل سروسز کے ذریعے 5% برائے برائے کام کی فراہمی کی ہے۔ اس کے ذریعے طبی سہولتوں کی فراہمی کے لئے
 1- فراہمی شدہ کارڈ کی فراہمی کے لئے طبی سہولتوں اور سروسز کی فراہمی کی اور جنوری 2016-02-05 سے 2016-02-03
 تک ہر ہفتہ 100-1 ایک ایک خریدتے ہیں۔ تمام تمام دوائی دہائیوں کے بند ہونے کی وجہ سے طبی سہولتوں کو فراہم کرنا
 مشکل ہے۔
 2- طبی سہولتوں کی فراہمی کے لئے 12-03-2016 کو ہر ہفتہ 2-00 روپے دوائی سہولتوں کی فراہمی کے لئے
 فراہم کیے۔ طبی سہولتوں کی فراہمی کے لئے سوشل ویلفیئر ٹرسٹ کی سروسز کی فراہمی کے لئے سوشل ویلفیئر ٹرسٹ کی سروسز
 کی فراہمی کے لئے سوشل ویلفیئر ٹرسٹ کی سروسز کی فراہمی کے لئے سوشل ویلفیئر ٹرسٹ کی سروسز کی فراہمی کے لئے
 3- فراہمی شدہ کارڈ کے لئے طبی سہولتوں کی فراہمی کے لئے سوشل ویلفیئر ٹرسٹ کی سروسز کی فراہمی کے لئے
 (i) طبی سہولتوں کی فراہمی کے لئے سوشل ویلفیئر ٹرسٹ کی سروسز کی فراہمی کے لئے سوشل ویلفیئر ٹرسٹ کی سروسز کی فراہمی کے لئے
 (ii) فراہمی کے لئے سوشل ویلفیئر ٹرسٹ کی سروسز کی فراہمی کے لئے سوشل ویلفیئر ٹرسٹ کی سروسز کی فراہمی کے لئے
 (iii) فراہمی کے لئے سوشل ویلفیئر ٹرسٹ کی سروسز کی فراہمی کے لئے سوشل ویلفیئر ٹرسٹ کی سروسز کی فراہمی کے لئے
 (iv) فراہمی کے لئے سوشل ویلفیئر ٹرسٹ کی سروسز کی فراہمی کے لئے سوشل ویلفیئر ٹرسٹ کی سروسز کی فراہمی کے لئے
 5- طبی سہولتوں کی فراہمی کے لئے سوشل ویلفیئر ٹرسٹ کی سروسز کی فراہمی کے لئے سوشل ویلفیئر ٹرسٹ کی سروسز کی فراہمی کے لئے
 6- طبی سہولتوں کی فراہمی کے لئے سوشل ویلفیئر ٹرسٹ کی سروسز کی فراہمی کے لئے سوشل ویلفیئر ٹرسٹ کی سروسز کی فراہمی کے لئے
 7- اس امر کا علاج ہر ہفتہ سوشل ویلفیئر ٹرسٹ کی سروسز کی فراہمی کے لئے سوشل ویلفیئر ٹرسٹ کی سروسز کی فراہمی کے لئے
 8- اس امر کا علاج ہر ہفتہ سوشل ویلفیئر ٹرسٹ کی سروسز کی فراہمی کے لئے سوشل ویلفیئر ٹرسٹ کی سروسز کی فراہمی کے لئے
 9- فراہمی کے لئے سوشل ویلفیئر ٹرسٹ کی سروسز کی فراہمی کے لئے سوشل ویلفیئر ٹرسٹ کی سروسز کی فراہمی کے لئے
 سول پروگراموں کو فروغ دینے کے لئے سوشل ویلفیئر ٹرسٹ کی سروسز کی فراہمی کے لئے سوشل ویلفیئر ٹرسٹ کی سروسز کی فراہمی کے لئے
 10- سوشل ویلفیئر ٹرسٹ کی سروسز کی فراہمی کے لئے سوشل ویلفیئر ٹرسٹ کی سروسز کی فراہمی کے لئے

کاموں کی فہرست

نمبر شمار	کام کا نام	تخمینی لاگت (ملین روپے)	تعمیراتی تاریخ
1	(i) مرمت ٹرنگ اسکول (ii) ٹرنگ اسکول کی اندرونی E.I.	7.50 0.80	10/04
2	(i) مردہ خانگی تعمیر (ii) مردہ خانگی اندرونی E.I.	5.00 0.50	10/04
3	تعمیر یا باہر اندرونی و بیرونی ڈیمو سٹریٹنگ اور لائٹنگ جیت آؤٹ اور اندرونی تعمیر یا باہر اندرونی GMMMC ہسپتال سکمر	8.00	10/04
4	(i) ہوسٹل بلڈنگ نمبر-2 کی تعمیر (ii) ہوسٹل بلڈنگ کی اندرونی E.I.	7.00 0.80	10/04
5	(I) متفرق کام (کیرپوریشن جوٹ کی مرمت، ہسپتال بلڈنگ کا باہر کا کام، پرانی انٹرا سٹراڈ بلڈنگ MRI بلڈنگ، انگریز پاس انجینئرنگ سول مرمت و تعمیر رہائشی عمارت)۔ (II) ہسپتال سے ملحق عمارت کی اندرونی E.I.	11.70 0.50	10/04
		مجموعی: 41.8 (ملین)	

میرٹھ میں طبی سہولتوں کی فراہمی کے لئے سوشل ویلفیئر ٹرسٹ کی سروسز کی فراہمی کے لئے
GMMMC ہسپتال سکمر
 INF-KRY-5194
 SAY NO TO CORRUPTION

ABC Certified

The Largest Circulated Sindhi Daily of Pakistan

DAILY KAWISH

ڪاوش

روزانه



(جلد 26) جمع 26 فيبروري 2016ء بمطابق 17 جنوري 1437ھ (شمارو 204) قيمت 15 روپيا

Friday 26 February, 2016

روزانه
021-3410
فون نمبر: 355

تدارڪ
KRY.No. 83/201
هن آفيس جي ٽينڊر جي
بني مرصعي رٽرونيشن
قوت اهر تي شيڊ 2
ني آهي.
اڪائونٽ رول- (i)
بند روٽيشن
ٽينڊر جمع ڪرڻ جو
بيلاسورا شرط ۽ ضلعا

INF/KRY.N

هڪ انسان

ايڊيشنل

9218255

انهي ڪري

INF/KRY.

اڪائونٽ

city for
IAU
ATCI
ERN

Following word
under document
registration certifi
GSO NTD

Grid 4

Boundary
eta

Well
12345

Grid 3

OP TENG
ice hours
documents
March 20

آفيس آف ڊي ميڊيڪل سپرنٽينڊنٽ
غلام محمد مهر ميڊيڪل ڪاليج اسپتال سکر
فون نمبر: 9310213-071، فيض نمبر: 9310119
No. MS/GMCHS/SUKKUR/2266/75 Dated: 19 February, 2016

ٽينڊر گھرائڻ جو نوٽيس

پبلڪ پروڪيورمينٽ ريگيوليشري ٿاڻ تي روز 2010 (نومبر 2013) تحت
اسٽينڊرڊ واک ڪاغذن تي سيني دلچسپي رکندڙ واک ڏيندڙن کان هيٺ ڄاڻايل ڪم
واسطي هر ڪم جو ڪمپونينٽ لاءِ ٽينڊر في 3000 روپيا ۽ سونو رقم 5% سميت
مهريند واک گھرائڻ ٿا.

سيريئل نمبر	GMMMC اسپتال سکر جي اير اينڊ آر جو ڪم	ڪم جو تفصيل	ڪيٽيگري لائيت (ملين روپيا)	تڪميل جو مدو
1.	(i) نرسنگ اسڪول جي مرمت (ii) نرسنگ اسڪول جي انٽرنيل E-1	ڪم جو تفصيل	7.50 0.80	04 مهينا
2.	(i) مورچي جي رٽرونيشن (ii) مورچي جي انٽرنيل E-1		5.00 0.50	04 مهينا
3.	آئوٽ ڊور، انڊور ۽ ٿيليميا سينٽر GMMMC اسپتال سکر جي انٽرنيل ۽ ايڪسٽرنيل واٽر ميلا، سيسٽري ٽنڪ، ڊرينيج لائين جي رٽرونيشن		8.00	04 مهينا
4.	(i) هاسٽل بلڊنگ نمبر 2 جي رٽرونيشن (ii) هاسٽل بلڊنگ جي انٽرنيل E-1		7.00 0.80	04 مهينا
5.	(i) مقرر ڌڻ ڪم (ڪنٽريبلنٽي روف جي مرمت، اسپتال عمارت، لولڊ الشرا سائونڊ، MRI بلڊنگ، اينڪروچڊ پاٽي، گيس جي مرمت سميت رهائشي عمارتن جي مرمت ۽ رٽرونيشن) رهيل ڪم. (ii) اسپتال سان لاڳاپيل عمارت جي انٽرنيل E-1		11.70 0.50	04 مهينا
جملو			41.8	

حوالو شدہ سرڪٽ ڪنڌڙ ٽينڊرن جو قلم سيٽ هر ڪم واسطي ٽينڊر في
ڪاغذ تي جي انگي غير ضروري 25-02-2016 کان 25-03-2016 منجهند 1:00
وڳي تائين خريد ڪري سگهڻ ٿا.

ٽينڊر جي ڏينهن يعني 2016-03-12 تي منجهند 2:00 وڳي تائين
وليس وقت ٽينڊر ٽيبلنگ/اوپوليٽيشن ڪميٽي ۽ واک ڏيندڙن يا سندن
مجال نمائندن جي موجودگيءَ پر جيڪي ان وقت موجود رهن ٿا، تنهن
جي رويو کوليا ويندا. جيڪڏهن ٽينڊر ٽيبل ڪم ڪري موقت ٿي ملي يا
جسٽ مين ٽينڊر ڪميٽي هڪٻئي کان پهرين آهي ته واک ڪاغذ 2016-03-14
تائين 29-03-2016 کان پهرين 29-03-2016 منجهند 1:00

ٽينڊر جي موجودگيءَ پر کوليا ويندا
ڪنڌڙن جي موجودگيءَ پر کوليا ويندا
دلچسپي رکندڙ سرڪٽ ڪنڌڙن لاءِ اعلويت جا شرط

(i) پاڪستان انجنيئرنگ ڪنٽرول ٽيبل سان ڪم جي دستاويزي
والتدارڪ ڪم جي رٽرونيشن ۽ مرمت
ڪم جي رٽرونيشن

(ii) هلندڙ وقت جي موجودگي ۽ دستاويزي ثبوت
(iii) اعلويت جي رٽرونيشن جو سرٽيفڪيٽ
(iv) هلندڙ ڪم جي فهرست جنهن ۾ ڪم جي ڏين جي لٽر جي ڪاپي ۽ هر
ڪم جي لائيت ڏيکاريل هجي.

(v) دستياب مشنري ۽ ايڪيورمينٽ جي فهرست گندوڪ مالڪي جو
دستاويزي ثبوت ۽ بينڪ جو سرٽيفڪيٽ جنهن ۾ قرض جي حد ڄاڻايل
هجي، بينڪ اسٽيٽمينٽ سميت.

4. انڪر ٽيڪس ڪاٽي سان رجسٽريشن (اين تي اين سرٽيفڪيٽ) ۽ سي اين
آءِ سي جي ڪاپي.
5. ان امر بابت حلفنامو ۽ فرم ڪنهن به قانوني چاره جوئي ۾ ملوث ناهي آهي.

14 کن 20
15 کن 20
16 کن 20
17 کن 20
18 کن 20
19 کن 20
20 کن 20
21 کن 20
22 کن 20
23 کن 20
24 کن 20
25 کن 20
26 کن 20
27 کن 20
28 کن 20
29 کن 20
30 کن 20

121/2002

INF/KRY/2



Health Department
Government of Sindh

NOTIFICATION

NO. HD (P&E) 5-6(7) / 2015. The partial modification of this department notification of even number dated 16-10-2015 the Government of Sindh, Health Department is pleased to constitute a revised Committee under Rules-7 of SPPRA, comprising of following members to carry out the repair and maintenance works (M&R) at Ghulam Mohammad Mahar Medical College Hospital, Sukkur for the year 2015-16:

- | | | |
|----|--|----------|
| 1. | Medical Superintendent
GMMMC Hospital, Sukkur | Chairman |
| 2. | Additional Medical Superintendent
GMMMC Hospital, Sukkur | Member |
| 3. | Representative of Commissioner
Sukkur Division Sukkur. | Member |
| 4. | Executive Engineer
Works and Services Department,
Govt. of Sindh District Sukkur | Member |
| 5. | Accounts Officer
GMMMC Hospital Sukkur. | Member |

- o The committee will observe all the codal formalities as per Sindh Public Procurement Rules 2010.
- o The committee will also supervise, monitor the repair and maintenance work regularly and to ensure that work done is of a quality.

Dr. Saeed Ahmed Mangnejo
Secretary Health

NO. HD (P&E) 5-6(7) / 2014.

Karachi, dated 19-10-2015

A copy forwarded for information and necessary action to:

- Commissioner Sukkur Division Sukkur with a request to supervise the M&R work.
- Medical Superintendent, Ghulam Mohammad Mahar Medical College Hospital, Sukkur
- Managing Director, Sindh Public, Procurement Authority, Government of Sindh, Karachi.
- All Committee Members.
- PS to Secretary Health, Govt. of Sindh, Karachi

Research Officer (Dev)

MS GMA	5439
Inw	24-12-2015
D	10-00 Bw
P.O.	9-12-2015



Phone # 99203108, 99204203

No. SO (M&I) 2-1/2013 (CRC)

**GOVERNMENT OF SINDH
HEALTH DEPARTMENT**

(PROCUREMENT MONITORING & INSPECTION CELL)
Karachi. Dated: the 28th March. 2015

NOTIFICATION

In supersession of this Department's notification of even number dated: 29th July, 2013 and in pursuance of Rules-31 and 32 of Sindh Public Procurement Rules 2010, the Government of Sindh, Health Department re-constitutes Complaint Redressal Committee (CRC) comprising of the following officers for scrutinizing the complaints of aggrieved bidders against tender invited by Health Institutions / Hospitals / Programmes / Projects in Sindh.

01	Secretary Health Department, Sindh	Chairman
02	Additional Secretary(PM&I),Health Department, Sindh	Member
03	Professor Khalida Soomro, Professor of Cardiology, Dow University of Health Sciences / Civil Hospital, Karachi.	Member
04	Dr. Syed Khalid Hussain, Procurement Executive, N.I.C.V.D., Karachi.	Member
05	Representative from Accountant General Sindh, Karachi	Member

TORs

- To scrutinize the complaints from the aggrieved bidders and decide the cases strictly in accordance with SPP Rules 2010.

**IFTIKHAR ALI SHALLWANI
SECRETARY HEALTH**

No. S.O.(PM&I) 2-1/2011(CRC)

Karachi, dated. the 28th March, 2015

C.C to:

1. The P.S.to Chief Secretary Sindh, Karachi.
2. The Managing Director, Sindh Public Procurement Regulatory Authority, Karachi.
3. The Executive Director, NICVD, Karachi.
4. The Director General Health Services Sindh, Hyderabad.
5. The Additional Secretary (Admn/Development/Public Health), Health Department.
6. The Chairman & all members of the Committee.
7. The P.S. to Secretary Health Sindh.

**(RASHID HUSSAIN)
SECTION OFFICER (PM&I)**


PHONE NO: 071-9310213 FAX 9310119.
 OFFICE OF THE MEDICAL SUPERINTENDENT GHULAM MUHAMMAD MAHAR MEDICAL COLLEGE HOSPITAL SUKKUR
 HEALTH DEPARTMENT GOVERNMENT OF SINDH ANNUAL PROCUREMENT PLAN (WORKS, GOODS, SERVICES)

<u>Sr.#</u>	<u>Description of Procurement</u>	<u>Quantity (where Applicable)</u>	<u>Estimated Unit Cost (where applicable) Million</u>	<u>Funds allocated (million)</u>	<u>Source of funds (ADPs Non ADPs)</u>	<u>Proposed Procurement Method</u>	<u>Timing of Procurements</u>				<u>Remarks</u>
							<u>1st QTR.</u>	<u>2nd QTR.</u>	<u>3rd QTR.</u>	<u>4th QTR.</u>	
1.	M&R to GMMMC Hospital Sukkur	Quantity mentioned in the Tender Documents	41.800 (M)	41.800 (M)	Non ADP	SPPRA Rules 2010 Clause 46(2) S	10.45(M)	10.45(M)	10.45(M) 4-2-2016	10.45(M)	

Deer
 ✓ MEDICAL SUPERINTENDENT
 GMMMC HOSPITAL SUKKUR

SEPPRA BIDDING DOCUMENTS

STANDARD BIDDING DOCUMENTS
WITH *EVALUATION CRITERIA*
GMMMC HOSPITAL SUKKUR.




EVALUATION CRITERIA

Eligibility conditions for intending participants are as under.

- 1/- Registration with Pakistan Engineering council in the relevant field of specialization of work & to the extent to tender amount each work.
- 2/- Bio-data of Engineers and Technical staff working with the firm.
- 3/- Documentary evidence of work executed / works in progress and certificate of satisfactory completion of work by the employers.
- 4/- List of work in progress, indicating cost of each work and copy of letter of award of work.
- 5/- List of machinery and equipment available with documentary evidence of its ownership certificate of Bank showing credit worthiness along with Bank statement.
- 6/- Registration with Income Tax Department (NTN Certificate) and copy of C.N.I.C.
- 7/- Undertaking of Affidavit that the firm is not involved in any litigation of abandoned any work in the department.
- 8/- The bidders should submit earnest money as shown against each work in shape of Call Deposit prepared from the scheduled bank in favour of the undersigned.
- 9/- Affidavit to the effect that the firm / contractor have not been black listed previously by any executing agency.
- 10/- Affidavit to the effect that all documents particulars / information furnished are true and correct.
- 11/- In case of firm, list of partners / Partnership Deed, giving full particulars of directors/ proprietors or others connected along with power of attorney. In case of being sole proprietors, such undertaking on affidavit be furnished.


NOTE:-

The undersigned and other competent authority reserve the right to reject any one or all the Bids/Components as per provision of SPPRA Rules 2010 (Amended 2013).



BIDDING DATA

- (a) Name of Procuring Agency Medical Superintending Ghulam Mohammad
Mahar Medical College Hospital Sukkur.
- (b) Brief Discription of Works Renovation of Hostel Building No.2 (Electric Work)
- (c) Procuring Agency Address Near Civil Hospital Sukkur
- (d) Estimated Cost 500,000
- (e) Amount of Bid Security 25,000
- (f) Period of Bid Validity (Days) 28 Days
- (g) Security Deposit (i/c bid Security) 50,000
- (h) Security to be deducted from bills 5%
- (i) Submission of bids along with time 25.02.2016 up to 1:00 PM
- (j) Time and Date of Bid Opening 12.03.2016 (2:00 PM)
- (k) Time for completion from written order of commencement 04 Months
- (l) Liquidated Demages _____
- (m) Deposit Receipt _____ Date _____ Amount _____
- (n) D.R No, Date & Amount _____
- (o) Tender Issued to (Mr. / M/S) _____



BILL OF QUANTITIES

4
11

Discription and Rate of Items based on Composite Schedule of Rates

NAME OF WORK :- RENOVATION OF HOSTEL BUILDING AT CIVIL HOSPITAL SUKKUR. (INTERNAL ELECTRIFICATION)

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
PART "A" NEW SCHEDULE ITEMS					
1	110	Wiring for light or fan point with 3/029 PVC insulated wire in 20mm (3/4") channel patti on surface as required (S.No. 129 P-15).	910	per point	100,100
2	20	Wiring for plug point with 3/029 PVC insulated wire in 20mm (3/4") channel patti on surface as required (S.I.No:130 P- No:15)	742	per point	14,840
3	1	Wiring for call bell point with 3/029 PVC insulated wire in 20mm (3/4") channel patti on surface as required. (S.I.No:131 P- No:15)	1590	per point	1,590
4	110	Providing & fixing one way SP 5amp switch flush type(S.I.No:219 P- No:33)	54	P.No	5,940
5	20	Providing & fixing two pin 5amp plug & socket (S.I.No:222 P- No:33)	80	P.No	1,600
6	5	Providing & fixing three pin 10/15amp plug & socket flush type (S.I.No:222 P- No:33)	162	P.No	810
7	50	Providing & fixing Brass Battern holder c(S.I.No:232 P- No:33)	70	P.No	3,500
8	20	Providing & fixing Brass Ceiling fan 56" (good quality) (S.I.No:235 P- No:34)	3185	P.No	63,700
9	400	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/029 copper conductor in 3/4" dia PVC conduit on surface (S.I.No:3 P- No:1)	171	P.Mtr	68,400
10	400	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/044 (6mm ²) copper conductor in 1" dia PVC conduit on surface (S.I.No:5 P- No:1).	305	P.Mtr	122,000
11	250	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/052 (10 mm ²) copper conductor in 1" dia PVC conduit on surface (S.I.No:6 P- No:1).	428	P.Mtr	107,000
12	20	Providing & fixing circuit breaker 6,10,15,20, 30,40,50 & 63amp SP (TB-5S) on prepared board as required (S.I.No:202 P- No:30)	916	P.No	18,320
13	1	Providing & fixing circuit breaker 15,20,30, 40,50,60,75 & 100amp TP (XS-100NS) on prepared board as required (S.I.No:207 P- No:31)	9261	P.No	9,261
14	1	Providing & fixing DP I/C change over switch 500volts 200amp on a prepared board	8767	P.No	8,767
15	4	Providing & Fixing of street light 250 watts (SON-T) having IP66 classification with 250w lamp, choke, capacitor & Internal wiring complete in all respect at the height With the help of hydraulic crane as per site requirement and instruction of El. (CSI No. 163 Page No. 25)	24790	P.No	99,160
TOTAL :-					624,988

PART "B" OLD SCHEDULE ITEMS

1	20	P/F energy sever superior quality including fixing on existing holder etc complete.(S.I.No:6 P- No:33)	497.00	Each	9,940
2	12	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.(S.I.No:5 P- No:33)	497.00	Each	5,964
3	3	P/F distribution metal board double shutter to accommodate circuit breakers including painting with enamel paint and for other simmlar job on surface (S.I.No:18 P- No:13)	907.96	P.Sft	2,724
4	1	P/F earthing set with 2x2x1/4" cooper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and chorcoal etc.in/e.making the pit 12" deep by excavation of all type of soil. Earth plat to be connected with No:8 S W G bare cooper wire run in 1/2" GI pipe straight from the earth plate up to the metallic electric meter by providing necessary Tee.(S.I.No:2 P- No:26)	3610.04	Each	3,610
5	9	P/F Bulb 100 Watts	25.00	Each	225
6	20	P/F mild steel bar fan clamp 15.8 mm (5/8")dia suitable for RCC roof (S.I.No:1 (c) P- No:14)	141.01	Each	2,820

Quantities	Description of items to be executed at site	Rate	Units	Amount
1	P/F AC or DC electric bell 200/250 volt 70MM. (S.I.No:21 P- No:11)	150.70	Each	151
1	P/F flush type electric bell bush button (S.I.No:23 P- No:12)	25.19	Each	25
			TOTAL :-	25,459

Amount Total (CSR)

Part "A" % Above / Below _____ Total Amount _____

Part "B" % Above / Below _____ Total Amount _____

Total "A+B" _____


PART "B" NON SCHEDULE ITEMS

1	30	P/F stair step LED light 6" x3" with PVC frame with 3/4" dia PVC pipe & ceiling LED light 12 watts etc complete approved by officer Incharge.		Each	
				TOTAL :-	

Total (b) in words & figures

CONTRACTOR


Com
 ✓ MEDICAL SUPERINTENDENT
 GMMMC HOSPITAL SUKKUR



BIDDING DATA

5
11

- (a) Name of Procuring Agency Medical Superintending Ghulam Mohammad Mahar Medical College Hospital Sukkur.
- (b) Brief Discription of Works Miscellaneous works (Repair of Casualty Roof, remaining work of Hospital Building Old Ultrasound Building, MRI Building, Encroched paths / gates including Repair & Renovation of Residential Buildings) (Electric Work) (Hospital Allied Building).
- (c) Procuring Agency Address Near Civil Hospital Sukkur
- (d) Estimated Cost 500,000
- (e) Amount of Bid Security 25,000
- (f) Period of Bid Validity (Days) 28 Days
- (g) Security Deposit (i/c bid Security) 50,000
- (h) Security to be deducted from bills 5%
- (i) Submission of bids along with time 25.02.2016 up to 1:00 PM
- (j) Time and Date of Bid Opening 12.03.2016 (2:00 PM)
- (k) Time for completion from written order of commencement 04 Months
- (l) Liquidated Damages _____
- (m) Deposit Receipt _____ Date _____ Amount _____
- (n) D.R No, Date & Amount _____
- (o) Tender Issued to (Mr. / M/S) _____



BILL OF QUANTITIES

Discription and Rate of Items based on Composite Schedule of Rates

S
11

NAME OF WORK :- REPAIR OF CASUALLY ROOF, MRI, STORE & RENOVATION OF RESIDENTIAL BUILDING AT GMMC HOSPITAL SUKKUR. (INTERNAL ELECTRIFICATION)

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
PART "A" NEW SCHEDULE ITEMS					
1	90	Wiring for light or fan point with 3/029 PVCinsulated wire in 20mm (3/4") channel patti on surface as required (S.No. 129 P-15).	910	per point	81,900
2	20	Wiring for plug point with 3/029 PVC insulated wire in 20mm (3/4") channel patti on surface as required (S.I.No:130 P- No:15)	742	per point	14,840
3	1	Wiring for call bell point with 3/029 PVC insulated wire in 20mm (3/4") channel patti on surface as required. (S.I.No:131 P- No:15)	1590	per point	1,590
4	90	Providing & fixing one way SP 5amp switch flush type(S.I.No:219 P- No:33)	54	P.No	4,860
5	20	Providing & fixing two pin 5amp plug & socket (S.I.No:222 P- No:33)	80	P.No	1,600
6	5	Providing & fixing three pin 10/15amp plug & socket flush type (S.I.No:222 P- No:33)	162	P.No	810
7	50	Providing & fixing Brass Battern holder c(S.I.No:232 P- No:33)	70	P.No	3,500
8	20	Providing & fixing Brass Ceiling fan 56" (good quality) (S.I.No:235 P- No:34)	3185	P.No	63,700
9	400	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/029 copper conductor in 3/4" dia PVC conduit on surface (S.I.No:3 P- No:1)	171	P.Mtr	68,400
10	200	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/044 (6mm ²) copper conductor in 1" dia PVC conduit on surface (S.I.No:5 P- No:1).	305	P.Mtr	61,000
11	130	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/052 (10 mm ²) copper conductor in 1" dia PVC conduit on surface (S.I.No:6 P- No:1).	428	P.Mtr	55,640
12	20	Providing & fixing circuit breaker 6,10,15,20, 30,40,50 & 63amp SP (TB-5S) on prepared board as required (S.I.No:202 P- No:30)	916	P.No	18,320
13	1	Providing & fixing circuit breaker 15,20,30, 40,50,60,75 & 100amp TP (XS-100NS) on prepared board as required (S.I.No:207 P- No:31)	9261	P.No	9,261
14	1	Providing & fixing DP I/C change over switch 500volts 200amp on a prepared board	8767	P.No	8,767
TOTAL :-					394,188

PART "B" OLD SCHEDULE ITEMS

1	39	P/Fenergy sever superior quality including fixing on existing holder etc complete.(S.I.No:6 P- No:33)	497.00	Each	19,383
2	15	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.(S.I.No:5 P- No:33)	497.00	Each	7,455
3	5	P/F distribution metal board double shutter to accommodate circuit breakers including painting with enamel paint and for other simmlar job on surface (S.I.No:18 P- No:13)	907.96	P.Sft	4,540
4	1	P/F earthing set with 2x2x1/4" cooper plate buried in groud at a depth of 12" or less if water comes out from the ground level with salt and chorcoal etc.in/e.making the pit 12"deep by excavation of all type of soil. Earth plat to be connected with No:8 S W G bare cooper wire run in 1/2' GI pipe straight from the earth plate up to the metallic electric assenary i/e providing necessary Tee.(S.I.No:2 P- No:26)	3610.04	Each	3,610
5	9	P/F Bulb 100 Watts	25.00	Each	225
6	20	P/F mild steel bar fan clamp 15.8 mm (5/8") dia suitable for RCC roof (S.I.No:1 (c) P- No:14)	141.01	Each	2,820
7	1	P/F AC or DC electric bell 200/250 volt 70MM. (S.I.No:21 P- No:11)	150.70	Each	151
8	1	P/F flush type electric bell bush button (S.I.No:23 P- No:12)	25.19	Each	25
TOTAL :-					38,209

No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
-----	------------	--	------	-------	--------

Amount Total (CSR)

Part "A" % Above / Below _____ Total Amount _____

Part "B" % Above / Below _____ Total Amount _____

Total "A+B" _____

PART "B" NON SCHEDULE ITEMS

1	30	P/F stair step LED light 6" x3" with PVC frame with 3/4" dia PVC pipe & ceiling LED light 12 watts etc complete approved by officer Incharge.		Each	
1	2	P/F Street / Search Light fitting with energy saver 85 watts complete with glass shade i/c G.I pipe bracket 1-1/4" dia of required length with clamps nuts bolts & wiring with connections etc.		Each	
TOTAL :-					

Total (b) in words & figures

CONTRACTOR


Com
 MEDICAL SUPERINTENDENT
 GMMMC HOSPITAL SUKKUR



BIDDING DATA

5
/

- (a) Name of Procuring Agency Medical Superintending Ghulam Mohammad Mahar Medical College Hospital Sukkur.
- (b) Brief Discription of Works Miscellaneous works (Repair of Casualty Roof, remaining work of Hospital Building Old Ultrasound Building, MRI Building, Encroched paths / gates including Repair & Renovation of Residential Buildings) (Civil Work)
- (c) Procuring Agency Address Near Civil Hospital Sukkur
- (d) Estimated Cost 12,000,000
- (e) Amount of Bid Security 600,000
- (f) Period of Bid Validity (Days) 28 Days
- (g) Security Deposit (i/c bid Security) 1,200,000
- (h) Security to be deducted from bills 5%
- (i) Submission of bids along with time 25.02.2016 up to 1:00 PM
- (j) Time and Date of Bid Opening 12.03.2016 (2:00 PM)
- (k) Time for completion from written order of commencement 04 Months
- (l) Liquidated Damages _____
- (m) Deposit Receipt _____ Date _____ Amount _____
- (n) D.R No, Date & Amount _____
- (o) Tender Issued to (Mr. / M/S) _____



BILL OF QUANTITIES

5

Discription and Rate of Items based on Composite Schedule of Rates

NAME OF WORK :- REPAIR OF CASUALLY ROOF, MRI, STORE & RENOVATION OF RESIDENTIAL BUILDING AT GMMMC HOSPITAL SUKKUR.

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
PART "A" SCHEDULE ITEMS					
1	3,200	Dismantling 2nd Class tile roofing (C.S.I No:22 (b) P-11).	378.13	%Cft	12,100
2	990	Dismantling brick work in lime or cement plaster (C.SI No:13 P-10).	1,285.63	%Cft	12,728
3	4,450	Dismantling cement concrete plain 1:3:6 (C.S.I No. 19 (b) P-10).	1,306.80	%Cft	58,153
4	16,700	Removing cement or lime plaster (C.S.I No:53 P-13).	121.00	%Sft	20,207
5	1,071	Dismantling cement concrete reinforced separating raiforcement from concrete clearing and straightnig the same (C.S.I No:20 P-10).	5,445.00	%Cft	58,316
6	181	Dismantling / Removing road mateling (CSI No. 51 Page No. 13).	121.00	%Sft	219
7	2,512	Excavation in foundation of building bridges and other structure including dressing refeling arround structure with excavated earth watering and ramming lead upto one chain and lift upto 5ft (b) in ordinary soil(C.S.I No:18 (b)P.5).	3,176.25	%OCft	7,979
8	720	Exceevation in hard rock requiring blasting and disposal of excavated material blasted material up to 50ft lead (Grade -) i/e dressing cleaning to design action etc complete (C.S.I No. 7 (f) P-2).	12,968.00	%OCft	9,337
9	1,004	Cement concrete brick or stone ballast 1 1/2" to 2" guage ratio 1:4:8 (C.S.I No: 4 (b) Page No:15)	9,416.28	%Cft	94,539
10	900	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6(C.S.I No:4 (e) P.21).	11,948.36	%Cft	107,535
11	4,748	Rein forced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid sepreteley this rate also includes all kinds of forms moulds:lifting shuttering curing rending and finishing the exposed surface (including screening and washing of shingle) (a) RC work in slab bams columns rafts lintels and other structural members laid in situ or pre cost laid in position complete in all respects. (l)Ratio (1:2:4) 90 Lbs cement 2 Cft. sand 4 Cft . shingle 1/8" to 1/4" guage.(C.S.I No:6 A (1) P.17).	337.00	P.Cft	1,600,076
12	254.36	Fabrication of Tor steel reinforceement for cement concrete including cutting, bending and laying in position making joints and fastings including cost of binding wire also includes removal of rust from bars (C.S.I No:8 B P.17).	5,001.70	P.Cwt	1,272,218
13	1,155	Pacca brick work in ground floor in cement sand mortar ratio: (C.S.I No: 5 (e) Page No: 21)	12,674.36	%Cft	146,389
14	219	Pacca brick work other then building including stricking of joints up to feet height (C.S.I No: 7 (e) Page No: 22)	12,346.65	%Cft	27,039
15	2,262	Dry rammed brick or stone blast 1/2" to 2" guage (C.S.I No. 2 P-No. 15).	3,327.50	%Cft	75,268
16	1,178	Filling watering and raming earth under floor with new earth excavated from outside lead upto on chain and lift upto 5ft. (C.S.I No: 22 P.4).	3,630.00	%OCft	4,276
17	1,178	Extra lead upto 5 miles	714.29	%Cft	8,414
18	16,700	Applying & Flooting coat of cement 1/32" thick (C.S.I No:14 P-53).	660.00	%Sft	110,220
19	19,988	Cement plaster upto 20' height 1/2" thick rario 1:6 (C.S.I No: 13 (b)Page No: 52).	2,206.60	%Sft	441,055
20	19,988	Cement plaster upto 20' height 3/8" thick rario 1:4 (C.S.I No: 11 (a) Page No: 52).	2,197.52	%Sft	439,240
21	6,221	Cement Concrete plain including placing compacting finishing and curing complete including screening complete and washing of stone agreegate without shuttring Ratio: 1:2:4. (C.S.I No. 5 (f) Page No:16)	14,429.25	%Cft	897,644
22	113.11	S/F Girder at Site of Work	3,850.00	P.Cwt	435,474
23	86.52	S/F T.Iron at Site of Work	3,575.00	P.Cwt	309,295
24	199.63	Errection rooled steel beam or old rails in roof etc errection and fixing in position (C.SI No:6 P-91).	186.34	P.Cwt	37,198

(Handwritten signature)

Quantities	Description of item to be executed at site	Rate	Units	Amount
5,086	1st class tiles roofing consisting of 4" earth and 1" mud plaster with leeping over 1/2" thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over one layer of 12"x6"x1" 1/4 tiles laid in 1"6 cement mortar including 1:2 cement pointing under neath of tiles complete including curing etc (C.S.I No:1 P.33).	11,443.10	%Sft	581,996
26	236 Providing and fixing G.I frames /Chowkates 7"2" or 41/2" x 3" for door using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ration 1:6 and repairing the jambs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:29 P.93).	228.90	P.Rft	54,020
27	403 First class deodar wood wrought joinery in doors and windos etc fixed in position i/c in chwoakts holds fasts hings iron tower bolts chowks cleats handles and cards with hooks etc Deodar paneled or paned are fully glazed 1/3/4" only shutter (C.S.I No:7 (b) P.58).	902.93	P.Sft	363,881
28	193 Suppling and fixing in position iron steel grill of 3/4"x 1/4" size flate iron of approved design i/c painting three coats etc complete weightg not less than 3.7 lbs of finsbed grill (C.S.I No:26 P.93).	180.50	P.Sft	34,837
29	98 Supplying & fixing in position aluminium channels framing for hanged doors or aleop made with 5 mm thick tinted glass glazing (Belguim) and alpha Japan locks i/c handels stoppers etc deluxe model (Bronze) (C.S.I No. 83 (b) P-108).	1,507.66	P.Sft	147,751
30	193 Supplying and fixing in position Aluminium channels framing for sliding windows and ventilators of aleo made with 5 mm thick tinted glass glazing (Belgium) & Aluminium glass Glazing (Blgium) & Aluminium fly screen i/c handles stoppers locking arrangement etc complete Deluxe model (Blonze) (C.S.I No:84 (b) P-108).	1,647.69	P.Sft	318,004
31	408 Making & fixing steel grated door with 1/16" thick sheeting including angle iron frame 2" x 2" 3/8" and 3/4" square bars 4" centre to centre with locking arrangementt. (C.S.I No:24 P-92)	726.72	P.Sft	296,502
32	1,200 Laying white marble flooring fine dressed in the surface without winging sate in lie mortar 1:2 including rubbing and polishing of the joints(C.S.I No:28 (a) P-43).	567.48	P.Sft	680,976
33	822 Providing and fixing 3/8" thick marble tiles of approved quality and colour shade size 8" x 4/6" x 4" in dado skirting and facing removal / tucking of exiting plaster surface etc over 1/2" thick base of cement mortar 1:3 setting mortar base including filling the joints and washing of tiles wiht white cement slurry current finishing cleaning and polishing etc complete (for new work) (C.SI No: 68 (i) P-49).	186.04	P.Sft	152,925
34	1,500 Providing and laying tiles glazed 6" x 6" x 1/4" on floor or wall facing in required colour and aptern of STILE specification jointed in white cement and pigment over a base of 1:2 grey cement mortar 3/4" thick including washing and filling of joints with slaurry of white cement and pigment in desired shape with finishing, clearing and cost of wax polish etc. complete including cutting tiles to proper profile. (C.S.I No:60 P-47).	30,509.77	%Sft	457,647
35	1,200 Supplying & Fixing false ceeling of plaster paris, in panels including making farme work of deodar wood including painting with soligia paint (C.SI No: 52 P-64).	25,293.42	%Sft	303,521
36	1,528 Providing and lying 2" thick topping cement concrete 1:2:4. Including surface finishing dividing into panels(C.S.I No:16 (c) P-42).	3,275.50	%Sft	50,050
37	1,528 Two coats of bitumen laid hot using 34"Lbs for 100sft over roof and blinded with sand at 1Sft per 100sft (C.S.I No:13 P.35).	1,887.40	%Sft	28,839
38	22,500 Scraping ordinary distember, oil bound distember or paint on walls (C.S.I No:54 (b) P-13).	226.80	%Sft	51,030
39	22,500 Destember three coats (C.S.I No:24 (c) P-54).	1,079.65	%Sft	242,921
40	3,288 Preparing the surface & painting with matt finish paint of approved make to old matt finish surface three coat (C.S.I No. 37 (C) P-55).	2,499.76	%Sft	82,192
41	2,100 Preparing the surface and painting with weather coat of approved make to old weather coat surface (CSI No. 39 (c) P. No. 56)	2,118.33	%Sft	44,485
42	735 Painting new surface, and paiting of doors and windows any type (i/c edges) 3 coats (C.S.I No:4 (c) P-76).	2,116.41	%Sft	15,556
43	2,050 Painting guard bars, gates iron bars gratings, railings including standard braces (etc.) and similar open work. Old Surface three coats (CSI No. 4 (d-iii) Page No. 69).	977.40	%Sft	20,037
44	193 Galavanized wire guaze fixed to chowkats with 3/4" deodar stips and screws. (C.S.I No. 14 (d) P-60).	190.72	P.Sft	36,809

Quantities	Description of item to be executed at site	Rate	Units	Amount
172	First class door & wood wrought joinery in wire glazed door and windows with 22. S.W.G galvanized wire glazed 144 mesh per square inch iron fitting complete 1 1/2" thick deodar wood framing including wire gauze with ordinary hinges. (C.S.I No:14 (B) P.67).	562.98	P.Sft	96,551
46	96 Providing & fixing deodar almirah 9" - 12" depth including boxing with back shelves shutters brass fitting complete (CSI No.23 P-61)	1,778.50	P.Sft	170,736
47	1,500 Providing & fixing cement paving blocks flooring having size of 197 x 97 x 60 (mm) of city / quaddra / cobble shape with pigmented, having strength b/w 5000 psi to 8500 psi l/c filling the joints with hill sand and laying in specified manner/ pattern and design etc: complete. (CSI No. 72 Page No. 49).	223.97	P.Sft	335,955
48	30 Rain forcement concrete spout including fixing in position 2 1/2" x 6" x 5" (C.S.I No:14 P.18).	261.25	Each	7,838
TOTAL :-				10,759,976

PART "B" SCHEDULE ITEMS

1	5	Providing & fixing squatting type white glazed of flush cistern with internal fitting & flush pipe with bend and making requisite numbers of holes in wall plinth & floor for pipe connection & making good in cement concrete 1:2:4. W.C not less than 19" clear opening between flushing rims and 3 gallons flushing tank with 4" dia C.I trap with C.I thumb. (S.I No:1 (b) i P-No:1)	4802.60	Each	24,013
2	5	Providing & fixing 24" x 18" lavatory basin in white glazed earthen ware complete with & l/c the cost of W.I or C.I cantilever brackets 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of 1/2" dia rubber plug & chrome plate brass chain 1-1/4" dia malleable iron or c.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection and making good in cement concrete 1: 2: 4 (Standard pattern). (S.I No.8 P-No:3).	4253.70	Each	21,269
3	5	Add: extra labour for providing and fixing of earthen wire pedestal white or colored glass standard pattern (S.I No:9 P-No:3).	938.47	Each	4,692
4	8	P/F in position nylon connections complete with 1/2" dia brass stop cock with pair of brass nuts and lining joints to nylon connection (S.I No:23 P-No:6).	447.15	Each	3,577
5	5	P/F 6" x 4" c.c gully trap with 4" dia out let complete with 4" thick 1:2:4 c.c for bed and 1/2" thick cement plaster 1:3 to the kerb c.I caning 6" x 6" and c.I cover and frame 12" x 12" in side etc complete (S.I No:1(a-i) P-No:21).	1193.17	Each	5,966
6	50	P/F 4" dia C.I soil and vent pipes including cutting and fitting and extra painting to match the colour of the building (S.I No:1 P-No:9).	333.29	P.Rft	16,665
7		RCC pipe with color class "B" and didding the traches to the required depth an fixing in positin l/c cutting fitting and jointing with max phalt composition and cemen mortar 1:1 and testing with water presure to head of 4 Ft aboe the top of the heigh			
	50	4" dia	146.57	P.Rft	7,329
	50	6" dia	199.25	P.Rft	9,963
8	5	Providing & fixing 6" x 2" or 6" x 3" C.I floor trap of the approved self cleaning design with a C.I screwed down gratting with or without a vent arm complete with & l/c making requisite number of holes in walls, plinth & floor for Pipe connections & making good cement concrete 1:2:4. (S.I No.. 20 Page No.3).	2042.43	P.Rft	10,212
9		Providing G.I Pipes, specials, and clamps etc, including fixing cutting & fitting complete with and l/c the cost of breaking thorough walls and roof, making good etc. painting two coats after cleaning the Pipe etc. with white zink paint with pigment to match the colour5 of the building and testing with water to a pressure head of 200 feet and handling. (SI No. 1 Page No.12)			
i	100	1/2" dia	73.21	P.Rft	7,321
ii	100	3/4" dia	95.79	P.Rft	9,579
iii	50	1" dia	128.55	P.Rft	6,428
vi	30	1-1/4" dia	153.19	P.Rft	4,596
10		Add : Extra labor for concealed G.I pipe and Fitting l/c making recess in the wall for pipe and making good in Cement mortar etc Complete			
	50	1/2" dia	7.82	P.Rft	391
	50	3/4" dia	8.45	P.Rft	423

	Quantities	Description of item to be executed at site	Rate	Units	Amount
i		Providing and fixing full way gun metal valves with wheels threaded or flanged ends with rubber washing (b) standard pattern (Note: Standarded Manufacture by M/S Anwar Mechanical works (S.I No:4 (b) P-No:17).			
	5	1/2" dia	161.92	Each	810
	5	3/4 dia	227.92	Each	1,140
12	6	S/F cancelled stop cock of superior quality with crystal head head 1/2" dia (S.I No:11 (b) P-No:18).	478.28	Each	2,870
13	5	S/F long bib cock of crystal head with c.p head 1/2" dia (S.I No:13 (b) P-No:19).	1109.46	Each	5,547
14	5	S./F wash been mixture of superior quality with c.p head 1/2" dia with crystal head (S.I No:16 (b) P-No:15).	2882.00	Each	14,410
15	2	Supplying & fixing Bath room accessories set (7 pieces l/c towel rod, brush holder, soap tray, shelf of approved quality and design etc complete. (Si No: 22 P-No:19)	10322.40	Each	20,645
16		P/F handle valves (China) (S.I No:7 P-No:14).			
ii	5	3/4" dia	271.92	Each	1,360
iii	5	1" dia	365.42	Each	1,827
16	50	Providing & fixing 4" x 4" dia C.I branch of the required degree with access doors, rubber washer 3/8" thick and bolts and nuts and extra painting to match the colour of the building.	702.00	Each	35,100
17	50	Providing & fixing 4" dia. C.I plain bend of the required degree including extra painting to match the colour of the building.	566.70	Each	28,335
18	10	Supplying & fixing C.P Muslim Showeer with double Bib cock & ring Pipe etc complete.	3432.00	Each	34,320
TOTAL :-					278,784

PART "C" SCHEDULE ITEMS

1		Providing PVC Pipes of class D equalvalent (make) fixinbg in trench i/c cutting fitting and jointing with "Z" joint with one rubber Ring i/c testing with water to head of 122 metere or 400ft. (S.I.No:3 Page No:23)			
	20	4" dia	137.00	P.Rft	2,740
	30	6" dia	226.00	P.Rft	6,780
2	2	Constructiong manhole or inspectionchamber for the required dia of circular sewer and 3'-6" (1067 mm) dpth with walls of BB in cement motor 1:3 cement plaster 1:3, 1/2" thick inside of walls and 1" (25 mm) thick over benchingh and channel i/c fixing CI manhole cover with fram of clear opening 1-1/2' x 1., 1/2' (457x457 mm) of 1.75 Cwt. (88.9 Kg) embedded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S steps 6' (150 mm) waide projecting 4" (102 mm) from the face of wall at 12" (305 mm) C.C dully painted etc. complete as per spacification and drawing (SI No. P Page No. 46). (PHE)	14748.00	Each	29,496
TOTAL :-					39,016

Amount Total (CSR)


Part "A"	% Above / Below _____	Total Amount _____
Part "B"	% Above / Below _____	Total Amount _____
Part "C"	% Above / Below _____	Total Amount _____
		Total "A+B+C" _____

Non Schedule Items

1	625	Making and Fixing Stainless Steel pipe Stair railing i/c all material and laour chrages approve by Engineer Incharge		P.Sft	
TOTAL :-					

Total (b) in words & figures

CONTRACTOR



✓ MEDICAL SUPERINTENDENT
GMMMC HOSPITAL SUKKUR

BIDDING DATA

- (a) Name of Procuring Agency Medical Superintending Ghulam Mohammad Mahar Medical College Hospital Sukkur.
- (b) Brief Discription of Works Repair of Nursing School. (Civil works)
- (c) Procuring Agency Address Near Civil Hospital Sukkur
- (d) Estimated Cost 7,500,000
- (e) Amount of Bid Security 375,000
- (f) Period of Bid Validity (Days) 28 Days
- (g) Security Deposit (i/c bid Security) 750,000
- (h) Security to be deducted from bills 5%
- (i) Submission of bids along with time 25.02.2016 up to 1:00 PM
- (j) Time and Date of Bid Opening 12.03.2016 (2:00 PM)
- (k) Time for completion from written order of commencement 04 Months
- (l) Liquidated Demages _____
- (m) Deposit Receipt _____ Date _____ Amount _____
- (n) D.R No, Date & Amount _____
- (o) Tender Issued to (Mr. / M/S) _____



BILL OF QUANTITIES

Discription and Rate of Items based on Composite Schedule of Rates

NAME OF WORK :- REPAIR OF NURSING SCHOOL AT GMMMC HOSPITAL SUKKUR.

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
PART "A" SCHEDULE ITEMS					
1	1230	Dismantling cement concrete rainforced separaiting raiforcement from concrete clearing and straightnig the same (C.S.I No:20 P-10).	5445.00	%Cft	66,974
2	215	Dismantling brick work in lime or cement plaster (C.SI No:13 P-10).	1285.63	%Cft	2,764
3	434	Dismantling 2nd Class tile roofing (C.S.I No:22 (b) P-11).	378.13	%Sft	1,641
4	6656	Removing cement or lime plaster (C.S.I No:53 P-13).	121.00	%Sft	8,054
5	919	Dismantling cement concrete plain 1:2:4 (C.S.I No. 19 (c) P-10).	3327.50	%Cft	30,580
6	9454	Disposal of dibries 05 miles	714.29	%Cft	67,529
7	2458	Pacca brick work in ground floor in cement sand mortor ratio: (C.S.I No: 5 (e) Page No: 21)	12674.36	%Cft	311,536
8	705	Rein forced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid sepreately this rate also includes all kinds of forms moulds:lifting shuttering curing rending and finishing the exposed surface (including screening and washing of shingle) (a) RC work in slabe bams columns rafts lintels and other structural members laid in situ or pre cost laid in position complete in all respects. (I)Ratio (1:2:4) 90 Lbs cement 2 Cft. sand 4 Cft . shingle 1/8" to 1/4" guage.(C.S.I No:6 A (1) P.17).	337.00	P.Cft	237,585
9	34:621	Fabrication of Tor steel reinforceement for cement concrete including cutting bending and laying in position making joints and fastings including cost of binding wire also includes removal of rust from bars (C.S.I No:7 B P.20).	5001.70	P.Cwt	173,164
10	102.723	S/F Girder at Site of Work	3850.00	P.Cwt	395,484
11	59.393	S/F T.Iron at Site of Work	3575.00	P.Cwt	212,330
12	162.116	Errection rooled steel beam or old rails in roof etc errection and fixing in position (C.SI No:6 P-91).	186.34	P.Cwt	30,209
13	3413	1st class tiles roofing consisting of 4"earth and 1" mud plaster with leeping over 1/2"thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over one layer of 12"x6"x1"1/4 tiles laid in 1"6 cement mortor icluding 1:2 cement pointing under neath of tiles complete including curing etc (C.S.I No:1 P.33).	11443.10	%Sft	390,553
14	6656	Applying & Flooting coat of cement 1/32" thick (C.S.I No:14 P-53).	660.00	%Sft	43,930
15	11092	Cement plaster upto 20' height 1/2" thick rario 1:6 (C.S.I No: 13 (b)Page No: 58).	2206.60	%Sft	244,756
16	11092	Cement plaster upto 20' height 3/8" thick rario 1:4 (C.S.I No: 11 (a) Page No: 52).	2197.52	%Sft	243,749
17	698	Supplying and filling sand under floor and pluggling in walls .(C.S.I No:29 P.26).	1141.25	%Cft	7,966
18	1084	Cement concrete brick or stone ballast 1 1/2" to 2" guage ratio 1:4:8 (C.S.I No: 4 (b) Page No:15)	9416.28	%Cft	102,072
19	474	Cement Concrete plain including placing compacting finishing and curing complete including screening complete and washing of stone agreegate without shutting Ratio: 1:2:4. (C.S.I No. 5 (f) Page No:16)	14429.25	%Cft	68,395

	Quantities	Description of item to be executed at site	Rate	Units	Amount
20	2882	Laying white marble flooring fine dressed in the surface without winging sate in lie mortar 1:2 including rubbing and polishing of the joints(C.S.I No:28 (a) P-43).	567.48	P.Sft	1,635,477
21	868	Providing and fixing 3/8" thick marble tiles of approved quality and colour shade size 6" x 4/8" x 4" in dado skirting and facing removal / tucking of exiting plaster surface etc over 1/2" thick base of cement mortar 1:3 setting mortar base including filling the joints and washing of tiles with white cement slurry current finishing cleaning and polishing etc complete (for new work) (C.S.I No: 68 (i) P-49).	186.04	P.Sft	161,483
22	2786	Supplying & Fixing false ceiling of plaster paris, in panels including making frame work of deodar wood including painting with soligia paint (C.S.I No: 52 P-64).	25293.42	%Sft	704,675
23	600	Providing and laying tiles glazed 6" x 6" x 1/4" on floor or wall facing in required colour and apttern of STILE specification jointed in white cement and pigment over a base of 1:2 grey cement mortar 3/4" thick including washing and filling of joints with slurry of white cement and pigment in desired shape with finishing, clearing and cost of wax polish etc. complete including cutting tiles to proper profile. (C.S.I No:60 P-47).	30509.77	%Sft	183,059
24	66	Providing and fixing G.I frames /Chowkates 7"2" or 4 1/2" x 3" for door using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ration 1:6 and repairing the jambs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:29 P.93).	228.90	P.Rft	15,107
25	100	First class deodar wood wrought joinery in doors and windos etcified inosition i/c in chwoakts holds fasts hings iron tower bolts chowks cleats handles and cards with hooks etc Deodar paneled or paned are fully glazed 1/3/4"only shutter (C.S.I No:7 (b) P.58).	902.93	P.Sft	90,293
26	65	Glazing with pains (16 oz to 18 oz) including cost of putty (C.S.I No:45 (a) P-63).	115.55	P.Sft	7,511
27	10	Rain forcement concrete spout including fixing in position 2 1/2" x 6" x 5" (C.S.I No:14 P.18).	261.25	P.Sft	2,613
28	45	Providing and fixing iron collapsible gate with channel framing of section 3/4" x 5/16" at 4" i/c revitted with 3/4" x 1/8" flat iron patti placed diagonally and provided with top & bottom T- section 1" x 1" 1/8" along with rollers also i/c locking arrangement and fixing in floor/ceiling or wall etc: completed. (C.S.I No:32 P-94).	387.04	P.Sft	17,417
29	1103	P/F colour create to wall surface to provide durable crust and aestheics having thickness upto 3/4" with specified colour having water, fire and temite resistance (upto 2' -0 height). (C.S>I No. 44 P-56).	6319.50	%Sft	69,704
30	620	P/L Halla pattern tiles glazed 6" x 6" x 1/4" of floor of walls facing required pattern stile specification jointed in white cement and pigment over a bazes 1:2 gra y cement mortar 3/4" thick i/c washing & filling of joints with sullury of white cement & pigment in desire shape with finishing cleaning and cost of wax polish etc complete i/c cutting tiles to proper profile. (C.S.I No: 61 P-48)	47651.56	%Sft	295,440
31	8736	Praparing the surface and painting with matt finish i/c rubbing the surface with bathy (silicon carbide rubbing brick) filling the voids with zink/ chal/ plaster of paris mixture , applying first coat premix making the surface smooth and then painting 3 coat with matt finish of aproved make etc complet (New Surface) Three Coat. (CSI No. 36 (C) Page No. 55).	3444.38	%Sft	300,901
32	246	Painting new surface, and painting of doors and windows any type (i/c edges) 3 coats (C.S.I No:4 (c) P-76).	2116.41	%Sft	5,206

Quantities	Description of item to be executed at site	Rate	Units	Amount
1818	Old Surface	1160.06	%Sft	21,090
33 3591	Painting guard bars gats iron bars grating raling including standard braces etc and smiller open work three coat (C.S.I No:4 (d) (ii) P-70).	1270.83	%Sft	45,636
			TOTAL :-	6,194,879

PART "B" SCHEDULE ITEMS

1	3	Providing & fixing squatting type white glazed of flushe cisten with internal fitting&flush pippe with bend and making requesite numbers of holes in wall plinth & floor for pipe conection & making good in cement concrete 1:2:4. W.C not less than 19" clear opening between flushing rims and 3 gallons flushing tank with 4" dia C.I trap with C.I thumble. (S.I No:1 (b) i P-No:1)	4802.60	Each	14,408
2	3	Providing & fixing 24" x 18" lavatory basin in white glazed earthen ware complete with & l/c the cost of W.I or C.I cantilever brackets 6 inches built into wall, painted white in two coast after a primary coat of red lead paint, a pair of 1/2" dia rubber plug & chrome plate brass chain 1-1/4" dia malloable iron or c.P brass traps malloable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection and making good in cement concrete 1: 2: 4 (Standard pattern): (S.I No:8 P-No:3).	4253.70	Each	12,761
3	3	Add: extra labour for providing and fixing of earthen wire padestle whiute or-colored glass standared pattern (S.I No:9 P-No:3).	938.47	Each	2,815
4	1	Providing & fixing European white glazed earthen ware wash down w.c pan complete with and l/c the cost of white/black plastic seat (Best Quality) and lid with c.P brass hineges and buffers, 3 gallons white glazed earthen earthen ware low level foushing cistern with siphon fitting 1-1/2" dia white porcelain enamelled flush bend 3/4" dia and making requiste number of holes in walls, plinth and floor for Pipe connectios and making good in cement concrete 1: 2: 4. (Foreign Quality).	11477.40	Each	11,477
5	8	P/F in position nyloon connections complete with 1/2"dia brass stop cock with pair of brass nuts and lining joints to nyloon connection (S.I No:23 P-No:6).	447.15	Each	3,577
6	20	P/F 4"dia C.I soil and vent pipes including cutting and fitting and extra painting to match the colour of the building (S.I.No:1 P-No:9).	333.29	P.Rft	6,666
7		RCC pipe with colar class "B" and didding the traches to the required depth an fixing in positin l/c cutting fitting and jointing with max phalt composition and cemen mortar 1:1 and testing with water presure to head of 4 Ft aboe the top of the heigh			
	100	4"dia	146.57	P.Rft	14,657
	50	6"dia	199.25	P.Rft	9,963
8	4	Providing & fixing 6" x 2" or 6" x 3" C.I floor trap of the approved self cleaning design with a C.I screwed down grating with or without a vent arm complete with & l/c making requisite number of holes in walls, plinth & floor for Pipe connections & making good cement concrete 1:2:4. (S.I No.. 20 Page No.3).	2042.43	P.Rft	8,170
9		Providing G.I Pipes, specials, and clamps etc, including fixing cutting & fitting complete with and l/c the cost of breaking thorough walls and roof, making good etc. painting two coats after cleaning the Pipe etc. with white zink paint with pigment to match the colour5 of the building and testing with water to a pressure head of 200 feet and handling. (SI No. 1 Page No.12)			
i	100	1/2"dia	73.21	P.Rft	7,321
ii	100	3/4"dia	95.79	P.Rft	9,579
10		Add : Extra labor for concealed G.I pipe and Fitting i/c making recess in the wall for pipe and making good in Cement motor etc Complete			
	50	1/2" dia	7.82	P.Rft	391
11		Providing and fixing full way gun metal values with wheels threaded or flanged ends with rubber washing (b) standared pattern (Note standared Manufacture by M/S Anwar Mechanical works (S.I No:4 (b) P-No:17).			
	4	1/2"dia	161.92	Each	648
	4	3/4 dia	227.92	Each	912


	Quantities	Description of item to be executed at site	Rate	Units	Amount
12	8	S/F cancelled stop cock of superior quality with crystal head head 1/2" dia (S.I No:11 (b) P-No:18).	478.28	Each	3,826
13	4	S/F long bib cock of crystal head with c.p head 1/2" dia (S.I No:13 (b) P-No:19).	1109.46	Each	4,438
14	2	S./F wash been mixture of superior quality with c.p head 1/2" dia with crystal head (S.I No:16 (b) P-No:15).	2882.00	Each	5,764
15		P/F handle values (China) (S.I No:7 P-No:14).			
i		1/2" dia			
ii	4	3/4" dia	271.92	Each	1,088
iii	4	1" dia	365.42	Each	1,462
16		Supplying & fixing fibre glass tank of approved quality and design and wall thickness as specified i/c cost of nutes, bolts and fixing in platform of cement concrete 1: 3: 6 and makin connections for in -let ,& ou-let & over flow pipes etc. complete.			
i		1/2" dia			
ii	2	250 Gallon	21990	Each	43,979
17		Providing PVC Pipes of class D equalvalent make) fixing in trench i/c cutting fitting and jointing with "Z" joint with one rubber Ring i/c testing with water to head of 122 metere or 400ft. (S.I.No:3 Page No:23)			
	100	3" dia	137.00	R.FT	13,700
	100	4" dia	226.00	R.FT	22,600
18	2	Constructiong manhole or inspection chamber for the required dia of circular sewer and 3'-6" (1067 mm) dpth with walls of BB in cement motor 1:3 cement plaster 1:3, 1/2" thick inside of walls and 1" (25 mm) thick over benchingh and channel i/c fixing CI manhole cover with fram of clear opening 1-1/2' x 1., 1/2' (457x457 mm) of 1.75 Cwt. (88.9 Kg) embedded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S steps 6' (150 mm) waide projecting 4" (102 mm) from the face of wall at 12" (305 mm) C.C dully painted etc. complete as per spacification and drawing (SI No. P Page No. 46). (PHE)	14748	Each	29,496
TOTAL :-					229,697

Amount Total (CSR)

Part "A"	% Above / Below _____	Total Amount _____
Part "B"	% Above / Below _____	Total Amount _____
Part "C"	% Above / Below _____	Total Amount _____
		Total "A+B+C" _____

CONTRACTOR


✓ *Com*
 MEDICAL SUPERITENDENT
 GMMMC HOSPITAL SUKKUR



BIDDING DATA

1
11

- (a) Name of Procuring Agency Medical Superintending Ghulam Mohammad Mahar Medical College Hospital Sukkur.
- (b) Brief Discription of Works Repair of Nursing School (Electric Work)
- (c) Procuring Agency Address Near Civil Hospital Sukkur
- (d) Estimated Cost 800,000
- (e) Amount of Bid Security 40,000
- (f) Period of Bid Validity (Days) 28 Days
- (g) Security Deposit (i/c bid Security) 80,000
- (h) Security to be deducted from bills 5%
- (i) Submission of bids along with time 25.02.2016 up to 1:00 PM
- (j) Time and Date of Bid Opening 12.03.2016 (2:00 PM)
- (k) Time for completion from written order of commencement 04 Months
- (l) Liquidated Demages _____
- (m) Deposit Receipt _____ Date _____ Amount _____
- (n) D.R No, Date & Amount _____
- (o) Tender Issued to (Mr. / M/S) _____

A circular stamp with a handwritten signature in the center, located at the bottom right of the page.

BILL OF QUANTITIES

Discription and Rate of Items based on Composite Schedule of Rates

NAME OF WORK :- REPAIR OF NURSING SCHOOL AT GMMMC HOSPITAL SUKKUR. (E.L)

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
PART "A" NEW SCHEDULE ITEMS					
1	110	Wiring for light or fan point with 3/029 PVCinsulated wire in 20mm (3/4") channel patti on surface as required (S.No. 129 P-15).	910	per point	100,100
2	20	Wiring for plug point with 3/029 PVC insulated wire in 20mm (3/4") channel patti on surface as required (S.I.No:130 P- No:15)	742	per point	14,840
3	1	Wiring for call bell point with 3/029 PVC insulated wire in 20mm (3/4") channel patti on surface as required. (S.I.No:131 P- No:15)	1590	per point	1,590
4	110	Providing & fixing one way SP 5amp switch flush type(S.I.No:219 P- No:33)	54	P.No	5,940
5	20	Providing & fixing two pin 5amp plug & socket (S.I.No:222 P- No:33)	80	P.No	1,600
6	5	Providing & fixing three pin 10/15amp plug & socket flush type (S.I.No:222 P- No:33)	162	P.No	810
7	50	Providing & fixing Brass Battern holder c(S.I.No:232 P- No:33)	70	P.No	3,500
8	20	Providing & fixing Brass Ceiling fan 56" (good quality) (S.I.No:235 P- No:34)	3185	P.No	63,700
9	400	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/029 copper conductor in 3/4" dia PVC conduit on surface (S.I.No:3 P- No:1)	171	P.Mtr	68,400
10	400	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/044 (6mm ²) copper conductor in 1" dia PVC conduit on surface (S.I.No:5 P- No:1).	305	P.Mtr	122,000
11	250	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/052 (10 mm ²) copper conductor in 1" dia PVC conduit on surface (S.I.No:6 P- No:1).	428	P.Mtr	107,000
12	20	Providing & fixing circuit breaker 6,10,15,20, 30,40,50 & 63amp SP.(TB-5S) on prepared board as required (S.I.No:202 P- No:30)	916	P.No	18,320
13	1	Providing & fixing circuit breaker 15,20,30, 40,50,60,75 & 100amp TP (XS-100NS) on prepared board as required (S.I.No:207 P- No:31)	9261	P.No	9,261
14	1	Providing & fixing DP I/C change over switch 500volts 200amp on a prepared board	8767	P.No	8,767
15	4	Providing & Fixing of street light 250 watts (SON-T) having IP66 classification with 250w lamp, choke, capacitor & Internal wiring complete in all respect at the height With the help of hydraulic crane as per site requirement and instruction of EI. (CSI No. 163 Page No. 25)	24790	P.No	99,160
TOTAL :-					624,988

PART "B" OLD SCHEDULE ITEMS

1	20	P/Fenergy sever superior quality including fixing on existing holder etc complete.(S.I.No:6 P- No:33)	497.00	Each	9,940
2	12	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.(S.I.No:5 P- No:33)	497.00	Each	5,964
3	3	P/F distribution metal board double shutter to accommodate circuit breakers including painting with enamel paint and for other simmlar job on surface (S.I.No:18 P- No:13)	907.96	P.Sft	2,724
4	1	P/F earthing set with 2x2x1/4" cooper plate burried in ground at a depth of 12" or less if water comes out from the ground level with salt and chorcoal etc.in/c.making the pit 12"deep by excavation of all type of soil. Earth plat to be connected with No:8 S W G bare cooper wire run in 1/2' GI pipe straight from the earth plate up to the metallic electric assesary i/e providing necessary Tee.(S.I.No:2 P- No:26)	3610.04	Each	3,610
5	9	P/F Bulb 100 Watts	25.00	Each	225
6	20	P/F mild steel bar fan clamp 15.8 mm (5/8")dia suitable for RCC roof (S.I.No:1 (c) P- No:14)	141.01	Each	2,820
7	1	P/F AC or DC electric bell 200/250 volt 70MM. (S.I.No:21 P- No:11)	150.70	Each	151
8	1	P/F flush type electric bell bush button (S.I.No:23 P- No:12)	25.19	Each	25
TOTAL :-					25,459

No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
-----	------------	--	------	-------	--------

Amount Total (CSR)

Part "A"	% Above / Below _____	Total Amount	_____
Part "B"	% Above / Below _____	Total Amount	_____
		Total "A+B"	_____

PART "B" NON SCHEDULE ITEMS

1	30	P/F stair step LED light 6" x3" with PVC frame with 3/4" dia PVC pipe & ceiling LED light 12 watts etc complete approved by officer Incharge.		Each	
TOTAL :-					

Total (b) in words & figures


CONTRACTOR

✓ *[Signature]*
 MEDICAL SUPERINTENDENT
 GMMMC HOSPITAL SUKKUR

[Signature]

BIDDING DATA

- (a) Name of Procuring Agency Medical Superintending Ghulam Mohammad
Mahar Medical College Hospital Sukkur.
- (b) Brief Discription of Works Renovation of Mortuary (Civil Work)
- (c) Procuring Agency Address Near Civil Hospital Sukkur
- (d) Estimated Cost 5,000,000
- (e) Amount of Bid Security 250,000
- (f) Period of Bid Validity (Days) 28 Days
- (g) Security Deposit (i/c bid Security) 500,000
- (h) Security to be deducted from bills 5%
- (i) Submission of bids along with time 25.02.2016 up to 1:00 PM
- (j) Time and Date of Bid Opening 12.03.2016 (2:00 PM)
- (k) Time for completion from written order of commencement 04 Months
- (l) Liquidated Demages _____
- (m) Deposit Receipt _____ Date _____ Amount _____
- (n) D.R No, Date & Amount _____
- (o) Tender issued to (Mr. / M/S) _____



BILL OF QUANTITIES

Description and Rate of Items based on Composite Schedule of Rates

2
1

NAME OF WORK :- RENOVATION OF MORTUARY AT CIVIL HOPITAL SUKKUR.

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
PART "A" SCHEDULE ITEMS					
1	996	Dismantling 2nd Class tile roofing (C.S.I No:22 (b) P-11).	378.13	%Sft	3,766
2	2,597	Dismantling brick work in lime or cement plaster (C.S.I No:13 P-10).	1,285.63	%Cft	33,388
3	725	Excavation in foundation of building bridges and other structure including dressing refeling around structure with excavated earth watering and ramming lead upto one chain and lift upto 5ft (b) in ordinary soil(C.S.I No:18 (b)P.5.	3,176.25	%0Cft	2,303
4	617	Cement concrete brick or stone ballast 1 1/2" to 2" guage ratio 1:4:8 (C.S.I No: 4 (b) Page No:15)	9,416.28	%Cft	58,098
5	442	Pacca brick work in foundation and plinth in cement sand mortor ratio 1:6(C.S.I No:4 (e) P.21).	11,948.36	%Cft	52,812
6	1,199	Rein forced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid sepreteley this rate also includes all kinds of forms moulds:lifting shuttering curing rending and finishing.the exposed surface (including screening and washing of shingle) (a) RC work in slabe bams columns rafts lintels and other structural members laid in situ or pre cost laid in position complete in all respects. (I)Ratio (1:2:4) 90 Lbs cement 2 Cft. sand 4 Cft . shingle 1/8" to 1/4" guage.(C.S.I No:6 A (1) P.17).	337.00	P.Cft	404,063
7	64.232	Fabrication of Tor steel reinforcement for cement concrete including cutting bending and laying in position making joints and fastings including cost of binding wire also includes removal of rust from bars (C.S.I No:8 B P.17).	5,001.70	P.Cwt	321,269
8	2,461	Filling watering and raming earth under floor with new earth excavated from outside lead upto on chain and lift upto 5ft. (C.S.I No: 22 P.4).	3,630.00	%0Cft	8,933
9	2,461	Extra lead upto 5 miles	714.29	%Cft	17,579
10	2,385	Pacca brick work in ground floor in cement sand mortor ratio: (C.S.I No: 5 (e) Page No: 21)	12,674.36	%Cft	302,283
11	4,153	Cement plaster upto 20' height 1/2" thick ratio 1:6 (C.S.I No: 13 (b)Page No: 52).	2,206.60	%Sft	91,640
12	4,153	Cement plaster upto 20' height 3/8" thick ratio 1:4 (C.S.I No: 11 (a) Page No: 52).	2,197.52	%Sft	91,263
13	21.205	S/F Girder at Site of Work	3,850.00	P.Cwt	81,639
14	19.679	S/F T.Iron at Site of Work	3,575.00	P.Cwt	70,352
15	40.884	Errection rooled steel beam or old rails in roof etc errection and fixing in position (C.S.I No:6 P-91).	186.34	P.Cwt	7,618
16	1,178	1st class tiles roofing consisting of 4"earth and 1" mud plaster with leeping over 1/2"thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over one layer of 12"x6"x1"1/4 tiles laid in 1"6 cement mortor icluding 1:2 cement pointing under neath of tiles complete including curing etc (C.S.I No:1 P.33).	11,443.10	%Sft	134,800
17	1,178	Providing and laying single per layer of polithin 0.13mm thick for water proffing per specification and instructions of engineer incharge(C.S.I No:38 P.38).	10.70	%Sft	12,605
18	225	Cement Concrete plain including placing compacting finishing and curing complete including screening complete and washing of stone agreegate without shuttring Ratio: 1:2:4. (C.S.I No. 5 (f) Page No:16)	14,429.25	%Cft	32,466
19	106	Providing and fixing G.I frames /Chowkates 7"2" or 4 1/2" x 3" for door using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ration 1:6 and repairing the jambs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:29 P.93).	228.90	P.Rft	24,263
20	14	Providing and fixing G.I frames /Chowkates 7"2" or 4 1/2" x 3" for windows using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ratio 1:6 and repairing the janbs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I Ne:28 P.93).	240.50	P.Rft	3,367

	Quantities	Description of item to be executed at site	Rate	Units	Amount
1	72	Suppling and fixing in position iron steel grill of 3/4"x 1/4" size flate iron of approved design I/c painting three coats etc complete weightg not less than 3.7 lbs of finished grill (C.S.I No:26 P.93).	180.50	P.Sft	12,996
22	136	First class deodar wood wrought joinery in doors and windos etc fixed in position I/c in chwoakts holds fasts hinges iron tower balts chowks cleats handles and cards with hooks etc Deodar paneled or paned are fully glazed 1/3/4" only shutter (C.S.I No:7 (b) P.58).	902.93	P.Sft	122,798
22	108	Supplying and fixing in position Aluminium channels framing for sliding windows and ventilators of alco made with 5 mm thick tinted glass glazing (Belgium) & Aluminium glass Glazing (Blgium) & Aluminium fly screen I/c handles stoppers locking arrangement etc complete Deluxe model (Blonze) (C.S.I No:84 (b) P-108).	1,647.69	P.Sft	177,951
23	1,281	Laying white marble flooring fine dressed in the surface without winging sate in lie mortar 1:2 including rubbing and polishing of the joints(C.S.I No:28 (a) P-43).	567.48	P.Sft	726,942
25	1,102	Supplying & Fixing false ceeling of plaster paris. in panels including making farne work of deodar wood including painting with soligia paint (C.SI No: 52 P-64).	25,293.42	%Sft	278,733
26	8	Rain forcement concrete spout including fixing in position 2 1/2" x 6" x 5" (C.S.I No:14 P.18).	261.25	Each	2,090
27	2,575	Providing and laying tiles glazed 6" x 6" x 1/4" on floor or wall facing in required colour and apttern of STILE specification jointed in white cement and pigment over a base of 1:2 grey cement mortar 3/4" thick including washing and filling of joints with slaurry of white cement and pigment in desired shape with finishing, clearing and cost of wax polish etc. complete including cutting tiles to proper profile. (C.S.I No:60 P-47).	30,509.77	%Sft	785,627
28	108	Galavanized wire guaze fixed to chowkats with 3/4" deodar stips and screws. (C.S.I No. 14 (d) P-60).	190.72	P.Sft	20,598
29	71	First class deodar wood wrought joinery in wire glazed door and windows with 22. S.W.G galavanized wire glazed 144 mesh per squaer inch iron fitting complete 1 1/2" thick deodar wood framing including wire gauze with ordinary hinges. (C.S.I No:14 (B) P.67).	562.98	P.Sft	39,972
30	1,154	P/F colour create to wall surface to provide durable crust and aestheies having thickness upto 3/4" with specified colour having water, fire and temite resistance (upto 2' -0 height). (C.S>I No. 44 P-56).	6,319.50	%Sft	72,927
31	4,153	Praparing the surface and painting with matt finish i/c rubbing the surface with bathy (silicon carbide rubbing brick) filling the voids with zink/ chalj/ plaster of paris mixture, applying first coat premix making the surface smooth and then painting 3 coat with matt finish of aproved make etc complet (New Surface) Three Coat. (CSI No. 36 (C) Page No. 55).	3,444.38	%Sft	143,045
32	529	French polishing complete (on new Work). (C.S.I No. 7 (b) P-71).	3,841.75	%Sft	20,323
33	1,115	Painting guard bars gats iron bars grating raling including standard braces etc and smiller open work three coat (C.S.I No:4 (d) (ii) P-70).	1,270.83	%Sft	14,170
TOTAL :-					4,172,679

PART "B" SCHEDULE ITEMS

1	2	Providing & fixing squatting type white glazed of flushe cisten with internal fitting&flush pippe with bend and making requisite numbers of holes in wall plinth & floor for pipe conection & making good in cement concrete 1:2:4. W.C not less than 19" clear opening between flushing rims and 3 gallons flushing tank with 4" dia C.I trap with C.I thumble. (S.I No:1 (b) i P-No:1)	4802.60	Each	9,605
2	2	Providing & fixing 24" x 18" lavatory basin in white glazed earthen ware complete with & I/c the cost of W.I or C.I cantilever brackets 6 inches built into wall, painted white in two coast after a primary coat of red lead paint, a pair of 1/2" dia rubber plug & chrome plate brass chain 1-1/4" dia malleable iron or c.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection and making good in cement concrete 1: 2: 4 (Standard pattern). (S.I No:8 P-No:3).	4253.70	Each	8,507
3	2	Add: extra labour for providing and fixing of earthen wire padestle whiute or colored glass standared pattern (S.I No:9 P-No:3).	938.47	Each	1,877
4	4	P/F in position nyloon connections complete with 1/2" dia brass stop cock with pair of brass nuts and lining joints to nyloon connection (S.I No:23 P-No:6).	447.15	Each	1,789

	Quantities	Description of item to be executed at site	Rate	Units	Amount
5	2	P/F 6" x 4" c.c gully trap with 4" dia out let complete with 4" thick 1:2:4 c.c for bed and 1/2" thick cement plaster 1:3 to the karb c.l caning 6" x 6" and c.l cover and frame 12" x 12" in side etc complete (S.I No:1(a-i) P-No:21).	1193.17	Each	2,386
6		RCC pipe with colar class "B" and didding the traches to the required depth an fixing in positin i/c cutting fitting and jointing with max phalt composition and cemen mortar 1:1 and testing with water presure to head of 4 Ft aboe the top of the heigh			
	50	4" dia	146.57	P.Rft	7,329
	85	6" dia	199.25	P.Rft	16,936
8	2	Providing & fixing 6" x 2" or 6" x 3" C.I floor trap of the approved self cleaning design with a C.I screwed down grating with or without a vent arm complete with & i/c making requisite number of holes in walls, plinth & floor for Pipe connections & making good cement concrete 1:2:4. (S.I No.. 20 Page No.3).	2042.43	P.Rft	4,085
9		Providing G.I Pipes, specials, and clamps etc, including fixing cutting & fitting complete with and i/c the cost of breaking thorough walls and roof, making good etc painting two coats after cleaning the Pipe etc. with white zink paint with pigment to match the colour5 of the building and testing with water to a pressure head of 200 feet and handling. (SI No. 1 Page No.12)			
i	100	1/2" dia	73.21	P.Rft	7,321
ii	50	3/4" dia	95.79	P.Rft	4,790
iii	50	1" dia	128.55	P.Rft	6,428
10		Add : Extra labor for concealed G.I pipe and Fitting i/c making recess in the wall for pipe and making good in Cement motor etc Complete			
	100	1/2" dia	7.82	P.Rft	782
	50	3/4" dia	8.45	P.Rft	423
11		Providing and fixing full way gun metal values with wheels threaded or flanged ends with rubber washing (b) standared pattern (Note standared Manufacture by M/S Anwar Mechanical works (S.I No:4 (b) P-No:17).			
	2	1/2" dia	161.92	Each	324
	2	3/4 dia	227.92	Each	456
12	3	S/F cancelled stop cock of superior quality with crystal head head 1/2" dia (S.I No:11 (b) P-No:18).	478.28	Each	1,435
13	6	S/F long bib cock of crystal head with c.p head 1/2" dia (S.I No:13 (b) P-No:19).	1109.46	Each	6,657
14	3	S/F wash been mixture of superior quality with c.p head 1/2" dia with crystal head (S.I No:16 (b) P-No:15).	2882.00	Each	8,646
14	3	S/F swan type pillers cock of Superior Quality	795.00	Each	2,385
15	1	Supplying & fixing Bath room accessories set (7 pieces like towel rod, brush holder, soap tray, shelf of approved quality and etc etc complete. (Si No: 22 P-No:19)	8122.40	Each	8,122
16		P/F handle values (China) (S.I No:7 P-No:14).			
ii	2	3/4" dia	271.92	Each	544
iii	2	1" dia	365.42	Each	731
17		S/F fibre glass tank			
i	1	500 Gallon	37505.42	Each	37,505
				TOTAL :-	139,061

PART "C" SCHEDULE ITEMS

1		Providing PVC Pipes of class D equalvalent (make) fixing in trench i/c cutting fitting and jointing with "Z" joint with one rubber Ring i/c testing with water to head of 122 metere or 400ft. (S.I.No:3 Page No:23)			
	20	4" dia	137.00	P.Rft	2,740
	30	6" dia	226.00	P.Rft	6,780

Handwritten signature

Quantities	Description of item to be executed at site	Rate	Units	Amount
2	Constructiong manhole or inspectionchamb er for the required dia of circular sewer and 3'-6" (1067 mm) dpth with walls of BB in cement motor 1:3 cement plaster 1:3, 1/2" thick inside of walls and 1" (25 mm) thick over benching and channel i/c fixing CI manhole cover with fram of clear opening 1-1/2' x 1., 1/2' (457x457 mm) of 1.75 Cwt. (88.9 Kg) embedded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S steps U' (150 mm) waide projecting 4" (102 mm) from the face of wall at 12" (305 mm) C.C dully painted etc. complete as per spacification and drawing (SI No. P Page No. 46). (PHE)	14748.00	Each	29,496
TOTAL :-				39,016

Amount Total (CSR)

Part "A"	% Above / Below _____	Total Amount	_____
Part "B"	% Above / Below _____	Total Amount	_____
Part "C"	% Above / Below _____	Total Amount	_____
		Total "A+B+C"	_____


Non Schedule Items

1	625	Making and Fixing Fibre Glass Sun Shade standard size 3mm sheet (02 layer) / moulded in panel i/c G.I pipe ILM 4" dia 20' height at 25ft centre fixing in C.C foundation with M.S sq pipe 1 1/2" x 1 1/2" double kanchi along around from with internal M.S sq pipe 2' by 2' c/c i/c welding assembly etc complete in all respect.	P.Sft	
2	1	P/F piston pump set 1 H.P single phase 220 volts with 1/4" x 1 1/4" suction and delivery (Local made) (Electric)	Each	
TOTAL :-				

Total (b) in words & figures

CONTRACTOR

✓ MEDICAL SUPERITENDENT
GMMMC HOSPITAL SUKKUR



BIDDING DATA

2
/

- (a) Name of Procuring Agency Medical Superintending Ghulam Mohammad Mahar Medical College Hospital Sukkur.
- (b) Brief Description of Works Renovation of Mortuary (Electric Work)
- (c) Procuring Agency Address Near Civil Hospital Sukkur
- (d) Estimated Cost 500,000
- (e) Amount of Bid Security 25,000
- (f) Period of Bid Validity (Days) 28 Days
- (g) Security Deposit (i/c bid Security) 50,000
- (h) Security to be deducted from bills 5%
- (i) Submission of bids along with time 25.02.2016 up to 1:00 PM
- (j) Time and Date of Bid Opening 12.03.2016 (2:00 PM)
- (k) Time for completion from written order of commencement 04 Months
- (l) Liquidated Damages _____
- (m) Deposit Receipt _____ Date _____ Amount _____
- (n) D.R No, Date & Amount _____
- (o) Tender Issued to (Mr. / M/S) _____



BILL OF QUANTITIES

2
11

Discription and Rate of Items based on Composite Schedule of Rates


NAME OF WORK :- RENOVATION OF MORTUARY AT CIVIL HOPITAL SUKKUR. (INTERNAL ELECTRIFICATION)

(E.I)

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
PART "A" NEW SCHEDULE ITEMS					
1	90	Wiring for light or fan point with 3/029 PVCinsulated wire in 20mm (3/4") channel patti on surface as required (S.No. 129 P-15).	910	per point	81,900
2	20	Wiring for plug point with 3/029 PVC insulated wire in 20mm (3/4") channel patti on surface as required (S.I.No:130 P- No:15)	742	per point	14,840
3	1	Wiring for call bell point with 3/029 PVC insulated wire in 20mm (3/4") channel patti on surface as required. (S.I.No:131 P- No:15)	1590	per point	1,590
4	90	Providing & fixing one way SP 5amp switch flush type (S.I.No:132 P- No:33)	54	P.No	4,860
5	20	Providing & fixing two pin 5amp plug & socket (S.I.No:221 P- No:33)	80	P.No	1,600
6	5	Providing & fixing three pin 10/15amp plug & socket (S.I.No:222 P- No:33)	162	P.No	810
7	50	Providing & fixing Brass Battern holder c(S.I.No:232 P- No:33)	70	P.No	3,500
8	20	Providing & fixing Brass Ceiling fan 56" (good quality) (S.I.No:34)	3185	P.No	63,700
9	400	Providing & laying (MAIN or SUB MAIN) PVC insulated 7/029 copper conductor in 3/4" dia PVC conduit on surface (S.I.No:3 P- No:1)	171	P.Mtr	68,400
10	200	Providing & laying (MAIN or SUB MAIN) PVC insulated 7/044 (6mm ²) copper conductor in 1" dia PVC conduit on surface (S.I.No:5 P- No:1).	305	P.Mtr	61,000
11	130	Providing & laying (MAIN or SUB MAIN) PVC insulated 7/052 (10 mm ²) copper conductor in 1" dia PVC conduit on surface (S.I.No:6 P- No:1).	428	P.Mtr	55,640
12	20	Providing & fixing circuit breaker 6,10,15,20, 30,40,50 & 60A (5S) on prepared board as required (S.I.No:202 P- No:30)	916	P.No	18,320
13	1	Providing & fixing circuit breaker 15,20,30, 40,50,60 & 75A (XS-100NS) on prepared board as required (S.I.No:207)	9261	P.No	9,261
14	1	Providing & fixing DP I/C change over switch 500volts on prepared board	8767	P.No	8,767
TOTAL :-					394,188

PART "B" OLD SCHEDULE ITEMS

1	39	P/F energy sever superior quality including fixing on wall complete.(S.I.No:6 P- No:33)	497.00	Each	19,383
2	15	P/F wall bracket light fancy type superior quality including connection and fixing on wall or ceiling etc complete.(S.I.No:7)	497.00	Each	7,455
3	5	P/F distribution metal board double shutter to accommodate breakers including painting with enamel paint and fixing on surface (S.I.No:18 P- No:13)	907.96	P.Sft	4,540
4	1	P/F earthing set with 2x2x1/4" cooper plate buried in ground less if water comes out from the ground level when rain etc./in/c.making the pit 12" deep by excavation of all type of soil connected with No:8 S W G bare cooper wire run in 1/2" GI pipe the earth plate up to the metallic electric assenary i/c of the Tee.(S.I.No:2 P- No:26)	3610.04	Each	3,610
5	9	P/F Bulb 100 Watts	25.00	Each	225
6	20	P/F mild steel bar fan clamp 15.8 mm (5/8") dia suitable (S.I.No:1 (c) P- No:14)	141.01	Each	2,820
7	1	P/F AC or DC electric bell 200/250 volt 70MVA (S.I.No:23)	150.70	Each	151
8	1	P/F flush-type electric bell bush button (S.I.No:23 P- No:1)	25.19	Each	25
TOTAL :-					38,209



Quantities	Description of item to be executed at site	Rate	Units	Amount
------------	--	------	-------	--------

Amount Total (CSR)

Part "A" % Above / Below _____ Total Amount _____

Part "B" % Above / Below _____ Total Amount _____

Total "A+B" _____


PART "B" NON SCHEDULE ITEMS

1	30	P/F stair step LED light 6" x3" with PVC frame with 3/4" dia pipe & ceiling LED light 12 watts etc complete approved by officer incharge		Each	
1	2	P/F Street / Search Light fitting with energy saver 85 watts etc with glass shade i/c G.I pipe bracket 1-1/4" dia of required length with chain bolts & wiring with connections etc.		Each	
TOTAL :-					

Total (b) in words & figures

CONTRACTOR


Com
 ✓ MEDICAL SUPERINTENDENT
 GMMMC HOSPITAL SUKKUR



BIDDING DATA

3.

- (a) Name of Procuring Agency Medical Superintending Ghulam Mohammad Mahar Medical College Hospital Sukkur.
- (b) Brief Discription of Works Renovation of Internal & External Water Supply / Sanitary Fitting Drainage line of outdoor, inddor & Thalesemia Centre GMMMC Hospital Sukkur. (Civil Work)
- (c) Procuring Agency Address Near Civil Hospital Sukkur
- (d) Estimated Cost 8,000,000
- (e) Amount of Bid Security 400,000
- (f) Period of Bid Validity (Days) 28 Days
- (g) Security Deposit (i/c bid Security) 800,000
- (h) Security to be deducted from bills 5%
- (i) Submission of bids along with time 25.02.2016 up to 1:00 PM
- (j) Time and Date of Bid Opening 12.03.2016 (2:00 PM)
- (k) Time for completion from written order of commencement 04 Months
- (l) Liquidated Demages _____
- (m) Deposit Receipt _____ Date _____ Amount _____
- (n) D.R No, Date & Amount _____
- (o) Tender Issued to (Mr. / M/S) _____



A circular stamp with a signature in the center. The signature appears to be 'Amr' or similar. The stamp is faint and partially obscured by the signature.

BILL OF QUANTITIES

3

Discription and Rate of Items based on Composite Schedule of Rates

NÂME OF WORK :- INTERNAL / EXTERNAL DRAINAGE LINE OF OUTDOOR WITH WATER SUPPLY AND SANITARY FITTING OF THALESEMIA CENTRE.

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
PART "A" SCHEDULE ITEMS					
1	5,248	Dismantling glazed or encaustic tiles etc (C.S.I No:55 P-13).	786.50	%Sft	41,276
2	173	Dismantling cement concrete plain 1:3:6 (C.S.I No. 19 (b) P-10).	1,306.80	%Cft	2,261
3	2,275	Dismantling / Removing road mateling (CSI No. 51 Page No. 13).	605.00	%Sft	13,764
4	4,550	Excavation in foundation of building bridges and other structure including dressing refeling arround structure with excavated earth watering and ramming lead upto one chain and lift upto 5ft (b) in ordinary soil(C.S.I No:18 (b)P.5.	3,176.25	%0Cft	14,452
5	1,138	Cement concrete brick or stone ballast 1 1/2" to 2" guage ratio 1:4:8 (C.S.I No: 4 (b) Page No:15)	9,416.28	%Cft	107,157
6	6,500	Errection and removal of cuttering for R.C.C or plain Cemnet concrete work for partial wood-vertical (C.S.I No. 19 (b) Page No: 18)	3,127.41	%Sft	203,232
7	1,303	Rein forced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid sepreteley this rate also includes all kinds of forms moulds:lifting shuttering curing rending and finishing the exposed surface (including screening and washing of shingle) (a) RC work in slabe bams columns rafts lintels and other structural members laid in situ or pre cost laid in position complete in all respects. (I)Ratio (1:2:4) 90 Lbs cement 2 Cft. sand 4 Cft . shingle 1/8" to 1/4" guage.(C.S.I No:6 A (1) P.17).	337.00	P.Cft	439,111
8	69.804	Fabrication of Tor steel reinforcement for cement concrete including cutting bending and laying in position making joints and fastings including cost of binding wire also includes removal of rust from bars (C.S.I No:8 B P.17).	5,001.70	P.Cwt	349,139
9	294	Pacca brick work in ground floor in cement sand mortor ratio: (C.S.I No: 5 (e) Page No: 21)	12,674.36	%Cft	37,263
10	788	Cement plaster upto 20' height 1/2" thick rario 1:6 (C.S.I No: 13 (b)Page No: 52).	2,206.60	%Sft	17,388
11	788	Cement plaster upto 20' height 3/8" thick rario 1:4 (C.S.I No: 11 (a) Page No: 52).	2,197.52	%Sft	17,316
12	2,611	Cement Concrete plain including placing compacting finishing and curing complete including screening complete and washing of stone agreeegate without shuttring Ratio: 1:2:4. (C.S.I No. 5 (f) Page No:16)	14,429.25	%Cft	376,748
13	5,248	Providing and laying tiles glazed 6" x 6" x 1/4" on floor or wall facing in required colour and apttern of STILE specification jointed in white cement and pigment over a base of 1:2 grey cement mortar 3/4" thick including washing and filling of joints with slaurry of white cement and pigment in desired shape with finishing, clearing and cost of wax polish etc. complete including cutting tiles to proper profile. (C.S.I No:60 P-47) .	30,509.77	%Sft	1,601,153
14	282	Providing and fixing G.I frames /Chowkates 7"2" or 4 1/2" x 3" for door using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ration 1:6 and repairing the jambs. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:29 P.93).	228.90	P.Rft	64,550
15	176	First class deodar wood wrought joinery in doors and windos etcfied inosition i/c in chwoakts holds fasts hings iron tower bolts chowks cleats handles and cards with hooks etc Deodar paneled or paned are fully glazed 1/3/4"only shutter (C.S.I No:7 (b) P.58).	902.93	P.Sft	158,916
16	4,575	Providing and lying 3" thick topping cement concrete 1:2:4. Including surface finishing dividing into panels (C.S.I No:16 (d) P-42).	4,411.82	%Sft	201,841
17	6,300	Providing & fixing cement paving blocks flooring having size of 197 x 97 x 60 (mm) of city / quddra / cobble shape with pigmented, having strength b/w 5000 psi to 8500 psi i/c filling the joints with hill sand and laying in specified manner/ pattern and design etc: complete. (CSI No. 72 Page No. 49).	223.97	P.Sft	1,411,011
TOTAL :-					5,056,625

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
PART "B" SCHEDULE ITEMS					
1	20	Providing & fixing squatting type white glazed of flush cisten with internal fitting & flush pipe with bend and making requisite numbers of holes in wall plinth & floor for pipe connection & making good in cement concrete 1:2:4. W.C not less than 19" clear opening between flushing rims and 3 gallons flushing tank with 4" dia C.I trap with C.I thumb. (S.I No:1 (b) i P-No:1)	4802.60	Each	96,052
2	20	Providing & fixing 24" x 18" lavatory basin in white glazed earthen ware complete with & l/c the cost of W.I or C.I cantilever brackets 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of 1/2" dia rubber plug & chrome plate brass chain 1-1/4" dia malleable iron or c.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection and making good in cement concrete 1: 2: 4 (Standard pattern). (S.I No:8 P-No:3).	4253.70	Each	85,074
3	20	Add: extra labour for providing and fixing of earthen wire pedestal white or colored glass standard pattern (S.I No:9 P-No:3).	938.47	Each	18,769
4	40	P/F in position nylon connections complete with 1/2" dia brass stop cock with pair of brass nuts and lining joints to nylon connection (S.I No:23 P-No:6).	447.15	Each	17,886
5	20	P/F 6" x 4" c.c gully trap with 4" dia out let complete with 4" thick 1:2:4 c.c for bed and 1/2" thick cement plaster 1:3 to the kerb c.I caning 6" x 6" and c.I cover and frame 12" x 12" in side etc complete (S.I No:1(a-i) P-No:21).	1193.17	Each	23,863
6	250	P/F 4" dia C.I soil and vent pipes including cutting and fitting and extra painting to match the colour of the building (S.I No:1 P-No:9).	333.29	P.Rft	83,323
7		RCC pipe with color class "B" and didding the traches to the required depth an fixing in positin l/c cutting fitting and jointing with max phalt composition and cemen mortar 1:1 and testing with water presure to head of 4 Ft aboe the top of the heigh			
	300	4" dia	146.57	P.Rft	43,971
	300	6" dia	199.25	P.Rft	59,775
	500	9" dia	250.00	P.Rft	125,000
8	20	Providing & fixing 6" x 2" or 6" x 3" C.I floor trap of the approved self cleaning design with a C.I screwed down grating with or without a vent arm complete with & l/c making requisite number of holes in walls, plinth & floor for Pipe connections & making good cement concrete 1:2:4. (S.I No. 20 Page No.3).	2042.43	P.Rft	40,849
9		Providing G.I Pipes, specials, and clamps etc, including fixing cutting & fitting complete with and l/c the cost of breaking thorough walls and roof, making good etc. painting two coats after cleaning the Pipe etc. with white zink paint with pigment to match the colour of the building and testing with water to a pressure head of 200 feet and handling. (SI No. 1 Page No.12)			
i	400	1/2" dia	73.21	P.Rft	29,284
ii	250	3/4" dia	95.79	P.Rft	23,948
iii	100	1" dia	128.55	P.Rft	12,855
vi	150	1-1/4" dia	153.19	P.Rft	22,979
10		Add: Extra labor for concealed G.I pipe and Fitting l/c making recess in the wall for pipe and making good in Cement motor etc Complete			
	200	1/2" dia	7.82	P.Rft	1,564
	150	3/4" dia	8.45	P.Rft	1,268
11		Providing and fixing full way gun metal valves with wheels threaded or flanged ends with rubber washing (b) standard pattern (Note standard Manufacture by M/S Anwar Mechanical works (S.I No:4 (b) P-No:17).			
	20	1/2" dia	161.92	Each	3,238
	20	3/4 dia	227.92	Each	4,558
12	20	S/F cancelled stop cock of superior quality with crystal head head 1/2" dia (S.I No:11 (b) P-No:18).	478.28	Each	9,566
13	50	S/F long bib cock of crystal head with c.p head 1/2" dia (S.I No:13 (b) P-No:19).	1109.46	Each	55,473
14	20	S/F wash been mixture of superior quality with c.p head 1/2" dia with crystal head (S.I No:16 (b) P-No:15).	2882.00	Each	57,640

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
15	8	Supplying & fixing Bath room accessories set (7 pieces i/c towel rod, brush holder, soap tray, shelf of approved quality and design etc complete. (SI No: 22 P-No:19)	10322.40	Each	82,579
16		P/F handle valves (China) (S.I No:7 P-No:14).			
ii	20	3/4" dia	271.92	Each	5,438
iii	20	1" dia	365.42	Each	7,308
16	150	Providing & fixing 4" x 4" dia C.I branch of the required degree. with access doors, rubber washer 3/8" thick and bolts and nuts and extra painting to match the colour of the building.	702.00	Each	105,300
17	150	Providing & fixing 4" dia. C.I plain bend of the required degree including extra painting to match the colour of the building.	566.70	Each	85,005
18	150	Supplying & fixing C.P Muslim Showerer with double Bib cock & ring Pipe etc complete.	3432.00	Each	514,800
				TOTAL :-	1,617,365

PART "C" SCHEDULE ITEMS

1		Providing PVC Pipes of class D equalvalent (make) fixing in trench i/c cutting fitting and jointing with "Z" joint with one rubber Ring i/c testing with water to head of 122 meters or 400ft. (S.I.No:3 Page No:23)			
	250	4" dia	137.00	P.Rft	34,250
	250	6" dia	226.00	P.Rft	56,500
	650	10" dia	1375.00	P.Rft	893,750
2	20	Construction of manhole or inspection chamber for the required dia of circular sewer and 3'-6" (1067 mm) depth with walls of BB in cement mortar 1:3 cement plaster 1:3, 1/2" thick inside of walls and 1" (25 mm) thick over benching and channel i/c fixing CI manhole cover with frame of clear opening 1-1/2' x 1., 1/2' (457x457 mm) of 1.75 Cwt. (88.9 Kg) embedded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S steps 6" (150 mm) wide projecting 4" (102 mm) from the face of wall at 12" (305 mm) C.C dully painted etc. complete as per specification and drawing (SI No. P Page No. 46). (PHE)	14748.00	Each	294,960
				TOTAL :-	1,279,460

Amount Total (CSR)

Part "A"	% Above / Below _____	Total Amount _____
Part "B"	% Above / Below _____	Total Amount _____
Part "C"	% Above / Below _____	Total Amount _____
		Total "A+B+C" _____

CONTRACTOR


✓ MEDICAL SUPERINTENDENT
GMMMC HOSPITAL SUKKUR

Om

BIDDING DATA

4

- (a) Name of Procuring Agency Medical Superintending Ghulam Mohammad Mahar Medical College Hospital Sukkur.
- (b) Brief Discription of Works Renovation of Hostel Building No.2 (Civil Work)
- (c) Procuring Agency Address Near Civil Hospital Sukkur
- (d) Estimated Cost 7,000,000
- (e) Amount of Bid Security 350,000
- (f) Period of Bid Validity (Days) 28 Days
- (g) Security Deposit (i/c bid Security) 700,000
- (h) Security to be deducted from bills 5%
- (i) Submission of bids along with time 25.02.2016 up to 1:00 PM
- (j) Time and Date of Bid Opening 12.03.2016 (2:00 PM)
- (k) Time for completion from written order of commencement 04 Months
- (l) Liquidated Demages _____
- (m) Deposit Receipt _____ Date _____ Amount _____
- (n) D.R No, Date & Amount _____
- (o) Tender Issued to (Mr. / M/S) _____



BILL OF QUANTITIES

4
1

Discription and Rate of Items based on Composite Schedule of Rates

NAME OF WORK :- RENOVATION OF HOSTEL BUILDING AT CIVIL HOSPITAL SUKKUR.


Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
PART "A" SCHEDULE ITEMS					
1	800	Dismantling brick work in lime or cement plaster. (C.S.I No:13 P-10).	1,285.63	%Cft	10,285
2	1,749	Dismantling cement concrete plain 1:3:6 (C.S.I No. 19 (b) P-10).	1,306.80	%Cft	22,856
3	8,708	Removing cement or lime plaster (C.S.I No:53 P-13).	121.00	%Sft	10,537
4	1,164	Dismantling glazed or encaustic tiles etc (C.S.I No:55 P-13).	786.50	%Sft	9,155
5	384	Excavation in foundation of building bridges and other structure including dressing refeling arround structure with excavated earth watering and ramming lead upto one chain and lift upto 5ft (b) in ordinary soil(C.S.I No:18 (b)P.5).	3,176.25	%0Cft	1,220
6	48	Cement concrete brick or stone ballast 1 1/2" to 2" guage ratio 1:4:8 (C.S.I No: 4 (b) Page No:15)	9,416.28	%Cft	4,520
7	150	Pacca brick work in foundation and plinth in cement sand mortor ratio 1:6(C.S.I No:4 (e) P.21).	11,948.36	%Cft	17,923
8	129	Rein forced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid sepreately this rate also includes all kinds of forms moulds:lifting shuttering curing rending and finishing the exposed surface (including screening and washing of shingle) (a) RC work in slabe bams columns rafts lintels and other structural members laid in situ or pre cost laid in position complete in all respects. (I)Ratio (1:2:4) 90 Lbs cement 2 Cft. sand 4 Cft. shingle 1/8" to 1/4" guage.(C.S.I No:6 A (1) P.17).	337.00	P.Cft	43,473
9	6.91	Fabrication of Tor steel reinforcement for cement concrete including cutting, bending and laying in position making joints and fastings including cost of binding wire also includes removal of rust from bars (C.S.I No:8 B P.17).	5,001.70	P.Cwt	34,567
8	8,708	Applying & Flooting coat of cement 1/32" thick (C.S.I No:14 P-53).	660.00	%Sft	57,473
9	8,908	Cement plaster upto 20' height 1/2" thick ratio 1:6 (C.S.I No: 13 (b)Page No: 52).	2,206.60	%Sft	196,564
10	8,908	Cement plaster upto 20' height 3/8" thick ratio 1:4 (C.S.I No: 11 (a) Page No: 52).	2,197.52	%Sft	195,755
11	1,749	Cement Concrete plain including placing compacting finishing and curing complete including screening complete and washing of stone agreegate without shuttring Ratio: 1:2:4. (C.S.I No. 5 (f) Page No:16)	14,429.25	%Cft	252,368
12	66	Providing and fixing G.I frames /Chowkates 7"2" or 41/2" x 3" for door using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hols fast filling with cement sand slurry of ration 1:6 and repairing the jams. Cost also i/c all carrage tools and plants used in making and fixing (C.S.I No:29 P.93).	228.90	P.Rft	15,107
13	227	First class deodar. wood wrought joinery in doors and windos etcfied inosition i/c in chwoakts holds fasts-hings iron tower bolts chowks cleats handles and cards with hooks etc Deodar paneled or paned are fully glazed 1/3/4"only shutter (C.S.I No:7 (b) P.58).	902.93	P.Sft	204,965
14	6,325	Laying white marble flooring fine dressed in the surface without winging sate in lie mortor 1:2 including rubbing and polishing of the joints(C.S.I No:28 (a) P-43).	567.48	P.Sft	3,589,311
15	3,006	Providing and fixing 3/8" thick marble tiles of approved quality and coloum shade size 8" x 4/6" x 4" in dado skitring and facing removal / tucking of exiting plaster surface etc over 1/2" thick base of cement mortor 1:3 setting mortor base including filling the joints and washing of tiles wht white cement slurry current finishing cleaning and polishing etc complete (for new work) (C.S.I No: 68 (i) P-49).	186.04	P.Sft	559,236

(Handwritten Signature)

Sl. No.	Quantity	Description of item to be executed at site	Rate	Units	Amount
	1,609	Providing and laying tiles glazed 6" x 6" x 1/4" on floor or wall facing in required colour and pattern of STILE specification jointed in white cement and pigment over a base of 1:2 grey cement mortar 3/4" thick including washing and filling of joints with slurry of white cement and pigment in desired shape with finishing, clearing and cost of wax polish etc. complete including cutting tiles to proper profile. (C.S.I No:60 P-47)	30,509.77	%Sft	490,902
17	7,224	Two coats of bitumen laid hot using 34"Lbs. for 100sft over roof and blinded with sand at 1Sft per 100sft (C.S.I No:13 P.35).	1,887.40	%Sft	136,346
18	2,813	Providing and laying 2" thick topping cement concrete 1:2:4. Including surface finishing dividing into panels(C.S.I No:16 (c) P-42).	3,275.50	%Sft	92,140
19	2,950	Providing & fixing cement paving blocks flooring having size of 197 x 97 x 60 (mm) of city / quddra / cobble shape with pigmented, having strength b/w 5000 psi to 8500 psi i/c filling the joints with hill sand and laying in specified manner/ pattern and design etc. complete. (CSI No. 72 Page No. 49).	223.97	P.Sft	660,712
20	20,499	Scraping ordinary distemper, oil bound distemper or paint on walls (C.S.I No:54 (b) P-13).	226.80	%Sft	46,492
21	531	Galvanized wire gauze fixed to chowkats with 3/4" deodar strips and screws. (C.S.I No. 14 (d) P-60).	190.72	P.Sft	101,272
22	245	First class deodar wood wrought joinery in wire glazed door and windows with 22 S.W.G galvanized wire glazed 144 mesh per square inch iron fitting complete 1 1/2" thick deodar wood framing including wire gauze with ordinary hinges. (C.S.I No:14 (B) P.67).	562.98	P.Sft	137,930
21	6,325	Distemper three coats (C.S.I No:24 (c) P-54).	1,079.65	%Sft	68,288
22	14,178	Preparing the surface & painting with matt finish paint of approved make to old matt finish surface three coat (C.S.I No. 37 (C) P-55).	2,499.76	%Sft	354,416
23	6,320	Preparing the surface and painting with weather coat of approved make to old weather coat surface (CSI No. 39 (c) P. No. 56)	2,118.33	%Sft	133,878
24	2,211	Painting new surface, and painting of doors and windows any type (i/c edges) 3 coats (C.S.I No:4 (c) P-76).	2,116.41	%Sft	46,794
25	481	Painting guard bars, gates iron bars gratings, railings including standard braces (etc.) and similar open work. Old Surface three coats (CSI No. 4 (d-iii) Page No. 69).	977.40	%Sft	4,701
30	45	Rain forcement concrete spout including fixing in position 2 1/2" x 6" x 5" (C.S.I No:14 P.18).	261.25	Each	11,756
TOTAL :-					7,510,941

PART "B" SCHEDULE ITEMS


1	5	Providing & fixing squatting type white glazed of flush cistern with internal fitting & flush pipe with bend and making requisite numbers of holes in wall plinth & floor for pipe connection & making good in cement concrete 1:2:4. W.C not less than 19" clear opening between flushing rims and 3 gallons flushing tank with 4" dia C.I trap with C.I thumble. (S.I No:1 (b) i P-No:1)	4802.60	Each	24,013
2	5	Providing & fixing 24" x 18" lavatory basin in white glazed earthen ware complete with & i/c the cost of W.I or C.I cantilever brackets 6 inches built into wall, painted white in two coat after a primary coat of red lead paint, a pair of 1/2" dia rubber plug & chrome plate brass chain 1-1/4" dia malleable iron or C.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection and making good in cement concrete 1: 2: 4 (Standard pattern). (S.I No:8 P-No:3).	4253.70	Each	21,269
3	5	Add: extra labour for providing and fixing of earthen wire pedestal white or colored glass standard pattern (S.I No:9 P-No:3).	938.47	Each	4,692
4	8	P/F in position nylon connections complete with 1/2" dia brass stop cock with pair of brass nuts and lining joints to nylon connection (S.I No:23 P-No:6).	447.15	Each	3,577
5	5	P/F 6" x 4" c.c gully trap with 4" dia outlet complete with 4" thick 1:2:4 c.c for bed and 1/2" thick cement plaster 1:3 to the kerb. c.i casing 6" x 6" and c.i cover and frame 12" x 12" in side etc complete (S.I No:1(a-i) P-No:21).	1193.17	Each	5,966
6	50	P/F 4" dia C.I soil and vent pipes including cutting and fitting and extra painting to match the colour of the building (S.I No:1 P-No:9).	333.29	P.Rft	16,665



Quantities	Description of item to be executed at site	Rate	Units	Amount
	RCC pipe with collar class "B" and didding the traches to the required depth an fixing in positin l/c cutting fitting and jointing with max phalt composition and centen mortar 1:1 and testing with water presure to head of 4 Ft aboe the top of the heigh			
50	4" dia	146.57	P.Rft	7,329
50	6" dia	199.25	P.Rft	9,963
8	5 Providing & fixing 6" x 2" or 6" x 3" C.I floor trap of the approved self cleaning design with a C.I screwed down gratting with or without a vent arm complete with & l/c making requisite number of hoies in walls, plinth & floor for Pipe connections & making good cement concrete 1:2:4. (S.I No. 20 Page No.3).	2042.43	P.Rft	10,212
9	Providing G.I Pipes, specials, and clamps etc, including fixing cutting & fitting complete with and l/c the cost of breaking thorough walls and roof, making good etc. painting two coats after cleaning the Pipe etc. with white zink paint with pigment to match the colour5 of the building and testing with water to a pressure head of 200 feet and handling. (SI No. 1 Page No.12)			
i	100 1/2" dia	73.21	P.Rft	7,321
ii	100 3/4" dia	95.79	P.Rft	9,579
iii	50 1" dia	128.55	P.Rft	6,428
vi	30 1-1/4" dia	153.19	P.Rft	4,596
10	Add : Extra labor for concealed G.I pipe and Fitting l/c making recess in the wall for pipe and making good in Cement motor etc Complete			
50	1/2" dia	7.82	P.Rft	391
50	3/4" dia	8.45	P.Rft	423
11	Providing and fixing full way gun metal values with wheels threaded or flanged ends with rubber washing (b) standared pattern (Note standared Manufacture by M/S Anwar Mechanical works (S.I No:4 (b) P-No:17).			
5	1/2" dia	161.92	Each	810
5	3/4 dia	227.92	Each	1,140
12	6 S/F cancelled stop cock of superior quality with crystal head head 1/2" dia (S.I No:11 (b) P-No:18).	478.28	Each	2,870
13	5 S/F long bib cock of crystal head with c.p head 1/2" dia (S.I No:13 (b) P-No:19).	1109.46	Each	5,547
14	5 S/F wash been mixture of superior quality with c.p head 1/2" dia with crystal head (S.I No:16 (b) P-No:15).	2882.00	Each	14,410
15	2 Supplying & fixing Bath room accessories set (7 pieces l/c towel rod, brush hloder, soap tray, shelf of approved quality and design etc complete. (Si No: 22 P-No:19)	10322.40	Each	20,645
16	P/F handle values (China) (S.I No:7 P-No:14).			
ii	5 3/4" dia	271.92	Each	1,360
iii	5 1" dia	365.42	Each	1,827
TOTAL :-				181,029

PART "C" SCHEDULE ITEMS

1	Providing PVC Pipes of class D equalvalent (make) fixing in trench l/c cutting fitting and jointing with "Z" joint with one rubber Ring l/c testing with water to head of 122 metere or 400ft. (S.I.No:3 Page No:23)			
40	4" dia.	137.00	P.Rft	5,480
50	6" dia	226.00	P.Rft	11,300
2	2 Constructiong manhole or inspectionchamb er for the required dia of circular sewer, and 3'-6" (1067 mm) dpth with walls of BB in cement motor 1:3 cement plaster 1:3, 1/2' thick inside of walls and 1" (25 mm) thick over benching and channel l/c fixing CI manhole cover with fram of clear opening 1-1/2' x 1., 1/2' (457x457 mm) of 1.75 Cwt. (88.9 Kg) embedded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S steps 6" (150 mm) waide projecting 4" (102 mm) from the face of wall at 12" (305 mm) C.C dully painted etc. complete as per specification and drawing (SI No. P Page No. 46). (PHE)	14748.00	Each	29,496
TOTAL :-				46,276




Quantities	Description of item to be executed at site	Rate	Units	Amount
------------	--	------	-------	--------

Court Total (CSR)

Part "A"	% Above / Below _____	Total Amount	_____
Part "B"	% Above / Below _____	Total Amount	_____
Part "C"	% Above / Below _____	Total Amount	_____
		Total "A+B+C"	_____

CONTRACTOR


 ✓ MEDICAL SUPERINTENDENT
 GMMMC HOSPITAL SUKKUR

