

SCHEDULE B (Civil)

Name Of Work **Construction of 3 Additional Classrooms @ SRSCCJ & High School (Remaining**

Work) Taluka Kotri District Jamshoro

Description	Quantity	Rate	Unit	Amount
01. Pacca brick work in foundation and plinth in cement sand mortar 1:6. (S.I.No. 4(i)/e/P-21)	30.00 Cft	Rs. 11948.36	%Cft	Rs. 3585.00
02. Cement plaster 1:6 upto 20 height (b) 1/2" thick. (S.I.No.13(b)/P-52)	6237.00 Sft	Rs. 2206.60	%Sft	Rs. 137626.00
03. Cement plaster 1:4 upto 20 height (a) 3/8" thick. (S.I.No.11(a)/P-52)	6237.00 Sft	Rs. 2197.52	%Sft	Rs. 137059.00
04. Notice board made with cement. (S.I.No.1/P-95)	120.00 Sft	Rs. 58.11	P.Sft	Rs. 6973.00
05. Laying floor of approved coloured glazed tiles 1/4" thick laid in white cement & pigment over a bed of 3/4" thick cement mortar 1:2. (S.I.No. 25/P-43)	1790.00 Sft	Rs. 27747.06	%Sft	Rs. 496672.00
06. Providing & Laying floor of Verona Marble Tiles 24"x12"x3/4" fine dressed on the surface without winding set in white cement over a base of 1:2 gray cement mortar 3/4" thick including filling of joints with slurry of white cement and pigment in desired shape with finishing, cleaning, curring, cutting tiles to proper profile etc complete.(R.A.A)	60.00 Sft	Rs. 364.95	P.Sft	Rs. 21897.00
07. Applying chemical polishing on existing mosaic or marble flooring / dado including cleaning , grinding with carborandum stone / sand paper and applying chemical polish as per requirement. (S.I.No. 70/P-49)	60.00 Sft	Rs. 36.60	P.Sft	Rs. 2196.00

Total S.I except Steel Work, Marble, G.Tiles, Alcop D&W, F.Door, W.Guaze & P.Block **Rs. 287439.00**

Total Steel Work **Rs. 0.00**

Total Marble, G.Tiles, Alcop D&W, F.Door, W.Guaze & P.Block **Rs. 496672.00**

Total N.S.I **Rs. 21897.00**

Premium _____ % on Total S.I except Steel Work, Marble, G.Tiles, Alcop D&W, F.Door, W.Guaze & P.Block **Rs.**

Premium _____ % on Steel Wo **Rs.**

Premium _____ % on Total Marble, G.Tiles, Alcop D&W, F.Door, W.Guaze & P.Block **Rs.**

Grand Total Part A **Rs.**