

SCHEDULE - B.

Name of Work:- **ADP.122 CONSTRUCTION OF ADDITION CLASS ROOMS IN EXISTING SCHOOL BUILDINGS IN DISTRICT BADIN @ GBPS TANDO GHULAM ALI (2C/R) (EXTERNAL DEVELOPMENT). TALUKA MATLI DISTRICT BADIN.**

S.No.	Description	Qty.	Rate	Unit.	Amount.
-------	-------------	------	------	-------	---------

PART - A CIVIL WORK (i).

- 1 Excavation in foundation of building briges and other structure I/c dagbelling dreesing,refilling around the structure with excavated earth watering and ramming lead upto 5 feet, (b) In ordinary soil. (S.I.No.18.b/P-4).

TOTAL 806.00 3176.25 %Cft Rs. **2560**

(Rs.Three thousand one hundred seventy six & ps twenty five only).

- 2 Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10. (S.I.No:- 4.C/P-15).

TOTAL 98.00 8694.95 %Cft Rs: **8521**

(Rs.Eight thousand six hundred ninety four & ps ninety five only).

- 3 R.C.C. work I/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid sperately. This rate also I/c all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface (I/c screening and washing of shingle)(a) R.C.work in roof slab,beams columns rafts lintels and other structural members laid in situ or precast laid in position complete in all respect(I) Ratio (1:2:4) 90 lbs cement 2 Cft sand 4 Cft shingle 1/8" to 1/4" gauge.(S.I.No.6(a),i/P-16).

TOTAL 438.00 337.00 P/Cft Rs: **147606**

(Rs.Three hundred thirty seven & ps zero only).

- 4 Pacca brick work in foundation & plinth in cement sand martor ratio 1:6 (S.I.No: 4,(I)(e) /P-20.21).

TOTAL 157.00 11948.36 %Cft Rs: **18759**

(Rs.Eleven thousand nine hundred fourty eight & ps thirty six only).

- 5 Filling watering & ramming earth in floors with surplus earth from foundation lead upto one chain and lift upto 5" feet (S.I.No.21/P-4).

TOTAL 269.00 1512.50 %0Cft Rs: **407**

(Rs.One thousand five hundred tweleve & ps fifty only).

- 6 Supplying & filling Sand under floor and plugging in walls.(S.I.No:29/P-26).

TOTAL	259.00	1141.25 %Cft	Rs:	2956
--------------	--------	--------------	-----	-------------

(Rs.One Thousand one hundred fourty one & ps twenty five only)

- 7 Pacca brick work in ground floor in cement sand mortar ratio 1:6.(S.I.No:5(I)(e) /P-21).

TOTAL	114.00	12674.36 % Cft.	Rs:	14449
--------------	--------	-----------------	-----	--------------

(Rs.Twelth thousand six hundred seventy four & ps thirty six only).

TOTAL:-	RS:	195258
----------------	------------	---------------

PART - A CIVIL WORK (ii).

- 1 (a)Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position, making joints and fastening i/c cost of binding wire (also i/c removal of (b) using Tor Bars) (S.I.No:8-(a)+(b)/P-17).

<u>a) Using Tor Bar</u>	TOTAL	19.55	5001.70 P/Cwt	Rs:	97783
--------------------------------	--------------	-------	---------------	-----	--------------

(Rs.Five Thousand one & ps seventy only).

<u>b) Using Mild Steel</u>	TOTAL	3.91	4820.20 P/Cwt	Rs:	18847
-----------------------------------	--------------	------	---------------	-----	--------------

(Rs.Four Thousand eight hundred twenty & ps twenty only).

TOTAL:-	RS:	116630
----------------	------------	---------------