

SCHEDULE "B"

Name of Work:- **ADP-159 Upgradation of Middle Schools to High Schools in Sindh (2008-09)**
(115 Units) @ GGMS Kadhan, Taluka & District Badin (Balance Work)
(Provincial ADP).

S.No.	Description.	Qty.	Rate.	Unit.	Amount.
a) Civil Work (i)					
1	Excavation in foundation of building bridges and other structure I/c dagbelling dressing around the structure with excavated earth watering a dramming lead upto one chain and lift upto 5 feet.	30.0	3176.25	%0Cft	Rs. 95287.50
					(Rs: Three thousand one hundred seventy six & Ps: twenty five only)
2	Cement concrete or stone ballast 1-1/2" to 2" gauge ratio 1:5:10.	517.00	8694.95	%Cft	Rs: 4491189.05
					(Rs: eight thousand six hundred ninety four & Ps: ninety five only)
3	Pacca brick work in foundation & plinth in cement sand	31.00	11948.36	%Cft	Rs: 370403.26
					(Rupees eleven thousand nine hundred forty eight & Ps: thirty six only)
4	Pacca brick work in ground floor I/c striking of joints in cement sand mortar ratio 1:6.	27.0	12674.36	%Cft	Rs: 342687.72
					(Rs: twelve thousand six hundred seventy four & Paisa thirty six only)
5	Pacca brick work in other than building I/c striking of joints in cement sand ratio 1:6.	107.0	12346.65	%Cft	Rs: 1321091.15
					(Rs: twelve thousand three hundred forty six & Ps: sixty five only)
6	Cement plaster 1:4 upto 12 ft height 3/4" thick.	2075.0	3015.76	%Sft	Rs: 6257700.00
					(Rs: three thousand fifteen & Paisa seventy six only)
7	Primary coat of chalk under distemper.	418.0	442.75	%Sft	Rs: 185068.50
					(Rs: four hundred forty two and paisa seventy five only)

S.No.	Description.	Qty	Rate.	Unit.	Amount.
-------	--------------	-----	-------	-------	---------

- 8 Distempering three coats.

418.00 1079.65 %Sft Rs: 451

(Rs: one thousand seventy nine and Ps: sixty five only)

- 9 P/L 3" thick topping cement concrete 1:2:4 I/c surface finishing and dividing into into panells.

3395.00 4411.82 %Sft Rs: 14978

(Rs: four thousand four hundred eleven & Paisa eighty two only)

Total Rs: 15430

PART- B (i)

- 1 Canceled C.P fitting or superior quality for tiles Bath room (a) S.F concealed bib cock of superior quality with C.P head 1/2" dia (S.I.No.13-a/ P-19).

1.00 1109.46 P.No Rs: 1109

(Rs: one thousand one hundred nine & Paisa forty six only)

- 2 P/F handle valves (China) (S.I.No.5-i/P-17).
1/2" dia

1.00 200.42 Each Rs: 200

(Rs: two hundred & Paisa forty two only)

Total Rs: 1309

PART- B (ii) (RCC & G.I Pipes)

- 1 Providing G.I. Pipes specials and clamps etc I/c fixing cutting & fitting I/c cost of breaking through walls and floor making good etc painting two coats after cleaning the pipe etc with white zink paint with pigment to match the colour of the building testing with water to a pressure head of 200 ft: and handling (S.I.No.1-iv/P-14)

20.00 225.73 P.Rft Rs: 451

(Rs: two hundred twenty five & Paisa seventy three only)

Total Rs: 451

S.No.	Description.	Qty.	Rate.	Unit.	Amount.
-------	--------------	------	-------	-------	---------

PART 'D' (PHE Schedule)

- 1 Providing PVC Pipes of Class "D" (equivalent) in trenches I/c cutting fitting and jointing with "2" joints with one rubber ring I/c testing with water to a head of 122 meters or 400 feet (25 mm) 1" dia (S.I.No.3/P-23).

175.00

28.00

P.Rft

Rs:

4900 /-

(Rs: twenty eight only)

Total

Rs:

4900 /-