

SCHEDULE "B"

Name of Work:-

**ADP-170/134 REPAIR & RENOVATION OF LAAR MUSEUM @ BADIN
(BALANCE WORK).**

S.No.	Description.	Qty.	Rate.	Unit.	Amount.
-------	--------------	------	-------	-------	---------

a) Civil Work (i)

- 1 Cement plaster 1:6 upto 12 ft height 1/2" thick.

2860.00 2206.60 % Sft Rs: 63099 /-

(Rs: two thousand two hundred six and paise sixty only)

- 2 Cement plaster 1:4 upto 12 ft height 3/8" thick. (S.I.No.11-a/P-51)

2860.00 2197.52 %Sft Rs: 62849 /-

(Rs: two thousand one hundred ninety seven and paise fifty two only)

- 3 P/F cement paving blocks flooring having size of 197x97x80mm) of city/ quddra / cobble shape with natural colours, having strength b/w 5000 psi to 8500 psi i/c filling the joints with hill sand and laying in specified manner/pattern and desin etc complete (S.I.No.73/P-49)

375.00 223.97 P.Sft Rs: 83989 /-

(Rs: five thousand one & Paise seventy only)

Total Rs: 209997 /-

b) Civil Work (ii) Tiles

- 1 Laying floors of approved coloured glazed tiles 1/4" thick laid in white cement and pigment on a bed of 3/4" thick cement mortar 1:2 complete (S.I.No.25/P-42)

1636.00 2777.06 %Sft Rs: 453941 /-

(Rs: twenty seven thousand seven hundred forty seven & Paise six only)

Total Rs: 453942 /-

c) Civil Work(iii) N.S.I.

- 1 S/F stone tileess 1/2" to 1" thick (12"x6") of GADAP quarry (25%) and (Loralai stone quarry) size 12"x6"x3/4" (75%) colour, shade designing and golas of approved quality and making in required shape fixing in dado skirting and facing scraping and of colour, tucking of existing plaster surface etc over 1/2" thick base of cement mortar 1:3 i/c filling the joints with white cement slurry and washing, rubbing and finishing etc complete in all respects as directed by Engineer Incharge (RA).

1590 252.0 P.Sft Rs: 400680 /-

(Rupees two hundred fifty two only)

Total Rs: 400680 /-