



OFFICE OF THE DISTRICT MUNICIPAL CORPORATION, MALIR KARACHI.

No.DMC Malir / B.Q.Zone/S.E/ 08 / 16

(Bin Qasim Zone)

Dated: 25/4 /2016.

TENDER NOTICE

The Tender is sealed covers are invited for the following work under SPPRA Rules-2010 from the firms having adequate experience in the relevant field. The tentative cost of work is under Rs: 1.00 Million

S.No.	Name of Work	Amount	Earnest Money	Time Allowed	Tender Fee Non Refundable
1.	CLEANING AND DE-SILTING OF SEWERAGE LINE AT RAZZAKABAD & VARIOUS PLACES OF UC-LANDHI BIN QASIM ZONE DMC MALIR	999400	20000	03 Month	1000

Tender Processing Schedule shall be as follows:-

1-Receiving of Applications & Issuance of Tenders	02-05-2016 To 16-05-2016 (DURING OFFICE HOURS)	Superintending Engineer, DMC Malir, Karachi
2-Dropping of Tenders	17-05-2016 12.00 PM	In the office of the Superintending Engineer, DMC Malir, Karachi
3-Opening of Tenders	17-05-2016 1.00 PM	Tender opening Committee in the office of Superintending Engineer, DMC Malir, Karachi

Terms & Conditions:

- The Tender Document will be issued to the Contractors on the submission of written request on their letterhead and on payment of non-refundable cost of tender price through pay order from any scheduled bank in favors of District Municipal Corporation, Malir Karachi as mentioned above each work.
- In case of any reason beyond our control, if the tenders are not responded on the above date, the next date of submission & opening of Tenders will be 02-06-2016 at 01:00 PM and the tender documents will be available for sale from 18-05-2016 To 01-06-2016
- In case the date of opening is declared as a public holiday by the government, the next official working day shall be deemed to the date for submission and opening of tenders of the same time as mentioned.
- Registration with income tax Department (NTN Copy) and Sindh Revenue Board.
- Documentary of work equivalent cost or above executed in last 3 years & Certificate of satisfactory completion showing date of start & completion from employer.
- List of machinery & equipment available with documentary proof of its ownership
- 2% of specified amount against each work in shape of Pay Order/Bank draft in favor of District Municipal Corporation, Malir Karachi shall be attached with the tender documents.
- Tenders in unsealed covers / without 2% Earnest Money will not be entertained and discarded.
- The single envelop procedure adopted for tender work as per S.P.P.R.A Rules-2010.
- The total bid amount as well as the rates of items must be filled both in figure and words and incase any correction is made by the contractor himself then each correction must be initiated by the contractor otherwise the tenders are liable to be summarily rejected.
- If any fake documents are found then the tender is liable to be rejected-cancelled without any compensation but penalty as per rules.
- Tenders can be seen/download on Authority's web sites S.P.P.R.A www.sppra.sindh.gov.pk.
- The procuring agency may reject all or any bid subject to the relevant provision of S.P.P.R.A Rules-2010.

SUPERINTENDING ENGINEER
DISTRICT MUNICIPAL CORPORATION
MALIR KARACHI

DIRECTOR (CB) S.P.P.R.A, GOS.

With a request to upload on the website of S.P.P.R.A (Authority) .A Soft copy (CD) is also enclosed.
Copy to:

- The Administrator, DMC Malir Karachi
- The Municipal Commissioner, DMC Malir Karachi.
- The Executive Engineer (B&R), Bin Qasim Zone DMC Malir Karachi.
- The Accounts Officer DMC Malir Karachi.
- P.S. to Managing Director, S.P.P.R.A

SUPERINTENDING ENGINEER
DISTRICT MUNICIPAL CORPORATION
MALIR, KARACHI

NO: 1383
DATED: 29-04-16

NAME OF WORK: - CLEANING AND DE-SILTING OF SEWERAGE LINE AT RAZZAKAAD & VARIOUS PLACES OF UC-LANDHII BIN QASIM ZONE DMC MALIR.

BILL OF QUANTITIES

(A) Description and rate of Items based on Composite Schedule of Rates.

S#	Quantities	Description of item to be executed at site	Rate	Unit	Amount in Rupees
1.	2.	3.	4.	5.	6.
1.	6998.0Rft	Cleaning inside sewerage lines completely restoring original silt free space/diameter of pipe line by labor and equipment (Mechanically/electrically driven). Including accessories like pulleys steel rope, bucket and draggers sizing from 6" to 18" dia their "to and fro" pulling action (No of pass shall be as many as required) would be taken in two phase (First stream) bringing down peak hours sewerage to flow inside pipe line (as free flow) and in second phase from upstream to downstream of entire length ensuring no silt is observed in bucket (6" dia to 18" dia) except only sewage water and finally passing a steel ball of dia 12" lesser than the diameter of pipe but not exceeding 48" dia ball even for larger dia pipe to ensure perfect cleaning. The job includes all the hire/cost of equipment and accessories of above winching machine / devices along with engines with winching drum set having steel rope pulley mounted over it, steel bucket from 6" to 18" dia hooks and other protection like safety barriers, traffic signs, traffic cones ensuring no damage to pipe along with ensuring safety to labor and other public property/lives and removal of silt/solid during desilting and clearance of site etc complete as per full satisfaction of site engineer. 12" Dia	Rs:80.50	P.Rft	Rs:563339.00
2.	250 Nos	Cleaning / De-silting of manhole or inspection chamber i/c cleaning and Roding of connected sewers (Average 50' per manhole removing sewerage and solid wastes and throwing out side KMC limits	Rs:474.83	Each	Rs:118708.00
3.	35 Nos	Manufacturing and supplying R.C.C Ring slab 21" dia out side 7.5" width and 6" thick i/c 3/8" dia to steel bar to concentric ring with 3/8" dia 8 Nos cross link bars 1/c curing staking and transportation within 10 Miles etc complete. (W S Schedule P-27 It-2)	Rs.1906.60	Each.	Rs:66731.00

4.		Manufacturing and supplying R.C.C manhole covers cast in 1:2:4 concrete ratio 3" deep at center to center reinforcement with 3/8" dia for steel bars at 4" center to center welded to 1/8" thick 2.5" deep M.S Plate 1/c curing staking and transportation with in 10 Miles etc complete.(W S Schedule P-27 It-1) 21" dia			
	92 Nos		92 Nos	Rs.913.63	Each Rs:84054.00

Amount Total (a) Rs:8,32,832.00

_____ %Above/Below On The Schedule Rates of CSR.

Amount to be Added/Deducted on the basis of premium quoted Total (b)

Total (A) = a + b in words & Figures:

Contractor

Executive Engineer / Procuring Agency

Summary of Bill of Quantities

Cost of Bid

Amount _____

1 (A) Cost based on composite Schedule of Rate

2 (B) Cost of based on Non / Offered Schedule of Rates.

TOTAL COST OF BID (C) = TOTAL (A) + Total (B)

Contractor

Executive Engineer / Procuring Agency