

M & R to Secretary Bungalow No. 3 at GOR-I Bath Island Karachi
(Water Proofing, Kitchen, Electric Work etc.)

SCHEDULE - B

S.No	Description	Unit	Quantity	Rate	Amount
SCHEDULE ITEM					
1	First class deodar wood wrought, joinery in doors and windows etc., fixed in position including chowkats hold fasts hinges, iron tower bolts, chocks cleats, handles and cords with hooks, etc. Deodar paneled or paneled and glazed, or fully glazed. (b) 1-3/4" thick. (S.I-7(b)/58)(1273.76(-)370.83=902.93 (Only Shutter)	Sft	88.86	902.93	80,233/-
2	First class deodar wood wrought, joinery work in wire gauze door and windows with 22 SWG. Galvanized wire gauze 144 mesh per square inch iron fitting complete. (b) 1-1/2" thick deodar wood framing including wire gauze with ordinary hinges. (S.I-14(b)/59)	Sft	58.50	562.98	32,934/-
3	Providing and fixing deodar wooden wardrobe including boxing with back shelves shutters drawers and brass fitting such as handles locking arrangement, hanger rod shoe rod and mirror measuring 2' x 1' complete as per approved design. (S.I-24/61)	Sft	225.72	2364.63	533,744/-
4	Supplying & fixing fiber glass tank of approved quality and design and wall thickness as specified i/c. cost of nutes bolts and fixing in plateform of cement concrete 1:3:6 and making connections for inlet & outlet & over flow pipes etc. complete. (d) 1000 gallons wall thickness 5.0mm (S.I-III3(d)/21)	Each	1.00	58962.94	58,963/-
TOTAL					705,874/-
Less: % Below on Item No. 1					
Add: % above on Item No. 4					
TOTAL OF SCHEDULE ITEM					
NON-SCHEDULE ITEM					
1	S/F Mono Block Pressure Pump 1 HP Single Phase 2850 RPM 1" x 1" suction delivery approved make quality as directed by the Engineer Incharge etc. complete.	Each	1.00		
2	Providing and fixing Donkey pump with Motor 2HP approved quality i/c. cartage the rate i/c. of material labour etc. complete.	Each	1.00		
3	Providing and fixing uPVC Pipe 3/4" dia including cutting making and jointing with switch pest with special approved quality including all cost of labour as directed by the Engineer Incharge etc. complete.	Each	325.00		
TOTAL OF NON-SCHEDULE ITEM					
GRAND TOTAL					

TERMS AND CONDITION

- Any typographical errors in the schedule B are subject to the correction with reference to the Schedule of rate General 2012 enforced from 12-07-2012 as approved by the SRC, Sindh Karachi.
- No. premium shall be paid on a Non Schedule Items.
- 100% well Graded crushed Bajri shall be used in items of work without any extra payment.
- No any items of excavated then the Quality Provided in the Schedule B without Prior of the Executive Engineer.
- All sample of items should be got approved by the Executive Engineer.

(CONTRACTOR)


(ASSISTANT ENGINEER)
Provincial Buildings Sub-Division-I
Karachi