

**NAME OF
WORK:-**

**CONSTRUCTION OF SURFACE DRAINS , CC BLOCK & PAVERS
BLOCK AT VARIOUS STREETS OF WARD NO: 13 M. C KHARIPUR**

BILL OF QUANTITIES

Description and Rates of Items based of Composite Schedule of Rates

Part- I Surface Drains

S.#	Quantity	Description of item to be executed as site	Rate	Unit	Amount
1	30.97	Dismantling cement concrete plain R- 1:2:4 (CSI No. 19 (c) P-10)	3327.50	P%Cft	1,031
2	73.80	Dismantling & removing road mantalling (CSI No. 16 P-10)	605.00	P%Cft	446
3	675.00	Dismantling brick work in lime or cement mortor (CSI No. 13 P-10)	1285.63	P%Cft	8,678
4	1575.00	Earth work in ashes sand soil silt clearence under lead up to 50 ' ft (CSI No: 1 (a) P- 1	1134.38	P%0cft	1,787
5	8440.00	Excavation in foundation of building bridges soft soil refelling around the structure with excavated earth watering ramming lead upto one chain and lift upto 5ft: in ordinary soil.	3176.25	P%0cft	26,808
6		Cement concrete plain including placing compacting finishing and curing complete including screening and washing stone aggregate without shuttering. (CSI No. 4 P-14)			
	1810.00	a) Ratio 1:4:8	11288.75	P%Cft	204,326
	50.00	b) Ratio 1:2:4	14429.25	P%Cft	7,215
7	4800.00	Pacca brick work in foundation and plinth in cement sand mortar Ratio: 1:6 (CSI No. 4 (c) P-19) Ratio 1:6	11948.36	P%Cft	573,521
8		Construction of standard of open drains cunette block of cement concrete in situ to the design profile i/c cost of mould as per drawing i/c appling floating coat of cement 1/32" inch thick to exposed face finished smooth curing etc complete. (As per detail drawing). (PHSI No: 1 P-58)			
	2000.00	a) T-I	94.00	P.rft	188,000
	800.00	b) T-II	174.00	P.rft	139,200