

2	1820.00	Cement concrete plain including placing compacting finishing and curing complete including screening and washing stone aggregate without shuttering. (CSI No. 4 P-14) Ratio 1:2:4	14429.25	P%Cft	262,612
3	4950.40	Crushed fire briks grated as sand (Sch of Gen Mat: item No: 51 P-3)	2500	P%Cft	123,760
4	29120.00	Providing & fixing cement paving blocks flowing having size of 197x97x60 mm of ceiling quantity cable shape with pigmnet having strength B/w 5000 Psi to 8500 Psi including filling the joints with Hill Sand & laying specified manner / pattern and design etc complete (CSI No: 71 P-48)	199.77	P.sft	5,817,302
TOTAL					6,340,625

ABSTRACT

Part- I Surface Drains	Rs 1,374,742 /-
Part- II CC Block	Rs 248,933 /-
Part- III Pavers Block	Rs 6,340,625 /-
Total Rs	7,964,299 /-


_____ % Above / Below on the rates of CSR Rs _____
Amount to be Added / Deducted on the Total

Total Amount in words _____

CERTIFICATE

- 1 Any error or omission in the description of items of works rates original schedule will be coorect , Accordingly in the insturction of the Administrator /CMO . Municipal Committee Khairpur
- 2 No premium will be allowed on non schedule items
- 3 The work to be carried out as per PWD / PHE specfication approval rates working estimates

CONTRACTOR


MUNICIPAL ENGINEER
Municipal Committee
KHAIRPUR