

	16250.000	Cement plaster (1:4) upto 20' height 1/2" thick (CSI No. 11 (b) P-51)	2283.93	P% <sup>s</sup> ft	371,139
12		Providing R.C.C Pipe & collars of Class "A" and fitting in trench i/c cutting fitting & jointing with maxphalt composition & cement mortar (1:1) i/c testing with water to a head of 4.5 meter or 15ft: (PHSI No.1 P-17)			
	50.00	a) 6&9" dia	142.00	P.rft	7,100
	30.00	b) 4" dia	113.00	P.rft	3,390
13	2282.77	Extra for every 50ft additional lead part thereof (a) For earth work ( Soft , hard and very hard) ( CSI No: 7 P-2)	5039.00	P%0cft	11,503
14	4380.00	Supplying and filling sand under floor and plugging in wells ( CSI No: 29 P-26)	1141.25	P% <sup>c</sup> ft	49,987
			<b>TOTAL</b>		<b>3,568,933</b>

### ABSTRACT

1 Surface Drains Rs 3,568,933 /-

% Above / Below on the rates of CSR \_\_\_\_\_ /-

Amount to be Added / Deducted on  
the Total

**TOTAL** /-

Total Amount in words \_\_\_\_\_

### CERTIFICATE

- Any error or omission in the description of items of works rates original schedule will be correct ,  
Accordingly in the insturction of the Administrator /CMO . Municipal Committee Khairpur
- No premium will be allowed on non schedule items
- The work to be carried out as per PWD / PHE specfication approval rates working estimates

**CONTRACTOR**

**MUNICIPAL ENGINEER**  
Municipal Committee  
KHAIRPUR