

|              |           |  |         |        |                  |
|--------------|-----------|--|---------|--------|------------------|
|              | 18805.000 | Cement plaster (1:4) upto 20' height 1/2" thick<br>(CSI No. 11 (b) P-51)   | 2283.93 | P%sf   | 429,493          |
| 12           |           | Providing R.C.C Pipe & collars of Class "A" and<br>fitting in trench i/c cutting fitting & jointing with<br>maxphalt composition & cement mortar (1:1) i/c<br>testing with water to a head of 4.5 meter or 15ft:<br>(PHSI No.1 P-17) |         |        |                  |
|              | 50.00     | a) 6&9" dia  | 142.00  | P.rft  | 7,100            |
|              | 30.00     | b) 4" dia  | 113.00  | P.rft  | 3,390            |
| 13           | 2282.77   | Extra for every 50ft additional lead part<br>thereof (a) For earth work ( Soft , hard and very<br>hard) ( CSI No: 7 P-2)   | 5039.00 | P%0cft | 11,503           |
| 14           | 4380.00   | Supplying and filling sand under floor and<br>plugging in wells ( CSI No: 29 P-26)   | 1141.25 | P%cft  | 49,987           |
| <b>TOTAL</b> |           |  |         |        | <b>3,577,143</b> |

### ABSTRACT

1 Surface Drains Rs 3,577,143 /-

\_\_\_\_\_ % Above / Below on the rates of CSR \_\_\_\_\_ /-  
Amount to be Added / Deducted on  
the Total


**TOTAL** /-

Total Amount in words \_\_\_\_\_

### CERTIFICATE

- 1 Any error or omission in the description of items of works rates original schedule will be correct ,  
Accordingly in the insturction of the Administrator /CMO . Municipal Committee Khairpur
- 2 No premium will be allowed on non schedule items
- 3 The work to be carried out as per PWD / PHE specfication approval rates working estimates

**CONTRACTOR**

  
**MUNICIPAL ENGINEER**  
Municipal Committee  
KHAIRPUR