

	21280.000	Cement plaster (1:4) upto 20' height 1/2" thick (CSI No. 11 (b) P-51)	2283.93	P%sf	486,020
12		Providing R.C.C Pipe & collars of Class "A" and fitting in trench i/c cutting fitting & jointing with maxphalt composition & cement mortar (1:1) i/c testing with water to a head of 4.5 meter or 15ft: (PHSI No.1 P-17)			
	50.00	a) 6&9" dia	142.00	P.rft	7,100
	30.00	b) 4" dia	113.00	P.rft	3,390
13	2282.77	Extra for every 50ft additional lead lead part thereof (a) For earth work (Soft , hard and very hard) (CSI No: 7 P-2)	5039.00	P%0cft	11,503
14	4380.00	Supplying and filling sand under floor and plugging in wells (CSI No: 29 P-26)	1141.25	P%cft	49,987
TOTAL					4,283,061

CERTIFICATE

- 1 Any error or omission in the description of items of works rates original schedule will be correct ,
Accordingly in the insturction of the Administrator /CMO . Municipal Committee Khairpur
- 2 No premium will be allowed on non schedule items
- 3 The work to be carried out as per PWD / PHE specfication approval rates working estimates

ABSTRACT


1 Surface Drains Rs 4,283,061 /-

_____ % Above / Below on the rates of CSR _____ - /-
Amount to be Added / Deducted on
the Total

TOTAL /-

Total Amount in words _____

CONTRACTOR


MUNICIPAL ENGINEER
Municipal Committee
KHAIRPUR