

	17625.000	Cement plaster (1:4) upto 20' height 1/2" thick (CSI No. 11 (b) P-51)	2283.93	P% ^{sft}	402,543
2		Providing R.C.C Pipe & collars of Class "A" and fitting in trench i/c cutting fitting & jointing with maxphalt composition & cement mortar (1:1) i/c testing with water to a head of 4.5 meter or 15ft: (PHSI No.1 P-17)			
	50.00	a) 6&9" dia	142.00	P.rft	7,100
	30.00	b) 4" dia	113.00	P.rft	3,390
13	2282.77	Extra for every 50ft additional lead part thereof (a) For earth work (Soft , hard and very hard) (CSI No: 7 P-2)	5039.00	P%0cft	11,503
14	4380.00	Supplying and filling sand under floor and plugging in wells (CSI No: 29 P-26)	1141.25	P% ^{cft}	49,987
			TOTAL		3,586,267

ABSTRACT

1 Surface Drains Rs 3,586,267 /-

% Above / Below on the rates of CSR - /-

Amount to be Added / Deducted on the Total


TOTAL /-

Total Amount in words

CERTIFICATE

- Any error or omission in the description of items of works rates original schedule will be correct, Accordingly in the insturction of the Administrator /CMO . Municipal Committee Khairpur
- No premium will be allowed on non schedule items
- The work to be carried out as per PWD / PHE specification approval rates working estimates

CONTRACTOR


MUNICIPAL ENGINEER
Municipal Committee
KHAIRPUR