

| | | | | | |
|--------------|-----------|--|---------|--------------------|------------------|
| 11 | 16325.000 | Cement plaster (1:4) upto 20' height 1/2" thick (CSI No. 11 (b) P-51) | 2283.93 | P% ^{sft} | 372,852 |
| 12 | | Providing R.C.C Pipe & collars of Class "A" and fitting in trench i/c cutting fitting & jointing with maxphalt composition & cement mortar (1:1) i/c testing with water to a head of 4.5 meter or 15ft: (PHSI No.1 P-17) | | | |
| | 50.00 | a) 6&9" dia | 142.00 | P.rft | 7,100 |
| | 30.00 | b) 4" dia | 113.00 | P.rft | 3,390 |
| 13 | 2282.77 | Extra for every 50ft additional lead lead part thereof (a) For earth work (Soft , hard and very hard) (CSI No: 7 P-2) | 5039.00 | P% ^{0cft} | 11,503 |
| 14 | 4380.00 | Supplying and filling sand under floor and plugging in wells (CSI No: 29 P-26) | 1141.25 | P% ^{cft} | 49,987 |
| TOTAL | | | | | 3,563,847 |

ABSTRACT

1 Surface Drains Rs 3,563,847 /-

_____ % Above / Below on the rates of CSR _____ /-

Amount to be Added / Deducted on
the Total


TOTAL /-

Total Amount in words _____

CERTIFICATE

- 1 Any error or omission in the description of items of works rates original schedule will be correct, Accordingly in the instruction of the Administrator /CMO . Municipal Committee Khairpur
- 2 No premium will be allowed on non schedule items
- 3 The work to be carried out as per PWD / PHE specification approval rates working estimates

CONTRACTOR


MUNICIPAL ENGINEER
Municipal Committee
KHAIRPUR