



OFFICE OF THE
SENIOR SUPERINTENDENT OF POLICE
SHIKARPUR

NO. EO / BLDG:/ / 2016,
DATED 30th May-2016.

ORDER.


TENDER COMMITTEE.

In pursuance of worthy Inspector General of Police, Sindh Karachi, vide his letter No:B-II/-421 dated 15-01-2016, a tender committee consisting of following Officers of this office, is hereby constituted for examining/floating the tenders for Repair / Renovation of Police Stations Chak, Khanpur & Police Headquarter Shikarpur scheduled to be held within a week, in presence of contractors, who are offered the tenders for the work.

2/- The committee is authorized to accept/reject the tenders.


3/- The Decision of the committee is final to assign the work.

- | | | |
|----|---|---------|
| 1. | Mr. Ali Bux Dhakan, DSP/SDPO Madeji Shikarpur | Member |
| 2. | SIP Aamir Hayat, SHO PS Chak | Member. |
| 3. | SIP Imam Bux Lashari, SHO PS Stuart Ganj | Member. |


(NASIR AFTAB), PPM, PSP
CHAIRMAN
SENIOR SUPERINTENDENT OF POLICE,
SHIKARPUR.

C.C to the :-

1. The Inspector General of Police, Sindh Karachi (Attention: DIGP/Finance) w/r to his office order No: quoted above.
2. The Deputy Inspector General of Police, Larkana Range.
3. DSP/SDPO Madeji, SHO PSs Chak & Stuart Ganj.


(NASIR AFTAB), PPM, PSP
CHAIRMAN
SENIOR SUPERINTENDENT OF POLICE,
SHIKARPUR.



OFFICE OF THE
SENIOR SUPERINTENDENT OF POLICE
SHIKARPUR.

Dated: / / 2016

TENDER NOTICE.

The Police Department Government of Sindh invited sealed Tender from Eligible Bidder / Firms registered with Pakistan Engineering Council, sales Tax, and Income Tax Department & Sindh Revenue Board for the Repair Renovation of Police Line Shikarpur, PS Chak, & Police Station Khanpur District Shikarpur.

S.No	Repair / Renovation Work.	Bid Security	Estimated Cost in Rs.	Tender Fee	Completion work.
1.	Repair Renovation of Police Line Shikarpur	2%	990,000/-	Rs. 1000/-	30 Days.
2.	Repair Renovation of Police PS. Chak District Shikarpur	2%	750,000/-	Rs. 1000/-	30 Days.
3.	Repair Renovation of Police Station Khanpur District Shikarpur	2%	750,000/-	Rs. 1000/-	30 Days.

2/- Complete Details are available in the tender documents, which can be purchased from the office of the Senior Superintendent of Police, Shikarpur from 31/05/2016 till 16/06/2016, during office hours by the submitting an application on their letter head along with tender fees (non refundable) and can also be downloaded from the Sindh Police website (www.sindhpolice.gov.pk) or SPPRA website (www.spprasindh.gov.pk).

3/- Single Stage One Envelope procedure will be followed. Bids in sealed envelopes should be submitted & dropped in the tender box kept in **Office of Senior Superintendent of Police, Shikarpur** from 31/05/2016 till 16/06/2016, 1300 hrs. The Bid shall be opened on the same day (16/06/2016) at 1400 hrs and at the same venue in the presence of Bidding Committee and intending bidders who choose to be present on the occasion.

4/- Bid Security 2% of the total bid in the form of Pay Order in the favour of the **Office of Senior Superintendent of Police, Shikarpur** should be submitted with Bids.

5/- Only bids offered on the prescribed tender form issued by the Police Department shall be accepted. However, additional sheet may be attached, if required.

6/- Conditional tender / application will not be entertained.

7/- The procuring Agency may reject any or all bids or postpone date as per relevant provision of SPPRA Rule, 2010.


(NASIR AFTAB), PPM, PSP
SENIOR SUPERINTENDENT OF POLICE
SHIKARPUR



OFFICE OF THE
SENIOR SUPERINTENDENT OF POLICE
SHIKARPUR.

Dated: / / 2016


ANNUAL PROCUREMENT PLAN REPAIR OF BUILDING FINANCIAL YEAR 2015-16.

S.NO	Description of Procurement	Quantity (where Applicable)	Estimates Total Cost	Fund Allocated	Source of funds (ADP/Nor ADP)	Proposed Procurement Method	Time of Procurements				Remarks
							1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
1	Repair Renovation of Police Line Shikarpur		990,000/-	990,000/-	Not Applicable				4th		
1	Repair Renovation of Police Dispensary Shikarpur		750,000/-	750,000/-	Not Applicable				4th		
1	Repair Renovation of Police Station Chak District Shikarpur		750,000/-	750,000/-	Not Applicable				4th		


(NASIR AFTAB), PPM, PSP
SENIOR SUPERINTENDENT OF POLICE
SHIKARPUR

**COST ESTIMATE & MEASUREMENT FOR REPAIR WORK OF
POLICE STATION CHAK, DISTT: SHIKARPUR.**

S/NO	DETAIL OF REQUIRED REPAIR/ ADDITION	DIMENSIONS	TOTAL COST ESTIMATE	Measurement
01	<u>REPAIR OF SHO & WHC ROOM.</u>	450ft x 25ft = 1250 sq	275,000/-	1. Dimensionally cement, cemented plain 1:2:4 (SI No19(c) P-II Roof floor = 1 x 450x 125 x 0.25 = 1000 of 1000 ft @ Rs: 1562/20%. 2. Cement brick or other 1 -1/2 to 2" gauge rate 1:4:8(SNO.4 P-17) Roof floor cement 1 x 450x 125 x 0.25 = 1000 of 1000 ft @ Rs: 3584/10%. 3. P/laying 1" tapping c.c (1:2:4) i/c surface finishing and dividing into parallel (SNo. 16(C) P-47. Barrack 1x160x25=1250 ft. 4000 ft @Rs: 1820/23%. 4. Add 50% of cost of cartage of material L.S 10% of the total. Add cost of diff: of cement @ Rs: 175/- per bag on 272 bags. For 1250 ft total Rs: 45000/- Total amount of per sq ft 45000.00 / 1250.
2	<u>PLASTER OF ROOM</u>	17.6 ft x11.5 ft 08 wall	164,560/-	1. Cement Plaster 1:4 upto 20' height ¾ meter (SNO:11 CC P-58) Portion walls 1x2x8x17.50x11.0=3080 ft @Rs: 3080 ft 729/96% ft. Add 20% above premium Add 10% cartage on Rs: 49852/- L.S. Add diff: affort of cement @ Rs: 175/- per bag on 60 bags. Add diff: cartage bricks @ Rs: 1000/- <u>COST PER UNIT.</u> =138000/570=145/61. <u>MATERIAL STATEMENT.</u> 3. Pacca Brick 1:4 570 qty, 25 cement bags, 146 H/sand 7695 bricks. 4. C.Plaster 1:4, 3080qty 35 cement bags 154 H/sand.
3	<u>DISTEMBER AND WHITE WASH.</u>	160 ft x 25 ft x 11-6 ft (two stories + both interior & exterior)	135,000/-	Distemper 2 codes (SNo:24 P-60). I/S barracks 2x2x2(160+25) 11.50 Of code barrack 2x2x2(160+25)11.50 33040 ft 204/22 % ft. Add 20% above premium Add 10% cartage Cost per unit 135,000/-
04	<u>REPAIR OF WOODEN DOOR & WINDOWS +OIL PAINT</u>	Doors & Windows (4ft x 2.5ft Each)	44780/-	1. Repair of Doors 06 jabs Rs: 1500/- each. 2. Painting old surface painting doors and windows and 2 codes (SNo:4 P-76) 1x2x16x10x7=2240 ft @ Rs: 550/36 per sq ft. Add 20% premium Item No:2. Add 10% cartage L.S.
05	<u>RENOVATION OF ELECTRICITY SYSTEM.</u>	Over all new wiring Boards and Switches etc.	130,720/-	Overall new wiring installation of new board and switches.


 ASSISTANT ENGINEER
 POLICE & PRISON WORKS
 SHIKARPUR


**COST ESTIMATE & MEASUREMENT FOR REPAIR WORK OF
POLICE STATION CHAK, DISTT: SHIKARPUR.**

S/NO	DETAIL OF REQUIRED REPAIR/ ADDITION	DIMENSIONS	TOTAL COST ESTIMATE	Measurement
01	<u>REPAIR OF SHO & WHC ROOM.</u>	450ft x 25ft = 1250 sq	275,000/-	1. Dimensionally cement, cemented plain 1:2:4 (SI No19(c) P-II Roof floor = 1 x 450x 125 x 0.25 = 1000 of 1000 ft @ Rs: 1562/20%. 2. Cement brick or other 1 -1/2 to 2" gauge rate 1:4:8(SNO:4 P-17) Roof floor cement 1 x 450x 125 x 0.25 = 1000 of 1000 ft @ Rs: 3584/10%. 3. P/laying 1" tapping c.c (1:2:4) i/c surface finishing and dividing into parallel (SNo: 16(C) P-47, Barrack 1x160x25=1250 ft. 4000 ft @Rs: 1820/23%. 4. Add 50% of cost of cartage of material L.S 10% of the total. Add cost of diff: of cement @ Rs: 175/- per bag on 272 bags. For 1250 ft total Rs: 45000/- Total amount of per sq ft 45000.00 / 1250.
2	<u>PLASTER OF ROOM</u>	17.6 ft x11.5 ft 08 wall	164,560/-	1. Cement Plaster 1:4 upto 20' height ¾ meter. (SNO:11 CC P-58) Portion walls 1x2x8x17.50x11.0=3080 ft @Rs: 3080 ft 729/96% ft. Add 20% above premium. Add 10% cartage on Rs: 49852/- L.S. Add diff: affort of cement @ Rs: 175/- per bag on 60 bags. Add diff: cartage bricks @ Rs: 1000/- <u>COST PER UNIT.</u> =138000/570=145/61. <u>MATERIAL STATEMENT.</u> 3. Pacca Brick 1:4 570 qty, 25 cement bags, 146 ll/sand 7695 bricks. 4. C.Plaster 1:4, 3080qty 35 cement bags 154 ll/sand.
3	<u>DISTEMBER AND WHITE WASH.</u>	160 ft x 25 ft x 11-6 ft (two stories + both interior & exterior)	135,000/-	Distemper 2 codes (SNo:24 P-60). 1/S barracks 2x2x2(160+25) 11.50 Of code barrack 2x2x2(160+25)11.50 33040 ft 204/22 % ft. Add 20% above premium Add 10% cartage Cost per unit 135,000/-
04	<u>REPAIR OF WOODEN DOOR & WINDOWS +OIL PAINT</u>	Doors & Windows (4ft x 2.5ft Each)	44780/-	1. Repair of Doors 06 jabs Rs: 1500/- each. 2. Painting old surface painting doors and windows and 2 codes (SNo:4 P-76) 1x2x16x10x7=2240 ft @ Rs: 550/36 per sq ft. Add 20% premium Item No:2. Add 10% cartage L.S.
05	<u>RENOVATION OF ELECTRICITY SYSTEM.</u>	Over all new wiring Boards and Switches etc.	130,720/-	Overall new wiring installation of new board and switches.

Shi
ASSISTANT ENGINEER
POLICE & PRISON WORK
SHIKARPUR


**COST ESTIMATE & MEASUREMENT FOR REPAIR WORK OF
POLICE STATION KHANPUR DISTT: SHIKARPUR.**

1	<u>PLASTER OF ROOMS</u>	17.6 ft x 11.5 ft Six walls	150,000/-	1. Cement Plaster 1:4 upto 20' height ¾ meter. (SNO:11 CC P-58) Portion walls 1x2x8x17.50x11.0=3080 ft @Rs: 3080 ft 729/96% ft. Add 20% above premium. Add 10% cartage on Rs: 49852/- LS. Add diff: affort of cement @ Rs: 175/- per bag on 60 bags. Add diff: cartage bricks @ Rs: 1000/- <u>COST PER UNIT.</u> =100000/570=145/61. <u>MATERIAL STATEMENT.</u> 2. Pacca Brick 1:4 570 qty, 25 cement bags, 146 H/sand 7695 bricks. C.Plaster 1:4, 3080qty 35 cement bags 154 H/sand.
02	<u>DISTEMBER AND WHITE WASH.</u>	160 ft x 25 ft x 11-6 ft (Ground floor both interior & exterior)	95,000/-	Distemper 2 codes (SNo:24 P-60). I/S barracks 2x2x2(160+25) 11.50 Of code barrack 2x2x2(160+25)11.50 33040 ft 204/22 % ft. Add 20% above premium Add 10% cartage
03	<u>CONSTRUCTION OF ONE WATER TANK</u>	8'x12'	100,000/-	1. Pacca brick for walls floor cement 1:4. Portion wall 3x2x10.5x0.37x11.5 = 268.0 sq ft. Cement plaster. 268sq ft 4531/45 % sq ft. 3x2x2x10.50x11.50 =1145 sq ft. 3145 sq ft 729.96 sq ft. C.C topping 2" 1x3x10.50x7.0 = 221.0 sq ft. Add 20% above premium. Add 10% cartage. Add diff: of cement Rs: 175 per bag on 35 bags. Add diff: cost bricks @ Rs: 1000/- per No.
04	<u>CONSTRUCTION OF WATER SWERAGE SYSTEM</u>	Drainage arrangement to pump sewerage water in to drain.	200,000/-	New drainage line 40 Rft mortar i/c separate tank. Mortar Hut. 01 job.
05	<u>RENOVATION OF ELECTRICITY SYSTEM.</u>	Over all new wiring Boards and Switches etc.	205,000/-	Overall new wiring installation of new board and switches.


 ASSISTANT ENGINEER
 POLICE & PRISON WORKS
 SHIKARPUR


**COST ESTIMATE & MEASUREMENT FOR REPAIR WORK OF
POLICE STATION KHANPUR DISTT: SHIKARPUR.**

1	<u>PLASTER OF ROOMS</u>	17.6 ft x 11.5 ft Six walls	150,000/-	1. Cement Plaster 1:4 upto 20' height ¼ meter. (SNO:11 CC P-58) Portion walls 1x2x8x17.50x11.0=3080 ft @Rs: 3080 ft 729/96% ft. Add 20% above premium. Add 10% cartage on Rs: 49852/- L.S. Add diff: affort of cement @ Rs: 175/- per bag on 60 bags. Add diff: cartage bricks @ Rs: 1000/- <u>COST PER UNIT.</u> =100000/570=145/61. <u>MATERIAL STATEMENT.</u> 2. Pacca Brick 1:4 570 qty. 25 cement bags. 146 H/sand 7695 bricks. C.Plaster 1:4. 3080qty 35 cement bags 154 H/sand.
02	<u>DISTEMBER AND WHITE WASH.</u>	160 ft x 25 ft x 11-6 ft (Ground floor both interior & exterior)	95,000/-	Distemper 2 codes (SNo:24 P-60). I/S barracks 2x2x2(160+25) 11.50 Of code barrack 2x2x2(160+25) 11.50 33040 ft 204/22 % ft. Add 20% above premium Add 10% cartage
03	<u>CONSTRUCTION OF ONE WATER TANK</u>	8'X12'	100,000/-	1. Pacca brick for walls floor cement 1:4. Portion wall 3x2x10.5x0.37x11.5 = 268.0 sq ft. Cement plaster. 268sq ft 4531/45 % sq ft. 3x2x2x10.50x11.50 = 1145 sq ft. 3145 sq ft 729,96 sq ft. C.C topping 2" 1x3x10.50x7.0 = 221.0 sq ft. Add 20% above premium. Add 10% cartage. Add diff: of cement Rs: 175 per bag on 35 bags. Add diff: cost bricks @ Rs: 1000/- per No.
04	<u>CONSTRUCTION OF WATER SWERAGE SYSTEM</u>	Drainage arrangement to pump sewerage water in to drain.	200,000/-	New drainage line 40 Rft mortar i/c separate tank. Mortar Hut. 01 job.
05	<u>RENOVATION OF ELECTRICITY SYSTEM.</u>	Over all new wiring Boards and Switches etc.	205,000/-	Overall new wiring installation of new board and switches.


 ASSISTANT ENGINEER
 POLICE & PRISON WORKS
 SHIKARPUR


**COST ESTIMATE & MEASUREMENT FOR REPAIR WORK OF
POLICE LINE & POLICE DISPENSARY SHIKARPUR.**

S/NO	DETAIL OF REQUIRED REPAIR/ ADDITION	DIMENSIONS	TOTAL COST ESTIMATE	JUSTIFICATION
01	<u>REPAIR ROOF OF Police Line Shikarpur</u>	160ft x 25ft = 8000 sq ft (one floor)	490,000/-	<p>1. Dimensionally cement, cemented plain 1:2:4 (SI No19(c) P-11) Roof floor = 1 x 160 x 125 x 0.25 = 1000 of 1000 ft @ Rs: 1597/20%.</p> <p>2. Cement brick or other 1 -1/2 to 2" gauge rate 1:4:3(SNO:4 P-17) Roof floor cement 1 x 160 x 25 x 0.25 = 1000 ft 1000 @ Rs: 3584/10%.</p> <p>3. P/laying 1" tapping c.c (1:2:4) i/c surface finishing and dividing into parallel (SNo: 16(C) P-47, Barrack 1x160x25=4000 ft. 4000 ft @Rs: 1820/23%.</p> <p>4. Add 50% of cost of cartage of material L.S 10% of the total. Add cost of diff: of cement @ Rs: 175/- per bag on 272 bags. For 8000 ft total Rs: 456600/- Total amount of per sq ft 530.00 /</p>
2	<u>PLASTER OF ROOMS</u>	17.6 ft x 11.5 ft Sixteen walls	350,000/-	<p>1. Cement Plaster 1:4 upto 20' height ¼ meter. (SNO:11 CC P-58) Portion walls 1x2x8x17.50x11.0=3080 ft @Rs: 3080 ft 729/96% ft. Add 20% above premium. Add 10% cartage on Rs: 49852/- LS. Add diff: affort of cement @ Rs: 175/- per bag on 60 bags. Add diff: cartage bricks @ Rs: 1000/-</p> <p><u>COST PER UNIT.</u> =138000/570=145/61.</p> <p><u>MATERIAL STATEMENT.</u> 1. Pacca Brick 1:4 570 qty, 25 cement bags, 146 H/sand 7695 bricks. C.Plaster 1:4, 3080qty 35 cement bags 154 H/sand.</p>
03	<u>DISTEMBER AND WHITE WASH.</u>	160 ft x 25 ft x 11-6 ft (two stories + both interior & exterior)	150,000/-	<p>Distemper 2 codes (SNo:24 P-60). I/S barracks 2x2x2(160+25) 11.50 Of code barrack 2x2x2(160+25)11.50 33040 ft 204/22 % ft. Add 20% above premium Add 10% cartage Cost per unit 45186/-</p>


 ASSISTANT ENGINEER
 POLICE & PRISON WORKS
 SHIKARPUR

**COST ESTIMATE & MEASUREMENT FOR REPAIR WORK OF
POLICE LINE & POLICE DISPENSARY SHIKARPUR.**

S/NO	DETAIL OF REQUIRED REPAIR/ ADDITION	DIMENSIONS	TOTAL COST ESTIMATE	JUSTIFICATION
01	<u>REPAIR ROOF OF Police Line Shikarpur</u>	160ft x 25ft = 8000 sq ft (one floor)	490,000/-	<p>1. Dimensionally cement, cemented plain 1:2:4 (SI No19(c) P-II) Roof floor = 1 x 160 x 125 x 0.25 = 1000 of 1000 ft @ Rs: 1597/20%.</p> <p>2. Cement brick or other 1 -1/2 to 2" gauge rate 1:4:8(SNO.4 P-17) Roof floor cement 1 x 160 x 25 x 0.25 = 1000 ft 1000 @ Rs: 3584/10%.</p> <p>3. P/laying 1" tapping c.c (1:2:4) i/c surface finishing and dividing into parallel (SNo: 16(C) P-47, Barrack 1x160x25=4000 ft. 4000 ft @Rs: 1820/23%.</p> <p>4. Add 50% of cost of cartage of material L.S 10% of the total. Add cost of diff: of cement @ Rs: 175/- per bag on 272 bags. For 8000 ft total Rs: 456600/- Total amount of per sq ft 530.00 /</p>
2	<u>PLASTER OF ROOMS</u>	17.6 ft x11.5 ft Sixteen walls	350,000/-	<p>1. Cement Plaster 1:4 upto 20' height ¾ meter. (SNO:11 CC P-58) Portion walls 1x2x8x17.50x11.0=3080 ft @Rs: 3080 ft 729/96% ft. Add 20% above premium. Add 10% cartage on Rs: 49852/- L.S. Add diff: affort of cement @ Rs: 175/- per bag on 60 bags. Add diff: cartage bricks @ Rs: 1000/-</p> <p><u>COST PER UNIT.</u> =138000/570=145/61.</p> <p><u>MATERIAL STATEMENT.</u> 1. Pacea Brick 1:4 570 qty, 25 cement bags, 146 H/sand 7695 bricks. C.Plaster 1:4, 3080qty 35 cement bags 154 H/sand.</p>
03	<u>DISTEMBER AND WHITE WASH.</u>	160 ft x 25 ft x 11-6 ft (two stories + both interior & exterior)	150,000/-	<p>Distemper 2 codes (SNo:24 P-60). I/S barracks 2x2x2(160+25) 11.50 Of code barrack 2x2x2(160+25)11.50 33040 ft 204/22 % ft. Add 20% above premium Add 10% cartage Cost per unit 45186/-</p>


 ASSISTANT ENGINEER
 POLICE & PRISON WO
 SHIKARPUR