OFFICE OF THE EXECUTIVE ENGINEER BUILDINGS-III

WORKS AND SERVICES DEPARTMENT KARACHI

VOUME-II: BILL OF QUANTITIES

(SINGLE STAGE ONE ENVELOPE METHOD)

(Along with eligibility & minimum qualification criteria *Method of Procurement)

NAME OF WORK **:- REHABILITATION / RECONSTRUCTION OF INTERNAL ROADS IN JINNAH COURT (DG RANGERS OFFICER / HEAD QUARTERS & DG RANGERS HOUSE)**

1.	Estimated Cost	Rs. 9.999 Million
2.	Bid Security	2% of Bid Amount
3.	Tender Cost	Rs. 3000/-

EXECUTIVE ENGINNER
BUILDING-III,W&S DEPARTMENT
KARACHI

Issued to M/S _____ P.O/D.R. No. _____

_____ Dated. _____

_____

Signature & Stamp of issuing Authority.

WORKS & SERVICES GOVERNMENT OF SINDH

REHABILITATION / RECONSTRUCTION OF INTERNAL ROADS IN JINNAH COURT (D.G RANGERS OFFICE / HEAD QUARTERS) & D.G (RANGERS HOUSE) KMC

Schedule ..... B

SR. #	Description	Unit	Quantity	Rate	Amount (Rs)
1	Earth work excavation undressed lead upto a single throw of Kassi Phawrah or shovel. **(Vol-III, Part-II, Chap-1, Pg-1, Sr. 1-b)**	%oCft	24,886.00	Rs. 1,361.25	**33,876.00**
2	Cartage of 100 CFT / 5 tons of all material likes one aggregate, spawl, coal, lime, surkhi etc. B.G. Rait fastenings points & crossing Bridges Girders, Pipes, Sheets Raits, M.S. Bars etc. or 1000 Nos brinks, 10' x 5' x 3' or 1000 manuds of fuel wood by trucks or any other means owned by the contractors (Lead upto 5 Miles etc). **(Vol-I, Part-I, Chap-1, Pg-1, Sr. 1)**	% Cft	24,886.00	Rs. 714.29	**177,758.00**
3	Preparing Sub-Base by supplying and spreading well graded pit or bed run gravel having a liquit limt not greater than 25 and plasticity index not greater than 6 in proper camber and grade including watering rolling and compacting in layers, thickness of each compacted layer not exceeding 6" compacted upto 98-100% density as per modified AASHO density (Rate i/c all cost of materials T&P and carriage upto 3 chanins). **(Vol-III, (Highway) Chap-2, Pg-4, Sr. 11d)**	% Cft	43,657.00	Rs. 3,341.71	**1,458,890.00**
4	Providing and laying Aggregate base course in proper grade and camber having CBR 80% as per AASHTO standard specifications i/c spreading and compacting by approved mechanical menas (Motor grader, Vibratory roller and Smooth wheel roller etc) watering to maintain the moisture content the compaction of each layer shall 100 percent to the max dry density (Rate i/c all cost of materials T&P and carriage upto 3 chains). **(Vol-III, (Highway) Chap-2, Pg-5, Sr. 13b)**	% Cft	37,703.00	Rs. 5,542.24	**2,089,591.00**
5	Laying to Proper line and grade plant mixed Asphalt concrete paver finished (Hydraulic / Electronic control) Prepared to specified fomula according to job mix formula approved by Engineer incharge including rolling and finishing to Properline, grade level and camber etc: (Machinery with POLs cost of material carriage) 2" (50 mm) Thick Asphalt Concrete Wearing Course Plant Mix **(Vol-III, (Highway) Chap-5, Pg-9, Sr. 24b)**	% Sft	75,405.00	Rs. 8,274.73	**6,239,560.00**
				TOTAL AMOUNT OF SCHEDULE ITEMS	**9,999,675.00**

OFFICE OF THE EXECUTIVE ENGINEER BUILDINGS-III

WORKS AND SERVICES DEPARTMENT KARACHI

QUOTED BID (SUMMARY)

NAME OF WORK :- **REHABILITATION / RECONSTRUCTION OF INTERNAL ROADS IN JINNAH COURT (DG RANGERS OFFICER / HEAD QUARTERS & DG RANGERS HOUSE)**

Date of Issuance from Publication to	02-09-2016
Date of Dropping Tender.	20-09-2016 Upto 2:00 P.M
Date of Opening.	20-09-2016 at 2:30 P.M

I/We hereby quoted as follows.

	In figures	In words.
PART-A **Civil Works Schedule Items** **@_____%** Above / Below on S.R Items		
PAR-B **Items Based on Non Schedule Items**		
G R A N D T O T A L (A + B)		

The total amount is Rs._____ (Rupees _____
(In figures) (In words)

_____ for the complete job for all schedule of rate, approved rate & other rates

(whichever is included in the BOQ)

I / We have attach a Bid Security amount to Rs._____ as per NIT in shape of pay order bearing

No._____ dated _____ issued from _____
(Bank)

Time Limit - -Months

Validity 90+30 Days as SPP Rules 2010.

NOTE:

Tender must be quoted in figure & in word both otherwise liable to be cancelled. All over writing & correction if any must be initialed & stamped by the bidder.

For office use.

Verified BOQ by

Signature of the contractor with stamp

Address._____