

**OFFICE OF THE
EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION, LARKANO**

(Near High Court Building, CMC Road Larkano Ph: 074-9410501, Fax 074-9410552, Email: ewlarkana@hotmail.com)

No. XEN(EWD)/TC/G-55/2480

Larkano, Dated

19/10 /2016

NOTICE INVITING TENDERS

Sealed tenders are invited on Standard Bidding Documents from interested contractors/firms for the following works as per SPPRA Rules 2010.

ADP No./ S.No.	Name of Scheme /Location	Estimated Cost (In million)	Earnest Money (In rupees)	Tender Fee (In rupees)	Period of Completion
182	Construction/Reconstruction of building for existing Primary Schools Taluka Larkano (9-Units) (2010-11 Programme)				
1	GGMS. Kehar (Electrification)	0.095	1900	500	06 months
2	GBPS. Gul Muhammad Brohi (Elect:)	0.095	1900	500	06 months
3	GBPS. Arija Phero (Elect:)	0.100	2000	500	06 months
4	GBPS. Jhangar (Elect:)	0.080	1600	500	06 months
184	Integrated rehabilitation of Primary Schools in Taluka Larkano (16 Units) (2010-11 Programme)				
5	GGPS. Rohal Khan Bugti (Elect:)	0.075	1500	500	06 months
185	Integrated rehabilitation of Primary Schools in Taluka Ratodero (13-Units) (2010-11 Programme)				
6	GBPS. Hashim Bozdar (Elect:)	0.110	2200	500	06 months
7	GBPS. Khairodero (Elect:)	0.085	1700	500	06 months
186	Integrated rehabilitation of Primary schools in Taluka Bakrani (13-Units) (2010-11 Programme)				
8	GGPS. Kot Mirza Kaloo (Elect:)	0.100	2000	500	06 months
187	Integrated rehabilitation of Primary schools in Taluka Dokri (11-Units) (2010-11 Programme)				
9	GBPS. Badeh Main (Elect:)	0.400	8000	750	06 months
10	GBPS. Muhammad Safar (balance work)	0.450	9000	500	06 months
191	Construction of building for existing shelterless Primary Schools in Taluka Ratodero (5-Units) (2011-12 Programme)				
11	GBPS. Maree Goth near Grid Station (Elect:)	0.110	2200	500	10 months
192	Construction of building for existing shelterless Primary Schools in Taluka Larkano (5-Units) (2011-12 Programme)				
12	GBPS. Sasti Basti (Elect:)	0.110	2200	500	10 months
195	Rehabilitation of building for existing Primary Schools in Taluka Larkano (14-Units) (2011-12 Programme)				
13	GBPS. Khan Muhamamd Jhinjhan (Elect:)	0.100	2000	500	10 months
196	Rehabilitation of building for existing Primary / Middle Schools in Taluka Ratodero (10 Units) (2011-12 Programme)				
14	GBPS. Panjoodero (Old Portion) (balance work)	0.500	10,000	750	10 months
198	Construction of additional class rooms in existing Primary Schools in Taluka Ratodero (16 Class Rooms) (2011-12 Programme)				
15	GBPS. Usman Unar (2 C.R) (Elect:)	0.100	2000	500	10 months
16	GBPS. Ali Hassan Junejo (1 C.R) (balance work)	1.000	20,000	1500	10 months
202	Reconstruction of dangerous Primary School Buildings in Taluka Ratodero ((9 Units) (2011-12 Programme)				
17	GBPS. Ali Khan Brohi (balance work)	0.300	6000	750	10 months

203	Reconstruction of dangerous Primary / Middle School Buildings in Taluka Bakrani / Dokri (12 Units) (2011-12 Programme)				
18	GGMS. Wado Wehan Tal: Bakrani (Elect:)	0.120	2400	500	10 months
211	Integrated rehabilitation of Elementary Schools in Taluka Dokri & Bakrani (14 Units) (2013-14 Programme)				
19	GBPS. Lal Khan Waggan Tal: Bakrani (Elect:)	0.120	2400	500	10 months
213	Construction of building for existing shelterless Primary Schools in Taluka Larkano (4 Units) (2015-16 Programme)				
20	GBPS. Muhammad Mithal Chandio (Elect:)	0.120	2400	500	10 months
21	GBPS. Tajoo-Ji-Wandh (Elect:)	0.120	2400	500	10 months
215	Construction of building for existing shelterless Primary Schools in Taluka Dokri (4 Units) (2015-16 Programme)				
22	GBPS. Jogi (Elect:)	0.120	2400	500	10 months
23	GBPS. Sultan Lakhair (Elect:)	0.120	2400	500	10 months
216	Construction of additional class rooms in existing Elementary Schools Taluka Larkano (7 Units) (2015-16 Programme)				
24	GBPS. Heesib Chandio (2 C.R) (Elect:)	0.120	2400	500	10 months
25	GBPS. Deen Muhammad Chandio (1 C.R) (Elect:)	0.070	1400	500	10 months
26	GBPS. Behram Luhur (1 C.R) (Elect:)	0.070	1400	500	10 months
27	GBPS. PTS Colony Larkano (2 C.R) (Elect:)	0.120	2400	500	10 months
217	Construction/Reconstruction of dangerous Primary Schools Taluka Larkano (8 Units) (2015-16 Programme)				
28	GBPS. Jeewan Bhutto (Elect:)	0.120	2400	500	10 months
29	GBPS. Sawayo Agham (Elect:)	0.120	2400	500	10 months
30	GBPS. Sabzal Brohi (Elect:)	0.070	1400	500	10 months
31	GBPS. Gadani (Elect:)	0.120	2400	500	10 months
218	Integrated rehabilitation of Primary Schools and Provision of missing facilities Taluka Larkano (14 Units) (2015-16 Programme)				
32	GBPS. Sajjan Sangi (Elect:)	0.120	2400	500	10 months
33	GBPS. New Nazar Muhalla Larkano (Elect:)	0.130	2600	500	10 months
34	GBPS. Nazar Muhalla (N/S Wing) (Elect:)	0.150	3000	500	10 months
35	GGPS. Railan (Elect:)	0.100	2000	500	10 months
36	GGMS. Kehar (Elect:)	0.150	3000	500	10 months
219	Provision of missing facilities (C.Wall, Lavatory, addl: C.Rooms) to existing Elementary Schools of Taluka Ratodero (12 Units) (2015-16 Programme)				
37	GBPS. Haji Khan Bosan (2 C.Rooms) (Elect:)	0.120	2400	500	10 months
38	GBPS. Gharibabad Naudero-1 (1 C.R) (Elect:)	0.070	1400	500	10 months
221	Integrated rehabilitation of existing Elementary Schools in Taluka Ratodero District Larkano (5 Units) (2015-16 Programme)				
39	GBPS. Behman (Elect:)	0.110	2200	500	10 months
40	GBMS. Bhai Khan Ghanghro (Elect:)	0.150	3000	500	10 months
222	Rehabilitation of existing Primary Schools in Taluka Ratodero District Larkano (11 Units) (2015-16 Programme)				
41	GBPS. Kechi Unar (Elect:)	0.075	2500	500	10 months
42	GBPS. Muhammad Murad Kasai (Elect:)	0.070	1400	500	10 months
43	GBPS. Sharif Abro (Elect:)	0.060	1200	500	10 months
223	Integrated rehabilitation of Primary Schools & Provision of missing facilities Taluka Bakrani (12 Units) (2015-16 Programme)				
44	GBPS. Latifabad (C.Wall)	0.700	14,000	750	10 months
225	Integrated rehabilitation of Primary Schools & Provision of missing facilities Taluka Dokri (11 Units) (2015-16 Programme)				
45	GGPS. Gabbar Massan (Elect:)	0.120	2400	500	10 months
46	GBPS. Othwal (C.Wall, Toilet)	0.800	16,000	1500	15 months

47	GBPS. Hatri Ghulam Shah	0.950	19,000	1500	15 months
226	Construction/Reconstruction of dangerous Primary Schools Taluka Dokri (8 Units) (2015-16 Programme)				
48	GGPS. Faiz Muhammad Khokhar (Elect:)	0.120	2400	500	10 months
227	Integrated rehabilitation of building for Govt. Boys High school Ratodero (2010-11 Programme)				
49	GBHS. Ratodero (balance work)	1.000	20,000	1500	12 months
241	Provision of essential facilities in existing High / Higher Secondary Schools in Taluka Ratodero (3 Units) (2011-12 Programme)				
50	GBHS (S.S) Ratodero (Science Lab, Computer Lab & Library) (Elect:)	0.500	10,000	750	12 months
247	Construction of Computer Block at Govt. Boys Higher Secondary School Ratodero (2011-12 Programme)				
51	GBHSS. Ratodero (Computer Block Balance work)	1.000	20,000	1500	12 months
252	Integrated rehabilitation of existing Secondary & Higher Secondary Schools in Taluka Larkano (5 Units) (2015-16 Programme)				
52	GBHS. Mahota (Elect:)	0.200	4000	500	10 months
53	GBHS. Kehar (Elect:)	0.110	2200	500	10 months
54	GBHS. Shaikh Zaid colony (W.Tank, Cycle Shed) (Electrification)	0.030	600	300	10 months
254	Construction of Residential Quarters/ Bungalows for District Education Officers (3 Units) (2011-12 Programme)				
55	XEN Education Works Division Larkano (Elect:)	0.200	4000	500	10 months
255	Rehabilitation / Improvement of Education Office Buildings District Larkano (6-Units) (2011-12 Programme)				
56	Director Schools Education Office, Larkano (Electric work)	0.300	6,000	750	15 months
	District New Schemes 2016-17				
6	Provision of missing facilities in existing Elementary Schools Taluka Dokri (2016-17 Programme)				
57	GBMS. Wakro (C.Wall & Toilet)	0.990	19,800	1500	24 months
58	GBPS. Fateh Muhammad Aiwan (C.Wall & Toilet)	0.900	18,000	1500	24 months
59	GBPS. Nau Goth (C.Wall & Toilet)	1.000	20,000	1500	24 months
7	Provision of missing facilities in existing Elementary Schools Taluka Bakrani (2016-17 Programme)				
60	GBPS. Usman Ssamti / Moryal Brohi (C.Wall)	0.950	19,000	1500	24 months
61	GBPS. Piyaro Buriro (C.Wall)	0.950	19,000	1500	24 months
62	GBPS. Thulah (C.Wall & Toilet)	0.950	19,000	1500	24 months
63	GBPS. Bahawal Gadhi (C.Wall & Toilet)	0.950	19,000	1500	24 months
64	GBPS. Panjoodero (C.Wall & Toilet)	0.625	12,500	1500	24 months
8	Reconstruction of Elementary School Buildings Taluka Larkano (2016-17 Programme)				
65	GBPS. Hamzo Jatoi	0.950	19,000	1500	24 months
11	Integrated rehabilitation of Primary / Elementary Schools Taluka Larkano (2016-17 Programme)				
66	GBPS. Mian Lal	0.600	12,000	1500	24 months
67	GBPS. Bheda	0.600	12,000	1500	24 months
68	GBPS. Ghulam Bhutto	0.800	16,000	1500	24 months
69	GBPS. Chakar Kalhoro	0.950	19,000	1500	24 months
70	GBPS. New Nazar Muhalla Larkano	0.800	16,000	1500	24 months
71	GBMS. Wapda Colony (Elect:)	0.300	6,000	750	06 months

12	Integrated rehabilitation of Primary / Elementary Schools Taluka Ratodero (2016-17 Programme)				
72	GBPS. Panjoo Lorir	0.950	19,000	1500	24 months
13	Integrated rehabilitation of Primary / Elementary Schools Taluka Dokri & Bakrani (2016-17 Programme)				
73	GBPS. Ghazi Jhatiyal (C.Wall, Toilet)	0.950	19,000	1500	24 months
16	Improvement / Provision of missing facilities in field offices of Education & Literacy Department District Larkano				
74	TEO (Female) Office Ratodero	0.950	19,000	1500	24 months
257	Rehabilitation of existing High / Higher Secondary Schools in Sindh (250 Units) (2008-09 Programme)				
75	GBHS. Main Ratodero (balance work)	1.000	20,000	1500	12 months
76	GGHS. Garhi Khuda Bux Bhutto (balance work)	0.500	10,000	750	12 months
287	Improvement of existing Public School in Larkano Division (2015-16 Programme)				
77	Public School Larkano (Elect:)	1.000	20,000	1500	06 months
455	Construction / Reconstruction of existing offices for Field Officers of Education & Literacy Department in Larkano Division (03 Units) (2014-15 Programme)				
78	Directorate of School Education Larkano (Elect:)	1.000	20,000	1500	06 months

2. Eligibility: Valid Registration with Income Tax, Sales Tax, Sindh Revenue Board.
3. Method of Procurement (Single Stage Single Envelope).
4. Bidding/Tender Documents:
 - i. **Issuance:** Documents will be issued from date of publication / hoisting i.e from **25-10-2016** to **11.11.2016**.
 - ii. **Submission:** Last date will be **14.11.2016 up to 1:00 pm**.
 - iii. **Opening:** will be opened on **14.11.2016 at 2:00 pm**.
 - iv. **Un-responded tenders** will be again issued / submitted/opened on following dates.

Attempt:	(a) Issue date:	(b) Submission & Opening date
<u>2nd</u>	15.11.2016 to 02.12.2016	05.12.2016 at 2:00 pm
5. **Terms & Conditions:**
 - a. Under following conditions bid will be rejected:-
 - i. Conditional and telegraphic bids/tenders.
 - ii. Bids not accompanied by bid security and form.
 - iii. Bids received after specified date and time.
 - iv. Bids of black listed firms.
 - b. **Bid Validity Period: 90 Days.**
 - c. If the undersigned or any member of the Procurement Committee remains out of head quarter on date of opening of tenders, the same will be opened on the next working day at the same time as mentioned above.
 - d. The bidder interested for electric work must have Electric License for the calendar year 2016.
 - e. During the opening of bids, the bidder must be present in person. No any representative of bidder will be allowed to participate in bid openings.
 - f. Bidder must submit Bank Certificate showing name of Bidder/Firm maintaining his/their account therein.
 - g. Procuring Agency reserves the right to reject all or any bids subject to the relevant provisions of Sindh Public Procurement Rules 2010.


EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
LARKANO

CFWCs to:

1. The Deputy Commissioner, Larkano for favour of his kind information.
2. The Chief Engineer, Education Works, Sukkur.
3. The Superintending Engineer, Education Works Circle, Larkano for favour of information and approval please.

4. The Director (Information), Advertisement Government of Sindh, Karachi along-with 03 extra copies for publication in the leading newspapers.
5. The Director (C.B) SPPRA, Planning and Development Department, GoS Karachi for posting NIT on website.
6. The Secretary (Focal Person), Information Technology Department, Govt. of Sindh, New Sindh Secretariat, 1st Floor, Karachi for floating tenders on website.
7. The Executive Engineer, Roads Division / Buildings Division, Larkano.
8. The Assistant Engineer, Education Works Sub-Division, Larkano/Ratodero/Dokri/Electric Works, Larkano Region for vide publicity.
9. The Member of Procurement Committee for information.
10. Copy to Divisional Accounts Officer/Draftsman/Establishment Branch/Notice Board (local).


EXECUTIVE ENGINEER

DMS



NOTIFICATION

NO SO(G) EDUE&ALPRO-EW/1-1-15: In pursuance of Rule - 7 of the Sindh Public Procurement Rules, 2010 a Departmental Procurement Committee comprising of following Officers for procurement of works for various Educational Institutes / Offices / Line Departments working under Administrative Department of Education & Literacy Department to be procured under ADP / Regular Budget / SNE of Government of Sindh is hereby notified as under

- | | |
|---|----------|
| 1. Executive Engineer (Education Works)
Concerned Education Works Division
Education & Literacy Department | Chairman |
| 2. Assistant Engineer
Local Government Public Health Engineering Department | Member |
| 3. Assistant Engineer (Education Works) of Headquarter
Concerned Education Works sub Division
Education & Literacy Department | Member |

Tasks

- Preparing bidding documents;
- Carrying out technical as well as financial evaluation of the bids;
- Preparing evaluation report as provided in Rule 45 of SPPRA 2010;
- Making recommendations for the award of contract to the competent authority; and
- Perform any other function ancillary and incidental to the above.

- DR. FAZLULLAH PECHUHO -
SECRETARY TO GOVT. OF SINDH

NO SO(G) EDUE&ALPRO-EW/1-1-15:

Karachi, date the 28th May, 2015

A copy is forwarded for information & necessary action to:-

1. All Members of the Committee.
2. The P.S. to Senior Minister, Education & Literacy Department, Govt. of Sindh, Karachi.
3. The P.S to Secretary, Education & Literacy Department.
4. The P.S to Secretary, Local Government Public Health Engineering Department.
5. Office Order File



SINDH EDUCATION &
LITERACY DEPARTMENT



DEPUTY SECRETARY (GA)



- GOVERNMENT OF SINDH
 EDUCATION & LITERACY DEPARTMENT
 Karachi, date the 28-04-2015

NOTIFICATION

NO.SO(G) EDU/EA/PRO-EW(CRC)/14-15: In pursuance of Rule – 31 of the Sindh Public Procurement Rules, 2010's Departmental Complaint Redressal Committee comprising of following Officers is constituted as under to resolve complaint's of aggrieved bidders:-

- | | |
|--|----------|
| 1. Superintendent Engineer (Education Works) of concerned Education Works Circle Education & Literacy Department | Chairman |
| 2. Representative of District Account Officer / Accountant General, Sindh | Member |
| Representative of Head of procuring Agency (Professional from relevant field concerning) | Member |

Tasks

- To perform according to Rule – 31 of SPPRA, 2010;
- Perform any other function ancillary and incidental to the above.

SECRETARY EDUCATION
 TO GOVT. OF SINDH
 Karachi, date the 28th May, 2015

NO.SO(G) EDU/EA/PRO-EW(CRC)/14-15:

A copy is forwarded for information & necessary action to:-

1. All Members of the Committee.
2. The P.S to Secretary, Education & Literacy Department.
3. Office Order File



EDUCATION &
 LITERACY DEPARTMENT



DEPUTY SECRETARY (GA)

28/04/15

ANNUAL PROCUREMENT PLAN FOR YEAR 2016-17

DEPARTMENT: EDUCATION WORKS DIVISION, LARKANO (EDUCATION & LITERACY DEPARTMENT)

Rs. in Million

ADP No./ S.No.	Description of Procurement	Estimated Cost Unit Cost (in million)	Estimated Total cost	Funds allocated	Source of funds (ADP/ Non-ADP)	Proposed procurement method	Timing of Procurement 2016-2017			
							Q1	Q2	Q3	Q4
182	Construction/Reconstruction of building for existing Primary Schools Taluka Larkano (9-Units) (2010-11 Programme)			1.500						
1	GGMS. Kehar (Electrification)	0.095	0.095		ADP	National opening competitive bidding	-	Yes	-	-
2	GBPS. Gul Muhammad Brohi (Elect:)	0.095	0.095		ADP	National opening competitive bidding	-	Yes	-	-
3	GBPS. Arja Phero (Elect:)	0.100	0.100		ADP	National opening competitive bidding	-	Yes	-	-
4	GBPS. Jhangar (Elect:)	0.080	0.080		ADP	National opening competitive bidding	-	Yes	-	-
184	Integrated rehabilitation of Primary Schools in Taluka Larkano (16 Units) (2010-11 Programme)			2.200						
5	GGPS. Rohal Khan Bugti (Elect:)	0.075	0.075		ADP	National opening competitive bidding	-	Yes	-	-
185	Integrated rehabilitation of Primary Schools in Taluka Ratodero (13-Units) (2010-11 Programme)			2.400						
6	GBPS. Hashim Bozdar (Elect:)	0.110	0.110		ADP	National opening competitive bidding	-	Yes	-	-
7	GBPS. Khairodero (Elect:)	0.085	0.085		ADP	National opening competitive bidding	-	Yes	-	-
186	Integrated rehabilitation of Primary schools in Taluka Bakrani (13-Units) (2010-11 Programme)			1.800						
8	GGPS. Kot Mirza Kaloo (Elect:)	0.100	0.100		ADP	National opening competitive bidding	-	Yes	-	-
187	Integrated rehabilitation of Primary schools in Taluka Dokri (11-Units) (2010-11 Programme)			5.000						
9	GBPS. Bاده Main (Elect:)	0.400	0.400		ADP	National opening competitive bidding	-	Yes	-	-
10	GBPS. Muhammad Safar (balance work)	0.450	0.450		ADP	National opening competitive bidding	-	Yes	-	-
191	Construction of building for existing shelterless Primary Schools in Taluka Ratodero (5-Units) (2011-12 Programme)			1.200						
11	GBPS. Mare Goth near Grid Station (Elect:)	0.110	0.110		ADP	National opening competitive bidding	-	Yes	-	-
192	Construction of building for existing shelterless Primary Schools in Taluka Larkano (5-Units) (2011-12 Programme)			1.400						
12	GBPS. Sasti Basti (Elect:)	0.110	0.110		ADP	National opening competitive bidding	-	Yes	-	-
195	Rehabilitation of building for existing Primary Schools in Taluka Larkano (14-Units)			3.000						

13	(2011-12 Programme) GBPS. Khan Muhammad Jhijhan (Elect:)	0.100	0.100		ADP	National opening competitive bidding	-	Yes	-	-
196	Rehabilitation of building for existing Primary / Middle Schools in Taluka Ratodero (10 Units) (2011-12 Programme)			2.000						
14	GBPS. Panjoodero (Old Portion) (balance work)	0.500	0.500		ADP	National opening competitive bidding	-	Yes	-	-
198	Construction of additional class rooms in existing Primary Schools in Taluka Ratodero (16 Class Rooms) (2011-12 Programme)			3.000						
15	GBPS. Usman Unar (2 C.R) (Elect:)	0.100	0.100		ADP	National opening competitive bidding	-	Yes	-	-
16	GBPS. Ali Hassan Junejo (1 C.R) (balance work)	1.000	1.000		ADP	National opening competitive bidding	-	Yes	-	-
202	Reconstruction of dangerous Primary School Buildings in Taluka Ratodero ((9 Units) (2011-12 Programme)			2.000						
17	GBPS. Ali Khan Brohi (Balance work)	0.300	0.300		ADP	National opening competitive bidding	-	Yes	-	-
203	Reconstruction of dangerous Primary / Middle School Buildings in Taluka Bakrani / Dokri (12 Units) (2011-12 Programme)			3.000						
18	GGMS. Wado Wahhan Tai: Bakrani (Elect:)	0.120	0.120		ADP	National opening competitive bidding	-	Yes	-	-
211	Integrated rehabilitation of Elementary Schools in Taluka Dokri & Bakrani (14 Units) (2013-14 Programme)			3.000						
19	GBPS. Lal Khan Waggan Tai: Bakrani (Elect:)	0.120	0.120		ADP	National opening competitive bidding	-	Yes	-	-
213	Construction of building for existing shelterless Primary Schools in Taluka Larkano (4 Units) (2015-16 Programme)			3.000						
20	GBPS. Muhammad Mithal Chandio (Elect:)	0.120	0.120		ADP	National opening competitive bidding	-	Yes	-	-
21	GBPS. Tajoo-Ji-Wandh (Elect:)	0.120	0.120		ADP	National opening competitive bidding	-	Yes	-	-
215	Construction of building for existing shelterless Primary Schools in Taluka Dokri (4 Units) (2015-16 Programme)			3.000						
22	GBPS. Jogi (Elect:)	0.120	0.120		ADP	National opening competitive bidding	-	Yes	-	-
23	GBPS. Sultan Lakhair (Elect:)	0.120	0.120		ADP	National opening competitive bidding	-	Yes	-	-
216	Construction of additional class rooms in existing Elementary Schools Taluka Larkano (7 Units) (2015-16 Programme)			3.000						
24	GBPS. Heesib Chandio (2 C.R) (Elect:)	0.120	0.120		ADP	National opening competitive bidding	-	Yes	-	-
25	GBPS. Deen Muhammad Chandio (1 C.R) (Elect:)	0.070	0.070		ADP	National opening competitive bidding	-	Yes	-	-
26	GBPS. Behram Luhur (1 C.R) (Elect:)	0.070	0.070		ADP	National opening competitive bidding	-	Yes	-	-
27	GBPS. PTS Colony Larkano (2 C.R) (Elect:)	0.120	0.120		ADP	National opening competitive bidding	-	Yes	-	-
217	Construction/Reconstruction of dangerous Primary Schools Taluka Larkano (8 Units) (2015-16 Programme)			2.000						
28	GBPS. Jeewan Bhutto (Elect:)	0.120	0.120		ADP	National opening competitive bidding	-	Yes	-	-

29	GBPS. Sawayo Agham (Elect:)	0.120	0.120		ADP	National opening competitive bidding	-	Yes	-	-
30	GBPS. Sabzal Brohi (Elect:)	0.070	0.070		ADP	National opening competitive bidding	-	Yes	-	-
31	GBPS. Gadani (Elect:)	0.120	0.120		ADP	National opening competitive bidding	-	Yes	-	-
218	Integrated rehabilitation of Primary Schools and Provision of missing facilities Tlauka Larkano (14 Units) (2015-16 Programme)			2.000						
32	GBPS. Sajjan Sangi (Elect:)	0.120	0.120		ADP	National opening competitive bidding	-	Yes	-	-
33	GBPS. New Nazar Muhalla Larkano (Elect:)	0.130	0.130		ADP	National opening competitive bidding	-	Yes	-	-
34	GBPS. Nazar Muhalla (N/S Wing) (Elect:)	0.150	0.150		ADP	National opening competitive bidding	-	Yes	-	-
35	GGPS. Ralian (Elect:)	0.100	0.100		ADP	National opening competitive bidding	-	Yes	-	-
36	GGMS. Kehar (Elect:)	0.150	0.150		ADP	National opening competitive bidding	-	Yes	-	-
219	Provision of missing facilities (C.Wall, Lavatory, addl: C.Rooms) to existing Elementary Schools of Taluka Ratodero (12 Units) (2015-16 Programme)			2.000						
37	GBPS. Haji Khan Bosan (2 C.Rooms) (Elect:)	0.120	0.120		ADP	National opening competitive bidding	-	Yes	-	-
38	GBPS. Gharbabad Naudero-1 (1 C.R) (Elect:)	0.070	0.070		ADP	National opening competitive bidding	-	Yes	-	-
221	Integrated rehabilitation of existing Elementary Schools in Taluka Ratodero District Larkano (5 Units) (2015-16 Programme)			3.000						
39	GBPS. Behman (Elect:)	0.110	0.110		ADP	National opening competitive bidding	-	Yes	-	-
40	GBMS. Bhai Khan Ghanghro (Elect:)	0.150	0.150		ADP	National opening competitive bidding	-	Yes	-	-
222	Rehabilitation of existing Primary Schools in Taluka Ratodero District Larkano (11 Units) (2015-16 Programme)			2.000						
41	GBPS. Kechi Unar (Elect:)	0.075	0.075		ADP	National opening competitive bidding	-	Yes	-	-
42	GBPS. Muhammad Murad Kasal (Elect:)	0.070	0.070		ADP	National opening competitive bidding	-	Yes	-	-
43	GBPS. Sharif Abro (Elect:)	0.060	0.060		ADP	National opening competitive bidding	-	Yes	-	-
223	Integrated rehabilitation of Primary Schools & Provision of missing facilities Taluka Bakrani (12 Units) (2015-16 Programme)			2.000						
44	GBPS. Latifabad (C.Wall)	0.700	0.700		ADP	National opening competitive bidding	-	Yes	-	-
225	Integrated rehabilitation of Primary Schools & Provision of missing facilities Taluka Dokri (11 Units) (2015-16 Programme)			2.000						
45	GGPS. Gabbar Massan (Elect:)	0.120	0.120		ADP	National opening competitive bidding	-	Yes	-	-
46	GBPS. Othwal (C.Wall, Toilet)	0.800	0.800		ADP	National opening competitive bidding	-	Yes	-	-
47	GBPS. Hatri Ghulam Shah	0.950	0.950		ADP	National opening competitive bidding	-	Yes	-	-
226	Construction/Reconstruction of dangerous Primary Schools Taluka Dokri (8 Units) (2015-16 Programme)			2.000						
48	GGPS. Faiz Muhammad Khokhar (Elect:)	0.120	0.120		ADP	National opening competitive bidding	-	Yes	-	-

227	Integrated rehabilitation of building for Govt. Boys High school Ratodero (2010-11 Programme)	1.000	1.000	2.000	ADP	National opening competitive bidding	-	Yes	-	-
49	GBHS, Ratodero (Balance work)									
241	Provision of essential facilities in existing High / Higher Secondary Schools in Taluka Ratodero (3 Units) (2011-12 Programme)	0.500	0.500	3.200	ADP	National opening competitive bidding	-	Yes	-	-
50	GBHS (S.S) Ratodero (Science Lab, Computer Lab & Library) (Elect.)									
247	Construction of Computer Block at Govt. Boys Higher Secondary School Ratodero (2011-12 Programme)	1.000	1.000	3.000	ADP	National opening competitive bidding	-	Yes	-	-
51	GBHSS, Ratodero (Computer Block Balance work)									
252	Integrated rehabilitation of existing Secondary & Higher Secondary Schools in Taluka Larkano (5 Units) (2015-16 Programme)	0.200	0.200	4.000	ADP	National opening competitive bidding	-	Yes	-	-
52	GBHS, Mahota (Elect.)	0.110	0.110		ADP	National opening competitive bidding	-	Yes	-	-
53	GBHS, Kehar (Elect.)	0.030	0.030		ADP	National opening competitive bidding	-	Yes	-	-
54	GBHS, Shaikh Zaid colony (W.Tank, Cycle Shed) (Electrification)									
254	Construction of Residential Quarters/ Bungalows for District Education Officers (3 Units) (2011-12 Programme)	0.200	0.200	5.000	ADP	National opening competitive bidding	-	Yes	-	-
55	XEN Education Works Division Larkano (Elect.)									
255	Rehabilitation / Improvement of Education Office Buildings District Larkano (6-Units) (2011-12 Programme)	0.300	0.300	5.000	ADP	National opening competitive bidding	-	Yes	-	-
56	Director Schools Education Office, Larkano (Electric work)									
	District New Schemes 2016-17									
	Provision of missing facilities in existing Elementary Schools Taluka Dokri (2016-17 Programme)			3.888						
6										
57	GBMS, Wakro (C.Wall & Toilet)	0.990	0.990		ADP	National opening competitive bidding	-	Yes	-	-
58	GBPS, Fateh Muhammad Aiwan (C.Wall & Toilet)	0.900	0.900		ADP	National opening competitive bidding	-	Yes	-	-
59	GBPS, Nau Goth (C.Wall & Toilet)	1.000	1.000		ADP	National opening competitive bidding	-	Yes	-	-
7	Provision of missing facilities in existing Elementary Schools Taluka Bakrani (2016-17 Programme)			3.307						
60	GBPS, Usman Ssamto / Moryal Brohi (C.Wall)	0.950	0.950		ADP	National opening competitive bidding	-	Yes	-	-
61	GBPS, Piyaro Burro (C.Wall)	0.950	0.950		ADP	National opening competitive bidding	-	Yes	-	-
62	GBPS, Thulah (C.Wall & Toilet)	0.950	0.950		ADP	National opening competitive bidding	-	Yes	-	-
63	GBPS, Bahawal Gadhi (C.Wall & Toilet)	0.950	0.950		ADP	National opening competitive bidding	-	Yes	-	-

64	GBPS. Panjodero (C.Wall & Toilet)	0.625	0.625		ADP	National opening competitive bidding	-	Yes	-	-
8	Reconstruction of Elementary School Buildings Taluka Larkano (2016-17 Programme)	0.950	0.950	1.500	ADP	National opening competitive bidding	-	Yes	-	-
65	GBPS. Hamzo Jatol			4.875						
11	Integrated rehabilitation of Primary / Elementary Schools Taluka Larkano (2016-17 Programme)	0.600	0.600		ADP	National opening competitive bidding	-	Yes	-	-
66	GBPS. Mian Lal	0.600	0.600		ADP	National opening competitive bidding	-	Yes	-	-
67	GBPS. Bheda	0.800	0.800		ADP	National opening competitive bidding	-	Yes	-	-
68	GBPS. Ghulam Bhutto	0.950	0.950		ADP	National opening competitive bidding	-	Yes	-	-
69	GBPS. Chakar Kalhoro	0.800	0.800		ADP	National opening competitive bidding	-	Yes	-	-
70	GBPS. New Nazar Muhalla Larkano	0.300	0.300		ADP	National opening competitive bidding	-	Yes	-	-
71	GBMS. Wapda Colony (Elect.)			3.875						
12	Integrated rehabilitation of Primary / Elementary Schools Taluka Ratodero (2016-17 Programme)	0.950	0.950		ADP	National opening competitive bidding	-	Yes	-	-
72	GBPS. Panjoo Lorir			3.559						
13	Integrated rehabilitation of Primary / Elementary Schools Taluka Dokri & Bakrani (2016-17 Programme)	0.950	0.950		ADP	National opening competitive bidding	-	Yes	-	-
73	GBPS. Ghazi Jhatiyal (C.Wall, Toilet)			3.000						
16	Improvement / Provision of missing facilities in field offices of Education & Literacy Department District Larkano	0.950	0.950		ADP	National opening competitive bidding	-	Yes	-	-
74	TEO (Female) Office Ratodero			2.000						
257	Rehabilitation of existing High / Higher Secondary Schools in Sindh (250 Units) (2008-09 Programme)	1.000	1.000		ADP	National opening competitive bidding	-	Yes	-	-
75	GBHS. Main Ratodero (balance work)	0.500	0.500		ADP	National opening competitive bidding	-	Yes	-	-
76	GGHS. Garhi Khuda Bux Bhutto (balance work)			10.000						
287	Improvement of existing Public School in Larkano Division (2015-16 Programme)	1.000	1.000		ADP	National opening competitive bidding	-	Yes	-	-
77	Public School Larkano (Elect.)			17.000						
455	Construction / Reconstruction of existing offices for Field Officers of Education & Literacy Department in Larkano Division (03 Units) (2014-15 Programme)	1.000	1.000		ADP	National opening competitive bidding	-	Yes	-	-
78	Directorate of School Education Larkano (Elect.)									

EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION, LARKANO

[Signature]

[Initials]

TENDER SHEET/ BIDDING DOCUMENT**S.No.** _____Issued to

And charged Rs. _____ only as tender cost

Vide D.R. No. _____ dt: ____/____/2016

a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano

b) Brief Description of Work:-

_____**(ADP No. _____ of 2016-17)**

c) Procuring Agency's address:- Near High Court Building, CMC Road, Larkano

d) Estimated Cost:- Rs. _____

e) Amount of Bid Security (2%) (Fill in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. _____

f) Period of Bid Security Validity (days):- 28 Days

g) Period of Bid Validity (days):- 90 Days

h) Security Deposit (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. _____

i) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs. _____

j) Deadline for Submission of Bids along- As per NIT with time:-

k) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano. As per NIT

l) Time for Completion from written order of commencement:- _____ Months

m) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)

n) Deposit Receipt No.dt:

o) Rate quoted by Contractor PART-A= above/ below schedule items.

PART-B = above/

CONTRACTOR


 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 LARKANO

SPRA BIDDING DOCUMENT

STANDARD BIDDING DOCUMENT

PROCUREMENT OF WORKS

(For Contracts Costing up to Rs 2.5 MILLION)


Executive Engineer
Education Works Division
LARKAÑO

Standard Bidding Document is intended as a model for admeasurements Percentage Rate/unit price for unit rates in a Bill of Quantities) types of contract. The main text refers to admeasurements contracts.

Instructions to Bidders/ Procuring Agencies.

General Rules and Directions for the Guidance of Contractors.

This section of the bidding documents should provide the information necessary for bidders to prepare responsive bids, in accordance with the requirements of the Procuring Agency. It should also give information on bid submission, opening and evaluation, and on the award of contract.

Matters governing the performance of the Contract or payments under the Contract, or matters affecting the risks, rights, and obligations of the parties under the Contract are included as Conditions of Contract and *Contract Data*.

The *Instructions to Bidders* will not be part of the Contract and will cease to have effect once the contract is signed.

1. All work proposed to be executed by contract shall be notified in a form of Notice Inviting Tender (NIT)/Invitation for Bid (IFB) hoisted on website of Authority and Procuring Agency and also in printed media where ever required as per rules.

NIT must state the description of the work, dates, time and place of issuing, submission, opening of bids, completion time, cost of bidding document and bid security either in lump sum or percentage of Estimated Cost/Bid Cost. The interested bidder must have valid NTN also.

2. Content of Bidding Documents must include but not limited to: Conditions of contract, Contract Data, specifications or its reference, Bill of Quantities containing description of items with scheduled/item rates with premium to be filled in form of percentage above/ below or on item rates to be quoted, Form of Agreement and drawings.

3. **Fixed Price Contracts:** The Bid prices and rates are fixed during currency of contract and under no circumstance shall any contractor be entitled to claim enhanced rates for any item in this contract.

4. The Procuring Agency shall have right of rejecting all or any of the tenders as per provisions of SPP Rules 2010.

5. **Conditional Offer:** Any person who submits a tender shall fill up the usual printed form stating at what percentage above or below on the rates specified in Bill of Quantities for items of work to be carried out: he is willing to undertake the work and also quote the rates for those items which are based on market rates. Only one rate of such percentage, on all the Scheduled Rates shall be framed. Tenders, which propose any alternative in the works specified in the said form of invitation to tender or in the time


Executive Engineer
Education Works Division
LARIKANO

allowed for carrying out the work, or which contain any other conditions, will be liable to rejection. No printed form of tender shall include a tender for more than one work, but if contractor wish to tender for two or more works, they shall submit a separate tender for each.

The envelope containing the tender documents shall refer the name and number of the work.

6. All works shall be measured by standard instruments according to the rules.

7. Bidders shall provide evidence of their eligibility as and when requested by the Procuring Agency.

8. Any bid received by the Agency after the deadline for submission of bids shall be rejected and returned unopened to the bidder.

9. Prior to the detailed evaluation of bids, the Procuring Agency will determine whether the bidder fulfills all codal requirements of eligibility criteria given in the tender notice such as registration with tax authorities, registration with PEC (where applicable), turnover statement, experience statement, and any other condition mentioned in the NIT and bidding document. If the bidder does not fulfill any of these conditions, it shall not be evaluated further.

10. Bid without bid security of required amount and prescribed form shall be rejected.

11. Bids determined to be substantially responsive shall be checked for any arithmetic errors. Arithmetical errors shall be rectified on the following basis;

(A) In case of schedule rates, the amount of percentage quoted above or below will be checked and added or subtracted from amount of bid of quantities to arrive the final bid cost.

(B) In case of item rates, If there is a discrepancy between the unit rate and the total cost that is obtained by multiplying the unit rate and quantity, the unit rate shall prevail and the total cost will be corrected unless in the opinion of the Agency there is an obvious misplacement of the decimal point in the unit rate, in which case the total cost as quoted will govern and the unit rate corrected. If there is a discrepancy between the total bid amount and the sum of total costs, the sum of the total costs shall prevail and the total bid amount shall be corrected.

(C) Where there is a discrepancy between the amounts in figures and in words, the amount in words will govern.


Executive Engineer
Education Works Division
LARKANO

Name of work:

Draft Bidding Document for Works up to 2.5 M

Estimated Cost: Rs.
Conditions of Contract Stamp Amount Rs=

Clause - 1: Commencement & Completion Dates of work. The contractor shall not enter upon or commence any portion or work except with the written authority and instructions of the Engineer-in-charge or of in subordinate-in-charge of the work. Failing such authority the contractor shall have no claim to ask for measurements or payment for work.

The contractor shall proceed with the works with due expedition and without delay and complete the works in the time allowed for carrying out the work as entered in the tender shall be strictly observed by the contractor and shall reckoned from the date on which the order to commence work is given to the contractor. And further to ensure good progress during the execution of the work, contractor shall be bound, in all in which the time allowed for completion of any work exceeds one month, to achieve progress on the prorate basis.

Clause - 2: Liquidated Damages. The contractor shall pay liquidated damages to the Agency at the rate per day stated in the bidding data for each day that the completion date is later than the Intended completion date; the amount of liquidated damage paid by the contractor to the Agency shall not exceed 10 per cent of the contract price. Agency may deduct liquidated damages from payments due to the contractor. Payment of liquidated damages does not affect the contractor's liabilities.

Clause - 3: Termination of the Contract.

(A) Procuring Agency/Executive Engineer may terminate the contract if either of the following conditions exists:-

- (i) contractor causes a breach of any clause of the Contract;
- (ii) the progress of any particular portion of the work is unsatisfactory and notice of 10 days has expired;
- (iii) in the case of abandonment of the work owing to the serious illness or death of the contractor or any other cause.
- (iv) contractor can also request for termination of contract if a payment certified by the Engineer is not paid to the contractor within 60 days of the date of the submission of the bill;

(B) The Executive Engineer/Procuring Agency has power to adopt any of the following courses as may deem fit:-

- (i) to forfeit the security deposit available except conditions mentioned at A (iii) and (iv) above;
- (ii) to finalize the work by measuring the work done by the contractor.

Contractor


Executive Engineer
Education Works Division
LARKANO

Sindh Public Procurement Regulatory Authority

(C) In the event of any of the above courses being adopted by the Executive Engineer/Procuring Agency, the contractor shall have:-

- (i) no claim to compensation for any loss sustained by him by reason of his having purchased or procured any materials, or entered into any engagements, or made any advances on account of, or with a view to the execution of the work or the performance of the contract,
- (ii) however, the contractor can claim for the work done at site duly certified by the executive engineer in writing regarding the performance of such work and has not been paid.

Procuring Agency/Engineer may invite fresh bids for remaining work.

Clause 4: Possession of the site and claims for compensation for delay. The Engineer shall give possession of all parts of the site to the contractor. If possession of site is not given by the date stated in the contract data, no compensation shall be allowed for any delay caused in starting of the work on account of any acquisition of land/water standing in borrow pits/ compartments or in according sanction to estimates. In such case, either date of commencement will be changed or period of completion is to be extended accordingly.

Clause -5: Extension of Intended Completion Date. The Procuring Agency either at its own initiatives before the date of completion or on desire of the contractor may extend the intended completion date, if an event (which hinders the execution of contract) occurs or a variation order is issued which makes it impossible to complete the work by the intended completion date for such period as he may think necessary or proper. The decision of the Executive Engineer in this matter shall be final; where time has been extended under this or any other clause of this agreement, the date for completion of the work shall be the date fixed by the order giving the extension or by the aggregate of all such orders, made under this agreement.

When time has been extended as aforesaid, it shall continue to be the essence of the contract and all clauses of the contract shall continue to be operative during the extended period.

Clause -6: Specifications. The contractor shall execute the whole and every part of the work in the most substantial and work-man-like manner and both as regards materials and all other matters in strict accordance with the specifications lodged in the office of the Executive Engineer and initialed by the parties, the said specification being a part of the contract. The contractor shall also confirm exactly, fully and faithfully to the designs, drawing, and instructions in writing relating to the work signed by the Engineer-in-charge and lodge in his office and to which the contractor shall be entitled to have access at such office or on the site of work for the purpose of inspection during office hours and the contractor shall, if he so requires, be entitled at his own expense to make or cause to be made copies of the specifications, and of all such designs, drawings, and instructions as aforesaid.

Contractor

Sindh Public Procurement Regulatory Authority


Executive Engineer
Education Works Division
LARKANO



Clause – 7: Payments.

- (A) **Interim/Running Bill.** A bill shall be submitted by the contractor as frequently as the progress of the work may justify for all work executed and not included in any previous bill at least once in a month and the Engineer-in-charge shall take or cause to be taken the requisite measurements for the purpose of having the same verified and the claim, as far as admissible, adjusted, if possible before the expiry of ten days from the presentation of the bill, at any time depute a subordinate to measure up the said work in the presence of the contractor or his authorized agent, whose countersignature to the measurement list will be sufficient to warrant and the Engineer-in-charge may prepare a bill from such list which shall be binding on the contractor in all respects.

The Engineer /Procuring Agency shall pass/certify the amount to be paid to the contractor, which he considers due and payable in respect thereof, subject to deduction of security deposit, advance payment if any made to him and taxes.

All such intermediate payment shall be regarded as payments by way of advance against the final payment only and not as payments for work actually done and completed, and shall not preclude the Engineer-in-charge from recoveries from final bill and rectification of defects and unsatisfactory items of works pointed out to him during defect liability period.


- (B) **The Final Bill.** A bill shall be submitted by the contractor within one month of the date fixed for the completion of the work otherwise Engineer-in-charge's certificate of the measurements and of the total amount payable for the works shall be final and binding on all parties.

Clause – 8: Reduced Rates. In cases where the items of work are not accepted as so completed, the Engineer-in-charge may make payment on account of such items at such reduced rates as he may consider reasonable in the preparation of final or on running account bills with reasons recorded in writing.

Clause – 9: Issuance of Variation and Repeat Orders.

- (A) Agency may issue a Variation Order for procurement of works, physical services from the original contractor to cover any increase or decrease in quantities, including the introduction of new work items that are either due to change of plans, design or alignment to suit actual field conditions, within the general scope and physical boundaries of the contract.
- (B) Contractor shall not perform a variation until the Procuring Agency has authorized the variation in writing subject to the limit not exceeding the contract cost by of 15% on the same conditions in all respects on which he agreed to do them in the

Contractor



Sindh Public Procurement Regulatory Authority **Executive Engineer**
Education Works Division
LARKANO



work, and at the same rates, as are specified in the tender for the main work. The contractor has no right to claim for compensation by reason of alterations or curtailment of the work.

- (C) In case the nature of the work in the variation does not correspond with items in the Bill of Quantities, the quotation by the contractor is to be in the form of new rates for the relevant items of work, and if the Engineer-in-charge is satisfied that the rate quoted is within the rate worked out by him on detailed rate analysis, and then only he shall allow him that rate after approval from higher authority.
- (D) The time for the completion of the work shall be extended in the proportion that the additional work bear to the original contract work.
- (E) In case of quantities of work executed result the Initial Contract Price to be exceeded by more than 15%, and then Engineer can adjust the rates for those quantities causing excess the cost of contract beyond 15% after approval of Superintending Engineer.
- (F) **Repeat Order:** Any cumulative variation, beyond the 15% of initial contract amount, shall be subject of another contract to be tendered out if the works are separable from the original contract.

Clause-10: Quality Control.

- (A) **Identifying Defects:** If at any time before the security deposit is refunded to the contractor/during defect liability period mentioned in bid data, the Engineer-in-charge or his subordinate-in-charge of the work may instruct the contractor to uncover and test any part of the works which he considers may have a defect due to use of unsound materials or unskillful workmanship and the contractor has to carry out a test at his own cost irrespective of work already approved or paid.
- (B) **Correction of Defects:** The contractor shall be bound forthwith to rectify or remove and reconstruct the work so specified in whole or in part, as the case may require. The contractor shall correct the notified defect within the Defects Correction Period mentioned in notice.
- (C) **Uncorrected Defects:**
 - (i) In the case of any such failure, the Engineer-in-charge shall give the contractor at least 14 days notice of his intention to use a third party to correct a defect. He may rectify or remove, and re-execute the work or remove and replace the materials or articles complained of as the case may be at the risk and expense in all respects of the contractor.

Contractor


Executive Engineer
Education Works Division
LARKANO

- (ii) If the Engineer considers that rectification/correction of a defect is not essential and it may be accepted or made use of; it shall be within his discretion to accept the same at such reduced rates as he may fix therefore.

Clause – 11:

- (A) **Inspection of Operations.** The Engineer and his subordinates shall at all reasonable times have access to the site for supervision and inspection of works under or in course of execution in pursuance of the contract and the contractor shall afford every facility for and every assistance in obtaining the right to such access.
- (B) **Dates for Inspection and Testing.** The Engineer shall give the contractor reasonable notice of the intention of the Engineer-in-charge or his subordinate to visit the work shall have been given to the contractor, then he either himself be present to receive orders and instructions, or have a responsible agent duly accredited in writing present for that purpose, orders given to the contractor's duly authorized agent shall be considered to have the same force and effect as if they had been given to the contractor himself.

Clause – 12: Examination of work before covering up.

- (A) No part of the works shall be covered up or put out of view/beyond the reach without giving notice of not less than five days to the Engineer whenever any such part of the works or foundations is or are ready or about to be ready for examination and the Engineer shall, without delay, unless he considers it unnecessary and advises the contractor accordingly, attend for the purpose of examining and measuring such part of the works or of examining such foundations;
- (B) If any work is covered up or placed beyond the reach of measurement without such notice having been given, the same shall be uncovered at the contractor's expense, and in default thereof no payment or allowance shall be made for such work, or for the materials with which the same was executed.

Clause – 13: Risks. The contractor shall be responsible for all risks of loss of or damage to physical property or facilities or related services at the premises and of personal injury and death which arise during and in consequence of its performance of the contract. If any damage is caused while the work is in progress or become apparent within three months of the grant of the certificate of completion, final or otherwise, the contractor shall make good the same at his own expense, or in default the Engineer may cause the same to be made good by other workmen, and deduct the expenses from retention money lying with the Engineer.

Contractor

Sindh Public Procurement Regulatory Authority


Executive Engineer
Education Works Division
LARKANO

Clause-14: Measures for prevention of fire and safety measures. The contractor shall not set fire to any standing jungle, trees, bush-wood or grass without a written permit from the Executive Engineer. When such permit is given, and also in all cases when destroying, cutting or uprooting trees, bush-wood, grass, etc by fire, the contractor shall take necessary measures to prevent such fire spreading to or otherwise damaging surrounding property. The contractor is responsible for the safety of all its activities including protection of the environment on and off the site. Compensation of all damage done intentionally or unintentionally on or off the site by the contractor's labour shall be paid by him.

Clause-15:Sub-contracting. The contractor shall not subcontract the whole of the works, except where otherwise provided by the contract. The contractor shall not subcontract any part of the works without the prior consent of the Engineer. Any such consent shall not relieve the contractor from any liability or obligation under the contract and he shall be responsible for the acts, defaults and neglects of any subcontractor, his agents, servants or workmen as if these acts, defaults or neglects were those of the contractor, his agents' servants or workmen. The provisions of this contract shall apply to such subcontractor or his employees as if he or it were employees of the contractor.

Clause - 16: Disputes. All disputes arising in connection with the present contract, and which cannot be amicably settled between the parties, , the decision of the Superintending Engineer of the circle/officer/one grade higher to awarding authority shall be final, conclusive and binding on all parties to the contract upon all questions relating to the meaning of the specifications, designs drawings, and instructions, hereinbefore mentioned and as to the quality of workmanship, or materials used on the work or as to any other questions, claim, right, matter, or thing whatsoever in any way arising out of, or relating to the contract design, drawings, specifications, estimates, instructions, orders or these conditions or otherwise concerning the works, or the execution, of failure to execute the same, whether arising, during the progress of the work, or after the completion or abandonment thereof.

Clause -17: Site Clearance. On completion of the work, the contractor shall be furnished with a certificate by the Executive Engineer (hereinafter called the Engineer in-charge) of such completion, but neither such certificate shall be given nor shall the work be considered to be complete until the contractor shall have removed all temporary structures and materials brought at site either for use or for operation facilities including cleaning debris and dirt at the site. If the contractor fails to comply with the requirements of this clause then Engineer-in-charge, may at the expense of the contractor remove and dispose of the same as he thinks fit and shall deduct the amount of all expenses so incurred from the contractor's retention money. The contractor shall have no claim in respect of any surplus materials as aforesaid except for any sum actually realized by the sale thereof.

Contractor



Clause -18: Financial Assistance /Advance Payment.

- (A) Mobilization advance is not allowed.
- (B) Secured Advance against materials brought at site.
- (i) Secured Advance may be permitted only against imperishable materials/quantities anticipated to be consumed/utilized on the work within a period of three months from the date of issue of secured advance and definitely not for full quantities of materials for the entire work/contract. The sum payable for such materials on site shall not exceed 75% of the market price of materials;
- (ii) Recovery of Secured Advance paid to the contractor under the above provisions shall be affected from the monthly payments on actual consumption basis, but not later than period more than three months (even if unutilized).

Clause -19: Recovery as arrears of Land Revenue. Any sum due to the Government by the contractor shall be liable for recovery as arrears of Land Revenue.

Clause -20: Refund of Security Deposit/Retention Money. On completion of the whole of the works (a work should be considered as complete for the purpose of refund of security deposit to a contractor from the last date on which its final measurements are checked by a competent authority, if such check is necessary otherwise from the last date of recording the final measurements), the defects notice period has also passed and the Engineer has certified that all defects notified to the contractor before the end of this period have been corrected, the security deposit lodged by a contractor (in cash or recovered in installments from his bills) shall be refunded to him after the expiry of three months from the date on which the work is completed.

Divisional Account Officer
Education Works Division Larkano

Contractor


Executive Engineer/Procuring Agency
Executive Engineer
Education Works Division
LARKANO

BILL OF QUANTITIES

(A) Description and rate of Items based on Composite Schedule of Rates.

Item No	Quantities	Description of item to be executed at site	Rate	Unit	Amount in Rupees
1	2	3	4	5	6
<p>Schedule B Attached Separately</p>					

Amount TOTAL (a)

PART - A
PART - B

..... % above/below on the rates of CSR.

Amount to be added/deducted on the basis
 Of premium quoted. TOTAL (b)

Total (A) = a+b in words & figures: Rs= _____

Contractor


 Executive Engineer/Procuring Agency
Executive Engineer
Education Works Division
LARKANO



(B) Description and rate of Items based on Market (Offered rates)

Item No	Quantities	Description of item to be executed at site	Rate	Unit	Amount in Rupees

Total (B) in words & figures:

Contractor


Executive Engineer/Procuring Agency
Executive Engineer
Education Works Division
LARKANO



Summary of Bill of Quantities.

Cost of Bid

Amount

1. (A) Cost based on Composite Schedule of Rates.

Rs= _____

2. (B) Cost based on Non/Offered Schedule of Rates.

TOTAL COST OF BID (C) = Total (A) + Total (B)

Rs= _____

Contractor


Executive Engineer/Procuring Agency
Executive Engineer
Education Works Division
LARKANO



SCHEDULE 'B'

Name of Work:- Construction Reconstruction of Building for Existing Primary Schools in Taluka Larkana (9 Units) (2010-11 Programme at GGMS Kehar

SN	ITEM OF WORK	Qty:	Rate	Unit	Amount.	
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15)	20.00	@ Rs: 910.0	P.Point	Rs: 18,200.00	
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742.0	P.Point	Rs: 2,226.00	
3	Providing and laying (Main or sub-Main) PVC insulated with size 2-7(029) Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	38.00	@ Rs: 171.0	P.Meter	Rs: 6,498.00	
4	Providing and laying (Main or sub-Main) PVC insulated with size 2-7(052)(10mm2) Copper conductor in 1" dia PVC conduit on surface (S.I.No: 6 P 1)	43.00	@ Rs: 428.0	P.Meter	Rs: 18,404.00	
5	Providing & Fixing A.C one way S.P 5amp switch flush type (S.I.No: 219 P 33)	17.00	@ Rs: 54.0	P.Each	Rs: 918.00	
6	Providing & Fixing 2 pin 5 amps plug & socket flush type (S.I.No: 225 P 33)	3.00	@ Rs: 83.0	P.Each	Rs: 249.00	
7	Providing & Fixing Brass Battern holder (S.I.No: 232 P 33)	12.00	@ Rs: 70.0	P.Each	Rs: 840.00	
8	P/fixing A.C Baklite Ceiling rose with two terminals (S.I.No: 228 P 33)	8.00	@ Rs: 72.0	P.Each	Rs: 576.00	
9	Providing and fixing brass ceiling fan 56" (good quality)	8.00	@ Rs: 3185.0	P.Each	Rs: 25,480.00	
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or columns & covered with plastic sheet (S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00	
11	P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00	
(Part - B) N.S.I					TOTAL:	Rs: 78,288.0
1	Fixing A.C ceiling fan regulator on S W board	6.00	@ Rs: 109.56	P.Each	Rs: 657.00	
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	6.00	@ Rs: 169.21	P.Each	Rs: 1,354.00	
3	P/F main panel board double shutter to accommodate heavy duty circuit breakers bus bar in painting.	1.00	@ Rs: 1089.51	P.Sq.ft.	Rs: 1,090.00	
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal, etc, i/c making the pit 12" deep by excavation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2" dia C.I pipe straight from the earth upto metallic electrical assembly i/c providing necessary tee.	1.00	@ Rs: 3084.4	P.Each	Rs: 3,084.00	
5	P/F Energy saver superior quality i/c fixing on extg. holder etc complete.	13.00	@ Rs: 596.40	P.Each	Rs: 7,753.00	
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	4.00	@ Rs: 596.40	P.Each	Rs: 2,386.00	
7	P/F hinged type double S W board accommodate main or sub-main control switches and for other similar jobs.	3.00	@ Rs: 140.26	P.Each	Rs: 420.00	
					Part 'B' TOTAL:	Rs: 16,744.0
					Part 'A' TOTAL:	Rs: 78,288.0
					TOTAL:	Rs: 95,032.0

XEN

SCHEDULE 'B'

Name of Work:- Construction Reconstruction of Buliding for Existing Primary Schools in
Taluka Larkana (9 Units) (2010-11 Programme at: GBPS Gul Muhammad Brohi

(2)

SN	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	17.00	@ Rs: 910.0	P.Point	Rs: 15,470.00
2	Wiring for Plug polint with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742.0	P.Point	Rs: 2,226.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	38.00	@ Rs: 171.0	P.Meter	Rs: 6,498.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-/052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	89.00	@ Rs: 428.0	P.Meter	Rs: 38,092.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	16.00	@ Rs: 54.0	P.Each	Rs: 864.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs: 83.0	P.Each	Rs: 249.00
7	Providing & Fixing Brass Battern holder.(S.I.No: 232 P 33)	13.00	@ Rs: 70.0	P.Each	Rs: 910.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	4.00	@ Rs: 72.0	P.Each	Rs: 288.00
9	Providing and fixing brass ceiling fan 56" (good quality).	4.00	@ Rs: 3185.0	P.Each	Rs: 12,740.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet (S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
(Part - B) N.S.I					
TOTAL:					Rs: 82,234.0
1	Fixing A.C ceiling fan regulator on S.W board.	4.00	@ Rs: 109.56	P.Each	Rs: 438.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	4.00	@ Rs: 169.21	P.Each	Rs: 677.00
3	P/F main panel board double shutter to accommodate heavey duty circuit breakers bus bar ine painting	1.00	@ Rs: 1089.5	P.Sq.ft.	Rs: 1,090.00
5	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.	13.00	@ Rs: 596.40	P.Each	Rs: 7,753.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	4.00	@ Rs: 596.40	P.Each	Rs: 2,386.00
7	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.	3.00	@ Rs: 140.26	P.Each	Rs: 420.00
Part 'B' TOTAL:					Rs: 12,764.0
Part 'A' TOTAL:					Rs: 82,234.0
TOTAL:					Rs: 94,998.0


XEN

SCHEDULE 'B'

3

Name of Work:- Construction Reconstruction of Buliding for Existing Primary Schools in Taluka Larkana (9 Units) (2010-11 Programme at: GBPS Arija Phero

SN	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	20.00	@ Rs: 910.0	P.Point	Rs: 18,200.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742.0	P.Point	Rs: 2,226.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029) Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	40.00	@ Rs: 171.0	P.Meter	Rs: 6,840.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-1.052)(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	55.00	@ Rs: 428.0	P.Meter	Rs: 23,540.00
5	Providing & Fixing A.C one way S.P 5ampswitch flush type (S.I.No: 219 P 33)	23.00	@ Rs: 54.0	P.Each	Rs: 1,242.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs: 83.0	P.Each	Rs: 249.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	12.00	@ Rs: 70.0	P.Each	Rs: 840.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	8.00	@ Rs: 72.0	P.Each	Rs: 576.00
9	Providing and fixing brass ceiling fan 56" (good quality).	8.00	@ Rs: 3185.0	P.Each	Rs: 25,480.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet.(S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Cirecuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
(Part - B) N.S.I					TOTAL: Rs: 84,090.0
1	Fixing A.C ceiling fan regulator on S.W board.	8.00	@ Rs: 109.56	P.Each	Rs: 880.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	8.00	@ Rs: 169.21	P.Each	Rs: 1,354.00
3	P/F main panel board double shutter to accommodate heavey duty circuit breakersbus bar ine painting.	1.00	@ Rs: 1089.5	P.Sq:ft:	Rs: 1,090.00
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavcation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee,	1.00	@ Rs: 3084.4	P.Each	Rs: 3,084.00
5	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.	12.00	@ Rs: 596.40	P.Each	Rs: 7,157.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	3.00	@ Rs: 596.40	P.Each	Rs: 1,789.00
7	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.	3.00	@ Rs: 140.26	P.Each	Rs: 420.00
Part 'B' TOTAL:					Rs: 15,774.0
Part 'A' TOTAL:					Rs: 84,090.0
TOTAL:					Rs: 99,864.0

4

SCHEDULE 'B'

Name of Work:- Construction Reconstruction of Buliding for Existing Primary Schools in
Taluka Larkana (9 Units) (2010-11 Programme at: GBPS Jhangar

SN	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	18.00	@ Rs: 910.0	P.Point	Rs: 16,380.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742.0	P.Point	Rs: 2,226.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	45.00	@ Rs: 171.0	P.Meter	Rs: 7,695.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-/052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	30.00	@ Rs: 428.0	P.Meter	Rs: 12,840.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	21.00	@ Rs: 54.0	P.Each	Rs: 1,134.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs: 83.0	P.Each	Rs: 249.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	9.00	@ Rs: 70.0	P.Each	Rs: 630.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	8.00	@ Rs: 72.0	P.Each	Rs: 576.00
9	Providing and fixing brass ceiling fan 56" (good quality).	8.00	@ Rs: 3185.0	P.Each	Rs: 25,480.00
10	P/F Cirecuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	4.00	@ Rs: 948.0	P.Each	Rs: 3,792.00

TOTAL: Rs: 71,002.0

(Part - B) N.S.I

1	Fixing A.C ceiling fan regulator on S.W board.	8.00	@ Rs: 109.56	P.Each	Rs: 876.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	8.00	@ Rs: 169.21	P.Each	Rs: 1,354.00
3	P/F main panel board double shutter to accommodate heavey duty circuit breakers bus bar ine painting.	1.00	@ Rs: 1089.54	P.Sq:ft	Rs: 1,090.00
4	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.	9.00	@ Rs: 596.40	P.Each	Rs: 5,368.00
5	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.	2.00	@ Rs: 140.26	P.Each	Rs: 281.00

Part 'B' TOTAL: Rs: 8,969.0

Part 'A' TOTAL: Rs: 71,002.0

TOTAL: Rs: 79,971.0


XEN

SCHEDULE 'B'

Name of Work:- Integrataed Re habilitation of Primary School in Taluka Larkana (16 units)
(2010-11 Progg:) at:GGPS Rohal Khan Bughti Taluka Larkano

SN	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15)	18.00	@ Rs: 910.0	P.Point	Rs: 16,380.00
2	Wiring for Plug polint with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742.0	P.Point	Rs: 2,226.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	34.00	@ Rs: 171.0	P.Meter	Rs: 5,814.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-/052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	25.00	@ Rs: 428.0	P.Meter	Rs: 10,700.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	21.00	@ Rs: 54.0	P.Each	Rs: 1,134.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs: 83.0	P.Each	Rs: 249.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	9.00	@ Rs: 70.0	P.Each	Rs: 630.00
8	P/Fixing A.C Baklite Ceiling rose with two terminls .(S.I.No: 228 P 33)	8.00	@ Rs: 72.0	P.Each	Rs: 576.00
9	Providing and fixing brass ceiling fan 56" (good quality).	8.00	@ Rs: 3185.0	P.Each	Rs: 25,480.00
10	P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I No: 2 P 20)	3.00	@ Rs: 948.0	P.Each	Rs: 2,844.00
TOTAL:					Rs: 66,033.0
(Part - B) N.S.I					
1	Fixing A.C ceiling fan regulator on S.W board.	8.00	@ Rs: 109.56	P.Each	Rs: 876.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	8.00	@ Rs: 169.21	P.Each	Rs: 1,354.00
3	P/F main panel board double shutter to accommodate heavey duty circuit breakers bus bar ine painting	1.00	@ Rs: 1089.54	P.Sq.ft:	Rs: 1,090.00
4	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.	9.00	@ Rs: 596.40	P.Each	Rs: 5,368.00
5	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.	2.00	@ Rs: 140.26	P.Each	Rs: 281.00
Part 'B' TOTAL:					Rs: 8,969.0
Part 'A' TOTAL:					Rs: 66,033.0
TOTAL:					Rs: 75,002.0


XEN

SCHEDULE 'B'

6

Name of Work:- Integrated Rehabilitation of Primary Schools in Taluka Ratodero
(13 Units) (2010-11 programme) at:GBPS Hashim Bozdar

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	21.00	@ Rs: 910.0	P.Point	Rs: 19,110.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	4.00	@ Rs: 742.0	P.Point	Rs: 2,968.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	60.00	@ Rs: 171.0	P.Meter	Rs: 10,260.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	63.00	@ Rs: 428.0	P.Meter	Rs: 26,964.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	21.00	@ Rs: 54.0	P.Each	Rs: 1,134.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	4.00	@ Rs: 83.0	P.Each	Rs: 332.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	13.00	@ Rs: 70.0	P.Each	Rs: 910.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	8.00	@ Rs: 72.0	P.Each	Rs: 576.00
9	Providing and fixing brass ceiling fan 56" (good quality).	8.00	@ Rs: 3185.0	P.Each	Rs: 25,480.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet.(S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
TOTAL:					Rs: 92,631.0



SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
(Part - B) N.S.I					
1	Fixing A.C ceiling fan regulator on S W board. 8.00	@ Rs: 109.56	P.Each	Rs:	876.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof. 8.00	@ Rs: 169.21	P.Each	Rs:	1,354.00
3	P/F main panel board double shutter to accommodate heavey duty circuit breakers bus bar inc painting. 1.00	@ Rs: 1089.55	P.Sq.ft:	Rs:	1,090.00
4	P/F Earthing set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal etc,i.c making the pit 12" deep by excavcation of all type of soil. Earth Plate to be connected with No.8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assarary i/c providing necessary tee, 1.00	@ Rs: 3084.44	P.Each	Rs:	3,084.00
5	P/F Energy saver superior quality i/c fixing on extg: holder etc complete. 13.00	@ Rs: 596.40	P.Each	Rs:	7,753.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete. 4.00	@ Rs: 596.40	P.Each	Rs:	2,386.00
7	P/F hinged type double S W board accommodate main or sub-main control switches and for other similar jobs. 4.00	@ Rs: 140.26	P.Each	Rs:	561.00
				Part 'B' TOTAL:	Rs: 17,104.0
				Part 'A' TOTAL:	Rs: 92,631.0
				TOTAL:	Rs: 109,735.0


XEN

SCHEDULE 'B'

Name of Work:- Integrated Rehabilitation of Primary Schools in Taluka Ratodero
(13 Units) (2010-11 programme) at:GBPS Khairodero

7

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	18.00	@ Rs: 910.0	P.Point	Rs: 16,380.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742.0	P.Point	Rs: 2,226.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	45.00	@ Rs: 171.0	P.Meter	Rs: 7,695.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/052}(10mm2) Copper conductor in 1" dia PVC conduit on surface (S.I.No: 6 P 1).	30.00	@ Rs: 428.0	P.Meter	Rs: 12,840.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	21.00	@ Rs: 54.0	P.Each	Rs: 1,134.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type (S.I.No: 225 P 33).	3.00	@ Rs: 83.0	P.Each	Rs: 249.00
7	Providing & Fixing Brass Battern holder. (S.I.No: 232 P 33)	9.00	@ Rs: 70.0	P.Each	Rs: 630.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals. (S.I.No: 228 P 33)	9.00	@ Rs: 72.0	P.Each	Rs: 648.00
9	Providing and fixing brass ceiling fan 56" (good quality).	9.00	@ Rs: 3185.0	P.Each	Rs: 28,665.00
10	P/F Circuit breakers 6 Amps to 63 Amps. D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
TOTAL:					Rs: 75,207.0
(Part - B) N.S.I					
1	Fixing A.C ceiling fan regulator on S.W board.	9.00	@ Rs: 109.56	P.Each	Rs: 986.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	9.00	@ Rs: 169.21	P.Each	Rs: 1,523.00
3	P/F main panel board double shutter to accommodate heavey duty circuit breakers bus bar ine painting.	1.00	@ Rs: 1089.55	P.Sq.ft.	Rs: 1,090.00
4	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.	9.00	@ Rs: 596.40	P.Each	Rs: 5,368.00
5	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.	5.00	@ Rs: 140.26	P.Each	Rs: 701.00
Part 'B' TOTAL:					Rs: 9,668.0
Part 'A' TOTAL:					Rs: 75,207.0
TOTAL:					Rs: 84,875.0

SCHEDULE 'B'

8

Name of Work:- Integrataed Re habilitation of Primary School in Taluka Bakrani (13 units)
(2010-11 Progg:) at:GGPS Kot Mirza KaloTaluka Bakrani

SN	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	20.00	@ Rs: 910.0	P.Point	Rs: 18,200.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20:am(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742.0	P.Point	Rs: 2,226.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	40.00	@ Rs: 171.0	P.Meter	Rs: 6,840.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-/052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	55.00	@ Rs: 428.0	P.Meter	Rs: 23,540.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	25.00	@ Rs: 54.0	P.Each	Rs: 1,350.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs: 83.0	P.Each	Rs: 249.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	12.00	@ Rs: 70.0	P.Each	Rs: 840.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals. (S.I.No: 228 P 33)	8.00	@ Rs: 72.0	P.Each	Rs: 576.00
9	Providing and fixing brass ceiling fan 56" (good quality).	8.00	@ Rs: 3185.0	P.Each	Rs: 25,480.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet (S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
(Part - B) N.S.I					
1	Fixing A.C ceiling fan regulator on S.W board.	8.00	@ Rs: 109.56	P.Each	Rs: 880.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	9.00	@ Rs: 169.21	P.Each	Rs: 1,354.00
3	P/F main panel board double shutter to accommodate heavey duty circuit breakers bus bar ine painting.	1.00	@ Rs: 1089.51	P.Sq.ft.	Rs: 1,090.00
4	P/F Earthing set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavcation of all type of soil. Earth Plate to be connected with No.8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee.	1.00	@ Rs: 3084.4	P.Each	Rs: 3,084.00
5	P/F Energy saver superior quality i/c fixing on extg. holder etc complete.	12.00	@ Rs: 596.40	P.Each	Rs: 7,157.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	3.00	@ Rs: 596.40	P.Each	Rs: 1,789.00
7	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.	3.00	@ Rs: 140.26	P.Each	Rs: 420.00
Part 'B' TOTAL:					Rs: 15,774.0
Part 'A' TOTAL:					Rs: 84,198.0
TOTAL:					Rs: 99,972.0


XEN

9

SCHEDULE 'B'

Name of Work:- Integrated Rehabilitation of Primary Schools in Taluka Dokri
(11 Units)(2010-11 Progg.) at: GBPS Badeh Main Taluka Dokri.

SN	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	100.00	@ Rs: 910.0	P.Point	Rs: 91,000.00
2	Wiring for Plug polint with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	6.00	@ Rs: 742.0	P.Point	Rs: 4,452.00
3	Wiring for Call beel with 1/1.13 (3/029) PVC insulated wire in 20mm(3/4")PVC conduit rescessed in the coloumns as required (S.I.No: 128 P 15)	3.00	@ Rs: 1764.0	P.Point	Rs: 5292.0
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	200.00	@ Rs: 171.0	P.Meter	Rs: 34,200.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7.044} Copper conductor in 1" dia PVC conduit on surface (S.I.No: 6 P 1).	100.00	@ Rs: 305.0	P.Meter	Rs: 30,500.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	92.00	@ Rs: 428.0	P.Meter	Rs: 39,376.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	98.00	@ Rs: 54.0	P.Each	Rs: 5,292.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type (S.I.No: 225 P 33).	6.00	@ Rs: 83.0	P.Each	Rs: 498.00
7	Providing & Fixing Brass Batiern holder..(S.I.No: 232 P 33)	19.00	@ Rs: 70.0	P.Each	Rs: 1,368.00
8	P/Fixing A.C Baklite Coiling rose with two terminals (S.I.No: 228 P 33)	13.00	@ Rs: 72.0	P.Each	Rs: 936.00
9	Providing and fixing brass ceiling fan 56" (good quality).	30.00	@ Rs: 3185.0	P.Each	Rs: 95,550.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet.(S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	10.00	@ Rs: 948.02	P.Each	Rs: 9,480.00
12	P/F Circuit breakers 15,20,30,40,50,60,75 & 100 Amps (T P (XS-100 NS) on a prepared board as required (S.I.No: 207 P 31)	2.00	@ Rs: 9261.0	P.Each	Rs: 18,522.00
TOTAL					336,606.00


XEN

SN	ITEM OF WORK	Qty:	Rate	Unit	Amount.
----	--------------	------	------	------	---------

(Part - B) N.S.I

1	Fixing A.C ceiling fan regulator on S.W board.				
	22.00 @ Rs. 109.56 P.Each			Rs:	2,410.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.				
	22.00 @ Rs. 169.21 P.Each			Rs:	3,723.00
3	P/F main panel board double shutter to accommodate heavy duty circuit breakers bus bar in painting.				
	6.00 @ Rs. 1089.51 P Sq.ft.			Rs:	6,537.00
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal, etc, i.c making the pit 12" deep by excavation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2" dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee.				
	1.00 @ Rs. 3084.4 P.Each			Rs:	3,084.00
5	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.				
	60.00 @ Rs. 596.40 P.Each			Rs:	35,784.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.				
	14.00 @ Rs. 596.40 P.Each			Rs:	8,350.00
7	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.				
	25.00 @ Rs. 140.26 P.Each			Rs:	3,506.00

Part 'B' TOTAL: Rs: **63,394.0**

Part 'A' TOTAL: Rs: **336,606.0**

TOTAL: Rs: **400,000.0**


XEN

SCHEDULE-B

Name of Work:- Integrated Rehabilitation of Primary Schools in Taluka Dokri
 (2010-11 Prog:) At: Govt: (Boys) Primary School Safar ¹⁰
Mul-ed Safar Taluka Dokri

S.No	DESCRIPTION	QUANTITY	RATE	UNIT	Rs:	AMOUNT
1	Excavation in foundation of building bridges and other structure member with excavated le chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).	170.00	@ Rs: 3176.25	%0 Cft	Rs:	540.00
2	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P/ (Eight Thousand Six Hund:Ninty Four & P.S Ninty five	267.00	@Rs: 8694.95	% Cft	Rs:	23243.00
3	Pacca brick work in foundation and plinth in cement sand mortor ration 1:6 (S.I No 4 (C) (Eleven Thousand Nine Hund: Fourty Eight & P.S	287.00	@ Rs: 11948.36	% S.ft	Rs:	34276.00
4	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls R (Rs: Four Thousand Four Hundred Eleven & P.S Eight	680.00	@ Rs: 3275.50	% S.ft	Rs:	22273.00
5	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/70) (Five Thousand One &P.S Seventy).	0.540	@ Rs: 5001.70	P.CWt	Rs:	2701.00
6	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or laid in position complete in all respect ratio 1:2:4 (S.I No. 6 (a) P/18) (Three Hundred Thirty Seven only)	8.00	@Rs: 337.0	P.Cft	Rs:	2527.00
7	S/F sand floor and plugging into walls (S.I.No 29 P/31). (Rs:One Thousand One Hund: Fourty One & P.S Twe	17850.00	@Rs: 1141.25	%Cft	Rs:	203713.00
B	Extra Lead (03) Miles (Rs:One Thousand One Hund: Fourty One & P.S Twe	17850.00	@Rs: 579.41	%Cft	Rs:	103424.00
					Rs:	392696.00

D
EN

11

SCHEDULE 'B'

Name of Work:- Construction of building for Existing Shelterless Primary Schools in Taluka Ratodero
(5 Units) (2011-12 programme at:GBPS Maree Goth near Grid Station

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	21.00	@ Rs: 910.0	P.Point	Rs: 19,110.00
2	Wiring for Plug polint with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	4.00	@ Rs: 742.0	P.Point	Rs: 2,968.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	60.00	@ Rs: 171.0	P.Meter	Rs: 10,260.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	63.00	@ Rs: 428.0	P.Meter	Rs: 26,964.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	21.00	@ Rs: 54.0	P.Each	Rs: 1,134.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	4.00	@ Rs: 83.0	P.Each	Rs: 332.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	13.00	@ Rs: 70.0	P.Each	Rs: 910.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	8.00	@ Rs: 72.0	P.Each	Rs: 576.00
9	Providing and fixing brass ceiling fan 56" (good quality).	8.00	@ Rs: 3185.0	P.Each	Rs: 25,480.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet.(S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Cirecuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
TOTAL:					Rs: 92,631.0


XEN

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
(Part - B) N.S.I					
1	Fixing A.C ceiling fan regulator on S.W board.	8.00	@ Rs: 109.56	P.Each	Rs: 876.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	8.00	@ Rs: 169.21	P.Each	Rs: 1,354.00
3	P/F main panel board double shutter to accommodate heavey duty circuit breakers bus bar ine painting.	1.00	@ Rs: 1089.55	P.Sq:ft:	Rs: 1,090.00
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavcation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2" dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee,	1.00	@ Rs: 3084.44	P.Each	Rs: 3,084.00
5	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.	13.00	@ Rs: 596.40	P.Each	Rs: 7,753.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	4.00	@ Rs: 596.40	P.Each	Rs: 2,386.00
7	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.	4.00	@ Rs: 140.26	P.Each	Rs: 561.00
Part 'B' TOTAL:					Rs: 17,104.0
Part 'A' TOTAL:					Rs: 92,631.0
TOTAL:					Rs: 109,735.0

XEN

Name of Work:- Constl: of building for existing Shelterless Primary Schools in Taluka Larkana (5 units)
(2011-12 Progg:) at:GBPS Sasti Basti Taluka Larkana

SN	ITEM OF WORK	Qty:	Rate	Unit	Amount.	
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	20.00	@ Rs: 910.0	P.Point	Rs: 18,200.00	
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742.0	P.Point	Rs: 2,226.00	
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029) Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	40.00	@ Rs: 171.0	P.Meter	Rs: 6,840.00	
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7.052)(10mm2) Copper conductor in 1" dia PVC conduit on surface (S.I.No: 6 P 1)	78.00	@ Rs: 428.0	P Meter	Rs: 33,384.00	
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	28.00	@ Rs: 54.0	P.Each	Rs: 1,512.00	
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs: 83.0	P.Each	Rs: 249.00	
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	12.00	@ Rs: 70.0	P.Each	Rs: 840.00	
8	P/Fixing A.C Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	8.00	@ Rs: 72.0	P.Each	Rs: 576.00	
9	Providing and fixing brass ceiling fan 56" (good quality).	8.00	@ Rs: 3185.0	P.Each	Rs: 25,480.00	
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet.(S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00	
11	P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00	
(Part - B) N.S.I					TOTAL	94,204.00
1	Fixing A.C ceiling fan regulator on S.W board.	8.00	@ Rs: 109.56	P.Each	Rs: 880.00	
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	8.00	@ Rs: 169.21	P.Each	Rs: 1,354.00	
3	P/F main panel board double shutter to accommodate heavey duty circuit breakers bus bar ine painting.	1.00	@ Rs: 1089.5	P.Sq.ft:	Rs: 1,090.00	
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee.	1.00	@ Rs: 3084.4	P.Each	Rs: 3,084.00	
5	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.	12.00	@ Rs: 596.40	P.Each	Rs: 7,157.00	
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	3.00	@ Rs: 596.40	P.Each	Rs: 1,789.00	
7	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.	3.00	@ Rs: 140.26	P.Each	Rs: 420.00	
Part 'B' TOTAL:					Rs: 15,774.0	
Part 'A' TOTAL:					Rs: 94,204.0	
TOTAL:					Rs: 109,978.0	


XEN

SCHEDULE 'B'

13

Name of Work:- Rehabilitation of Bulding for Existing Primary Schools in Taluka Larkana
(14 Units) (2011-12 Programme at: GBPS Khan Muhammad Jhinjhan

SN	ITEM OF WORK	Qty:	Rate	Unit	Amount.	
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	20.00	@ Rs: 910.0	P.Point	Rs: 18,200.00	
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742.0	P.Point	Rs: 2,226.00	
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	40.00	@ Rs: 171.0	P.Meter	Rs: 6,840.00	
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	55.00	@ Rs: 428.0	P.Meter	Rs: 23,540.00	
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	25.00	@ Rs: 54.0	P.Each	Rs: 1,350.00	
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs: 83.0	P.Each	Rs: 249.00	
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	12.00	@ Rs: 70.0	P.Each	Rs: 840.00	
8	P/Fixing A.C Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	8.00	@ Rs: 72.0	P.Each	Rs: 576.00	
9	Providing and fixing brass ceiling fan 56" (good quality).	3.00	@ Rs: 3185.0	P.Each	Rs: 25,480.00	
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet.(S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00	
11	P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00	
(Part - B) N.S.I					TOTAL:	Rs: 84,198.0
1	Fixing A.C ceiling fan regulator on S W board.	8.00	@ Rs: 109.56	P.Each	Rs: 880.00	
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	3.00	@ Rs: 169.21	P.Each	Rs: 1,354.00	
3	P/F main panel board double shutter to accommodate heavey duty circuit breakersbus bar ine painting.	1.00	@ Rs: 1089.5	P.Sq.ft:	Rs: 1,090.00	
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i,c making the pit 12" deep by excavcation of all type of soil. Earth Plate to be connected with No 8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee,	1.00	@ Rs: 3084.4	P.Each	Rs: 3,084.00	
5	P/F Energy saver superior quality i/c fixing on extg. holder etc complete.	12.00	@ Rs: 596.40	P.Each	Rs: 7,157.00	
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete	3.00	@ Rs: 596.40	P.Each	Rs: 1,789.00	
7	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.	3.00	@ Rs: 140.26	P.Each	Rs: 420.00	
Part 'B' TOTAL:					Rs: 15,774.0	
Part 'A' TOTAL:					Rs: 84,198.0	
TOTAL:					Rs: 99,972.0	


XEN

Schedule-B

14

Name of Work:- REHABILITATION OF BUILDING FOR EXISTING PRIMARY / MIDDLE SCHOOLS IN TALUKA RATODERO (2011-12 PROGRAMME) (10 UNITS) @ GBPS PANJODERO (OLD PORTION) (BALANCE WORK) TALUKA RATODERO DISTRICT LARKANO. AOP 196

Sr.	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.	207.00	@ Rs: 3,176.25	% 0Cft	Rs: 657
	(Thirty one Hundred seventy six rup: & twenty five paisa only)				
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge Ratio 1:5:10. (S.I No. 4 P/14)	1468.00	@ Rs: 8,694.95	% Cft	Rs: 127,642
	(Eighty six hund: ninty four rup: & ninty five paisa only)				
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	273.00	@ Rs: 11,948.36	% Cft	Rs: 32,619
	(Eleven thousand nine hund: forty eight rup: & thirty six paisa only)				
4	Providing and Laying 1" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)				
(A)	<u>3" Thick</u>	4287.00	@ Rs: 4,411.82	% Sft	Rs: 189,135
	(Forry four hundred eleven rup: & eighty two paisa only)				
5	Filling Watering and ramming earth Under floor with Surplus Earth (Excavated from outside) lead upto one chain and lift upto 5 feet (S.I. No. 22 P/4)	4247.00	@ Rs: 1,512.0	% 0Cft	Rs: 6,421
	(Fifteen hundre & twelve rupees only)				
6	Supply and fixing sand under floor including plugging in to walls	2123.00	@ Rs: 1,141.25	% Cft	Rs: 24,229
	(Eleven hundred forty one rupees & twenty five paisa only)				
7	Pacca brick work other than building i/c striking of joints in cement sand mortar ratio 1:6.	218.00	@ Rs: 12,346.75	% Cft	Rs: 26,916
	(Twelve thousand three hund: forty six rup: & seventy five paisa only)				
8	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)	363.00	@ Rs: 2,206.60	% Cft	Rs: 8,010
	(Twenty tow hund: six rup: & sixty paisa only)				
9	Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)	363.00	@ Rs: 2,197.52	% Sft	Rs: 7,977
	(Twenty one hund: ninty seven rup: & fifty two paisa only)				
10	Making Notice board made with cement.	32.00	@ Rs: 58.11	P. Sft	Rs: 1,860
	(Fifty eight rupees & Eleven paisa only)				


XEN

Sr. Description Qty

11 Primary coat of chalk distemper(S.I No. 25 P/53)

363.00 @ Rs: 442.75 % Sft Rs: 1,607
(Four hundred forty two rupees & seventy five paisa only)

12 Distemping Three Coats (S.I No. 24 P/53)

363.00 @ Rs: 1,079.65 % Sft Rs: 3,919
(One thousand Seventy nine rup: & sixty five paisa only)

13 Preparing surface & painting with weather coat i/c rubbing the surface with rubbing brick / sand paper filling the voids with chalk / plaster then painting with weather Two coats of approved make (New Surface). (38 (a) P/55)

363.00 @ Rs: 1,498.48 % Cft Rs: 5,439
(One thousand Four hund: Ninety eight rup: & Forty Eight paisa only)

14 Providing & lying HALLA or pattern tiles glazed 8"x8"x1/4" on floor or wall facing in required floor & pattern of STILE specification jointed in white cement & pigment over a base of 1:2 grey cement mortar 3/4" thick etc i/c the cost of polish & cutting t

28.00 @ Rs: 34,520.31 % Sft Rs: 9,666
(Tharly Four Thousand Five hund: Twenty rup: & Thirty One paisa only)

Total Rs. 446,097


XEN

PART - B

- 1 P/F squatting type white glazed earthen ware W.C pan of with i/c cost of flushing cistern with internal tilting & flush pipe with bend making good in cement concrete 1:2:4. (i) W.C not less than 19" clear opening b/w flushing & 6 gallons flushing tank with

2.00 @ Rs: 4,846.80 P. No. Rs. 9,694
(Forty eight hundred forty six rup: & eighty paisa only)

- 2 Providing G.I pipe specials & clamps etc i/c fixing, cutting & fitting complete two coats of after cleaning the pipe etc with white zink paint with pigment to match the colour of the building & testing the pressure head of 200" & handling.

(a) 1" dia

12.00 @ Rs: 76.21 P. Rft Rs. 915
(Seventy Six rupees Twenty One paisa only)

(b) 3/4" dia

24.00 @ Rs: 95.79 P. Rft Rs. 2,299
(Ninty five rupees seventy nine paisa only)

- 3 P/F approved quality A.C motor pumping set (Javed Engineering) made 1-1/4" 1" section & delivery with base & complying 1 H.Power single phase motor (Siemens make) 60" ft; head of 2800 KPM i/c the cost of C.I fitting nuts, bolts & the cost of 1:2:4 plate f

1.00 @ Rs: 5,115.00 P. No. Rs. 5,115
(Fifty one hundred fifteen rupees only)

- 4 S/F Fibre Glass Tank of approved quality & design & wall thickness as specified i/c the cost of nuts, bolts & fixing in plate form of cement concrete 1:2:6 & making connection for inlet-outlet & over flow pipe etc complete. (250 Gallons).

250.00 @ Rs: 87.95 P. Gallon Rs. 21,988
(Eighty Seven rup: & Ninety Five paisa only)

Total Rs. 40,685

N.S.I Rs. 5,115

Grand Total	Rs. (S.I)	24,775
-------------	-----------	--------


XEN

SCHEDULE 'B'

Name of Work:- Construction of Additional class rooms in Existing Primary Schools in Taluka Ratodero
16 Class Rooms (2011-12 Programme at: GBPS Usman Unar (2 C.R)

15

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1 13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	20.00	@ Rs: 910.0	P Point	Rs: 18,200.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742.0	P.Point	Rs: 2,226.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	40.00	@ Rs: 171.0	P.Meter	Rs: 6,840.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-/052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	55.00	@ Rs: 428.0	P.Meter	Rs: 23,540.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	23.00	@ Rs: 54.0	P.Each	Rs: 1,242.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs: 83.0	P.Each	Rs: 249.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	12.00	@ Rs: 70.0	P.Each	Rs: 840.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals (S.I.No: 228 P 33)	8.00	@ Rs: 72.0	P.Each	Rs: 576.00
9	Providing and fixing brass ceiling fan 56" (good quality).	8.00	@ Rs: 3185.0	P.Each	Rs: 25,480.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet (S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Cirecuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
				TOTAL:	Rs: 84,090.0



SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
(Part - B) N.S.I					
1	Fixing A.C ceiling fan regulator on S.W board. 8.00	@ Rs: 109.56	P.Each	Rs:	880.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof. 8.00	@ Rs: 169.21	P.Each	Rs:	1,354.00
3	P/F main panel board double shutter to accommodate heavy duty circuit breakers bus bar in painting. 1.00	@ Rs: 1089.55	P.Sq.ft:	Rs:	1,090.00
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal, etc. i.c making the pit 12" deep by excavation of all type of soil. Earth Plate to be connected with No.8 S.W.G bare copper wire run in 1/2" dia C.I pipe straight from the earth upto metallie electrical assary i/c providing necessary tee. 1.00	@ Rs: 3084.44	P.Each	Rs:	3,084.00
5	P/F Energy saver superior quality i/c fixing on extg: holder etc complete. 12.00	@ Rs: 596.40	P.Each	Rs:	7,157.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete. 3.00	@ Rs: 596.40	P.Each	Rs:	1,789.00
7	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs. 3.00	@ Rs: 140.26	P.Each	Rs:	420.00
				Part 'B' TOTAL:	Rs: 15,774.0
				Part 'A' TOTAL:	Rs: 84,090.0
				TOTAL:	Rs: 99,864.0


XEN

SCHEDULE "B"

16

**CONSTRUCTION OF ADDITIONAL C/ROOMS IN EXISTING
PRIMARY SCHOOLS IN TALUKA RATODERO (2011-12) PROG:
(16 CLASS ROOMS). @ GBPS ALI HASSAN JUNEJO (1 CR).**

S.No.	Description	Qty:	Rate	Unit	Amount
1	Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).	816.00	@ Rs: 3:76/25	% Cft	Rs: 2,591.00 (Rs: three thous: one hund: seventy hund: twenty five only)
2	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No: P/).	245.00	@ Rs: 8694/95	% Cft	Rs: 21,302.00 (Rs: eight thous: six hund: ninty four & ninty five only)
3	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (a) P/20)	665.00	@ Rs:11948/36	% Cft	Rs: 79,456.00 (Rs: eleven thous: nine hund: eighty five & thirty six only)
4	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).	533.00	@ Rs:337/-	P.Cft	Rs: 179,621.00 (Rs: three hund: thirty seven only)
5	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)	26.00	@ Rs:5001/70	P.Cwt	Rs: 130,044.00 (Rs: five thous: one & seventy only)
6	Supplying and filling sand under floor and plugging in walls.(S.I.No: 29 P/25).	1272.00	@ Rs: 1141/25	% Cft	Rs: 14,516.00 (Rs: one thous: one hund: forty one & twenty five only)
7	Extra lead 3.0 miles	1272.00	@ Rs: 579/41	% Cft	Rs: 7,370.00 (Rs: five hund: sevnty nine & forty one only)
8	Providing and laying single per layer of polythene sheet 0.13 mm thick for water proffing as per specification and instruction of Engineer incharge. (S.I.No: 38 P/37).	163.00	@ Rs:10/70	P.Sft	Rs: 1,744.00 (Rs: ten & seventy only)


XEN

S.No:	Description:	Qty:	Rate	Unit	Amount
9	Dry rammed brick or stone ballast 1 1/2" to 2" guage. (S.I.No.2 P/14).				
		137.00	@ Rs: 3327/50	% Cft	Rs: 4,558.00
			(Rs: three thous: two hund: twenty seven & fifty only)		
10	Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).				
		1077.00	@ Rs:12674/36	% Cft	Rs: 136,502.00
			(Rs: tweleve thous: six hund: seventy four & thirty six only)		
11	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: P.).				
		28.00	@ Rs:228/90	P.Rft	Rs: 6,409.00
			(Rs: two hund: twenty eight & ninty only)		
12	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: 29 P. 98).				
		114.00	@ Rs: 240/50	P.Rft	Rs: 27,417.00
			(Rs: two hund: forty & fifty only)		
13	Suppling M.S square, bar 5/8" dia (Sch: of matrial).				
		1.00	@ Rs: 3350/-	P.Cwt	Rs: 3,550.00
			(Rs: three thous: three hund; fifty only)		
14	Cutting and fixing iron bars for barred windows. (S.I.No.18 P/97).				
		26.00	@ Rs: 28/23	P.Bar	Rs: 733.00
			(Rs: twenty eight & twenty five only)		
15	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4" thick. (Only Shutters).				
		72.00	@ Rs: 902/93	P.Sft	Rs: 65,010.00
			(Rs: nine hud: two & ninty three only)		
16	Cement plaster 1:3 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).				
		2013.00	@ Rs:2206/60	% Sft	Rs: 44,418.00
			(Rs: two thous: two hund: six & sixty only)		
17	Cement plaster 1:3 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).				
		1981.00	@ Rs:2197/52	% Sft	Rs: 43,532.00
			(Rs: two thous: one hund: ninty seven & twenty two only)		


XEN

S.No:	Description	Qty:	Rate	Unit	Amount
18	Cement pointing & rucking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).	629.00	@ Rs:1287/44	% Sft	Rs: 8,097.00
					(Rs: one thous: two hund: eighty seven & forty four only)
19	Notice board made with cement. (S.I.No: 1 P/94)	32.00	@ Rs: 58/11	P.Sft	Rs: 1,859.00
					(Rs: fifty eight & eleven only)
20	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing and dividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 43).	440.00	@ Rs: 4411/82	% Sft	Rs: 19,412.00
					(Rs: four thous: four hund: eleven & eighty two only)
(E)	<u>1-1/2" Thick</u>	716.00	@ Rs: 2548/29	% S.ft	Rs: 18,245.00
					(Rs: two thous: five hund: forty eight & twenty nine only)
21	Providing and fixing ornamental cement jalli 2" thick. (1:2:4) with out steel. (S.I.No.11 P/17).	59.00	@ Rs:226/02	P.Sft	Rs: 13,335.00
					(Rs: two hund; twenty six & two only)
22	Two Coats of bituman laid hot using 34 Lbs for % Sft. Ober roof and blinded with sand at one Cft. Per % Sft. (S.I.No: 13 P/34).	716.00	@ Rs:1887/40	% Sft	Rs: 13,513.00
					(Rs: one thous: eight hund; eighty seven & fourteen only)
23	Primary coat of chalk distempering. (S.I.No.23 P/57).	2320.00	@ Rs:442/75	% Sft	Rs: 10,271.00
					(Rs: four hund; forty two & seventy five only)
24	Distempering three coats. (S.I.No.24 (c) P/53).	2320.00	@ Rs:1079/65	% Sft	Rs: 25,047.00
					(Rs: one thos: seventy nine & sixty five only)
(B)	<u>Two coats.</u>	440.00	@ Rs:1043/90	% Sft	Rs: 4,593.00
					(Rs: ten hund; forty three & ninty only)

S.No:	Description	Qty:	Rate	Unit	Amount
25	Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of pairs and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).	317.00	@ Rs: 1948/10	% Sft	Rs: 6,175.00
			(Rs: one thous: nine hund: forty eight & ten only)		
26	Preparing surface and painting of doors and windows any type (including edges) (ii) Each subsequent coat of paint. (S.I.No.5 (c) P/69).	207.00	@ Rs:2116/41	% Sft	Rs: 4,380.00
			(Rs: two thous: one hund: sixteen & forty one only)		
G.Total:					Rs: 893,700.00


XEN

Schedule-B

17

Name of Work:- RECONSTRUCTION OF DANGEROUS PRIMARY SCHOOL BUILDINGS IN TALUKA RATODERO (2011-12 PROGRAMME) (09 UNITS) @ GBPS ALI KHAN BROHI (BALANCE WORK) TALUKA RATODERO DISTRICT LARKANO.

S #	Description	Qty	Rate	Unit	Amount
1	Supply and fixing sand under floor including plugging in to walls 12785.00 @ Rs: 1,141.25 % Cft (Eleven hundred forty one rupees & twenty five paisa only)				Rs: 145,909
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10. (S.I. No. 4 © P/14) 292.00 @ Rs: 8,694.95 % Cft (Eighty six hund: ninty four rup: & ninty five paisa only)				Rs: 25,389
3	Providing and Laying 3" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41) 885.00 @ Rs: 4,411.82 % Sft (Forry four hundred eleven rup: & eighty two paisa only)				Rs: 39,045

Total Rs:

210,343


XEN

S.#	Description	Rate	Unit	Qty	Amount
PART - B					
1	P/F squatting type white glazed earthen ware W.C pan of with i/c cost of flushing cistern with internal fitting & flush pipe with bend making good in cement concrete 1:2:4.(i) W/C not less than 19" clear opening b/w flushing & 6 gallons flushing tank with	1.00 @ Rs: 4,846.80	P. No.	Rs.	4,847
	(Forty eight hundred forty six rup: & eighty paisa only)				
2	P/F 22"x16" lavatory basin in white glazed earthen ware complete with & i/c the cost of W.I & C.I cantilever brackets 6 inches built into walls painted white in two coats after a primary cost of red lead painted & pair of 1/2" dia etc & making requisite n	1.00 @ Rs: 4,694.80	P. No.	Rs.	4,695
	(Forty six hundred ninty four rupees & eighty paisa only)				
3	P/F 6"x6" C.I Floor Trap of the approved self cleaning & C.I secured down grating holes in walls plinth & floor for pipe connection & making good in C.C 1:2:4.	1.00 @ Rs: 2,042.46	P. No.	Rs.	2,042
	(Two thousand fourty two rup: forty six pessa only)				
4	P/F in position Nyloon connections complete with 1/2" dia brass stop cock with pair of brass nuts lining joints to Nyloon connections.	1.00 @ Rs: 447.15	P. No.	Rs.	447
	(Four hundred forty seven rup: & fifteen paisa only)				
5	P/F 4" dia C.I soil vent pipe i/c cutting, fitting & extra painting to match the colour of the building.	2.00 @ Rs: 666.21	P. Rft	Rs.	1,332
	(Six hundred Sixty Six rup: & Twenty One paisa only)				
6	P/F 4"x4"x4" dia C.I branch of the required degree with access doors, rubber washer 1/4" thick & bolts & nuts & extra painting to match the colour of the building.	1.00 @ Rs: 270.60	P. No.	Rs.	270
	(Two hundred seventy rupees & sixty paisa only)				
7	Providing G.I pipe specials & clamps etc i/c fixing, cutting & fitting complete two coats of after cleaning the pipe etc with white zink paint with pigment to match the colour of the				
(A)	1/2" dia	12.00 @ Rs: 76.21	P. Rft	Rs.	915
	(Seventy six rupees & twenty paisa only)				
(B)	3/4" dia	20.00 @ Rs: 95.79	P. Rft	Rs.	1,916
	(Ninty five rupees seventy nine paisa only)				
8	P/F 4" dia C.I terminal guard i/c extra painting to match the colour of the building.	1.00 @ Rs: 689.70	P. No.	Rs.	690
	(Three hundred eighty nine rupees & seventy paisa only)				
9	P/F full way gun metal valves with whelds threaded of flanged endswith rubber washing 6/4" standard pattern.	1.00 @ Rs: 197.12	P. No.	Rs.	197
	(one hundred ninty seven rupees & twelve paisa only)				


XEN

SCHEDULE 'B'

18

Name of Work:- Re-Constt of Dangerous Primary / Middle School building in Taluka Bakrani/Dokri
(12 Units)(2011-12 Progg:) at GGMS Wado Wahan Taluka Bakrani

Sl No	ITEM OF WORK	Qty:	Rate	Unit	Amount.
	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15)	20.00	@ Rs: 910.0	P.Point	Rs: 18,200.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742.0	P.Point	Rs: 2,226.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	68.00	@ Rs: 171.0	P.Meter	Rs: 11,628.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/052}(10mm2) Copper conductor in 1" dia PVC conduit on surface (S.I.No: 6 P 1).	85.00	@ Rs: 428.0	P.Meter	Rs: 36,380.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	28.00	@ Rs: 54.0	P.Each	Rs: 1,512.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs: 83.0	P.Each	Rs: 249.00
7	Providing & Fixing Brass Battern holder.(S.I.No: 232 P 33)	10.00	@ Rs: 70.0	P.Each	Rs: 700.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	8.00	@ Rs: 72.0	P.Each	Rs: 576.00
9	Providing and fixing brass ceiling fan 56" (good quality).	6.00	@ Rs: 3185.0	P.Each	Rs: 25,480.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet (S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
(Part - B) N.S.i					
TOTAL					101,848.00
1	Fixing A.C ceiling fan regulator on S.W board.	8.00	@ Rs: 109.56	P.Each	Rs: 880.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	8.00	@ Rs: 169.21	P.Each	Rs: 1,354.00
3	P/F main panel board double shutter to accommodate heavy duty circuit breakers bus bar in painting.	1.00	@ Rs: 1089.54	P.Sq.ft.	Rs: 1,090.00
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i,c making the pit 12" deep by excavation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2" dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee.	1.00	@ Rs: 3084.4	P.Each	Rs: 3,084.00
5	P/F Energy saver superior quality i/c fixing on extg. holder etc complete.	16.00	@ Rs: 596.40	P.Each	Rs: 9,542.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	3.00	@ Rs: 596.40	P.Each	Rs: 1,789.00
7	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.	3.00	@ Rs: 140.26	P.Each	Rs: 420.00
Part 'B' TOTAL:					Rs: 18,159.0
Part 'A' TOTAL:					Rs: 101,848.0
TOTAL:					Rs: 120,007.0


XEN

SCHEDULE 'B'

Name of Work:- Integrated Rehabilitation of Elementary Schools in Taluka Dokri/Bakrani
(14 Units)(2013-14 Progg.) at:GBPS Lal Khan Wagan Taluka Bakrani

S.No	ITEM OF WORK	Qty:	Rate	Unit	Amount.
	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	20.00	@ Rs: 910.0	P.Point	Rs: 18,200.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742.0	P.Point	Rs: 2,226.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	68.00	@ Rs: 171.0	P.Meter	Rs: 11,628.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-1.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	85.00	@ Rs: 428.0	P.Meter	Rs: 36,380.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	28.00	@ Rs: 54.0	P.Each	Rs: 1,512.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33)	3.00	@ Rs: 83.0	P.Each	Rs: 249.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	10.00	@ Rs: 70.0	P.Each	Rs: 700.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals (S.I.No: 228 P 33)	8.00	@ Rs: 72.0	P.Each	Rs: 576.00
9	Providing and fixing brass ceiling fan 56" (good quality).	8.00	@ Rs: 3185.0	P.Each	Rs: 25,480.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet.(S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
(Part - B) N.S.I					
TOTAL					101,848.00
1	Fixing A.C ceiling fan regulator on S.W board.	8.00	@ Rs: 109.56	P.Each	Rs: 880.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	8.00	@ Rs: 169.21	P.Each	Rs: 1,354.00
3	P/F main panel board double shutter to accommodate heavey duty circuit breakers bus bar in painting	1.00	@ Rs: 1089.5	P.Sq.ft:	Rs: 1,090.00
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee.	1.00	@ Rs: 3084.4	P.Each	Rs: 3,084.00
5	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.	16.00	@ Rs: 596.40	P.Each	Rs: 9,542.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	3.00	@ Rs: 596.40	P.Each	Rs: 1,789.00
7	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.	3.00	@ Rs: 140.26	P.Each	Rs: 420.00
Part 'B' TOTAL:					Rs: 18,159.0
Part 'A' TOTAL:					Rs: 101,848.0
TOTAL:					Rs: 120,007.0


XEN

SCHEDULE 'B'

Name of Work:- Constt: of building for existing Shelterless Primary Schools in Taluka Larkana (4 units)
(2015-16 Progg:) at:GBPS Muhammad Mithal Chandio Taluka Larkana

ITEM OF WORK	Qty:	Rate	Unit	Amount.
Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	20.00	@ Rs: 910.0	P.Point	Rs: 18,200.00
2 Wiring for Plug polint with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742.0	P.Point	Rs: 2,226.00
3 Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	68.00	@ Rs: 171.0	P.Meter	Rs: 11,628.00
4 Providing and laying (Main or sub-Main) PVC insulated wirh size 2-/052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1)	85.00	@ Rs: 428.0	P.Meter	Rs: 36,380.00
5 Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	28.00	@ Rs: 54.0	P.Each	Rs: 1,512.00
6 Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs: 83.0	P.Each	Rs: 249.00
7 Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	10.00	@ Rs: 70.0	P.Each	Rs: 700.00
8 P/Fixing A.C Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	8.00	@ Rs: 72.0	P.Each	Rs: 576.00
9 Providing and fixing brass ceiling fan 56" (good quality).	8.00	@ Rs: 3185.0	P.Each	Rs: 25,480.00
10 Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet (S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11 P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
(Part - B) N.S.I				
TOTAL				101,848.00
1 Fixing A.C ceiling fan regulator on S.W board.	8.00	@ Rs: 109.56	P.Each	Rs: 880.00
2 P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	8.00	@ Rs: 169.21	P.Each	Rs: 1,354.00
3 P/F main panel board double shutter to accommodate heavey duty circuit breakers bus bar inc painting.	1.00	@ Rs: 1089.5	P Sq.ft	Rs: 1,090.00
4 P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavcation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee.	1.00	@ Rs: 3084.4	P.Each	Rs: 3,084.00
5 P/F Energy saver superior quality i/c fixing on extg: holder etc complete.	16.00	@ Rs: 596.40	P.Each	Rs: 9,542.00
6 P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	3.00	@ Rs: 596.40	P.Each	Rs: 1,789.00
7 P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.	3.00	@ Rs: 140.26	P.Each	Rs: 420.00
Part 'B' TOTAL:				Rs: 18,159.0
Part 'A' TOTAL:				Rs: 101,848.0
TOTAL:				Rs: 120,000.0



SCHEDULE 'B'

Name of Work:- Constt: of building for existing Shelterless Primary Schools in Taluka Larkana (4 units)
(2015-16 Progg.) at:GBPS Tajoo Ji Wandh Taluka Larkana

ITEM OF WORK	Qty:	Rate	Unit	Amount.
1 Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	20.00	@ Rs: 910.0	P.Point	Rs: 18,200.00
2 Wiring for Plug polint with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742.0	P.Point	Rs: 2,226.00
3 Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	68.00	@ Rs: 171.0	P.Meter	Rs: 11,628.00
4 Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface (S.I.No: 6 P 1).	85.00	@ Rs: 428.0	P.Meter	Rs: 36,380.00
5 Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	28.00	@ Rs: 54.0	P.Each	Rs: 1,512.00
6 Providing & Fixing 2 pin 5 amps plug & socket flush type (S.I.No: 225 P 33).	3.00	@ Rs: 83.0	P.Each	Rs: 249.00
7 Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	10.00	@ Rs: 70.0	P.Each	Rs: 700.00
8 P/Fixing A.C Baklite Ceiling rose with two terminals (S.I.No: 228 P 33)	8.00	@ Rs: 72.0	P.Each	Rs: 576.00
9 Providing and fixing brass ceiling fan 56" (good quality).	8.00	@ Rs: 3185.0	P.Each	Rs: 25,480.00
10 Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet (S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11 P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
(Part - B) N.S.I				
TOTAL				101,848.00
1 Fixing A.C ceiling fan regulator on S.W board.	8.00	@ Rs: 109.56	P.Each	Rs: 880.00
2 P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	8.00	@ Rs: 169.21	P.Each	Rs: 1,354.00
3 P/F main panel board double shutter to accommodate heavey duty circuit breakers bus bar ine painting.	1.00	@ Rs: 1089.51	P.Sq.ft:	Rs: 1,090.00
4 P/F Earthing set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2" dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee.	1.00	@ Rs: 3084.4	P.Each	Rs: 3,084.00
5 P/F Energy saver superior quality i/c fixing on extg: holder etc complete.	16.00	@ Rs: 596.40	P.Each	Rs: 9,542.00
6 P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	3.00	@ Rs: 596.40	P.Each	Rs: 1,789.00
7 P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.	3.00	@ Rs: 140.26	P.Each	Rs: 420.00
Part 'B' TOTAL:				Rs: 18,159.0
Part 'A' TOTAL:				Rs: 101,848.0
TOTAL:				Rs: 120,000.0



XEN

SCHEDULE 'B'

Name of Work:- Constt: of building for existing Shelterless Primary Schools in Taluka Dokri (4 units)
(2015-16 Progg.) at:GBPS Jogi Taluka Dokri

Sl. No.	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	20.00	@ Rs: 910.0	P.Point	Rs: 18,200.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742.0	P.Point	Rs: 2,226.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	68.00	@ Rs: 171.0	P.Meter	Rs: 11,628.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	85.00	@ Rs: 428.0	P.Meter	Rs: 36,380.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	28.00	@ Rs: 54.0	P.Each	Rs: 1,512.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs: 83.0	P.Each	Rs: 249.00
7	Providing & Fixing Brass Battern holder.(S.I.No: 232 P 33)	10.00	@ Rs: 70.0	P.Each	Rs: 700.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals.(S.I.No: 228 P 33)	8.00	@ Rs: 72.0	P.Each	Rs: 576.00
9	Providing and fixing brass ceiling fan 56" (good quality).	8.00	@ Rs: 3185.0	P.Each	Rs: 25,480.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet.(S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S I No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
(Part - B) N.S.I.					
TOTAL					101,848.00
1	Fixing A.C coiling fan regulator on S.W board.	8.00	@ Rs: 109.56	P.Each	Rs: 880.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	8.00	@ Rs: 169.21	P.Each	Rs: 1,354.00
3	P/F main panel board double shutter to accommodate heavey duty circuit breakers bus bar the painting.	1.00	@ Rs: 1089.5	P.Sq.ft.	Rs: 1,090.00
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee.	1.00	@ Rs: 3084.4	P.Each	Rs: 3,084.00
5	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.	16.00	@ Rs: 596.40	P.Each	Rs: 9,542.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	3.00	@ Rs: 596.40	P.Each	Rs: 1,789.00
7	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.	3.00	@ Rs: 140.26	P.Each	Rs: 420.00
Part 'B' TOTAL:					Rs: 18,159.0
Part 'A' TOTAL:					Rs: 101,848.0
TOTAL:					Rs: 120,000.0


XEN

SCHEDULE 'B'

Name of Work:- Constt: of building for existing Shelterless Primary Schools in Taluka Dokri (4 units)
(2015-16 Progg:) at:GBPS Sultan Lakhair Taluka Dokri

SN	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	20.00	@ Rs: 910.0	P.Point	Rs: 18,200.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742.0	P.Point	Rs: 2,226.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	68.00	@ Rs: 171.0	P.Meter	Rs: 11,628.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-/.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	85.00	@ Rs: 428.0	P.Meter	Rs: 36,380.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	28.00	@ Rs: 54.0	P.Each	Rs: 1,512.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs: 83.0	P.Each	Rs: 249.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	10.00	@ Rs: 70.0	P.Each	Rs: 700.00
8	P/Fixing A.C Baklite Coiling rose with two terminals .(S.I.No: 228 P 33)	8.00	@ Rs: 72.0	P.Each	Rs: 576.00
9	Providing and fixing brass ceiling fan 56" (good quality).	8.00	@ Rs: 3185.0	P.Each	Rs: 25,480.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet.(S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Cirecuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
(Part - B) N.S.I					
TOTAL					101,848.00
1	Fixing A.C ceiling fan regulator on S.W board.	8.00	@ Rs: 109.56	P.Each	Rs: 880.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	8.00	@ Rs: 169.21	P.Each	Rs: 1,354.00
3	P/F main panel board double shutter to accommodate heavey duty circuit breakers bus bar ine painting.	1.00	@ Rs: 1089.5	P.Sq.ft:	Rs: 1,090.00
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavalation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee.	1.00	@ Rs: 3084.4	P.Each	Rs: 3,084.00
5	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.	16.00	@ Rs: 596.40	P.Each	Rs: 9,542.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	3.00	@ Rs: 596.40	P.Each	Rs: 1,789.00
7	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.	3.00	@ Rs: 140.26	P.Each	Rs: 420.00
Part 'B' TOTAL:					Rs: 18,159.0
Part 'A' TOTAL:					Rs: 101,848.0
TOTAL:					Rs: 120,000.0

SCHEDULE B

24

Name of Work:- Construction of Additional Class Rooms in Existing Elementary Schools in Taluka Larkano
(7units) (2015-16) Programme At: GBPS Haseeb Chandio (2 C/R)

ITEM OF WORK	Qty:	Rate	Unit	Amount.
1 Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	20.00	@ Rs: 910.0	P.Point	Rs: 18,200.00
2 Wiring for Plug polint with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742.0	P.Point	Rs: 2,226.00
3 Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	68.00	@ Rs: 171.0	P.Meter	Rs: 11,628.00
4 Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1)	85.00	@ Rs: 428.0	P.Meter	Rs: 36,380.00
5 Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	28.00	@ Rs: 54.0	P.Each	Rs: 1,512.00
6 Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs: 83.0	P.Each	Rs: 249.00
7 Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	10.00	@ Rs: 70.0	P.Each	Rs: 700.00
8 P/Fixing A.C Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	8.00	@ Rs: 72.0	P.Each	Rs: 576.00
9 Providing and fixing brass ceiling fan 56" (good quality).	8.00	@ Rs: 3185.0	P.Each	Rs: 25,480.00
10 Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet.(S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11 P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
(Part - B) N.S.I				
TOTAL				101,848.00
1 Fixing A.C ceiling fan regulator on S.W board.	8.00	@ Rs: 109.56	P.Each	Rs: 880.00
2 P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	8.00	@ Rs: 169.21	P.Each	Rs: 1,354.00
3 P/F main panel board double shutter to accommodate heavy duty circuit breakers bus bar ine painting.	1.00	@ Rs: 1089.5!	P.Sq:ft:	Rs: 1,090.00
4 P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee.	1.00	@ Rs: 3084.4	P.Each	Rs: 3,084.00
5 P/F Energy saver superior quality i/c fixing on extg: holder etc complete.	16.00	@ Rs: 596.40	P.Each	Rs: 9,542.00
6 P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	3.00	@ Rs: 596.40	P.Each	Rs: 1,789.00
7 P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.	3.00	@ Rs: 140.26	P.Each	Rs: 420.00
Part 'B' TOTAL:				Rs: 18,159.0
Part 'A' TOTAL:				Rs: 101,848.0
TOTAL:				Rs: 120,000.0


XEN

SCHEDULE 'B'

25

Name of Work:- Construction of Additional Class Rooms in Existing Elementary Schools in Taluka Larkano (7 unit) (2015-16 Progg.) at: GBPS Deen Muhammad Chandio (1 Class Rooms)

SN	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	13.00	@ Rs: 910.0	P.Point	Rs: 11,830.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	2.00	@ Rs: 742.0	P.Point	Rs: 1,484.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	30.00	@ Rs: 171.0	P.Meter	Rs: 5,130.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-1.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface (S.I.No: 6 P 1).	31.00	@ Rs: 428.0	P.Meter	Rs: 13,268.00
5	Providing & Fixing A.C one way S.P 5ampswitch flush type (S.I.No: 219 P 33)	15.00	@ Rs: 54.0	P.Each	Rs: 810.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type (S.I.No: 225 P 33).	2.00	@ Rs: 83.0	P.Each	Rs: 166.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	7.00	@ Rs: 70.0	P.Each	Rs: 490.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals (S.I.No: 228 P 33)	6.00	@ Rs: 72.0	P.Each	Rs: 432.00
9	Providing and fixing brass ceiling fan 56" (good quality).	6.00	@ Rs: 3185.0	P.Each	Rs: 19,110.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet.(S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No. 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
TOTAL:					Rs: 57,617.0
(Part - B) N.S.I					
1	Fixing A.C ceiling fan regulator on S W board.	6.00	@ Rs: 109.56	P.Each	Rs: 657.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	6.00	@ Rs: 169.21	P.Each	Rs: 1,015.00
3	P/F main panel board double shutter to accommodate heavey duty circuit breakers bus bar ine painting.	1.00	@ Rs: 1089.51	P.Sq ft.	Rs: 1,090.00
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i c making the pit 12" deep by excavcation of all type of soil. Earth Plate to be connected with No:8 S.W G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee.	1.00	@ Rs: 3064	P.Each	Rs: 3,084.00
5	P/F Energy saver superior quality i/c fixing on extg. holder etc complete.	7.00	@ Rs: 596.40	P.Each	Rs: 4,175.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	4.00	@ Rs: 596.40	P.Each	Rs: 2,386.00
Part 'B' TOTAL:					Rs: 12,407.0
Part 'A' TOTAL:					Rs: 57,617.0
TOTAL:					70,024.0


XEN

SCHEDULE 'B'

26

Name of Work:- Construction of Additional Class Rooms in Existing Elementary Schools in Taluka Larkano
(7 unit) (2015-16 Progg:)at: GBPS Behram Luhur (1 Class Rooms)

SN	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	13.00	@ Rs: 910.0	P.Point	Rs: 11,830.00
2	Wiring for Plug polint with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	2.00	@ Rs: 742.0	P.Point	Rs: 1,484.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	30.00	@ Rs: 171.0	P.Meter	Rs: 5,130.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-/052}(10mm2) Copper conductor in 1" dia PVC conduit on surface (S.I.No: 6 P 1).	31.00	@ Rs: 428.0	P.Meter	Rs: 13,268.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	15.00	@ Rs: 54.0	P.Each	Rs: 810.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	2.00	@ Rs: 83.0	P.Each	Rs: 166.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	7.00	@ Rs: 70.0	P.Each	Rs: 490.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	6.00	@ Rs: 72.0	P.Each	Rs: 432.00
9	Providing and fixing brass ceiling fan 56" (good quality).	6.00	@ Rs: 3185.0	P.Each	Rs: 19,110.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet.(S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
TOTAL:					Rs: 57,617.0
(Part - B) N.S.I					
1	Fixing A.C ceiling fan regulator on S.W board.	6.00	@ Rs: 109.56	P.Each	Rs: 657.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	6.00	@ Rs: 169.21	P.Each	Rs: 1,015.00
3	P/F main panel board double shutter to accommodate heavey duty circuit breakers bus baring painting.	1.00	@ Rs: 1089.51	P.Sq.ft.	Rs: 1,090.00
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavcation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee.	1.00	@ Rs: 3084	P.Each	Rs: 3,084.00
5	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.	7.00	@ Rs: 596.40	P.Each	Rs: 4,175.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	4.00	@ Rs: 596.40	P.Each	Rs: 2,386.00
Part 'B' TOTAL:					Rs: 12,407.0
Part 'A' TOTAL:					Rs: 57,617.0
TOTAL:					70,000.0


XEN

SCHEDULE 'B'

Name of Work:- Construction of Additional Class Rooms in Existing Elementary Schools in Taluka Larkano
(7units) (2015-16) Programme At: GBPS P.T.S Colony (2 C/R)

SN	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	20.00	@ Rs: 910.0	P.Point	Rs: 18,200.00
2	Wiring for Plug polint with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742.0	P.Point	Rs: 2,226.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	68.00	@ Rs: 171.0	P.Meter	Rs: 11,628.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	85.00	@ Rs: 428.0	P.Meter	Rs: 36,380.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	28.00	@ Rs: 54.0	P.Each	Rs: 1,512.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs: 83.0	P.Each	Rs: 249.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	10.00	@ Rs: 70.0	P.Each	Rs: 700.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	8.00	@ Rs: 72.0	P.Each	Rs: 576.00
9	Providing and fixing brass ceiling fan 56" (good quality).	8.00	@ Rs: 3185.0	P.Each	Rs: 25,480.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet.(S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Cirecuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
(Part - B) N.S.I					
TOTAL					101,848.00
1	Fixing A.C ceiling fan regulator on S.W board.	8.00	@ Rs: 109.56	P.Each	Rs: 880.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	8.00	@ Rs: 169.21	P.Each	Rs: 1,354.00
3	P/F main panel board double shutter to accommodate heavey duty circuit breakers bus bar ine painting.	1.00	@ Rs: 1089.51	P.Sq:ft:	Rs: 1,090.00
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavcation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assary i/c providing necessary tee,	1.00	@ Rs: 3084.4	P.Each	Rs: 3,084.00
5	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.	16.00	@ Rs: 596.40	P.Each	Rs: 9,542.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	3.00	@ Rs: 596.40	P.Each	Rs: 1,789.00
7	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.	3.00	@ Rs: 140.26	P.Each	Rs: 420.00
Part 'B' TOTAL:					Rs: 18,159.0
Part 'A' TOTAL:					Rs: 101,848.0
TOTAL:					Rs: 120,000.0


XEN

SCHEDULE 'B'

28

Name of Work:- Constt. of Dangerous Primary School building in Taluka Larkano
(8 Units)(2015-16 Progg.) at:GBPS Jeewan Bhutto Taluka Larkano

S.N	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15)	20.00	@ Rs: 910.0	P.Point	Rs: 18,200.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742.0	P.Point	Rs: 2,226.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	68.00	@ Rs: 171.0	P.Meter	Rs: 11,628.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-1.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	85.00	@ Rs: 428.0	P.Meter	Rs: 36,380.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	28.00	@ Rs: 54.0	P.Each	Rs: 1,512.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs: 83.0	P.Each	Rs: 249.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	10.00	@ Rs: 70.0	P.Each	Rs: 700.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	8.00	@ Rs: 72.0	P.Each	Rs: 576.00
9	Providing and fixing brass ceiling fan 56" (good quality).	8.00	@ Rs: 3185.0	P.Each	Rs: 25,480.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet.(S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
(Part - B) N.S.I					
TOTAL					101,848.00
1	Fixing A.C ceiling fan regulator on S.W board.	8.00	@ Rs: 109.56	P.Each	Rs: 880.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	8.00	@ Rs: 169.21	P.Each	Rs: 1,354.00
3	P/F main panel board double shutter to accommodate heavey duty circuit breakers bus bar i/c painting	1.00	@ Rs: 1089.5	P.Sq.ft.	Rs: 1,090.00
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavation of all type of soil. Earth Plate to be connected with No.8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assarary i/c providing necessary tee.	1.00	@ Rs: 3084.4	P.Each	Rs: 3,084.00
5	P/F Energy saver superior quality i/c fixing on extg. holder etc complete.	16.00	@ Rs: 596.40	P.Each	Rs: 9,542.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	3.00	@ Rs: 596.40	P.Each	Rs: 1,789.00
7	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.	3.00	@ Rs: 140.26	P.Each	Rs: 420.00
Part 'B' TOTAL:					Rs: 18,159.0
Part 'A' TOTAL:					Rs: 101,848.0
TOTAL:					Rs: 120,000.0

XEN

SCHEDULE 'B'

29

Name of Work:- Constt.of Dangerous Primary School building in Taluka Larkano
(8 Units)(2015-16 Progg:) at:GBPS Sawayo Agham Taluka Larkano

SN	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15)	20.00	@ Rs: 910.0	P.Point	Rs: 18,200.00
2	Wiring for Plug point with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742.0	P.Point	Rs: 2,226.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029) Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	68.00	@ Rs: 171.0	P.Meter	Rs: 11,628.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-/.052)(10mm2) Copper conductor in 1" dia PVC conduit on surface (S.I.No: 6 P 1).	85.00	@ Rs: 428.0	P.Meter	Rs: 36,380.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	28.00	@ Rs: 54.0	P.Each	Rs: 1,512.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs: 83.0	P.Each	Rs: 249.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	10.00	@ Rs: 70.0	P.Each	Rs: 700.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	8.00	@ Rs: 72.0	P.Each	Rs: 576.00
9	Providing and fixing brass ceiling fan 56" (good quality).	8.00	@ Rs: 3185.0	P.Each	Rs: 25,480.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet.(S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Cirecuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
(Part - B) N.S.I					
TOTAL					101,841.00
1	Fixing A.C ceiling fan regulator on S.W board.	8.00	@ Rs: 109.56	P.Each	Rs: 880.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	8.00	@ Rs: 169.21	P.Each	Rs: 1,354.00
3	P/F main panel board double shutter to accommodate heavy duty circuit breakers bus bar inc painting.	1.00	@ Rs: 1089.5	P.Sq.ft.	Rs: 1,090.00
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee.	1.00	@ Rs: 3084.4	P.Each	Rs: 3,084.00
5	P/F Energy saver superior quality i/c fixing on extg. holder etc complete.	16.00	@ Rs: 596.40	P.Each	Rs: 9,542.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	3.00	@ Rs: 596.40	P.Each	Rs: 1,789.00
7	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.	3.00	@ Rs: 140.26	P.Each	Rs: 420.00
Part 'B' TOTAL:					Rs: 18,159.0
Part 'A' TOTAL:					Rs: 101,841.0
TOTAL:					Rs: 120,000.0



XEN

SCHEDULE 'B'

30

Name of Work:- Constt:of Dangerous Primary School building in Taluka Larkano
(8 Units)(2015-16 Progg:) at:GBPS Sabzal Brohi Taluka Larkano

SN	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	13.00	@ Rs: 910.0	P.Point	Rs: 11,830.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	2.00	@ Rs: 742.0	P.Point	Rs: 1,484.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	30.00	@ Rs: 171.0	P.Meter	Rs: 5,130.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	23.00	@ Rs: 428.0	P.Meter	Rs: 9,844.00
5	Providing & Fixing A.C one way S.P 5amps switch flush type (S.I.No: 219 P 33)	17.00	@ Rs: 54.0	P.Each	Rs: 918.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	2.00	@ Rs: 83.0	P.Each	Rs: 166.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	7.00	@ Rs: 70.0	P.Each	Rs: 490.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	6.00	@ Rs: 72.0	P.Each	Rs: 432.00
9	Providing and fixing brass ceiling fan 56" (good quality).	8.00	@ Rs: 3185.0	P.Each	Rs: 25,480.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet (S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Circuitt breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
TOTAL:					Rs: 60,671.0
(Part - B) N.S.I					
1	Fixing A.C ceiling fan regulator on S.W board.	6.00	@ Rs: 109.56	P.Each	Rs: 657.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	6.00	@ Rs: 169.21	P.Each	Rs: 1,015.00
3	P/F main panel board double shutter to accommodate heavey duty circuit breakers bus bar inc painting.	1.00	@ Rs: 1089.5	P.Sq:ft.	Rs: 1,090.00
5	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.	7.00	@ Rs: 596.40	P.Each	Rs: 4,175.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	4.00	@ Rs: 596.40	P.Each	Rs: 2,386.00
Part 'B' TOTAL:					Rs: 9,323.0
Part 'A' TOTAL:					Rs: 60,671.0
TOTAL:					69,994.0


XEN

SCHEDULE 'B'

Name of Work:- Constt of Dangerous Primary School building in Taluka Larkano
(8 Units)(2015-16 Progg:) at:GBPS Gadani Taluka Larkano

3/1

SN	ITEM OF WORK	Qty:	Rate	Unit	Amount
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	24.00	@ Rs: 910.0	P.Point	Rs: 21,840.00
2	Wiring for Plug polint with (3/ 029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742.0	P.Point	Rs: 2,226.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	65.00	@ Rs: 171.0	P.Meter	Rs: 11,115.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-/.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	45.00	@ Rs: 428.0	P.Meter	Rs: 19,260.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	28.00	@ Rs: 54.0	P.Each	Rs: 1,512.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33)	3.00	@ Rs: 83.0	P.Each	Rs: 249.00
7	Providing & Fixing Brass Battern holder. (S.I.No: 232 P 33)	10.00	@ Rs: 70.0	P.Each	Rs: 700.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals (S.I.No: 228 P 33)	8.00	@ Rs: 72.0	P.Each	Rs: 576.00
9	Providing and fixing brass ceiling fan 56" (good quality).	12.00	@ Rs: 3185.0	P.Each	Rs: 38,220.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or colourms & covered with plastic sheet (S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
(Part - B) N.S.I					
TOTAL					100,595.00
1	Fixing A.C ceiling fan regulator on S.W board.	12.00	@ Rs: 109.56	P.Each	Rs: 1,315.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof	12.00	@ Rs: 169.21	P.Each	Rs: 2,031.00
3	P/F main panel board double shutter to accommodate heavey duty circuit breakers bus bar inc painting.	1.00	@ Rs: 1089.51	P.Sq.ft.	Rs: 1,090.00
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal etc,i.c making the pit 12" deep by excavcation of all type of soil. Earth Plate to be connected with No:8 S.W G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee.	1.00	@ Rs: 3084.4	P.Each	Rs: 3,084.00
5	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.	16.00	@ Rs: 596.40	P.Each	Rs: 9,542.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	3.00	@ Rs: 596.40	P.Each	Rs: 1,789.00
7	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs	3.00	@ Rs: 140.26	P.Each	Rs: 420.00
Part 'B' TOTAL:					Rs: 19,271.0
Part 'A' TOTAL:					Rs: 100,595.0
TOTAL:					Rs: 119,866.0

XEN

SCHEDULE 'B'

Name of Work:- Integrated Rehabilitation of Primary Schools & Provision of missing facilities in Taluka Larkano
(14 Units)(2015-16 Progg.) at:GBPS Sajjan Sangi Taluka Larkana

ITEM OF WORK	Qty:	Rate	Unit	Amount.
1 Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	20.00	@ Rs: 910.0	P.Point	Rs: 18,200.00
2 Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742.0	P.Point	Rs: 2,226.00
3 Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	68.00	@ Rs: 171.0	P.Meter	Rs: 11,628.00
4 Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	85.00	@ Rs: 428.0	P.Meter	Rs: 36,380.00
5 Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	28.00	@ Rs: 54.0	P.Each	Rs: 1,512.00
6 Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs: 83.0	P.Each	Rs: 249.00
7 Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	10.00	@ Rs: 70.0	P.Each	Rs: 700.00
8 P/Fixing A.C Baklite Coiling rose with two terminals (S.I.No: 228 P 33)	8.00	@ Rs: 72.0	P.Each	Rs: 576.00
9 Providing and fixing brass coiling fan 56" (good quality).	8.00	@ Rs: 3185.0	P.Each	Rs: 25,480.00
10 Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet.(S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11 P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
(Part - B) N.S.I				
TOTAL				101,848.00
1 Fixing A.C ceiling fan regulator on S.W board.	8.00	@ Rs: 109.56	P.Each	Rs: 880.00
2 P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	8.00	@ Rs: 169.21	P.Each	Rs: 1,354.00
3 P/F main panel board double shutter to accommodate heavy duty circuit breakers bus bar ine painting.	1.00	@ Rs: 1089.5!	P.Sq:ft	Rs: 1,090.00
4 P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavcation of all type of soil. Earth Plate to be connected with No:8 S.W.C bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee.	1.00	@ Rs: 3084.4	P.Each	Rs: 3,084.00
5 P/F Energy saver superior quality i/c fixing on extg: holder etc complete.	16.00	@ Rs: 596.40	P.Each	Rs: 9,542.00
6 P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	3.00	@ Rs: 596.40	P.Each	Rs: 1,789.00
7 P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.	3.00	@ Rs: 140.26	P.Each	Rs: 420.00
Part 'B' TOTAL:				Rs: 18,159.0
Part 'A' TOTAL:				Rs: 101,848.0
TOTAL:				Rs: 120,000.0


XEN

SCHEDULE 'B'

Name of Work:- Integrated Rehabilitation of Primary Schools & Provision of missing facilities in Taluka Larkano
(14 Units)(2015-16 Progg.) at:GBPS New Nazar Muhalla Taluka Larkana

SN	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	32.00	@ Rs: 910.0	P.Point	Rs: 29,120.00
2	Wiring for Plug polint with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	6.00	@ Rs: 742.0	P.Point	Rs: 4,452.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	77.00	@ Rs: 171.0	P.Meter	Rs: 13,167.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	66.00	@ Rs: 428.0	P.Meter	Rs: 28,248.00
5	Providing & Fixing A C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	32.00	@ Rs: 54.0	P.Each	Rs: 1,728.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type (S.I.No: 225 P 33).	6.00	@ Rs: 83.0	P.Each	Rs: 498.00
7	Providing & Fixing Brass Battern holder. (S.I.No: 232 P 33)	19.00	@ Rs: 70.0	P.Each	Rs: 1,368.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals (S.I.No: 228 P 33)	13.00	@ Rs: 72.0	P.Each	Rs: 936.00
9	Providing and fixing brass ceiling fan 56" (good quality).	9.00	@ Rs: 3185.0	P.Each	Rs: 28,665.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet (S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	6.00	@ Rs: 948.0	P.Each	Rs: 5,688.00
(Part - B) N.S.I					
TOTAL					114,027.00
1	Fixing A.C ceiling fan regulator on S.W board.	16.00	@ Rs: 109.56	P.Each	Rs: 1,753.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	16.00	@ Rs: 169.21	P.Each	Rs: 2,707.00
3	P/F main panel board double shutter to accommodate heavey duty circuit breakers bus bar ine painling.	1.00	@ Rs: 1089.5	P.Sq.ft:	Rs: 1,090.00
5	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.	13.00	@ Rs: 596.40	P.Each	Rs: 7,753.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	3.00	@ Rs: 596.40	P.Each	Rs: 1,789.00
7	P/F hinged type double S W board accommodate main or sub-main control switches and for other similar jobs.	6.00	@ Rs: 140.26	P.Each	Rs: 842.00
Part 'B' TOTAL:					Rs: 15,934.0
Part 'A' TOTAL:					Rs: 114,027.0
TOTAL:					Rs: 129,961.0


XEN

SCHEDULE 'B'

34

Name of Work:- Integrated Rehabilitation of Primary Schools & Provision of missing facilities in Taluka Larkano
(14 Units)(2015-16 Progg.) at:GBPS Nazar Muhalla(North Side Wing) Taluka Larkana

S.No	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	36.00	@ Rs: 910.0	P.Point	Rs: 32,760.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	6.00	@ Rs: 742.0	P.Point	Rs: 4,452.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	79.00	@ Rs: 171.0	P.Meter	Rs: 13,509.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	75.00	@ Rs: 428.0	P.Meter	Rs: 32,100.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	32.00	@ Rs: 54.0	P.Each	Rs: 1,728.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type (S.I.No: 225 P 33).	6.00	@ Rs: 83.0	P.Each	Rs: 498.00
7	Providing & Fixing Brass Battern holder.(S.I.No: 232 P 33)	19.00	@ Rs: 70.0	P.Each	Rs: 1,368.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals.(S.I.No: 228 P 33)	13.00	@ Rs: 72.0	P.Each	Rs: 936.00
9	Providing and fixing brass ceiling fan 56" (good quality).	12.00	@ Rs: 3185.0	P.Each	Rs: 38,220.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet (S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	6.00	@ Rs: 948.0	P.Each	Rs: 5,688.00
(Part - B) N.S.I					
TOTAL					131,416.00
1	Fixing A.C ceiling fan regulator on S.W board.	12.00	@ Rs: 109.56	P.Each	Rs: 1,315.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	16.00	@ Rs: 169.21	P.Each	Rs: 2,707.00
3	P/F main panel board double shutter to accommodate heavey duty circuit breakers bus bar ine painting.	1.00	@ Rs: 1089.5!	P.Sq.ft:	Rs: 1,090.00
4	P/F Earthing sel with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavcation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee.	1.00	@ Rs: 3084.4	P.Each	Rs: 3,084.00
5	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.	13.00	@ Rs: 596.40	P.Each	Rs: 7,753.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	3.00	@ Rs: 596.40	P.Each	Rs: 1,789.00
7	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.	6.00	@ Rs: 140.26	P.Each	Rs: 842.00
Part 'B' TOTAL:					Rs: 18,580.0
Part 'A' TOTAL:					Rs: 131,416.0
TOTAL:					Rs: 149,996.0


XEN

SCHEDULE 'B'

Name of Work:- Integrated Rehabilitation of Primary Schools & Provision of missing facilities in Taluka Larkana
(14 Units)(2015-16 Progg:) at:GGPS Railan Taluka Larkana

S.N	ITEM OF WORK	Qty:	Rate	Unit	Amount.	
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	20.00	@ Rs: 910.0	P.Point	Rs: 18,200.00	
2	Wiring for Plug polint with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742.0	P.Point	Rs: 2,226.00	
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	40.00	@ Rs: 171.0	P.Meter	Rs: 6,840.00	
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-/.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	55.00	@ Rs: 428.0	P.Meter	Rs: 23,540.00	
5	Providing & Fixing A.C one way S P 5ampsswitch flush type (S.I.No: 219 P 33)	23.00	@ Rs: 54.0	P.Each	Rs: 1,242.00	
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs: 83.0	P.Each	Rs: 249.00	
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	12.00	@ Rs: 70.0	P.Each	Rs: 840.00	
8	P/Fixing A.C Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	8.00	@ Rs: 72.0	P.Each	Rs: 576.00	
9	Providing and fixing brass ceiling fan 56" (good quality).	8.00	@ Rs: 3185.0	P.Each	Rs: 25,480.00	
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet (S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00	
11	P/F Cirecuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00	
(Part - B) N.S.I					TOTAL:	Rs: 84,090.0
1	Fixing A.C ceiling fan regulator on S.W board.	8.00	@ Rs: 109.56	P.Each	Rs: 880.00	
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof	8.00	@ Rs: 169.21	P.Each	Rs: 1,354.00	
3	P/F main panel board double shutter to accommodate heavy duty circuit breakers bus bar ine painting	1.00	@ Rs: 1089.5	P Sq:ft	Rs: 1,090.00	
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by exccavation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee,	1.00	@ Rs: 3084.4	P.Each	Rs: 3,084.00	
5	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.	12.00	@ Rs: 596.40	P.Each	Rs: 7,157.00	
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	3.00	@ Rs: 596.40	P.Each	Rs: 1,789.00	
7	P/F hinged type double S W board accommodate main or sub-main control switches and for other similar jobs.	3.00	@ Rs: 140.26	P.Each	Rs: 420.00	
					Part 'B' TOTAL:	Rs: 15,774.0
					Part 'A' TOTAL:	Rs: 84,090.0
					TOTAL:	Rs: 99,864.0



SCHEDULE 'B'

37

Name of Work:- Provision of missing facilities (C. Wall, Lavatory, addl: C. Rooms) to Existing Elementary Schools of Taluka Ratodero (12 Units) (2015-16 programme) at: GBPS Haji Khan Bosan (2 Class Rooms)

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	25.00	@ Rs: 910.0	P.Point	Rs: 22,750.00
2	Wiring for Plug point with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	5.00	@ Rs: 742.0	P.Point	Rs: 3,710.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	60.00	@ Rs: 171.0	P.Meter	Rs: 10,260.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	70.00	@ Rs: 428.0	P.Meter	Rs: 29,960.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	25.00	@ Rs: 54.0	P.Each	Rs: 1,350.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	4.00	@ Rs: 83.0	P.Each	Rs: 332.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	17.00	@ Rs: 70.0	P.Each	Rs: 1,190.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	8.00	@ Rs: 72.0	P.Each	Rs: 576.00
9	Providing and fixing brass ceiling fan 56" (good quality).	8.00	@ Rs: 3185.0	P.Each	Rs: 25,480.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet.(S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Cirecuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
				TOTAL:	Rs: 100,505.0



XEN

No:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
-----	--------------	------	------	------	---------

(Part - B) N.S.I

1	Fixing A.C ceiling fan regulator on S.W board. 8.00	@ Rs: 109.56	P.Each	Rs:	876.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof. 8.00	@ Rs: 169.21	P.Each	Rs:	1,354.00
3	P/F main panel board double shutter to accommodate heavy duty circuit breakers bus bar line painting. 1.00	@ Rs: 1089.55	P.Sq.ft:	Rs:	1,090.00
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assary i/c providing necessary tee. 1.00	@ Rs: 3084.44	P.Each	Rs:	3,084.00
5	P/F Energy saver superior quality i/c fixing on extg: holder etc complete. 17.00	@ Rs: 596.40	P.Each	Rs:	10,139.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete. 4.00	@ Rs: 596.40	P.Each	Rs:	2,386.00
7	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs. 4.00	@ Rs: 140.26	P.Each	Rs:	561.00

Part 'B' TOTAL: Rs: 19,490.0

Part 'A' TOTAL: Rs: 100,505.0

TOTAL: Rs: 119,995.0


XEN

SCHEDULE 'B'

38

Name of Work:- Provision of missing facilities (C. Wall, Lavatory, addl: C. Rooms) to Existing Elementary Schools of Taluka Ratodero (12 Units) (2015-16 programme) at: GBPS Gharibabad Naudero -I (1 Class Rooms)

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	13.00	@ Rs: 910.0	P.Point	Rs: 11,830.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	2.00	@ Rs: 742.0	P.Point	Rs: 1,484.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	30.00	@ Rs: 171.0	P.Meter	Rs: 5,130.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	31.00	@ Rs: 428.0	P.Meter	Rs: 13,268.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	15.00	@ Rs: 54.0	P.Each	Rs: 810.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	2.00	@ Rs: 83.0	P.Each	Rs: 166.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	7.00	@ Rs: 70.0	P.Each	Rs: 490.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	6.00	@ Rs: 72.0	P.Each	Rs: 432.00
9	Providing and fixing brass ceiling fan 56" (good quality).	6.00	@ Rs: 3185.0	P.Each	Rs: 19,110.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet.(S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
TOTAL:					Rs: 57,617.0



XEN

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
(Part - B) N.S.I					
1	Fixing A.C ceiling fan regulator on S.W board. 6.00	@ Rs: 109.56	P.Each	Rs:	657.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof. 6.00	@ Rs: 169.21	P.Each	Rs:	1,015.00
3	P/F main panel board double shutter to accommodate heavey duty circuit breakers bus bar ine painting. 1.00	@ Rs: 1089.55	P.Sq.ft:	Rs:	1,090.00
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavcation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee, 1.00	@ Rs: 3084	P.Each	Rs:	3,084.00
5	P/F Energy saver superior quality i/c fixing on extg: holder etc complete. 7.00	@ Rs: 596.40	P.Each	Rs:	4,175.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete. 4.00	@ Rs: 596.40	P.Each	Rs:	2,386.00
				Part 'B' TOTAL: Rs:	12,407.0
				Part 'A' TOTAL: Rs:	57,617.0
				TOTAL:	70,024.0


XEN

SCHEDULE 'B'

59

Name of Work:- Integrated Rehabilitation of Existing Elementary Schools in Taluka Ratodero
District Larkano (5 Units) (2015-16 programme at:GBPS Behman

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	21.00	@ Rs: 910.0	P.Point	Rs: 19,110.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	4.00	@ Rs: 742.0	P.Point	Rs: 2,968.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7(029) Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	60.00	@ Rs: 171.0	P.Meter	Rs: 10,260.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7(052)(10mm ²) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	63.00	@ Rs: 428.0	P.Meter	Rs: 26,964.00
5	Providing & Fixing A.C one way S.P 5amp switch flush type (S.I.No: 219 P 33)	21.00	@ Rs: 54.0	P.Each	Rs: 1,134.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	4.00	@ Rs: 83.0	P.Each	Rs: 332.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	13.00	@ Rs: 70.0	P.Each	Rs: 910.00
8	P/fixing A.C Baklife Ceiling rose with two terminals .(S.I.No: 228 P 33)	8.00	@ Rs: 72.0	P.Each	Rs: 576.00
9	Providing and fixing brass ceiling fan 56" (good quality).	8.00	@ Rs: 3185.0	P.Each	Rs: 25,480.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet.(S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
TOTAL:					Rs: 92,600.00

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
<u>(Part - B) N.S.I</u>					
1	Fixing A.C ceiling fan regulator on S.W board. 8.00	@ Rs: 109.56	P.Each	Rs:	876.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof. 8.00	@ Rs: 169.21	P.Each	Rs:	1,354.00
3	P/F main panel board double shutter to accommodate heavy duty circuit breakers bus bar inc painting. 1.00	@ Rs: 1089.55	P.Sq.ft:	Rs:	1,090.00
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee, 1.00	@ Rs: 3084.44	P.Each	Rs:	3,084.00
5	P/F Energy saver superior quality i/c fixing on extg: holder etc complete. 13.00	@ Rs: 596.40	P.Each	Rs:	7,753.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete. 4.00	@ Rs: 596.40	P.Each	Rs:	2,386.00
7	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs. 4.00	@ Rs: 140.26	P.Each	Rs:	561.00
				Part 'B' TOTAL:	Rs: 17,104.0
				Part 'A' TOTAL:	Rs: 92,631.0
				TOTAL:	Rs: 109,735.0


XEN

SCHEDULE 'B'

40

Name of Work:- Intergrated Rehabilitation of Existing Elementary Schools in Taluka Ratodero District
Larkano (5 Units) (2015-16 Programme at: GBMS Bhai Khan Ghanghro

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	36.00	@ Rs: 910.0	P.Point	Rs: 32,760.00
2	Wiring for Plug polint with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	4.00	@ Rs: 742.0	P.Point	Rs: 2,968.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	55.00	@ Rs: 171.0	P.Meter	Rs: 9,405.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-/052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	70.00	@ Rs: 428.0	P.Meter	Rs: 29,960.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	40.00	@ Rs: 54.0	P.Each	Rs: 2,160.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	4.00	@ Rs: 83.0	P.Each	Rs: 332.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	24.00	@ Rs: 70.0	P.Each	Rs: 1,680.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals ,(S.I.No: 228 P 33)	12.00	@ Rs: 72.0	P.Each	Rs: 864.00
9	Providing and fixing brass ceiling fan 56" (good quality).	12.00	@ Rs: 3185.0	P.Each	Rs: 38,220.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet.(S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	7.00	@ Rs: 948.0	P.Each	Rs: 6,636.00
TOTAL:					Rs: 125,142.0


XEN

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
(Part - B) N.S.I					
1	Fixing A.C ceiling fan regulator on S.W board. 12.00	@ Rs: 109.56	P.Each	Rs:	1,315.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof. 12.00	@ Rs: 169.21	P.Each	Rs:	2,031.00
3	P/F main panel board double shutter to accommodate heavy duty circuit breakers bus bar iné painting. 1.00	@ Rs: 1089.55	P.Sq.ft:	Rs:	1,090.00
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.e making the pit 12" deep by excavation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee, 1.00	@ Rs: 3084.44	P.Each	Rs:	3,084.00
5	P/F Energy saver superior quality i/c fixing on extg: holder etc complete. 24.00	@ Rs: 596.40	P.Each	Rs:	14,314.00
6	P/F wall bracket light fancy type superior quality including necessary electric connéction and fixing on wall or ceiling etc complete. 4.00	@ Rs: 596.40	P.Each	Rs:	2,386.00
7	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs. 4.00	@ Rs: 140.26	P.Each	Rs:	561.00
Part 'B' TOTAL:					Rs: 24,781.0
Part 'A' TOTAL:					Rs: 125,142.0
TOTAL:					Rs: 149,923.0


XEN

SCHEDULE 'B'Name of Work:- Rehabilitation of Existing Primary Schools in Taluka Ratodero District Larkano
(11 Units(2015-16 programme at: GBPS Kechi Unar)

41

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	16.00	@ Rs: 910.0	P.Point	Rs: 14,560.00
2	Wiring for Plug polint with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	2.00	@ Rs: 742.0	P.Point	Rs: 1,484.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029) Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	40.00	@ Rs: 171.0	P.Meter	Rs: 6,840.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-/052)(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	31.00	@ Rs: 428.0	P.Meter	Rs: 13,268.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	18.00	@ Rs: 54.0	P.Each	Rs: 972.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	2.00	@ Rs: 83.0	P.Each	Rs: 166.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	8.00	@ Rs: 70.0	P.Each	Rs: 560.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	8.00	@ Rs: 72.0	P.Each	Rs: 576.00
9	Providing and fixing brass ceiling fan 56" (good quality).	6.00	@ Rs: 3185.0	P.Each	Rs: 19,110.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet.(S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Cirecuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
TOTAL:					Rs: 62,433.0


XEN

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
(Part - B) N.S.I					
1	Fixing A.C ceiling fan regulator on S.W board.				
	6.00	@ Rs: 109.56	P.Each	Rs:	657.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.				
	6.00	@ Rs: 169.21	P.Each	Rs:	1,014.00
3	P/F main panel board double shutter to accommodate heavey duty circuit breakers bus bar ine painting.				
	1.00	@ Rs: 1089.55	P.Sq:ft:	Rs:	1,090.00
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavcation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee,				
	1.00	@ Rs: 3084	P.Each	Rs:	3,084.00
5	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.				
	8.00	@ Rs: 596.40	P.Each	Rs:	4,771.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.				
	2.00	@ Rs: 596.40	P.Each	Rs:	1,193.00
7	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.				
	3.00	@ Rs: 140.26	P.Each	Rs:	421.00
Part 'B' TOTAL:					Rs: 12,230.0
Part 'A' TOTAL:					Rs: 62,433.0
TOTAL:					Rs: 74,663.0

XEN

SCHEDULE 'B'

42

Name of Work:- Rehabilitation of Existing primary schools in Taluka Ratodero District larkano
(11 units) (2015-16) Programme At: GBPS Muhammad Murad Kasai

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	13.00	@ Rs: 910.0	P.Point	Rs: 11,830.00
2	Wiring for Plug polint with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	2.00	@ Rs: 742.0	P.Point	Rs: 1,484.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029) Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	30.00	@ Rs: 171.0	P.Meter	Rs: 5,130.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/052)(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	31.00	@ Rs: 428.0	P.Meter	Rs: 13,268.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	15.00	@ Rs: 54.0	P.Each	Rs: 810.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	2.00	@ Rs: 83.0	P.Each	Rs: 166.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	7.00	@ Rs: 70.0	P.Each	Rs: 490.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	6.00	@ Rs: 72.0	P.Each	Rs: 432.00
9	Providing and fixing brass ceiling fan 56" (good quality).	6.00	@ Rs: 3185.0	P.Each	Rs: 19,110.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet.(S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Cirecuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
TOTAL:					Rs: 57,617.0


XEN

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
	<u>(Part - B) N.S.I</u>				
1	Fixing A.C ceiling fan regulator on S.W board. 6.00	@ Rs: 109.56		P.Each	Rs: 657.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof. 6.00	@ Rs: 169.21		P.Each	Rs: 1,015.00
3	P/F main panel board double shutter to accommodate heavy duty circuit breakers bus bar ine painting. 1.00	@ Rs: 1089.55		P.Sq:ft:	Rs: 1,090.00
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavcation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee, 1.00	@ Rs: 3084		P.Each	Rs: 3,084.00
5	P/F Energy saver superior quality i/c fixing on extg: holder etc complete. 7.00	@ Rs: 596.40		P.Each	Rs: 4,175.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete. 4.00	@ Rs: 596.40		P.Each	Rs: 2,386.00
Part 'B' TOTAL:					Rs: 12,407.0
Part 'A' TOTAL:					Rs: 57,617.0
TOTAL:					70,024.0


XEN

SCHEDULE 'B'

Name of Work:- Rehabilitation of Existing Primary Schools in Taluka Ratodero
(11 units) (2015-16) Programme At: GBPS Sharif Abro

43

SNo:	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15)	13.00	@ Rs: 910.0	P.Point	Rs: 11,830.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	2.00	@ Rs: 742.0	P.Point	Rs: 1,484.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	42.00	@ Rs: 171.0	P Meter	Rs: 7,182.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	30.00	@ Rs: 428.0	P.Meter	Rs: 12,840.00
5	Providing & Fixing A.C one way S.P 5ampswitch flush type (S.I.No: 219 P 33)	12.00	@ Rs: 54.0	P.Each	Rs: 648.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	2.00	@ Rs: 83.0	P.Each	Rs: 166.00
7	Providing & Fixing Brass Batterm holder.(S.I.No: 232 P 33)	6.00	@ Rs: 70.0	P.Each	Rs: 420.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals (S.I.No: 228 P 33)	4.00	@ Rs: 72.0	P.Each	Rs: 288.00
9	Providing and fixing brass ceiling fan 56" (good quality).	4.00	@ Rs: 3185.0	P.Each	Rs: 12,740.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet (S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	4.00	@ Rs: 948.0	P.Each	Rs: 3,792.00
TOTAL:					Rs: 51,547.0
(Part - B) N.S.I					
1	ixing A.C ceiling fan regulator on S.W board.	4.00	@ Rs: 109.56	P.Each	Rs: 438.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	4.00	@ Rs: 169.21	P.Each	Rs: 677.00
3	P/F main panel board double shutter to accommodate heavey duty circuit breakers bus bar ine painting.	1.00	@ Rs: 1089.55	P.Sq.ft.	Rs: 1,090.00
4	P/F Energy saver superior quality i/c fixing on extg. holder etc complete.	10.00	@ Rs: 596.40	P.Each	Rs: 5,964.00
5	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.	2.00	@ Rs: 140.26	P.Each	Rs: 281.00
Part 'B'TOTAL:					Rs: 8,450.0
Part 'A'TOTAL:					Rs: 51,547.0
TOTAL:					Rs: 59,997.0



SCHEDULE "B"

Name of Work:-

Integrataed Rehabilitation of primary School and provoision of missing facilities (12 unts) (2015-16 Progg:) At: GBPS Latifabad Taluka Bakra

App 223

S.No	Description	Qty:	Rate		Amount
1	Excavation in foundation of building bridges and other structure member with excavated lead upto chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).	560.0	@ Rs: 3176.25	%0 CFT	Rs: 1,778
2	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P/16).	371.0	@ Rs: 8694.95	% CFT	Rs: 32,258
3	Pacca brick work in foundation and plinth in cement sand mortor ration 1:6 (S.I No 4 (C) 23.	464.0	@ Rs: 11948.36	% CFT	Rs: 55,440
4	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I No. 6 (a) P/18)	100.0	@ Rs: 337.00	P.CFT	Rs: 33,700
5	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/20)	4.5	@ Rs: 5001.70	P. CWT	Rs: 22,328
6	Pacca brick work in other than building i/c stricking of joints cement sand mortor Ratio 1:6 (S.I No	450.0	@ Rs: 12346.65	% CFT	Rs: 55,560
7	Pacca brick work in Ground floor i/c stricking of joints cement sand mortor Ratio 1:6 (S.I No 5 (C)	16.0	@ Rs: 12674.36	% CFT	Rs: 2,028
8	S/F sand floor and plugging into walls (S.I.No 29 P/31).	158.0	@ Rs: 1141.25	% CFT	Rs: 1,803
9	Cement plaster 1;6 upto 20' ft; height 1/2" thick. (S.I No.13 P/57)	1,520.0	@ Rs: 2206.60	% CFT	Rs: 33,540
10	Cement plaster 1:4 upto 20' ft; height 3/8" thick. (S.I No: 11(a) P 57)	1,520.0	@ Rs: 2197.52	% CFT	Rs: 33,402
11	Cement pointing and stricking of joints on walls ratid. 1: 2 (S.I No.19 (a) P/53)	708.0	@ Rs: 1287.44	% CFT	Rs: 9,115
12	Cemnet concret plain i/c placing compacting finishing and curring complete i/c screeing and wash stone aggregate without shuttering Ratio 1:2:4, (S.I.No 5 P/18)	11.0	@ Rs: 14429.25	%SFT	Rs: 1,587
13	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenls Ration 3" (S.I No:16 (C) P/46)	805.0	@ Rs: 4411.82	%SFT	Rs: 35,515
B 2 Thick		111.0	@ Rs: 3275.50	%SFT	Rs: 3,636

Id	Description	Qty:	Rate		Amount
4	P/L Hala pattered tiles glazed 4" x 4 1/4" of floor of wall cacing in required pattern of cement over a base of 1:2 grey cement mortar 3/4" thick i/c washing and filling joints with slurry of white cement and pigment desired shape with finishing cleaning and cost of wax polish etc complete i/c cutting tile to proper profile (S.I No: 62 P/53)	33.0	@ Rs: 34520.31	%CFT	Rs: 11,392
15	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4" thick. (Only Shutters)	17.5	@ Rs: 1273.76	P.CFT	Rs: 22,928
16	Split tiles 1/4" thick matt glazed or double glazed jointed in white and laid 1:2 grey cement sand mortar i/c finishing complete (Flooring and Facing) (S.I.No 69 P/55).	50.0	@ Rs: 21021.11	%CFT	Rs: 10,511
17	White wash three coats.	50.0	@ Rs: 829.95	%CFT	Rs: 415
18	Primary coat of chalk under distemping (S.I No: 23 P 59)	360.0	@ Rs: 442.75	%CFT	Rs: 1,594
19	Preparing the surface and painting with weather coat i/c rubbing the surface coat i/c rubbing the surface brick /sen paper filling the voids with chalk plaster of paris and then painting with weather coat of app. make New surface. (S.I.No 39 (a) P/62).	1,400.0	@ Rs: 1948.10	%CFT	Rs: 27,273
20	Distemping three coats (S.I No: 24(B) P 59)	3,080.0	@ Rs: 1043.90	% Sft	Rs: 32,152
21	Making and fixing steel grated doors with 1/16" thick sheeting including angle iron frame 2"x2"x3/4" bars 4" centre to cement .	20.0	@ Rs: 726.72	P.Sft	Rs: 14,534
22	Painting doors & window any type, (S.I.No 05 P/ 76)	70.0	@Rs: 2116.41	%Cft	Rs: 1,481
23	S/F in position iron steel grill of 3/4" X flate iron of approved design i/c painting three coats etc complete with not to be less than 3.7 Lbs sq: ft: of finished grill.	13.7	@Rs: 194.16	%Cft	Rs: 2,718
TOTAL: Rs:					459,192


XEN

Description	Qty:	Rate		Amount
Part B				
1 P/F Squating type white glass W.C pan of i/c coat of finishing cistring with internal fitting and flush pipe between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.	2.0	@ Rs: 4846.60	P.No:	9694.00
2 P/F & 22"x16" Lavatory basin in white glazed earthen ware complete with & i/c the cost of W.I conntilever brackets 6 inch built into walls painted white in two cost after a primary cost of red land plinth a pair of 1/4" dia chrome plate pillar trape 1-1/2" dia P3	1.0	@ Rs: 4694.80	P.No:	4695.00
3 P/F 6'x2" or 6'x3" C.I floor tape.	3.0	@ Rs: 2042.43	P.No:	6073.00
4 P/F in position nyloon connection complete with 1/2" dia brass stop cock with pair brass nuts lining joints to nyloon connections	2.0	@ Rs: 77.85	P.No:	894.00
5 P/F 4" dia C.I soil and vent pipe i/c cutting fitting and extra painting to match the colour of the building	12.0	@Rs: 333.21	P.RFT	3999.00
6 P/F 4"x4" dia C.I branch of the required degree with access doors rubber washer 3/8" thick and bolts and unts and extra painting to match the colour of the building.	2.0	@ Rs: 270.60	P/No	541.20
7 Providing G.I pipe specials and clamps etc i/c fixing cutting fitting complete two coats of after cleaning the pipe etc with white zink paint with pigment to macth the colour of lthe building and testing pressure head of 200' and handling.				
(A) <u>1/2" dia</u>	25.00	@ Rs: 73.21	PRft	1830.00
(B) <u>3/4" dia</u>	50.00	@ Rs: 95.79	PRft	4790.00
8 Providing and fixing 4" dia C.I terminal guard i/c extra painting to match the colour of the colour of the building.	2.0	@ Rs: 389.70	PRft	779.00
9 Providing and fixing full way gun metal vallues with whelds threabed of flanged ends with rubber washing.(ii)3/4" (Light pattern)	1.0	@ Rs: 197.12	P.No	197.00
10 P/F C:P.Bross bib cock 1/2 " Dia.	2.00	@ Rs: 337.92	P.No	676.00
11 Providing RCC pipe with colors class"B" & dying trenches to required depth & fixing in position & Cement Morter 1:1 & test staff (a) 4"Dia Refilling with excavted staff.				
4"Dia	24.00	@ Rs: 146.57	Each	3518.00
6"Dia	12.00	@ Rs: 199.25	Each	2391.00
12 S/F Concealed stop cock of superior quality with C.P head 1/2"Dia	2.00	@ Rs: 478.28	P.No	957.00

Description	Qty:	Rate		Amount
13 S/F Long b/w-cock of superior quality with C.P head 1/2" Dia	1.00	@ Rs: 1109.46	P.No	1109.00
14 P/F approved quality AC Motor pumping set(Javed Engineering) Made etc.	1 No.	@ Rs: 5115	P.No:	5115.00
15 S/F Fibre glass tank of approved quality and design and wall thickness as specified i/c the cost of nuts and bolts and fixing in plate form of cement concrete 1:2:6 and making connection for inlet-outlet and over flow pipe etc complete. (250 Gallons).	1.0	@Rs: 21989.61	P.Gallans	13193.00
16 Hand pump all accessoried i/c fitting and fixing with local made coir strainer with wooden shoe i/c the complete.				
A <u>Filter.</u>	10.0	@ Rs: 76.05	P.Rft	761.00
B <u>G.I pipe</u>	40.0	@Rs: 38.95	P.Rft	3506.00
C <u>Machine</u>	1 No.	@Rs: 1441.65	P.No:	1442.00
TOTAL				64131.00


XEN

SCHEDULE 'B'

93

Name of Work - Integrated Rehabilitation of Primary Schools & Provision of missing facilities in Taluka Dokri
(11 Units)(2015-16 Progg.) at:GGPS Gabbar Massan Taluka Dokri

S.No	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1. 13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	20.00	@ Rs: 910.0	P.Point	Rs: 18,200.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742.0	P.Point	Rs: 2,226.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	68.00	@ Rs: 171.0	P.Meter	Rs: 11,628.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	85.00	@ Rs: 428.0	P.Meter	Rs: 36,380.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	28.00	@ Rs: 54.0	P.Each	Rs: 1,512.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	3.00	@ Rs: 83.0	P.Each	Rs: 249.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	10.00	@ Rs: 70.0	P.Each	Rs: 700.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals (S.I.No: 228 P 33)	8.00	@ Rs: 72.0	P.Each	Rs: 576.00
9	Providing and fixing brass ceiling fan 56" (good quality).	8.00	@ Rs: 3185.0	P.Each	Rs: 25,480.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet (S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
(Part - B) N.S.I					
TOTAL					101,848.00
1	Fixing A.C ceiling fan regulator on S.W board.	8.00	@ Rs: 109.56	P.Each	Rs: 880.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	8.00	@ Rs: 169.21	P.Each	Rs: 1,354.00
3	P/F main panel board double shutter to accommodate heavey duty circuit breakers bus bar inc painting	1.00	@ Rs: 1089.5	P.Sq.ft:	Rs: 1,090.00
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i,c making the pit 12" deep by excavcation of all type of soil. Earth Plate to be connected with No.8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee.	1.00	@ Rs: 3084.4	P.Each	Rs: 3,084.00
5	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.	16.00	@ Rs: 596.40	P.Each	Rs: 9,542.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	3.00	@ Rs: 596.40	P.Each	Rs: 1,789.00
7	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.	3.00	@ Rs: 140.26	P.Each	Rs: 420.00
Part 'B' TOTAL:					Rs: 18,159.0
Part 'A' TOTAL:					Rs: 101,848.0
TOTAL:					Rs: 120,000.0



SCHEDULE-B

Name of Work:- Integrated Rehabilitation of Primary Schools & Provision of Missing Facilities Taluka Dokri (11-Units) (2015-16 Prog:) At: Govt: (Boys) Primary School Othwal Taluka Dokri

S.No	DESCRIPTION	QUANTITY	RATE	UNIT	Rs:	AMOUNT
1	Dismantling Pacca brick work in cement mortar	90.0	@Rs: 1285.63	%Cft	Rs: 1157.00	
						3 (Rs: Twolve thousand Eighty Five & P.S Sixty Three)
2	Removing Cement or Lime Plaster	2259.0	@Rs: 121.0	%Cft	Rs: 2734.00	
						(Rs: One Hunared Twenty One only)
3	Dismantlin C.C plain 1:2:4. (S.I.No 19 (c) P/11).	166.0	@Rs: 3327.50	%Cft	Rs: 5512.00	
						(Rs: Three thousand Three Hundred Twenty Seven &
4	Excavation in foundation of building bridges and other structure member with excavated le chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).	367.00	@ Rs: 3176.25	%0 Cft	Rs: 1166.00	
5	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (P/	422.00	@Rs: 8694.95	% Cft	Rs: 36714.00	
						(Eight Thousand Six Hund:Ninty Four & P.S Ninty five
6	S/F sand floor and plugging into walls (S.I.No 29 P/31).	640.00	@Rs: 1141.25	%Cft	Rs: 7302.00	
						(Rs:One Thousand One Hund: Forty One & P.S Two
7	Single layer of tiles 9"x4-1/2"x2" laid over 4"earth mud plaster without Bhoosa grouted wit on top of RCC slab provide with 34 Lbs bitumen coating sand binded.	1039.0	@Rs: 5310.35	P.Sft	Rs: 55154.00	
						(Rs: Ten & P.S Seventy only)
8	Pacca brick work in foundation and plinth in cement sand mortar ration 1:6 (S.I No 4 (C)	210.00	@ Rs: 11948.36	% S.ft	Rs: 25032.00	
						(Eleven Thousand Nine Hund: Forty Eight & P.S
9	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or laid in position complete in all respect ratio 1:2:4 (S.I No. 6 (a) P/18)	46.00	@Rs: 337.0	P.Cft	Rs: 15377.00	
						(Three Hundred Thirty Seven only)
10	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bendin and laying ir i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/18)	2.240	@ Rs: 5001.70	P.CWt	Rs: 11204.00	
						(Five Thousand One &P.S Seventy).
11	Pacca brick work in other than building i/c stricking of joints cement sand mortar Ratio 1:6	270.00	@Rs: 12346.65	% Cft	Rs: 33335.00	
						(Tolive Thousand Three Hundred Fourty Six & P.S Si


EN

S.No	DESCRIPTION	QUANTITY	RATE	UNIT	Rs:	AMOUNT
12	Pacca brick work in Ground floor i/c striking of joints cement sand mortar Ratio 1:6 (S.I No. 12)	153.00	@Rs: 12674.36	% Cft	Rs: 19436.00	(Twelve thousand Six Hundred Seventy Four & Thirty)
13	Cement plaster 1:6 upto 20' ft; height 1/2" thick. (S.I No.13 P/57)	3170.00	@Rs; 2206.60	% Sft	Rs: 69960.00	(Two hundred Three Hund: Fifty Six & P.S Seventy I
14	Cement plaster 1:4 upto 20' ft; height 3/8" thick. (S.I No: 11(a) P 57)	3170.00	@ Rs: 2197.52	%S.ft	Rs: 69672.00	(Two Twousand One Hund: Ninty Seven & P.S Fifty
15	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c dec panelled and glazed (b) 1-3/4thicks.(Only Shutters)	60.00	@ Rs: 1273.76	P.Sft	Rs: 76426.00	(One Thousand Seventy Three & P.S Seventy Six)
B	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c dec panelled and glazed (b) 1-3/4thicks.(Only Shutters)	44.00	@ Rs: 902.93	P.Sft	Rs: 39729.00	(Nine Hundrad Two P.S Ninty Three only)
16	Cement pointing and striking of joints on walls ratio. 1: 2 (S.I No.19 (a) P/53)	360.00	@ Rs: 1287.44	%Cft	Rs: 4635.00	(Twelve Thousand Eighty Seven & P.S Fourty Four
17	White wash three coats (S.I.No 26 (c) 59).	978.0	@Rs: 829.95	% Sft	Rs: 8117.00	(Rs: Four Hundred Twenty Five & P.S Eighty Four on
18	Primary coat of chalk under distemping (S.I No: 23 P 59)	4,895.0	@ Rs; 442.75	% Sft	Rs: 21673.00	(Four Hundred Fourty Two & P.S Seventy Five only)
19	Distemping three coats, (S.I.No 24 (b) P/59)	4,895.0	@ Rs: 1079.65	% Sft	Rs: 52849.00	(Rs: One Thousand Seventy Nine & P.S Sixty Five or
20	Notice board made with cement.	32.00	@Rs; 58.11	% Sft	Rs: 1860.00	(Eighty Eight & P.S Eleven only)
21	S/Fin position iron steel grill of 3/4" X 1/4"plate iron of approved design i/c painting three cc not to beless than 3.7 Lbs sq: ft: of finished grill.	21.00	@Rs: 194.16	P.Sft	Rs: 4077.00	(Rs: One hundred Ninty Four & P.S Sixteen only)
22	M/F Steel grated doors with 1/16" thick sheeting i/c agnle iron frame 2"x2"x1/3" square bar	24.00	@ Rs: 726.72	%Sft	Rs: 17441.00	(Rs: Seven Hundred Twenty Six & P.S Seventy Three c


XEN

S.No	DESCRIPTION	QUANTITY	RATE	UNIT	Rs:	AMOUNT
23	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into panels Ra	1035.00	@ Rs: 4411.82	% S.ft	Rs: 45677.00	
						(Rs: Four Thousand Four Hundred Eleven & P.S Eight
(b)	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into panels Ra	402.00	@ Rs: 3275.50	% S.ft	Rs: 13168.00	
						(Rs: Four Thousand Four Hundred Eleven & P.S Eight
24	Preparing the surface and painting with weather coat i/c rubbing the surface coat i/c rubbr brick /sen paper filling the voids with chalk plaster of paris and then painting with weather make old surface.	1171.00	@Rs: 1948.10	%Sft	Rs: 22812.00	
						(One Thousand Nine Hundred Fourty Eight & P.S Ter
25	Painting doors & Window any type.	374.0	@ Rs: 2116.41	%Cft	Rs: 7915.00	
						(Rs: One Two Thousand one Hund: Sixteen & P.S Fo

Rs: 670134.00


XEN

47

SCHEDULE-B

Name of Work:- Integrated Rehabilitaiton of Primary Schools & Provision of Missing
Facilities Taluka Dokri (11-Units) (2015-16 Prog:) At: Govt: (Boys)
Primary School Hatri Ghulam Shah Taluka Dokri

S.No	DESCRIPTION	QUANTITY	RATE	UNIT	Rs:	AMOUNT
1	Dismantling Pacca brick work in cement mortor	210.0	@Rs: 1285.63	-- %Cft	Rs: 2700.00	(Rs: Twolve thousand Eighty Five & P.S Sixty Three)
2	Dismantlin C.C plain 1:2:4. (S.I.No 19 (c) P/11).	323.0	@Rs: 3327.50	%Cft	Rs: 10748.00	(Rs: Three thousand Three Hundred Twenty Seven &
3	Removing Cement or Lime Plaster	1212.0	@Rs: 121.0	%Cft	Rs: 1467.00	(Rs: One Hunared Twenty One only)
4	Excavation in foundation of building bridges and other structure member with excavated le chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).	24.00	@ Rs: 3176.25	%0 Cft	Rs: 762.00	
5	Sft sand floor and plugging into walls (S.I.No 29 P/31).	834.00	@Rs: 1141.25	%Cft	Rs: 9518.00	(Rs:One Thousand One Hund: Fourty One & P.S Tw
6	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P/	924.00	@Rs: 8694.95	% Cft	Rs: 80334.00	(Eight Thousand Six Hund:Ninty Four & P.S Ninty five
7	Pacca brick work in foundation and plinth in cement sand mortor ration 1:6 (S.I No 4 (C)	192.00	@ Rs: 11948.36	% S.ft	Rs: 22941.00	(Eleven Thousand Nine Hund: Fourty Eight & P.S
8	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or laid in position complete in all respect ratio 1:2:4 (S.I No. 6 (a) P/18)	42.00	@Rs: 337.0	P.Cft	Rs: 14154.00	(Three Hundred Thirty Seven only)
9	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying ir i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/20)	1.875	@ Rs: 5001.70	P.CWt	Rs: 9378.00	(Five Thousand One &P.S Seventy).
10	Pacca brick work in other than building i/c stricking of joints cement sand mortor Ratio 1:6	252.00	@Rs: 12346.65	% Cft	Rs: 31114.00	(Tolive Thousand Three Hundred Fourty Six & P.S Si
11	Single layer of tiles 9"x4-1/2"x2" laid over 4"earth mud plaster without Bhoosa grouted w on top of RCC slab provide with 34 Lbs bitumen coating sand binded.	2168.0	@Rs: 5310.35	P.Sft	Rs: 115126.00	(Rs: Ten & P.S Seventy only)
12	Cement plaster 1:6 upto 20' ft; height 1/2" thick (S.I.No.13 P/57)	1884.00	@Rs: 2206.60	% Sft	Rs: 41572.00	(Two hundred Three Hund: Fifty Six & P.S Seventy

S.No	DESCRIPTION	QUANTITY	RATE	UNIT	Rs:	AMOUNT
13	Cement plaster 1:4 upto 20' ft; height 3/8" thick. (S.I No: 11(a) P 57)	1884.00	@ Rs: 2197.52	%S.ft	Rs: 41401.00	(Two Twousand One Hund: Ninty Seven & P.S Fifty
14	Cement pointing and stricking of joints on walls ratio. 1: 2 (S.I No.19 (a) P/53)	672.00	@ Rs: 1287.44	%Cft	Rs: 8652.00	(Twolive Thousand Eighty Seven & P.S Fourty Four
15	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c dec panelled and glazed (b) 1-3/4thicks.(Only Shutters)	88.00	@ Rs: 902.93	P.Sft	Rs: 79458.00	(Nine Hundraed Two P.S Ninty Three only)
16	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls R	2295.00	@ Rs: 3275.50	% S.ft	Rs: 75173.00	(Rs: Four Thousand Four Hundred Eleven & P.S Eight
17	Notice board made with cement.	32.00	@Rs: 58.11	% Sft	Rs: 1860.00	(Eighty Eight & P.S Eleven only)
18	S/Fin position iron steel grill of 3/4" X 1/4"flate iron of approved design i/c painting three cc not to beless than 3.7 Lbs sq: ft: of finished grill.	18.00	@Rs: 194.16	P.Sft	Rs: 3495.00	(Rs: One hundred Ninty Four & P.S Sixteen only)
19	White wash three coats (S.I.No 26 (c) 59).	2,058.0	@Rs: 829.95	% Sft	Rs: 17080.00	(Rs: Four Hundred Twenty Five & P.S Eighty Four on
20	Primary coat of chalk under distemping (S.I No: 23 P 59)	8,698.0	@ Rs; 442.75	% Sft	Rs: 38510.00	(Four Hundred Fourty Two & P.S Seventy Five only)
21	Distemping three coats, (S.I.No 24 (b) P/59)	8,698.0	@ Rs: 1079.65	% Sft	Rs: 93908.00	(Rs: One Thousand Seventy Nine & P.S Sixty Five or
22	Painting doors & Window any type.	380.0	@ Rs: 2116.41	%Cft	Rs: 8042.00	(Rs: One Two Thousand one Hund: Sixteen & P.S F
23	Preparing the surface and painting with weather coat i/c rubbing the surface coat i/c rubbir brick /sen paper filling the voids with chalk plaster of paris and then painting with weather make old surface.	3434.00	@Rs: 1948.10	%Sft	Rs: 66898.00	(One Thousand Nine Hundred Fourty Eight & P.S Ter

TOTAL: Rs: 774,291.00


XEN

SCHEDULE 'B'

Name of Work:- Constt:of Dangerous Primary Schools in Taluka Dokri
(8 Units)(2015-16 Progg.) at:GGPS Faiz Muhammad Khokhar Taluka Dokri

S.No.	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	20.00	@ Rs: 910.0	P.Point	Rs: 18,200.00
2	Wiring for Plug polint with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	3.00	@ Rs: 742.0	P.Point	Rs: 2,226.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	68.00	@ Rs: 171.0	P.Meter	Rs: 11,628.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-/.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface (S.I.No: 6 P 1).	85.00	@ Rs: 428.0	P.Meter	Rs: 36,380.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	28.00	@ Rs: 54.0	P.Each	Rs: 1,512.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type (S.I.No: 225 P 33).	3.00	@ Rs: 83.0	P.Each	Rs: 249.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	10.00	@ Rs: 70.0	P.Each	Rs: 700.00
8	P/Fixing A C Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	8.00	@ Rs: 72.0	P.Each	Rs: 576.00
9	Providing and fixing brass ceiling fan 56" (good quality).	8.00	@ Rs: 3185.0	P.Each	Rs: 25,480.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet (S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
(Part - B) N.S.I					
TOTAL					101,848.00
1	Fixing A.C ceiling fan regulator on S W board.	8.00	@ Rs: 109.56	P Each	Rs: 880.00
2	P/F mild steel bar fan clam 15 8 mm (5/8") dia suitable for RCC roof.	8.00	@ Rs: 169.21	P Each	Rs: 1,354.00
3	P/F main panel board double shutter to accommodate heavy duty circuit breakers bus bar ine painting.	1.00	@ Rs: 1089.54	P.Sq.ft:	Rs: 1,090.00
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i,c making the pit 12" deep by excavcation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee.	1.00	@ Rs: 3084.4	P Each	Rs: 3,084.00
5	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.	16.00	@ Rs: 596.40	P.Each	Rs: 9,542.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	3.00	@ Rs: 596.40	P.Each	Rs: 1,789.00
7	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.	3.00	@ Rs: 140.26	P.Each	Rs: 420.00
Part 'B' TOTAL:					Rs: 18,159.0
Part 'A' TOTAL:					Rs: 101,848.0
TOTAL:					Rs: 120,000.0

Schedule-B

INTEGRATED REHABILITATION OF BUILDING FOR GBHS RATODERO (2010-11 PROGRAMME) (01 UNIT) TALUKA RATODERO DISTRICT LARKANO.

S #	Description	Qty	Rate	Unit	Amount
1	Dismantling cement concrete reinforced separating reinforcement from concrete cleaning & straightening the same. (S.I No. 20 P/10)	97.00	@ Rs. 5,445.00	% Cft (Fifty four hundred & forty five rupees only)	Rs. 5,282
2	Dismantling brick work in lime or cement mortar. (S.I No.13 P/10)	82.00	@ Rs: 1,285.63	% Cft (Twelve hundred eighty five rup & sixty three paisa only)	Rs: 1,054
3	Removing cement or lime plaster. (S.I No. 53 P/13)	1267.00	@ Rs: 121.00	% Cft (One hundred & twenty rup: only)	Rs: 1,533
4	Dismantling cement concrete reinforced separating reinforcement from concrete cleaning & straightening the same. (S.I No. 22 P/10)	37.00	@ Rs: 3,327.50	% Cft (Thirty three hundred twenty seven rup:& fifty paisa only)	Rs: 1,231
5	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.	600.00	@ Rs: 3,176.25	% OCft (Thirty one Hundred seventy six rup: & twenty five paisa only)	Rs: 1,906
6	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10.(S.I No. 3(d) P/14)	759.00	@ Rs: 8,694.95	% Cft (Eighty six hund: ninty four rup: & ninty five paisa only)	Rs: 65,995
7	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	789.00	@ Rs: 11,948.36	% Cft (Eleven thousand nine hund: forty eight rup: & thirty six paisa only)	Rs: 94,273
8	Supply and fixing sand under floor including plugging in to walls	4522.00	@ Rs: 1,141.25	% Cft (Eleven hundred forty one rupees & twenty five paisa only)	Rs: 51,607
9	Providing and Laying 3" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)	2000.00	@ Rs: 4,411.82	% Sft (Forry four hundred eleven rup: & eighty two paisa only)	Rs: 88,236
(B)	<u>2" Thick First Floor</u>	206.00	@ Rs: 3,275.50	% Sft (Thirty two hundred seventy five rup: & fifty paisa only)	Rs: 6,748
10	Pacca brick work in Ground Floor i/c striking of joints in cement sand mortar ratio 1:6.	47.00	@ Rs. 12,674.36	% Cft (Twelve thousand six hundred seventy four rup: & thity six paisa only)	Rs. 5,957

XEN

S #	Description	Qty	Rate	Unit	Amount
11	Pacca brick work other than building i/c striking of joints in cement sand mortar ratio 1:6. 218.00 @ Rs. 12,346.65 % Cft (Twelve thousand three hund: forty six rup: & sixty five paisa only)	218.00	@ Rs. 12,346.65	% Cft	Rs. 26,916
12	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15) 97.00 @ Rs: 337.00 P.Cft (Three hundred Thirty seven rup: only)	97.00	@ Rs: 337.00	P.Cft	Rs: 32,689
13	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I. No. 8 (b) P/16) 4.76 @ Rs: 5,001.70 P.Cwt (Five thousand one rup: & seventy paisa only)	4.76	@ Rs: 5,001.70	P.Cwt	Rs: 23,808
14	Cement concrete plain i/c placing, compacting, finishing & curing complete i/c screening & washing of stone aggregate without shuttering. Ratio 1:3:6. 24.00 @ Rs. 14,429.25 % Cft (Fourteen thousand four hund: twenty nine rup: & twenty paisa only)	24.00	@ Rs. 14,429.25	% Cft	Rs. 3,463
15	P/L tile glazed 6"x6" 1/4 on floor on wall facing required floor and pattern and stile specification joint in white cement and pigment over a base of 1:2 grey (S.I. P/46) 642.00 @ Rs. 30,509.77 % Sft (Thirty thousand five hund: nine rupees & seventy seven paisa only)	642.00	@ Rs. 30,509.77	% Sft	Rs. 195,873
16	P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools and pla 64.00 @ Rs: 228.90 P. Rft (Two hundred twenty eight rupees & ninty paisa only)	64.00	@ Rs: 228.90	P. Rft	Rs: 14,650
17	P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools and pla 29.00 @ Rs: 240.50 P. Rft (Two hundred forty rupees & fifty paisa only)	29.00	@ Rs: 240.50	P. Rft	Rs: 6,975
18	1 st class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25 P/60) 86.00 @ Rs: 902.93 P. Sft (Nine hund: two rup: & ninty three paisa only)	86.00	@ Rs: 902.93	P. Sft	Rs: 77,652
19	Making & fixing steel gated doors with 1 1/6" thick sheeting i/c angle iron frame 2"x2"x3/4" and square bars 4" centre to cement. 24.00 @ Rs. 726.72 P. Sft (Seven hundred twenty six rupees & seventy two paisa only)	24.00	@ Rs. 726.72	P. Sft	Rs. 17,441
20	Providing and fixing iron steel grill door with angle iron frame of 1 1/2" x 1 1/2" x 1/4" and flat iron of 3/4" x 1/4" with approved design and locking arrangement embeded in Masonry as per instructions of Engineer in charg.(S.I No. 31 P No. 93) 99.00 @ Rs. 231.60 P. Sft (Two hundred thiry one rup: & sixty Paisa only)	99.00	@ Rs. 231.60	P. Sft	Rs. 22,928

S #	Description	Qty	Rate	Unit	Amount
21	Cement Plaster 1:4 upto 12" height. 3/4" thick (S.I No. 11 (c) P/51)	1267.00	@ Rs: 3,015.76	% Sft	Rs: 38,210
	(Three thousand fifteen rup: & seventy six paisa only)				
22	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)	485.00	@ Rs. 2,206.60	% Cft	Rs. 10,702
	(Twenty tow hund: six rup: & sixty paisa only)				
23	Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)	485.00	@ Rs: 2,197.52	% Sft	Rs: 10,658
	(Twenty one hund: ninty seven rup: & fifty two paisa only)				
24	Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)	291.00	@ Rs: 1,287.44	% Sft	Rs: 3,746
	(Twelve hundred eighty seven rupees & forty for paisa only)				
25	Two coats of Bitumen laid hot using 34lbs, for % over with sand of one 3/4" thick. (S.I No. 13 P/34)	206.00	@ Rs. 1,887.40	% Sft	Rs. 3,888
	(Eighteen hundred eighty seven rupees & forty paisa only)				
26	P/F ornamental Cement jali 2" thick (1:2:4) Without steel	88.00	@ Rs: 226.02	P. Sft	Rs: 19,890
	(Two hundred twenty six rupees & two paisa only)				
27	Primary coat of chalk distemper(S.I No. 23 P/53)	1752.00	@ Rs: 442.75	% Sft	Rs: 7,757
	(Four hundred forty two rupees & seventy five paisa only)				
28	Distemping Three Coats (S.I No. 24 ©P/53)	1752.00	@ Rs: 1,079.65	% Sft	Rs: 18,915
	(One thousand Seventy nine rup: & sixty five paisa only)				
29	Preparing surface & painting with weather coat i/c rubbing the surface with rubbing brick / sand paper filling the voids with chalk / plaster then painting with weather coat of approved make(New surface)(S.I No.38 (a) P/55)	291.00	@ Rs: 1,948.10	% Sft	Rs: 5,669
	(Nineteen hundred forty eight rupees & ten paisa only)				
26	Prepairing surface and painting of doors and widows any type, (including edges) (3 coats) (new surface) (S.I.No: 4 (c) P. 76 (ii)).	172.00	@ Rs: 2,116.41	% Sft	Rs: 3,640
	(Twenty one hundred sixteen rup & forty one paisa only)				
31	Preparing surface & painting Guard bars, gates / iron bars gating rakings i/c standard braces etc & similar open work.	48.00	@ Rs. 1,270.83	% Sft	Rs. 610
	(Twelve Hundred seventy rupees & cithy three paisa only)				

Total Rs:

869,918

XEN

SCHEDULE 'B'

Name of Work:- Provision Of essential Facilities in Existing High / Higher Secondary Schools in Taluka Ratodero (3 Units) (2011-12 Programme) at: GBHS (S.S) Ratodero (science Lab, Computer Lab & Library)

S.No.	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4")PVC conduit rescessed in the coloumns as required (S.I.No: 124 P 15)	72.00	@ Rs: 1130.0	P.Point	81360.0
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4")PVC conduit rescessed in the coloumns as required (S.I.No: 126 P 15)	15.00	@ Rs: 985.0	P.Point	14775.0
3	Wiring for Call beel with 1/1.13 (3/029) PVC insulated wire in 20mm(3/4")PVC conduit rescessed in the coloumns as required (S.I.No: 128 P 15)	3.00	@ Rs: 1764.0	P.Point	5292.0
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7(.029) Copper conductor in 3/4" PVC conduit rescessed in the wall or coloum as required (S.I.No: 24 P 4)	375.00	@ Rs: 222.0	P.Meter	83250.0
5	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7(.044)(6mm2)Copper conductor in 1" PVC conduit rescessed in the wall or coloum as required (S.I.No: 26 P 4)	150.00	@ Rs: 341.0	P.Meter	51150.0
6	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7(.052)(10mm2) Copper conductor in 1" dia PVC conduit on surface.	200.00	@ Rs: 428.0	P.Meter	85600.0
7	Providing & Fixing A.C one way S.P 10/15 amps switch flush type (S.I.No: 219 P33).	72.00	@ Rs: 58.0	P.Each	4176.0
8	Providing & Fixing 2 pin 5 amos plug & socket flush type. (S.I.No: 225 P 33).	15.00	@ Rs: 83.0	P.Each	1245.0
9	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	5.00	@ Rs: 162.0	P.Each	810.0
10	Providing & Fixing Bras batten holder . (S.I.No: 232 P 33).	44.00	@ Rs: 70.0	P.Each	3080.0
11	P/Fixing Brase Baklite Ceiling rose with two terminals (S.I.No: 228 P 33)	28.00	@ Rs: 72.0	P.Each	2016.0
12	Providing and fixing brass ceiling fan 56" (good quality) (S.I.No: 235 P 34)	28.00	@ Rs: 3185.0	P.Each	89180.0
13	P/F Circuit breakers 15,20,30 40,50,60,75 & 100 Amps (T P (XS-100 NS on a prepared board as required (S.I.No: 207 P 31)	2.00	@ Rs: 9261.0	P.Each	18,522.00
14	Fixing A.C or D.C Electric beel 200/250 Volts 70 MM (S.I.No: 19 P 12)	3.00	@ Rs: 150.70	P.Each	452.0
15	P/F flush type electric beel push button (S.I.No: 23 P 12)	3.00	@ Rs: 25.19	P.Each	76.0
16	P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection (S.I.No: 2 P 20)	12.00	@ Rs: 948.02	P.Each	11376.0
TOTAL:					Rs: 452360.0

XEN

SNo:	ITEM OF WORK	Qty:	Rate	Amount.
(Part - B) N.S.I				
1	Fixing A.C ceiling fan regulator on S.W board. 28.00	@ Rs: 109.56	P.Each	Rs: 3,061.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof. 28.00	@ Rs: 169.21	P.Each	Rs: 4,738.00
3	P/F main panel board double shutter to accommodate heavy duty circuit breakers bus bar ine painting. 3.00	@ Rs: 1089.55	P.Sq.ft:	Rs: 3,269.00
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal, etc. i.c making the pit 12" deep by excavation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2" dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee, 1.00	@ Rs: 3084.44	P.Each	Rs: 3,084.00
5	P/F Energy saver superior quality i/c fixing on extg: holder etc complete. 44.00	@ Rs: 596.40	P.Each	Rs: 26,242.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete. 10.00	@ Rs: 596.40	P.Each	Rs: 5,964.00
7	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs. 8.00	@ Rs: 140.26	P.Each	Rs: 1,122.00
Part 'B' TOTAL:				Rs: 47480.0
Part 'A' TOTAL:				Rs: 452360.0
TOTAL:				Rs: 499840.0


XEN

Schedule-B

51

CONSTRUCTION OF COMPUTER BLOCK @ GBHS RATODERO TALUKA

Name of Work:- **RATODERO (2011-12 PROGRAMME) TALUKA RATODERO DISTRICT LARKANA (BALANCE WORK).**

S #	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.	630.00	@ Rs: 3,176.25	% Cft	Rs: 2,001
	(Thirty one Hundred seventy six rup: & twenty five paisa only)				
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10.(S.I No. 3(d) P/14)	2194.00	@ Rs: 8,694.95	% Cft	Rs: 190,767
	(Eighty six hund: ninty four rup: & ninty five paisa only)				
3	Supply and fixing sand under floor including plugging in to walls	12487.00	@ Rs: 1,141.25	% Cft	Rs: 142,508
	(Eleven hundred forty one rupees & twenty five paisa only)				
4	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	867.00	@ Rs: 11,948.36	% Cft	Rs: 103,592
	(Eleven thousand nine hund: forty eight rup: & thirty six paisa only)				
5	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)	700.00	@ Rs. 2,206.60	% Cft	Rs. 15,446
	(Twenty tow hund: six rup: & sixty paisa only)				
6	Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)	700.00	@ Rs: 2,197.52	% Sft	Rs: 15,383
7	Providing and Laying 3" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)	6226.00	@ Rs: 4,411.82	% Sft	Rs: 274,680
	(Forry four hundred eleven rup: & eighty two paisa only)				
8	Galvanized wire guage fixing to chowkats 3/4" deodar slips and screws (S.I No. 14 (C) P/69).	144.00	@ Rs. 190.72	P. Sft	Rs. 27,464
	(One hundred Ninety rupees & seventy two paisa only)				
9	Painting doors & Windows any type (New Surface).(S.I No. 4 (c) P/67)	403.00	@ Rs: 1,212.21	% Sft	Rs: 4,885
	(Twelive hundred twelive rup :& twenty one paisa only)				
10	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)	53.00	@ Rs: 337.00	P.Cft	Rs: 17,861
	(Three hundred Thirty seven rup: only)				
11	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I .No. 8 (b) P/16)	2.366	@ Rs: 5,001.70	P.Cwt	Rs: 11,834
	(Five thousand one rup: & seventy paisa only)				

Total Rs: 806,421


XEN

S.#	Description	Rate	Unit	Qty	Amount
-----	-------------	------	------	-----	--------

PART - B

- 1 P/F squatting type white glazed earthen ware W.C pan of with i/c cost of flushing cistern with internal fitting & flush pipe with bend making good in cement concrete 1:2:4. (i) W.C not less than 19" clear opening b/w flushing & 6 gallons flushing tank with

2.00 @ Rs: 4,846.80 P. No. Rs. 9,694
(Forty eight hundred forty six rup: & eighty paisa only)

- 2 Providing G.I pipe specials & clamps etc i/c fixing, cutting & fitting complete two coats of after cleaning the pipe etc with white zink paint with pigment to match the colour of the building & testing the pressure head of 200" & handling.

(A) **1" Dia**

12.00 @ Rs: 76.21 P. Rft Rs. 915
(Seventy six rupees & twenty One paisa only)

(B) **3/4" dia**

24.00 @ Rs: 95.79 P. Rft Rs. 2,299
(Ninty five rupees seventy nine paisa only)

- 3 S/F C.P brass bib cock 1/2" dia standard pattern.

2.00 @ Rs: 337.92 P. No. Rs. 676
(Three hundred thirty seven rupees & ninty two paisa only)

- 4 P/F approved quality A.C motor pumping set (Javed Engineering) made 1-1/4" 1" section & delivery with base & complying 1 H.Power single phase motor (Siemens make) 60" ft. head of 2800 KPM i/c the cost of C.I fitting nuts, bolts & the cost of 1:2:4 plate f

1.00 @ Rs: 5,115.00 P. No. Rs. 5,115
(Fifty one hundred fifteen rupees only)

- 5 S/F Fibre Glass Tank of approved quality & design & wall thickness as specified i/c the cost of nuts, bolts & fixing in plate form of cement concrete 1:2:6 & making connection for inlet-outlet & over flow pipe etc complete. (150 Gallons).

150.00 @ Rs: 87.95 P. Gallon Rs. 13,193
(Eighty Seven rup: & Ninety Five paisa only)

S.I Rs. 31,890

N.S.I Rs. 5,115

Grand Total	Rs. (S.I)	26,775
--------------------	------------------	---------------


XEN

SCHEDULE 'B'

Name of Work:- Integrated Rehabilitation of Existing Secondary & Higher Secondary Schools in Taluka Larkano (5 Units)(2015-16 Progg.) at:GBHS Mahotta Taluka Larkana

S. No.	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	42.00	@ Rs: 910.0	P.Point	Rs: 38,220.00
2	Wiring for Plug polint with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	6.00	@ Rs: 742.0	P.Point	Rs: 4,452.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	81.00	@ Rs: 171.0	P.Meter	Rs: 13,851.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7.044} Copper conductor in 1" dia PVC conduit on surface (S.I.No: 6 P 1).	70.00	@ Rs: 305.0	P.Meter	Rs: 21,350.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface (S.I.No: 6 P 1).	65.00	@ Rs: 428.0	P.Meter	Rs: 27,820.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	32.00	@ Rs: 54.0	P.Each	Rs: 1,728.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	6.00	@ Rs: 83.0	P.Each	Rs: 498.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	19.00	@ Rs: 70.0	P.Each	Rs: 1,365.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	13.00	@ Rs: 72.0	P.Each	Rs: 936.00
9	Providing and fixing brass ceiling fan 56" (good quality).	18.00	@ Rs: 3185.0	P.Each	Rs: 57,330.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet (S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	10.00	@ Rs: 948.0	P.Each	Rs: 9,480.00
(Part - B) N.S.I					
1	Fixing A.C ceiling fan regulator on S.W board.	12.00	@ Rs: 109.56	P.Each	Rs: 1,315.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	16.00	@ Rs: 169.21	P.Each	Rs: 2,707.00
3	P/F main panel board double shutter to accommodate heavey duty circuit breakersbus bar ine painting	1.00	@ Rs: 1089.51	P.Sq.ft	Rs: 1,090.00
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal.etc.i.c making the pit 12" deep by excavcation of all type of soil. Earth Plate to be connected with No.8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee,	1.00	@ Rs: 3084.4	P.Each	Rs: 3,084.00
5	P/F Energy saver superior quaity i/c fixing on extg: holder etc complete.	20.00	@ Rs: 596.40	P.Each	Rs: 11,928.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	3.00	@ Rs: 596.40	P.Each	Rs: 1,789.00
7	P/F hinged type double S.W board accomodate main or sub-main control switches and for other similar jobs	6.00	@ Rs: 140.26	P.Each	Rs: 842.00
Part 'B' TOTAL:					Rs: 22,755.00
Part 'A' TOTAL:					Rs: 177,190.00
TOTAL:					Rs: 199,945.00



SCHEDULE 'B'

53

Name of Work:- Integrated Rehabilitation of Existing Secondary & Higher Secondary Schools in Taluka Larkano
(5 Units)(2015-16 Progg.) at:GBHS Kehar Taluka Larkana

SN	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	21.00	@ Rs: 910.0	P.Point	Rs: 19,110.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	4.00	@ Rs: 742.0	P.Point	Rs: 2,968.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	60.00	@ Rs: 171.0	P.Meter	Rs: 10,260.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-/052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	63.00	@ Rs: 428.0	P.Meter	Rs: 26,964.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	25.00	@ Rs: 54.0	P.Each	Rs: 1,350.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	4.00	@ Rs: 83.0	P.Each	Rs: 332.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	13.00	@ Rs: 70.0	P.Each	Rs: 910.00
8	P/Fixing A C Baklite Ceiling rose with two terminals (S.I.No: 228 P 33)	8.00	@ Rs: 72.0	P.Each	Rs: 576.00
9	Providing and fixing brass ceiling fan 56" (good quality).	8.00	@ Rs: 3185.0	P.Each	Rs: 25,480.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet.(S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Cirecuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	5.00	@ Rs: 948.0	P.Each	Rs: 4,740.00
TOTAL:					Rs: 92,847.0
(Part - B) N.S.I					
1	Fixing A.C ceiling fan regulator on S.W board	8.00	@ Rs: 109.56	P.Each	Rs: 876.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	8.00	@ Rs: 169.21	P.Each	Rs: 1,354.00
3	P/F main panel board double shutter to accommodate heavey duty circuit breakersbus bar ine painting.	1.00	@ Rs: 1089.5	P.Sq.ft:	Rs: 1,090.00
4	P/F Earthing set with 2"x2"x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavcation of all type of soil. Earth Plate to be connected with No.8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee.	1.00	@ Rs: 3084.4	P.Each	Rs: 3,084.00
5	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.	13.00	@ Rs: 596.40	P.Each	Rs: 7,753.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	4.00	@ Rs: 596.40	P.Each	Rs: 2,386.00
7	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.	4.00	@ Rs: 140.26	P.Each	Rs: 561.00
Part 'B' TOTAL:					Rs: 17,104.0
Part 'A' TOTAL:					Rs: 92,847.0
TOTAL:					Rs: 109,951.0


XEN

54

SCHEDULE 'B'

Name of Work:- Integrated Rehabilitation of Existing Secondary & Higher Secondary Schools in Taluka Larkana (5 Units)(2015-16 Progg:) at:GBHS Shaikh Zaid Colony (Water Tank,Cycle Shed) Taluka Larkana

SN	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	9.00	@ Rs: 910.0	P.Point	Rs: 8,190.00
2	Wiring for Plug polint with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	1.00	@ Rs: 742.0	P.Point	Rs: 742.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029) Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	31.00	@ Rs: 171.0	P.Meter	Rs: 5,301.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-/052)(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	20.00	@ Rs: 428.0	P.Meter	Rs: 8,560.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	10.00	@ Rs: 54.0	P.Each	Rs: 540.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	1.00	@ Rs: 83.0	P.Each	Rs: 83.00
7	Providing & Fixing Brass Battern holder. (S.I.No: 232 P 33)	9.00	@ Rs: 70.0	P.Each	Rs: 630.00
11	P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	2.00	@ Rs: 948.0	P.Each	Rs: 1,896.00
TOTAL:					Rs: 25,928.0
(Part - B) N.S.I					
3	P/F main panel board double shutter to accommodate heavy duty circuit breakersbus bar ine painting.	1.00	@ Rs: 1089.5	P.Sq.ft:	Rs: 1,090.00
5	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.	5.00	@ Rs: 596.40	P.Each	Rs: 2,982.00
Part 'B' TOTAL:					Rs: 4,072.0
Part 'A' TOTAL:					Rs: 25,928.0
TOTAL:					Rs: 30,000.0


XEN

SCHEDULE 'B'

Name of Work:- Construction of Residential Quarters/Bunglows District Education Officers
(3 Units)(2011-12 Progg.) at: XEN Education Works Division Larkana

SN	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	42.00	@ Rs: 910.0	P.Point	Rs: 38,220.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 129 P 15)	6.00	@ Rs: 742.0	P.Point	Rs: 4,452.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	81.00	@ Rs: 171.0	P Meter	Rs: 13,851.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/044} Copper conductor in 1" dia PVC conduit on surface (S.I.No: 6 P 1).	70.00	@ Rs: 305.0	P.Meter	Rs: 21,350.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/052}(10mm2) Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	65.00	@ Rs: 428.0	P.Meter	Rs: 27,820.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	32.00	@ Rs: 54.0	P.Each	Rs: 1,728.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	6.00	@ Rs: 83.0	P.Each	Rs: 498.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	19.00	@ Rs: 70.0	P.Each	Rs: 1,368.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	13.00	@ Rs: 72.0	P.Each	Rs: 936.00
9	Providing and fixing brass ceiling fan 55" (good quality).	18.00	@ Rs: 3185.0	P.Each	Rs: 57,330.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet.(S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	10.00	@ Rs: 948.0	P.Each	Rs: 9,480.00
(Part - B) N.S.I					
1	Fixing A.C ceiling fan regulator on S.W board.	12.00	@ Rs: 109.56	P.Each	Rs: 1,315.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	16.00	@ Rs: 169.21	P.Each	Rs: 2,707.00
3	P/F main panel board double shutter to accommodate heavey duty circuit breakersbus bar ine painting.	1.00	@ Rs: 1089.5	P.Sq.ft:	Rs: 1,090.00
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i.c making the pit 12" deep by excavation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee,	1.00	@ Rs: 3084.4	P.Each	Rs: 3,084.00
5	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.	20.00	@ Rs: 596.40	P.Each	Rs: 11,928.00
6	P/F wall bracket light fancy type superior quaity including necessary electric connection and fixing on wall or ceiling etc complete.	3.00	@ Rs: 596.40	P.Each	Rs: 1,789.00
7	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.	6.00	@ Rs: 140.26	P.Each	Rs: 842.00
Part 'B' TOTAL:					Rs: 22,755.0
Part 'A' TOTAL:					Rs: 177,190.0
TOTAL:					Rs: 199,945.0

SCHEDULE 'B'

56

Name of Work:- Rehabilitation/Improment of Education Office Building District Larkano
(6 Units)(2011-12 Progg:) at: Director Schools Education Office Larkana

SN	ITEM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/.029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	80.00	@ Rs: 910.0	P.Point	Rs: 72,800.00
2	Wiring for Plug polint with (3/.029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	6.00	@ Rs: 742.0	P Point	Rs: 4,452.00
3	Wiring for Call beel with 1/1.13 (3/.029) PVC insulated wire in 20mm(3/4")PVC conduit recessed in the coloumns as required (S.I.No: 128 P 15)	3.00	@ Rs: 1764.0	P Point	Rs: 5292.0
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	81.00	@ Rs: 171.0	P.Meter	Rs: 13,851.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-/.044} Copper conductor in 1" dia PVC conduit on surface (S.I.No: 6 P 1).	70.00	@ Rs: 305.0	P.Meter	Rs: 21,350.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-/.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface (S.I.No: 6 P 1).	65.00	@ Rs: 428.0	P.Meter	Rs: 27,820.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	32.00	@ Rs: 54.0	P.Each	Rs: 1,728.00
14	Fixing A.C or D.C Electric beel 200/250 Volts 70 MM (S.I.No:19 P 12).	3.00	@ Rs: 150.70	P.Each	Rs: 452.0
15	P/F flush type electric beel push button.(S.I.No: 23 P 12)	3.00	@ Rs: 25.19	P.Each	Rs: 76.0
6	Providing & Fixing 2 pin 5 amps plug & socket flush type (S.I.No: 225 P 33).	6.00	@ Rs: 83.0	P.Each	Rs: 498.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	19.00	@ Rs: 70.0	P.Each	Rs: 1,368.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	13.00	@ Rs: 72.0	P.Each	Rs: 936.00
9	Providing and fixing brass ceiling fan 56" (good quality).	20.00	@ Rs: 3185.0	P.Each	Rs: 63,700.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet (S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Cirecuit breakers 6 Amps to 63 Amps D.P /c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	10.00	@ Rs: 948.0	P.Each	Rs: 9,480.00
12	P/F Cirecuit breakers 15,20,30,40,50,60,75 & 100 Amps (T P (XS-100 NS on a prepared board as required (S.I.No: 207 P 31)	2.00	@ Rs: 9261.0	P.Each	Rs: 18,522.00
TOTAL					242,482.00

XEN

SN	ITEM OF WORK	Qty:	Rate	Unit	Amount.
----	--------------	------	------	------	---------

(Part - B) N.S.I

1	Fixing A.C ceiling fan regulator on S.W board.	22.00	@ Rs: 109.56	P.Each	Rs: 2,410.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	22.00	@ Rs: 169.21	P.Each	Rs: 3,723.00
3	P/F main panel board double shutter to accommodate heavy duty circuit breakers bus bar line painting.	6.00	@ Rs: 1089.51	P.Sq.ft:	Rs: 6,537.00
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal, etc, i.e making the pit 12" deep by excavation of all type of soil. Earth Plate to be connected with No.8 S.W.G bare copper wire run in 1/2" dia C.I pipe straight from the earth upto metallie electrical assarary i/c providing necessary tee.	1.00	@ Rs: 3084.40	P.Each	Rs: 3,084.00
5	P/F Energy saver superior quality i/c fixing on extg. holder etc complete.	50.00	@ Rs: 596.40	P.Each	Rs: 29,820.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	14.00	@ Rs: 596.40	P.Each	Rs: 8,350.00
7	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.	25.00	@ Rs: 140.26	P.Each	Rs: 3,506.00

Part 'B' TOTAL: Rs: 57,430.0

Part 'A' TOTAL: Rs: 242,482.0

TOTAL: Rs: 299,912.0


XEN

SCHEDULE "B"

Name of Work:- Provon of missing facilities in Existing Elemantary School
At: GBMS Wakro (C/Wall Toilet) Taluka Dokri

57

S.No	DESCRIPTION	QUANTITY	RATE	UNIT	QUANTITY	AMOUNT
1	Excavation in foundation of building bridges and other structure member with excavated lead upto one chain and lift upto 5" ft in ordingay soil (S.I.No: 1p1).					
				=	1290.00	CFT
		@Rs: 3176.25	%0 Cft			Rs: 4092.00
2	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P- 14).					
				=	321.00	Cft
		@Rs: 8694.95	% Cft			Rs: 27911.00
3	Pacca brick work in foundation and plinth in cement sand mortor ration 1:6 (S.I No 4 (C) P- 20.)					
				=	1178.00	Sft
		@Rs: 11948.36	% S.ft			Rs: 139796.00
4	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I No. 6 (a) P/16)					
				=	276.00	Pcft
		@Rs: 337.00	P.CrT			Rs: 93012.00
5	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars, (S.I.No 8 (b) P/16)					
				=	12.321	Pcwt
		@Rs: 5001.70	P.CWT			Rs: 61626.00
6	Supplying filling Sand under floor plugging into walls, (S.I.No 29 P/ 25).					
				=	1964.00	Cft
		@Rs: 1141.25	%Sft			Rs: 22414.00
7	Pacca brick work in Ground floor i/c stricking of joints cement sand mortor Ratio 1:6 (S.I No 5 (C) P/20)					
				=	278.00	CFT
		@Rs: 12674.36	%CFT			Rs: 35235.00
8	Pacca brick work in other than building i/c stricking of joints cement sand mortor Ratio 1:6 (S.I No 7 (E) P/					
				=	792.00	Cft
		@Rs: 12765.65	%Cft			Rs: 101103.95
9	P/F G.I frame chokats Door of size 7" x2" or 4" x 3" for Door using 20 gauge G.I sheet i/c solded higues and fixing at site with necessary hold fosts filling with cement sand repairing i/c all carriage tools and planst used in making and fixing. (S.I.No 28 P/98)					
				=	32.00	Sft
		@ Rs: 228.90	P.Rft			Rs: 7325.00
10	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4thicks.					
				=	35.00	SFT
		@Rs: 902.93	P.SFT			Rs: 31603.00
11	S/F in position iron steel grill of 3/4" X flate iron of approved design i/c painting three coats etc complete w not to beless than 3.7 lbs sq: ft: of finished grill.					
				=	5.00	
		@Rs: 194.16	P.SFT			Rs: 971.00
12	Making and fixing steel grated doors with 1/16" thick sheeting including angle iron frame 2"x2"x3/4" and sb bars 4" centre to cement .					
				=	48.00	SFT
		@Rs: 726.72	P.Sft			Rs: 34883.00
13	Cement plaster 1:6 upto 20' ft: height 1/2" thick. (S.I No.13(b) P/57)					
				=	2232.00	Sft
		@Rs: 2206.60	% Sft			Rs: 50355.00


XEN

S.No	DESCRIPTION	QUANTITY	RATE	UNIT	QUANTITY	AMOUNT
------	-------------	----------	------	------	----------	--------

14	Cement plaster 1;4 upto 20' ft; height 3/8" thick. (S.I No.13(b) P/57)	=			2282.000	SFT
	@Rs; 2197.52	% Sft			Rs;	50147.00
15	Cement pointing and stricking of joints on walls ratid. 1: 2 (S.I No.11(a) P/51)	=			2282.00	CFT
	@Rs: 1287.44	%Cft			Rs:	15861.00
16	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ration 3" thick. (S.I No:16 (C) P/41)	=			82.00	Cft
	@Rs: 4411.82	%Cft			Rs:	3618.00
(b)	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ration 2" thick. (S.I No:16 (C) P/41)	=			121.00	CFT
	@Rs: 3275.50	%Cft			Rs:	3963.00
17	White wash two coats.	=			112.00	Cft
	@Rs: 829.95	%Cft			Rs:	930.00
18	Primary coat of chalk under distemping (S.I No: 23 P 59)	=			2198.000	CFT
	@Rs: 442.75	%Cft			Rs:	9731.65
19	Distemping three coats (S.I No: 24(B) P 53)	=			2198.000	Cft
	@Rs: 1079.65	%Cft			Rs:	23730.71
20	Preparing the surface and painting with weather coat i/c rubbing the surface coat i/c rubbing the surface with brick /sen paper filling the voids with chalk plaster of paris and then painting with weather coat of approve make old surface. (S.I.No 39 (a) P/62).	=			1231.00	Cft
	@Rs: 1948.10	% Sft			Rs:	23981.11
21	Painting doors & window any type, (S.I.No 05 P/ 76)	=			70.00	Cft
	@Rs: 2116.41	%Cft			Rs:	1481.00
22	Preparing surface painting guards bars gates iron grating railing i/c standards brass etc similar open work. (S.I.No 4 II d P/76)	=			96.00	Cft
	@Rs: 1270.83	%Cft			Rs:	1220.00
					Total Rs:	744990.41


XEN

S.No.	DESCRIPTION	QUANTITY	RATE	UNIT	QUANTITY	AMOUNT
-------	-------------	----------	------	------	----------	--------

Part B

1 P/F Squating type white glass W.C pan of i/c coat of finishing cistring with internal fitting and flush pipe between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.

2.0 @ Rs: 4802.66 P.No: Rs: 9,605

2 Providing G.I pipe specials and clamps etc i/c fixing cutting fitting complete two coats of after cleaning the pipe etc with white zink paint with pigment to machh the colour of lthe building and testing pressure head of 200' and handling.

A 1/2" dia

30.00 @ Rs: 73.21 PRft Rs: 2,196

B 3/4" dia

60.00 @ Rs: 95.79 PRft Rs: 5,747

3 P/F C:P.Bross bib cock 1/2 " Dia.

2.00 @ Rs: 337.92 P.No Rs: 676

4 P/F approved quality AC Motor pumping set(Javed Engineering) Made etc.

1.0 @ Rs: 5115 P.No: Rs: 5,115

5 S/F Fibre glass tank of approved quality and design and wall thickness as specified i/c the cost of nuts and bolts and fixing in plate form of cement concrete 1:2:6 and making connection for inlet-outlet and over flow pipe etc complete. (250 Gallons).

250.0 @Rs: 87.95 P.Gallans Rs: 21,988

6 Hand pump all accessoried i/c fitting and fixing with local made coir strainer with wooden shoe i/c the complete.

Filter.

10.0 @ Rs: 76.05 P.Rft Rs: 761

G.I pipe

70.0 @Rs: 38.95 P.Rft Rs: 2,727

Machine

1 No. @Rs: 1441.65 P.No: Rs: 1,442

Rs: 50,257


XEN

SCHEDULE-B

Name of work: Provision of Missing Facilities in Existing Elementary Schools At: GBPS Fateh Muhammad Awan Taluka Dokri (C.Wall+ Toilet)

58

S.No	Discription	Quantity	@Rs:	Rate	Unit	Rs:	Amount.
1	Dismenlin Pacca brick work in cement mortor	507.00	@Rs: 1285.63	%CFT	Rs:	6,518	(Rs: Twolve thousand Eighty Five & P.S Sixty Three only)
2	Dismenlin C.C plain 1:2:4. (S.I.No 19 (c) P/11).	231.00	@Rs: 3327.50	P.SFT	Rs:	7,687	(Rs: Three thousand Three Hundred Twenty Seven & P.S Fifi)
3	Excavation in foundation of building bridges and other structure member with excavated lead upto one chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).	1,860.00	@Rs: 3176.25	%OCF	Rs:	5,908	(Three Thousand One Hund:Seventy Six & P.S Twenty Five
4	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P/16).	384.00	@Rs: 8694.95	%CFT	Rs:	33,389	(Eight Thousand Six Hund:Ninty Four & P S Ninty five only)
5	Pacca brick work in foundation and plinth in cement sand mortor ration 1:6 (S.I No 4 (C) 23.	1,444.65	@Rs: 11948.36	%SFT	Rs:	172,612	(Eleven Thousand Nine Hund: Forty Eight & P.S Thirty Si
6	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I No. 6 (a) P/18)	261.84	@Rs: 337.00	P.CFT	Rs:	88,240	(Three Hundred Thirty Seven only)
7	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/20)	11.689	@Rs: 5001.70	P.CWt	Rs:	58,465	(Five Thousand One &P.S Seventy).
8	Pacca brick work in other than building i/c striking of joints cement sand mortor Ratio 1:6 (S.I No 5 (C) F	842.44	@Rs: 12346.65	%CFT	Rs:	104,013	(Tolive Thousand Three Hundred Fourty Six & P.S Sixty Five
9	Pacca brick work in Ground floor i/c striking of joints cement sand mortor Ratio 1:6 (S.I No 5 (C) P/24)	54.00	@Rs: 12674.36	%CFT	Rs:	6,844	(Twlove thousand Six Hundred Seventy Four & Thirty Six or
10	S/F sand floor and plugging into walls (S.I.No 29 P/31).	4941.93	@Rs: 1141.25	%CFT	Rs:	56,400	(Rs:One Thousand One Hund: Forty On & P.S Twenty Five
11	P/F G.I frame of size 7x2 or 4-1/2"x3" for Window 20" guage G.I sheet i/c weldenings & fixing etc i/c all carriagew tools and plants used in making and fixing (S.I.No:29 P/98)	66.96	@Rs: 228.90	P.RFT	Rs:	15,327	(Rs: Two Hundrad Twenty Einght & P.S Ninty only)
12	P/F G.I frame of size 7x2 or 4-1/2"x3" for Door 20" guage G.I sheet i/c weldedhings & fixing etc i/c all carriagew tools and plants used in making and fixing (S.I.No:29 P/98)	179.76	@Rs: 240.50	P.RFT	Rs:	43,232	(Rs: Two hundred Fourty & P>S Fifty only)



XEN

S.No	Discription	Quantity	@RS:	Rate	Unit	Rs:	Amount.
13	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4thicks.(Only Shutters)	95.00	@Rs: 902.93	%CFT Rs:		85,778	(Nine Hundraed Two P.S Ninty Three only)
14	S/Fin position iron steel grill of 3/4" X 1/4"plate iron of approved design i/c painting three coats et cetera not to beless than 3.7 Lbs sq: ft: of finished grill.	22.50	@Rs: 194.16	P.SFT Rs:		4,369	(Rs: One hundred Ninty Four & P.S Sixteen only)
15	M/F Steel grated doors with 1/16" thick sheeting i/c agnle iron frame 2"x2"x1/3" square bars 4" centre to c	24.00	@Rs: 726.72	%SFT Rs:		17,441	(Rs: Seven Hundred Twenty Six & P.S Seventy Two only)
16	Cement plaster 1:6 upto 20' ft; height 1/2" thick. (S.I No.13 P/57)	4262.70	@Rs: 2206.60	%SFT Rs:		94,061	(Two hundred Three Hund: Fifty Six & P S Seventy Eight or
17	Cement plaster 1:4 upto 20' ft; height 3/8" thick. (S.I No: 11(a) P 57)	4262.70	@Rs: 2197.52	%SFT Rs:		93,674	(Two Twousand One Hund: Ninty Seven & P.S Fifty Two on
18	Cement pointing and stricking of joints on walls ratio. 1: 2 (S.I No.19 (a) P/53)	1548.00	@Rs: 1287.44	%CFT Rs:		19,930	(Twolve Thousand Eighty Seven & P.S Fourty Four only)
19	C.C plain i/c compacting and curring etc complete l/c screening and washaning of stone aggregate without shuttering Ratio. 1:2:4 (S.I.No 5 P/18)	11.00	@Rs: 14429.25	%CFT Rs:		1,587	(Rs: Fourteen thousand Four Hundred Twenty Nine & P.S Tw
20	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ration 3 to 4 k. (S	2005.25	@Rs: 4411.82	%SFT Rs:		88,468	(Rs: Four Thousand Four Hundred Eleven & P.S Eighty Two
(B)	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ration 2 " thick. (S	1261.22	@Rs: 3275.50	%SFT Rs:		41,311	(Rs: Four Thousand Four Hundred Eleven & P.S Eighty Two
21	White glazed tiles 1/4" thick dado jointed in white cement and laid over 1:2 cement sand mortar 3/4" thick (S.I.No. 37 P/50).	72.00	@Rs: 28253.61	%SFT Rs:		20,343	(Rs: Twenty Thousand Two Hund:Fifty Three & P.S Sixty One
22	Glazed Tile Dado 1/4"Thick laid in Pigment over 1:2	182.00	@Rs: 28299.30	%SFT Rs:		51,505	(Rs: Twenty Thousand Two Hund:Fifty Three & P.S Sixty One
22	P/L Hala patteren tiles glazed 8"*8 1/4" of floor of wall cacing in required pattern of cement over a base of 1:2 grey cement mortar 3/4" thick i/c washing and filling joints with slury of white cement and pigment in desired shape with finishing cleaning and cost of wax polish etc complete i/c cutting tile to proper profile. (S.I No: 62 P/53)	143.00	@Rs: 34520.31	%SFT Rs:		49,364	(Rs: Thity Four Thousand Five Hundred Twenty & P.S Thirty


XEN

S.No	Discription	Quantity	@RS:	Rate	Unit	Rs:	Amount.
23	White wash three coats (S.I.No 26 (c) 59).	967.84	@Rs: 829.95		P.SFT	Rs: 8,033	(Rs: Four Hundred Twenty Five & P.S Eighty Four only)
24	Primary coat of chalk under distemping (S.I No: 23 P 59)	6143.44	@Rs: 442.75		%SFT	Rs: 27,200	(Four Hundred Fourty Two & P.S Seventy Five only)
25	Distemping three coats, (S.I.No 24 (b) P/59)	6143.44	@Rs: 1079.65		%SFT	Rs: 66,328	(Rs: One Thousand Seventy Nine & P.S Sixty Five only)
26	Preparing the surface and painting with weather coat i/c rubbing the surface coat i/c rubbing the surface w brick /sen paper filling the voids with chalk plaster of paris and then painting with weather coat of approve make old surface.	2637.32	@Rs: 1948.10		%SFT	Rs: 51,378	(One Thousand Nine Hundred Fourty Eight & P.S Ten only)
27	Painting doors & Window any type.	374.00	@Rs: 2116.41		%CFT	Rs: 7,915	(Rs: One Two Thousand one Hund: Sixteen & P.S Fourty O)
28	Preparing surface painting guards bars gates iron grating railing i/c standards brass etc similar open work (S.I.No 4 d P/76 ii)	96.00	@Rs: 1270.83		%CFT	Rs: 1,220	(Rs: Five Hundred Eighty Five & Fifty Four only)

Grand Total:- Rs: 1,328,538


XEN

Part B

- 1 P/F Squating type white glass W.C pan of i/c coat of finishing cistring with internal fitting & Flush Pipe between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thur
2.0 @ Rs: 4846.60 P.No: **Rs:** 9694.00
 - 2 P/F & 22"x16" Lavatory basin in white glazed earthen ware complete with & i/c the cost of W.I conntilever brackets 6 inch built into walls painted white in two cost after a primary cost of red land plinth a pair of 1/4" dia chrome plate pillar trape 1-1/2" dia P3
1.0 @ Rs: 4694.80 P.No: **Rs:** 4695.00
 - 3 P/F 6'x2" or 6"x3" C.I floor tape.
3.0 @ Rs: 2042.43 P.No: **Rs:** 6073.00
 - 4 P/F in position nyloon connection complete with 1/2" dia brass stop cock with pair brass nuts lining joints to nyloon coonections
2.0 @ Rs: 77.85 P.No: **Rs:** 894.00
 - 5 P/F 4" dia C.I soil and vent pipe i/c cutting fitting and extra painting to match the colour of t
12.0 @Rs: 333.21 P.RFT **Rs:** 3999.00
 - 6 P/F 4"x4" dia C.I branch of the required degree with access doors rubber washer 3/8" thick and bolts and unts and extra painting to match the colour of the building.
2.0 @ Rs: 270.60 P/No **Rs:** 541.20
 - 7 Providing G.I pipe specials and clamps etc i/c fixing cutting fitting complete two coats of after cleaning the pipe etc with white zink paint with pigment to machth the colour of lthe building and testing pressure head of 200' and handling.
- (A) 1/2" dia
25.00 @ Rs: 73.21 PRft **Rs:** 1830.00
- (B) 3/4" dia
50.00 @ Rs: 95.79 PRft **Rs:** 4790.00
- 8 Providing and fixing 4" dia C.I terminal guard i/c extra painting to match the colour of the colour of the building.
2.0 @ Rs: 389.70 PRft **Rs:** 779.00
 - 9 Providing and fixing full way gun metal vallues with whelds threabed of flanged ends with rubber washing.(ii)3/4" (Light pattern)
1.0 @ Rs: 197.12 P.No **Rs:** 197.00
 - 10 P/F C:P.Bross bib cock 1/2 " Dia.
2.00 @ Rs: 337.92 P.No **Rs:** 676.00
 - 11 Providing RCC pipe with colors class"B" & dying trenches to required depth & fixing in position & Cement Morter 1:1 & test staff (a) 4"Dia Refilling with excavted staff.
4"Dia
24.00 @ Rs: 146.57 Each **Rs:** 3518.00
6"Dia
12.00 @ Rs: 199.25 Each **Rs:** 2391.00

- 12 S/F Concealed stop cock of superior quality with C.P head 1/2"Dia
2.00 @ Rs: 478.28 P.No Rs: 957.00
- 13 S/F Long bib-cock of superior quality with C.P head 1/2" Dia
1.00 @ Rs: 1109.46 P.No Rs: 1109.00
- 14 P/F approved quality AC Motor pumping set(Javed Engineering) Made etc.
1 No. @ Rs: 5115 P.No: Rs: 5115.00
- 15 S/F Fibre glass tank of approved quality and design and wall thickness as specified
i/c the cost of nuts and bolts and fixing in plate form of cement concrete 1:2:6 and
making connection for inlet-outlet and over flow pipe etc complete.(250 Gallons).
1.0 @Rs: 21989.61 P.Gallon: Rs: 13193.00
- 16 Hand pump all accessoried i/c fitting and fixing with local made coir strainer with wooden
shoe i/c the complete.

A **Filter.**

10.0 @ Rs: 76.05 P.Rft Rs: 761.00

B **G.I pipe**

40.0 @Rs: 38.95 P.Rft Rs: 3506.00

C **Machine**

1 No. @Rs: 1441.65 P.No: Rs: 1442.00

TOTAL Rs: 64131.00


XEN

SCHEDULE "B"

Name of Work:- Provision of missing facilities in Existing Elementary School
At: GBPS Nau Goth (C/Wall Toilet) Taluka Dokri

59

S.No	DESCRIPTION	QUANTITY	RATE	UNIT	QUANTITY	AMOUNT
1	Excavation in foundation of building bridges and other structure member with excavated lead up to chain and lift upto 5" ft in ordinary soil (S.I.No: 1p1).	=			1290.00	CFT
	@Rs: 3176.25	%0 Cft			Rs: 4092.00	
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge Ratio 1.5:10 (S.I.No 4 (C) P- 14).	=			321.00	Cft
	@Rs: 8694.95	% Cft			Rs: 27911.00	
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6 (S.I No 4 (C) P- 20.)	=			1170.00	Sft
	@Rs: 11948.36	% S.ft			Rs: 139796.00	
4	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I No. 6 (a) P/16)	=			276.00	Pcft
	@Rs: 337.00	P.CFT			Rs: 93012.00	
5	Fabrication of For steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars, (S.I.No 8 (b) P/16)	=			12.321	Pcwt
	@Rs: 5001.70	P.CWT			Rs: 61626.00	
6	Supplying filling Sand under floor plugging into walls, (S.I.No 29 P/ 25).	=			1964.00	Cft
	@Rs: 1141.25	%Sft			Rs: 22414.00	
7	Pacca brick work in Ground floor i/c striking of joints cement sand mortar Ratio 1:6 (S.I No 5 (C) P/16)	=			278.00	CFT
	@Rs: 12674.36	%CFT			Rs: 35235.00	
8	Pacca brick work in other than building i/c striking of joints cement sand mortar Ratio 1:6 (S.I No 5 (C) P/16)	=			792.00	Cft
	@Rs: 12765.65	%Cft			Rs: 101103.95	
9	P/F G.I frame chokats Door of size 7" x2" or 4" x 3" for Door using 20 gauge G.I sheet i/c soldered hinged and fixing at site with necessary hold fasts filling with cement sand repairing i/c all carriage tools used in making and fixing. (S.I.No 28 P/98)	=			32.00	Sft
	@ Rs: 228.90	P.Rft			Rs: 7325.00	
10	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4thicks.	=			35.00	SFT
	@Rs: 902.93	P.SFT			Rs: 31603.00	
11	S/F in position iron steel grill of 3/4" X flate iron of approved design i/c painting three coats etc not to beless than 3.7 lbs sq: ft: of finished grill.	=			5.00	
	@Rs: 194.16	P.SFT			Rs: 971.00	
12	Making and fixing steel grated doors with 1/16" thick sheeting including angle iron frame 2"x2"x3/8" bars 4" centre to cement.	=			48.00	SFT
	@Rs: 726.72	P.Sft			Rs: 34883.00	
13	Cement plaster 1:6 upto 20' ft; height 1/2" thick. (S.I No.13(b) P/57)	=			2282.00	Sft
	@Rs: 2206.60	% Sft			Rs: 50355.00	
14	Cement plaster 1:4 upto 20' ft; height 3/8" thick (S.I No.13(b) P/57)	=			2282.000	SFT
	@Rs: 2197.52	% Sft			Rs: 50147.00	

No	DESCRIPTION	QUANTITY	RATE		
15	Cement pointing and striking of joints on walls ratio 1:2 (S.I No.11(a) P/51)			=	2282.00 CFT
		@Rs: 1287.44	%Cft		Rs: 15861.00
16	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into panels Ratio 3" thick. (S.I No:16 (C) P/41)			=	82.00 Cft
		@Rs: 4411.82	%Cft		Rs: 3618.00
(b)	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into panels Ratio 2" thick. (S.I No:16 (C) P/41)			=	121.00 CFT
		@Rs: 3275.50	%Cft		Rs: 3963.00
17	White wash two coats.			=	112.00 Cft
		@Rs: 829.95	%Cft		Rs: 930.00
18	Primary coat of chalk under distemping (S.I No: 23 P 59)			=	2198.000 CFT
		@Rs: 442.75	%Cft		Rs: 9731.65
19	Distemping three coats (S.I No: 24(B) P 53)			=	2198.000 Cft
		@Rs: 1079.65	%Cft		Rs: 23730.71
20	Preparing the surface and painting with weather coat i/c rubbing the surface coat i/c rubbing the surface brick /sen paper filling the voids with chalk plaster of paris and then painting with weather coat of app make old surface. (S.I.No 39 (a) P/62).			=	1231.00 Cft
		@Rs: 1948.10	% Sft		Rs: 23981.11
21	Painting doors & window any type, (S.I.No 05 P/ 76)			=	70.00 Cft
		@Rs: 2116.41	%Cft		Rs: 1481.00
22	Preparing surface painting guards bars gates iron grating railing i/c standards brass etc similar open v. (S.I.No 4 H d P/76)			=	96.00 Cft
		@Rs: 1270.83	%Cft		Rs: 1220.00
Total Rs:					744990.41

[Handwritten Signature]

S.No	DESCRIPTION	QUANTITY	RATE	UNIT	QUANTITY	AMOUNT
------	-------------	----------	------	------	----------	--------

Part B

1	P/F Squating type white glass W.C pan of i/c coat of finishing cistern with internal fitting and flush between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.	2.0	@ Rs: 4802.65	P.No:	Rs:	9,605
2	Providing G.I pipe specials and clamps etc i/c fixing cutting fitting complete two coats of after cleaning the pipe etc with white zink paint with pigment to match the colour of lthe building and testing pressure head of 200' and handling.					
A	<u>1/2" dia</u>	30.00	@ Rs: 73.21	PRft	Rs:	2,196
B	<u>3/4" dia</u>	60.00	@ Rs: 95.79	PRft	Rs:	5,747
3	P/F C:P.Bross bib cock 1/2 " Dia.	2.00	@ Rs: 337.92	P.No	Rs:	676
4	P/F approved quality AC Motor pumping set(Javed Engineering) Made etc.	1.0	@ Rs: 5115	P.No:	Rs:	5,115
5	S/F Fibre glass tank of approved quality and design and wall thickness as specified i/c the cost of nuts and bolts and fixing in plate form of cement concrete 1:2:6 and making connection for inlet-outlet and over flow pipe etc complete.(250 Gallons).	250.0	@Rs: 87.95	P.Gallans	Rs:	21,988
6	Hand pump all accessoried i/c fitting and fixing with local made coir strainer with wooden shoe i/c the complete.					
	<u>Filter.</u>	10.0	@ Rs: 76.05	P.Rft	Rs:	761
	<u>G.I pipe</u>	70.0	@Rs: 38.95	P.Rft	Rs:	2,727
	<u>Machine</u>	1 No.	@Rs: 1441.65	P.No:	Rs:	1,442
					Rs:	50,257

D

SCHEDULE "B"

Name of Work:-

Provision of Missing Facilities in Elementary Schools in Taluka Bakrani
At: GBPS Usman Samtio / Moriyal Brohi Taluka Bakrani.

S.No	Description	Qty:	Rate		Amount
1	Dismantling pacca brick work in cement mortar.			=	119
	@ Rs: 1285.63		%CFT	Rs:	1,530
2	Removing cement or lime plaster. (S.I.No 53 P/14)			=	507
	@ Rs: 121.00		%SFT	Rs:	613
3	Excavation in foundation of building bridges and other structure member with excavated lead upto one chain and lift upto 5" ft in ordingay soil (S.I.No. 18p4).			=	596
	@ Rs: 3176.25		%0 CFT	Rs:	1,893
4	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1.5:10 (S.I.No 4 (C) P/16).			=	329
	@ Rs: 8694.95		% CFT	Rs:	28,606
5	Pacca brick work in foundation and plinth in cement sand mortar raticn 1:6 (S.I No 4 (C) 23.			=	941
	@ Rs: 11948.36		% CFT	Rs:	112,434
6	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I No. 6 (a) P/18)			=	172
	@ Rs: 337.00		P.CFT	Rs:	57,964
7	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars, (S.I No 07 (b) P/20)			=	7,679
	@ Rs: 5001.70		P.CWT	Rs:	38,406
8	Pacca brick work in other than building i/c stricking of joints cement sand mortar Ratio 1:6 (S.I No 5 (C			=	750
	@ Rs: 12346.65		%SFT	Rs:	92,600
9	Pacca brick work in Ground floor i/c stricking of joints cement sand mortar Ratio 1:6 (S.I No 5 (C) P/24			=	75
	@ Rs: 12674.36		%SFT	Rs:	9,506
10	S/F sand floor and plugging into walls (S.I.No 29 P/31)			=	2,363
	@ Rs: 1141.25		%SFT	Rs:	26,968
11	Cement plaster 1:6 upto 20' ft; height 1/2" thick. (S.I No. 13 P/57)			=	2,064
	@ Rs: 2206.60		%SFT	Rs:	45,544
12	Cement plaster 1:4 upto 20' ft; height 3/8" thick. (S.I No: 11(a) P 57)			=	2,064
	@ Rs: 2197.52		%SFT	Rs:	45,357

S.No	Description	Qty:	Rate		Amount
13	Cement pointing and striking of joints on walls ratio 1: 2 (S.I No.19 (a) P/53)			=	1,108
		@ Rs: 1287.44	%SFT		Rs: 14,265
14	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4, (S.I.No 5 P/18)			=	11
		@ Rs: 14429.25	%SFT		Rs: 1,587
15	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into panels Ratio 3" thick. (S.I No:16 (C) P/46)			=	805
		@ Rs: 4411.82	%SFT		Rs: 35,515
(B)	Ratio 2" thick,			=	111
		@ Rs: 3275.50	%SFT		Rs: 3,636
16	P/L Hala pattern tiles glazed 4" x 4 1/4" of floor of wall facing in required pattern of cement over a base of 1:2 grey cement mortar 3/4" thick i/c washing and filling joints with slurry of white cement and pigment desired shape with finishing cleaning and cost of wax polish etc complete i/c cutting tile to proper profile (S.I No: 62 P/53)			=	127
		@ Rs: 34520.31	%CFT		Rs: 43,841
17	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4" thick. (Only Shutters)			=	35
		@ Rs: 1273.76	P.CFT		Rs: 44,582
18	Split tiles 1/4" thick matt glazed or double glazed jointed in white and laid 1:2 grey cement sand mortar i/c finishing complete (Flooring and Facing) (S.I.No 69 P/55).			=	50
		@ Rs: 21021.11	%CFT		Rs: 10,511
19	White wash three coats.			=	50
		@ Rs: 829.95	%CFT		Rs: 415
20	Primary coat of chalk under distemping (S.I No: 23 P 59)			=	360
		@ Rs: 442.75	%CFT		Rs: 1,594
21	Preparing the surface and painting with weather coat i/c rubbing the surface coat i/c rubbing the surface brick /sen paper filling the voids with chalk plaster of paris and then painting with weather coat of approx make New surface. (S.I.No 39 (a) P/62).			=	4,480
		@ Rs: 1948.10	%CFT		Rs: 87,275
22	Distemping three coats (S.I No: 24(B) P 59)			=	360
		@ Rs: 1043.90	% Sft		Rs: 3,758
23	Making and fixing steel grated doors with 1/16" thick sheeting including angle iron frame 2"x2" and bars 4" centre to cement.			=	360

S.No	Description	Qty:	Rate		Amount
24	Painting doors & window any type, (S.I No 05 P/ 76)			= 70	
		@Rs: 2116.41	%Cft	Rs:	1,481
25	S/F in position iron steel grill of 3/4" X flate iron of approved design i/c painting three coats etc complete with not to beless than 3.7 Lbs sq: ft: of finished grill.			= 70	
		@Rs: 194.16	%Cft	Rs:	15,165
TOTAL: Rs:					768,647.91

Part B

1	P/F Squating type white glass W.C pan of i/c coat of finishing cistring with internal fitting and flush pipe between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.	2.0	@ Rs: 4846.60	P.No: 9694.00	
2	P/F & 22"x16" Lavatory basin in white glazed earthen ware complete with & i/c the cost of W.I conntilever brackets 6 inch built into walls painted white in two cost after a primary cost of red land plinth a pair of 1/4" dia chrome plate pillar trape 1-1/2" dia P3	1.0	@ Rs: 4694.80	P.No: 4695.00	
3	P/F 6"x2" or 6"x3" C.I floor tape.	3.0	@ Rs: 2012.43	P.No: 6073.00	
4	P/F in position nyloon connection complete with 1/2" dia brass stop cock with pair brass nuts lining joints to nyloon coonections	2.0	@ Rs: 77.85	P.No: 894.00	
5	P/F 4" dia C.I soil and vent pipe i/c cutting fitting and extra painting to match the colour of the building	12.0	@Rs: 333.21	P.RFT 3999.00	
6	P/F 4"x4" dia C.I branch of the required degree with access doors rubber washer 3/8" thick and bolts and unts and extra painting to match the colour of the building	2.0	@ Rs: 270.60	P/No 541.20	
7	Providing G.I pipe specials and clamps etc i/c fixing cutting fitting complete two coats of after cleaning the pipe etc with white zink paint with pigment to mach the colour of lthe building and testing pressure head of 200' and handling.				
(A)	<u>1/2" dia</u>	25.00	@ Rs: 73.21	PRft 1830.00	
(B)	<u>3/4" dia</u>	50.00	@ Rs: 95.79	PRft 4790.00	


XEN

9	Providing and fixing full way gun metal valves with wheels threaded of flanged ends with rubber washing. (ii) 3/4" (Light pattern)	1.0	@ Rs: 197.12	P.No	197.00
10	P/F C.P. Brass bib cock 1/2" Dia.	2.00	@ Rs: 337.92	P.No	676.00
11	Providing RCC pipe with colors class "B" & drying trenches to required depth & fixing in position & Cement Mortar 1:1 & test staff (a) 4" Dia Refilling with excavated staff.				
	4" Dia	24.00	@ Rs: 146.57	Each	3518.00
	6" Dia	12.00	@ Rs: 199.25	Each	2391.00
12	S/F Concealed stop cock of superior quality with C P head 1/2" Dia	2.00	@ Rs: 478.28	P.No	957.00
13	S/F Long bib-cock of superior quality with C.P head 1/2" Dia	1.00	@ Rs: 1109.46	P.No	1109.00
14	P/F approved quality AC Motor pumping set (Javed Engineering) Made etc.	1 No.	@ Rs: 5115	P.No:	5115.00
15	S/F Fibre glass tank of approved quality and design and wall thickness as specified i/c the cost of nuts and bolts and fixing in plate form of cement concrete 1:2:6 and making connection for inlet-outlet and over flow pipe etc complete (250 Gallons)	1.0	@Rs: 21989.61	P.Gallans	13193.00
16	Hand pump all accessoried i/c fitting and fixing with local made coir strainer with wooden shoe i/c the complete.				
A	Filter.	10.0	@ Rs: 76.05	P.Rft	761.00
B	G.I pipe	40.0	@Rs: 38.95	P.Rft	3506.00
C	Machine	1 No.	@Rs: 1441.65	P.No:	1442.00

TOTAL #####


XEN

SCHEDULE "B"

Name of Work:-

Provision of Missing Facilities in Elementary Schools in Taluka Bakrani
At: GBPS Piyaro Buriro Taluka Bakrani.

S.No	Description	Qty.	Rate		Amount
1	Removing cement or lime plaster. (S.I.No 53 P/14)			=	507
	@ Rs: 121.00		%SFT		Rs: 613.47
2	Excavation in foundation of building bridges and other structure member with excavated lead upto one chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).			=	1,396
	@ Rs: 3176.25		% CFT		Rs: 4,434.0
3	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ratio: 1:3:10 (S.I.No 4 (C) P/16).			=	580
	@ Rs: 8694.95		% CFT		Rs: 50,431
4	Pacca brick work in foundation and plinth in cement sand mortar ration 1:6 (S.I.No 4 (C) 23.			=	1,166
	@ Rs: 11948.36		% CFT		Rs: 139,313
5	RCC work in roof slab beam columns rafts lintel and other structure member laid in site or precast laid in position complete in all respect ratio 1:2:4 (S.I.No. 6 (a) P/18)			=	172
	@ Rs: 337.00		P.CFT		Rs: 57,964
6	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/20)			=	7.679
	@ Rs: 5001.70		P.CWT		Rs: 38,406
7	Pacca brick work in other than building i/c striking of joints cement sand mortar Ratio 1:6 (S.I.No 5 (C)			=	750
	@ Rs: 12346.65		%SFT		Rs: 92,600
8	Pacca brick work in Ground floor i/c striking of joints cement sand mortar Ratio 1:6 (S.I.No 5 (C) P/24)			=	75
	@ Rs: 12674.36		%SFT		Rs: 9,506
9	S/F sand floor and plugging into walls (S.I.No 29 P/31)			=	2,363
	@ Rs: 1141.25		%SFT		Rs: 26,968
10	Cement plaster 1:6 upto 20' ft; height 1/2" thick (S.I.No.13 P/57)			=	2,054
	@ Rs: 2206.60		%SFT		Rs: 45,544
11	Cement plaster 1:4 upto 20' ft; height 3/8" thick (S.I.No: 11(a) P/57)			=	2,064
	@ Rs: 2197.52		%SFT		Rs: 45,357

S.No	Description	Qnty	Rate		Amount
12	Cement pointing and striking of joints on walls ratio 1:2 (S.I No 19 (a) P/53)			=	1,108
	@ Rs: 1287.44	%SFT		Rs:	14,265
13	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4, (S.I.No 5 P/18)			=	11
	@ Rs: 14429.25	%SFT		Rs:	1,587
14	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into panels Ratio 3" thick. (S.I No:16 (C) P/46)			=	805
	@ Rs: 4411.82	%SFT		Rs:	35,515
(B)	Ratio 2" thick,			=	111
	@ Rs: 3275.50	%SFT		Rs:	3,636
15	P/L Hala pattern tiles glazed 4" x 4 1/4" of floor of wall facing in required pattern of cement over a base of 1:2 grey cement mortar 3/4" thick i/c washing and filling joints with slurry of white cement and pigment desired shape with finishing cleaning and cost of wax polish etc complete i/c cutting tile to proper profile (S.I No: 62 P/53)			=	127
	@ Rs: 34520.31	%CFT		Rs:	43,841
16	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4" thick. (Only Shutters)			=	18
	@ Rs: 1273.76	P.CFT		Rs:	22,928
17	Split tiles 1/4" thick matt glazed or double glazed jointed in white and laid 1:2 grey cement sand mortar i/c finishing complete (Flooring and Facing) (S.I.No 69 P/55).			=	50
	@ Rs: 21021.11	%CFT		Rs:	10,511
18	White wash three coats.			=	50
	@ Rs: 829.95	%CFT		Rs:	415
19	Primary coat of chalk under distemping (S.I No: 23 P 59)			=	360
	@ Rs: 442.75	%CFT		Rs:	1,594
20	Preparing the surface and painting with weather coat i/c rubbing the surface coat i/c rubbing the surface brick /sen paper filling the voids with chalk plaster of paris and then painting with weather coat of approx make New surface. (S.I.No 39 (a) P/62).			=	3,640
	@ Rs: 1948.10	%CFT		Rs:	70,911


XEN

S.No	Description	Qty:	Rate	Amount
21	Distemping three coats (S.I No 24(B) P 59)			
			=	360
		@ Rs. 1043.90	% Sft	Rs. 3,758
22	Making and fixing steel grated doors with 1/16" thick sheeting including angle iron frame 2"x2"x3/4" and bars 4" centre to cement .			
			=	40
		@ Rs. 726.72	P.Sft	Rs. 29,069
23	Painting doors & window any type, (S.I.No 05 P/ 76)			
			=	70
		@Rs. 2116.41	%Cft	Rs. 1,481
TOTAL: Rs:				750,649.94

XEN

S.No	Description	Qty:	Rate	Amount
Part B				
1	P/F Squating type white glass W.C pan of i/c coat of finishing cistern with internal fitting and flush pipe between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble	2.0	@ Rs. 4846.60	P.No 9694.00
2	P/F & 22"x16" Lavatory basin in white glazed earthen ware complete with & i/c the cost of W.I conntilever brackets 6 inch built into walls painted white in two cost after a primary cost of red land plinth a pair of 1/4" dia chrome plate pillar trape 1-1/2" dia P3	1.0	@ Rs. 4694.80	P.No 4695.00
3	P/F 6"x2" or 6"x3" C.I floor tape.	3.0	@ Rs. 2042.43	P.No 6073.00
4	P/F in position nyloon connection complete with 1/2" dia brass stop cock with pair brass nuts lining joints to nyloon connections	2.0	@ Rs. 77.85	P.No. 894.00
5	P/F 4" dia C.I soil and vent pipe i/c cutting fitting and extra painting to match the colour of the building	12.0	@Rs: 333.21	P.Rft 3999.00
6	P/F 4"x4" dia C.I branch of the required degree with access doors rubber washer 3/8" thick and bolts and unts and extra painting to match the colour of the building.	2.0	@ Rs: 270.60	P/No 541.20
7	Providing G.I pipe specials and clamps etc i/c fixing cutting fitting complete two coats of after cleaning the pipe etc with white zink paint with pigment to mach the colour of lthe building and testing pressure head of 200' and handling			
(A)	<u>1/2" dia</u>	25.00	@ Rs: 73.21	PRft 1830.00
(B)	<u>3/4" dia</u>	50.00	@ Rs: 95.79	PRft 4790.00
8	Providing and fixing 4" dia C.I terminal guard i/c extra painting to match the colour of the colour of the building.	2.0	@ Rs: 389.70	PRft 779.00
9	Providing and fixing full gun metal valves with wheilds threaded or flanged ends with rubber washing. (ii) 3/4" (Light pattern)	1.0	@ Rs: 197.12	P.No 197.00
10	P/F C.P. Brass bib cock 1/2 " Dia.	2.00	@ Rs: 337.92	P.No 676.00
11	Providing RCC pipe with colors class "B" & dying trenches to required depth & fixing in position & Cement Morter 1:1 & test staff (a) 4"Dia Refilling with excavted staff.			
	4"Dia	24.00	@ Rs. 146.57	Each 3518.00
	6"Dia	12.00	@ Rs: 199.25	Each 2391.00
12	S/F Conceled stop cock of superior quality with C.P head 1/2" Dia	2.00	@ Rs: 478.28	P.No 957.00

S.No	Description	Qty:	Rate	Amount
12	S/F Long bib-cock of superior quality with C.P head 1/2" Dia	1.00	@ Rs: 1109.40	P.No: 1109.00
13	P/F approved quality AC Motor pumping set(Javed Engineering) Made etc.	1 No.	@ Rs: 5115	P.No: 5115.00
14	S/F Fibre glass tank of approved quality and design and wall thickness as specified i/c the cost of nuts and bolts and fixing in plate form of cement concrete 1.2.6 and making connection for inlet-outlet and over flow pipe etc complete (250 Gallons).	1.0	@Rs: 21989.61	P Gallans 13193.00
15	Hand pump all accessoried i/c fitting and fixing with local made coir strainer with wooden shoe i/c the complete.			
A	<u>Filter.</u>	10.0	@ Rs: 76.05	P.Rft 761.00
B	<u>G.I pipe</u>	40.0	@Rs: 38.95	P.Rft 3596.00
C	<u>Machine</u>	1 No.	@Rs: 1441.65	P.No: 1442.00
TOTAL				64131.00



XEN

SCHEDULE "B"

62

Name of Work:-

Provision of Missing Facilities in Elementary Schools in Taluka Bakrani
At: GBPS Thulliah Taluka Bakrani.

S.No	Description	Qty:	Rate		Amount
1	Removing cement or lime plaster. (S.I.No 53 P/14)			=	507
		@ Rs: 121.00	%SFT	Rs:	613.47
2	Excavation in foundation of building bridges and other structure member with excavated lead upto one chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).			=	1,396
		@ Rs: 3176.25	%0 CFT	Rs:	4,434.0
4	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P/16)			=	580
		@ Rs: 8694.95	% CFT	Rs:	50,431
5	Pacca brick work in foundation and plinth in cement sand mortar raron 1:6 (S.I.No 4 (C) 23.			=	1,166
		@ Rs: 11948.36	% CFT	Rs:	139,318
6	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S I No. 6 (a) P/18)			=	172
		@ Rs: 337.00	P CFT	Rs:	57,964
7	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/20)			=	7,679
		@ Rs: 5001.70	P.CWT	Rs:	38,406
8	Pacca brick work in other than building i/c striking of joints cement sand mortar Ratio 1:6 (S.I.No 5 (C			=	750
		@ Rs: 12346.65	%SFT	Rs:	92,600
9	Pacca brick work in Ground floor i/c striking of joints cement sand mortar Ratio 1:6 (S.I.No 5 (C) P/24			=	75
		@ Rs: 12674.36	%SFT	Rs:	9,506
10	S/F sand floor and plugging into walls (S.I.No 29 P/31)			=	2,383
		@ Rs: 1141.25	%SFT	Rs:	26,968
9	Cement plaster 1:6 upto 20' ft; height 1/2" thick. (S.I.No 13 P/57)			=	2,064
		@ Rs: 2206.60	%SFT	Rs:	45,544
10	Cement plaster 1:4 upto 20' ft; height 3/8" thick. (S.I.No: 11(a) P 57)			=	2,064
		@ Rs: 2197.52	%SFT	Rs:	45,357

XEN

S No	Description	Qty:	Rate		Amount
11	Cement pointing and striking of joints on walls ratio 1:2 (S.I No.19 (a) P/53)			=	1,108
		@ Rs: 1287.44	%SFT		Rs: 14,265
12	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4, (S.I.No 5 P/18)			=	11
		@ Rs: 14429.25	%SFT		Rs: 1,587
13	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into panels Ratio 3" thick. (S.I No.16 (C) P/46)			=	805
		@ Rs: 4411.82	%SFT		Rs: 35,515
(B)	Ratio 2" thick,			=	111
		@ Rs: 3275.50	%SFT		Rs: 3,636
14	P/L Hala pattern tiles glazed 4" x 4 1/4" of floor of wall facing in required pattern of cement over a base of 1:2 grey cement mortar 3/4" thick i/c washing and filling joints with slurry of white cement and pigment desired shape with finishing cleaning and cost of wax polish etc complete i/c cutting tile to proper profile (S.I No: 62 P/53)			=	127
		@ Rs: 34520.31	%CFT		Rs: 43,841
15	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4" thick. (Only Shutters)			=	18
		@ Rs: 1273.76	P.CFT		Rs: 22,928
16	Split tiles 1/4" thick matt glazed or double glazed jointed in white and laid 1:2 grey cement sand mortar i/c finishing complete (Flooring and Facing) (S.I.No 69 P/55)			=	50
		@ Rs: 21021.11	%CFT		Rs: 10,511
17	White wash three coats.			=	50
		@ Rs: 829.95	%CFT		Rs: 415
18	Primary coat of chalk under distemping (S.I No. 23 P 59)			=	360
		@ Rs: 442.75	%CFT		Rs: 1,594
19	Preparing the surface and painting with weather coat i/c rubbing the surface coat i/c rubbing the surface brick /sen paper filling the voids with chalk plaster of paris and then painting with weather coat of approx make New surface. (S.I.No 39 (a) P/62).			=	3,640
		@ Rs: 1948.10	%CFT		Rs: 70,911
20	Distemping three coats (S.I No: 24(B) P 59)			=	360
		@ Rs: 1043.90	% Sft		Rs: 3,758

S No	Description	Qty:	Rate		Amount
22	Making and fixing steel grated doors with 1/16" thick sheeting including angle iron frame 2"x2"x3/4" and bars 4" centre to cement.			=	40
			@ Rs: 726.72	P Sft	Rs: 29,069
23	Painting doors & window any type, (S.I.No 05 P/ 76)			=	70
			@Rs: 2116.41	%Cft	Rs: 1,481
TOTAL: Rs:					750,649.94

Part B

1	P/F Squating type white glass W.C pan of i/c coat of finishing cisterning with internal fitting and flush pipe between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.	2.0	@ Rs: 4846.60	P.No:	9694.00
2	P/F & 22"x16" Lavatory basin in white glazed earthen ware complete with & i/c the cost of W I cantilever brackets 6 inch built into walls painted white in two cost after a primary cost of red land plinth a pair of 1/4" dia chrome plate pillar trape 1-1/2" dia P3	1.0	@ Rs: 4694.80	P.No:	4695.00
3	P/F 6"x2" or 6"x3" C.I floor tape	3.0	@ Rs: 2042.43	P.No:	6073.00
4	P/F in position nyloon connection complete with 1/2" dia brass stop cock with pair brass nuts lining joints to nyloon connections	2.0	@ Rs: 77.85	P.No:	894.00
5	P/F 4" dia C I soil and vent pipe i/c cutting fitting and extra painting to match the colour of the building	12.0	@Rs: 333.21	P.RFT	3999.00
6	P/F 4"x4" dia C.I branch of the required degree with access doors rubber washer 3/8" thick and bolts and unts and extra painting to match the colour of the building.	2.0	@ Rs: 270.60	P/No	541.20
7	Providing G I pipe specials and clamps etc i/c fixing cutting fitting complete two coats of after cleaning the pipe etc with white zink paint with pigment to mach the colour of lthe building and testing pressure head of 200' and handling				
(A)	1/2" dia	25.00	@ Rs: 73.21	PRft	1830.00
(B)	3/4" dia	50.00	@ Rs: 95.79	PRft	4790.00
8	Providing and fixing 4" dia C.I terminal guard i/c extra painting to match the colour of the colour of the building.	2.0	@ Rs: 389.70	PRft	779.00


XEN

S.No	Description	Qty:	Rate	Amount
------	-------------	------	------	--------

	Providing and fixing full way gun metal valves with wheels threaded of flanged ends with rubber washing. (ii) 3/4" (Light pattern)	1.0	@ Rs: 197.12	P.No 197.00
10)	P/F C.P. Brass bib cock 1/2" Dia	2.00	@ Rs: 337.92	P.No 676.00
11	Providing RCC pipe with colors class "B" & drying trenches to required depth & fixing in position & Cement Mortar 1:1 & test staff (a) 4" Dia Refilling with excavated staff.			
	4" Dia	24.00	@ Rs: 146.57	Each 3518.00
	6" Dia	12.00	@ Rs: 199.25	Each 2391.00
11	S/F Concealed stop cock of superior quality with C.P head 1/2" Dia	2.00	@ Rs: 478.28	P.No 957.00
12	S/F Long bib-cock of superior quality with C.P head 1/2" Dia	1.00	@ Rs: 1109.46	P.No 1109.00
13	P/F approved quality AC Motor pumping set (Javed Engineering) Made etc.	1 No	@ Rs: 5115	P.No: 5115.00
13	S/F Fibre glass tank of approved quality and design and wall thickness as specified i/c the cost of nuts and bolts and fixing in plate form of cement concrete 1:2:6 and making connection for inlet-outlet and over flow pipe etc complete. (250 Gallons)	1.0	@Rs: 21989.61	P.Gallans 13193.00
11	Hand pump all accessoried i/c fitting and fixing with local made coir strainer with wooden shoe i/c the complete.			
A	<u>Filter.</u>	10.0	@ Rs: 76.05	P.Rft 761.00
B	<u>G.I pipe</u>	40.0	@Rs: 38.95	P.Rft 3506.00
C	<u>Machine</u>	1 No	@Rs: 1441.65	P.No: 1442.00
TOTAL				64131.00


XEN

Schedule "B"

63

Name of Work:-

Provision of Missing Facilities in Elementary Schools in Taluka Bakrani
At: GBPS Bhawal Gadhi Taluka Bakrani.

S.No	Description	Qty:	Rate		Amount
1	Excavation in foundation of building bridges and other structure member with excavated lead upto one chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).			=	1,396
		@ Rs: 3176.25	%0 CFT	Rs:	4,434
2	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P/16).			=	580
		@ Rs: 8694.95	% CFT	Rs:	50,431
3	Pacca brick work in foundation and plinth in cement sand mortar ration 1:6 (S.I No 4 (C) 23.			=	1,166
		@ Rs: 11948.36	% CFT	Rs:	139,317
4	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I No. 6 (a) P/18)			=	172
		@ Rs: 337.00	P.CFT	Rs:	57,964
5	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars. (S.I.No 07 (b) P/20)			=	7.679
		@ Rs: 5001.70	P.CWT	Rs:	38,406
6	Pacca brick work in other than building i/c striking of joints cement sand mortar Ratio 1:6 (S.I No 5 (C)			=	750
		@ Rs: 12346.65	%SFT	Rs:	92,600
7	Pacca brick work in Ground floor i/c striking of joints cement sand mortar Ratio 1:6 (S.I No 5 (C) P/2			=	75
		@ Rs: 12674.36	%SFT	Rs:	9,506
8	S/F sand floor and plugging into wails (S.I.No 29 P/31)			=	2,363
		@ Rs: 1141.25	%SFT	Rs:	26,968
9	Cement plaster 1:6 upto 20' ft; height 1/2" thick (S.I No.13 P/57)			=	1,557
		@ Rs: 2206.60	%SFT	Rs:	34,357
10	Cement plaster 1:4 upto 20' ft; height 3/8" thick (S.I No: 11(a) P 57)			=	1,557
		@ Rs: 2197.52	%SFT	Rs:	34,215
11	Cement pointing and striking of joints on walls ratid 1: 2 (S.I No.19 (a) P/53)			=	1,108
		@ Rs: 1287.44	%SFT	Rs:	14,265
12	Cemnet concret plain i/c placing compacting finishing and curing complete i/c screeing and wash stone aggregate without shuttering Ratio 1:2:4. (S.I.No 5 P/18)			=	11
		@ Rs: 14429.25	%SFT	Rs:	1,587


XEN

S.No	Description	Qty:	Rate		Amount
13	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into panels Ration 3" thick. (S.I No:16 (C) P/46)			=	805
		@ Rs: 4411.82	%SFT	Rs:	35,515
(B)	Ratio 2" thick,			=	111
		@ Rs: 3275.50	%SFT	Rs:	3,636
14	P/L Hala patternen tiles glazed 4"*4 1/4" of floor of wall cacing in required pattern of cement over a base of 1:2 grey cement mortar 3/4" thick i/c washing and filling joints with slury of white cement and pigment desired shape with finishing cleaning and cost of wax polish etc complete i/c cutting tile to proper profile (S.I No: 62 P/53)			=	127
		@ Rs: 34520.31	%CFT	Rs:	43,841
15	First Class deodar wood wrought joinery in doors and windows etc. fixed in position i/c deodar panelled and glazed (b) 1-3/4thicks.(Only Shutters)			=	35
		@ Rs: 1273.76	P.CFT	Rs:	44,582
16	Split tiles 1/4" thick matt glazed or double glazed jointed in white and laid 1:2 grey cement sand mortar, i/c finishing complete (Flooring and Facing) (S.I.No 69 P/55).			=	50
		@ Rs: 21021.11	%CFT	Rs:	10,511
17	White wash three coats.			=	50
		@ Rs: 829.95	%CFT	Rs:	415
18	Primary coat of chalk under distemping (S.I No: 23 P 59)			=	360
		@ Rs: 442.75	%CFT	Rs:	1,594
19	Preparing the surface and painting with weather coat i/c rubbing the surface coat i/c rubbing the surface brick /sen paper filling the voids with chalk plaster of paris and then painting with weather coat of apprc make New surface. (S.I.No 39 (a) P/62).			=	4,480
		@ Rs: 1948.10	%CFT	Rs:	87,275
20	Distemping three coats (S.I No: 24(B) P 59)			=	360
		@ Rs: 1043.90	% Sft	Rs:	3,758
21	Making and fixing steel grated doors with 1/16" thick sheeting including angle iron frame 2"x2"x3/4" and bars 4" centre to cement .			=	40
		@ Rs: 726.72	P.Sft	Rs:	29,069
22	Painting doors & window any type, (S.I.No 05 P/ 76)			=	70
		@Rs: 2116.41	%Cft	Rs;	1,481
23	S/F in position iron steel grill of 3/4" X flate iron of approved design i/c painting three coats etc complete with not to beless than 3.7 Lbs sq. ft. of finished grill.			=	14
		@Rs: 194.16	%Cft	Rs;	2,718

S.No	Description	Qty:	Rate	Amount
Part B				
1	P/F Squating type white glass W.C pan of i/c coat of finishing cistring with internal fitting and flush pipe between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.	2.0	@ Rs: 4846.60	P.No: 9694.00
2	P/F & 22"x16" Lavatory basin in white glazed earthen ware complete with & i/c the cost of W.I conntilever brackets 6 inch built into walls painted white in two cost after a primary cost of red land plinth a pair of 1/4" dia chrome plate pillar trape 1-1/2" dia P3	1.0	@ Rs: 4694.80	P No: 4695.00
3	P/F 6"x2" or 6"x3" C.I floor tape.	3.0	@ Rs: 2042.43	P.No: 6073.00
4	P/F in position nyloon connection complete with 1/2" dia brass stop cock with pair brass nuts lining joints to nyloon coonnections	2.0	@ Rs: 77.85	P No: 894.00
5	P/F 4" dia C.I soil and vent pipe i/c cutting fitting and extra painting to match the colour of the building	12.0	@Rs: 333.21	P.RFT 3999.00
6	P/F 4"x4" dia C.I branch of the required degree with access doors rubber washer 3/8" thick and bolts and unts and extra painting to match the colour of the building.	2.0	@ Rs: 270.60	P/No 541.20
7	Providing G.I pipe specials and clamps etc i/c fixing cutting fitting complete two coats of after cleaning the pipe etc with white zink paint with pigment to match the colour of lthe building and testing pressure head of 200' and handling.			
(A)	<u>1/2" dia</u>	25.00	@ Rs: 73.21	PRft 1830.00
(B)	<u>3/4" dia</u>	50.00	@ Rs: 95.79	PRft 4790.00
8	Providing and fixing 4" dia C.I terminal guard i/c extra painting to match the colour of the colour of the building.	2.0	@ Rs: 389.70	PRft 779.00
9	Providing and fixing full way gun metal vallues with whelds threaded of flanged ends with rubber washing. (ii)3/4" (Light pattern)	1.0	@ Rs: 197.12	P No 197.00
10	P/F C:P.Bross bib cock 1/2 " Dia.	2.00	@ Rs: 337.92	P No 676.00
11	Providing RCC pipe with colors class"B" & dying trenches to required depth & fixing in position & Cement Morter 1:1 & test staff (a) 4"Dia Refilling with excavted staff.			
	4"Dia	24.00	@ Rs: 146.57	Each 3518.00
	6"Dia	12.00	@ Rs: 199.25	Each 2391.00
12	S/F Conceled stop cock of superior quality with C.P head 1/2"Dia	2.00	@ Rs: 478.28	P.No 957.00

S.No	Description	Qty:	Rate	Amount
13	S/F Long bib-cock of superior quality with C.P head 1/2" Dia	1.00	@ Rs: 1109.46	P.No 1109.00
14	P/F approved quality AC Motor pumping set(Javed Engineering) Made etc.	1 No.	@ Rs: 5115	P.No 5115.00
15	S/F Fibre glass tank of approved quality and design and wall thickness as specified i/c the cost of nuts and bolts and fixing in plate form of cement concrete 1:2:6 and making connection for inlet-outlet and over flow pipe etc complete.(250 Gallons).	1.0	@Rs: 21989.61	P Gallans 13193.00
16	Hand pump all accessoried i/c fitting and fixing with local made coir strainer with wooden shoe i/c the complete.			
A	<u>Filter.</u>	10.0	@ Rs: 76.05	P.Rft 761.00
B	<u>G.I pipe</u>	40.0	@Rs: 38.95	P.Rft 3506.00
C	<u>Machine</u>	1 No.	@Rs: 1441.65	P.No 1442.00

TOTAL

64131-0


XEN

SCHEDULE "B"

64

Name of Work:-

Provision of Missing Facilities in Elementary Schools in Taluka Bakrani
At: GBPS Panjoo Dero Taluka Bakrani.

S.No	Description	Qty.	Rate		Amount
1	Excavation in foundation of building bridges and other structure member with excavated lead upto one chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).			=	560
		@ Rs: 3176.25	%0 CFT	Rs:	1,778
2	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P/16).				
		@ Rs: 8694.95	% CFT	Rs:	32,258
3	Pacca brick work in foundation and plinth in cement sand mortar: ration 1:6 (S.I No 4 (C) 23			=	464
		@ Rs: 11948.36	% CFT	Rs:	55,440
4	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I No. 6 (a) P/18)			=	100
		@ Rs: 337.00	P.CFT	Rs:	33,700
5	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars, (S I.No 07 (b) P/20)			=	4.464
		@ Rs: 5001.70	P.CWT	Rs:	22,328
6	Pacca brick work in other than building i/c stricking of joints cement sand mortar Ratio 1:6 (S.I No 5 (C			=	450
		@ Rs: 12346.65	%SFT	Rs:	55,560
7	Pacca brick work in Ground floor i/c stricking of joints cement sand mortar Ratio 1:6 (S.I No 5 (C) P/24			=	16
		@ Rs: 12674.36	%SFT	Rs:	2,028
8	S/F sand floor and plugging into walls (S.I.No 29 P/31).			=	158
		@ Rs: 1141.25	%SFT	Rs:	1,803
9	Cement plaster 1:6 upto 20' ft; height 1/2" thick. (S.I No.13 P/57)			=	1,520
		@ Rs: 2206.60	%SFT	Rs:	33,540
10	Cement plaster 1:4 upto 20' ft; height 3/8" thick. (S.I No: 11(a) P 57)			=	1,520
		@ Rs: 2197.52	%SFT	Rs:	33,402
11	Cement pointing and stricking of joints on walls ratid. 1: 2 (S.I No.19 (a) P/53)			=	708
		@ Rs: 1287.44	%SFT	Rs:	9,115
12	Cemnet concret plain i/c placing compacting finishing and curring complete i/c screening and washing of stone aggregate without shuttering Ratio 1:2:4. (S.I.No 5 P/18)			=	11
		@ Rs: 14429.25	%SFT	Rs:	1,587
13	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ration 3" thick. (S.I No:16 (C) P/46)			=	805
		@ Rs: 4411.82	%SFT	Rs:	35,515
				=	111
B 2 Thick		@ Rs: 3275.50	%SFT	Rs:	3,636

XEN

S.No	Description	Qty.	Rate	Amount
14	P/L Hala pattered tiles glazed 4" x 4 1/4" of floor of wall facing in required pattern of cement over a base of 1:2 grey cement mortar 3/4" thick i/c washing and filling joints with slurry of white cement and pigment desired shape with finishing cleaning and cost of wax polish etc complete i/c cutting tile to proper profile (S.I No: 62 P/53)		=	33
		@ Rs: 34520.31	%CFT	Rs: 11,392
15	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4" thick. (Only Shutters)		=	18
		@ Rs: 1273.76	P.CFT	Rs: 22,928
16	Split tiles 1/4" thick matt glazed or double glazed jointed in white and laid 1:2 grey cement sand mortar i/c finishing complete (Flooring and Facing) (S.I.No 69 P/55).		=	50
		@ Rs: 21021.11	%CFT	Rs: 10,511
17	White wash three coats.		=	50
		@ Rs: 829.95	%CFT	Rs: 415
18	Primary coat of chalk under distempering (S.I No: 23 P 59)		=	360
		@ Rs: 442.75	%CFT	Rs: 1,594
19	Preparing the surface and painting with weather coat i/c rubbing the surface coat i/c rubbing the surface brick /sen paper filling the voids with chalk plaster of paris and then painting with weather coat of approx make New surface. (S.I.No 39 (a) P/62).		=	1,400
		@ Rs: 1948.10	%CFT	Rs: 27,273
20	Distempering three coats (S.I No: 24(B) P 59)		=	3,080
		@ Rs: 1043.90	% Sft	Rs: 32,152
21	Making and fixing steel grated doors with 1/16" thick sheeting including angle iron frame 2"x2"x3/4" and bars 4" centre to cement .		=	20
		@ Rs: 726.72	P.Sft	Rs: 14,534
22	Painting doors & window any type, (S.I.No 05 P/ 76)		=	70
		@Rs: 2116.41	%Cft	Rs: 1,481
23	S/F in position iron steel grill of 3/4" X flate iron of approved design i/c painting three coats etc complete with not to be less than 3.7 Lbs sq. ft. of finished grill.		=	14
		@Rs: 194.16	%Cft	Rs: 2,718
TOTAL: Rs:				459,192


XEN

S.No	Description	Qty:	Rate	Amount
Part B				
1	P/F Squating type white glass W.C pan of i/c coat of finishing cistern with internal fitting and flush pipe between flushing and 3 gallons flushing tank with 4" dia C.P. trap and C.I thumble.	2.0	@ Rs: 4846.60	P.No: 9694.00
2	P/F & 22"x16" Lavatory basin in white glazed earthen ware complete with & i/c the cost of W.I conntilever brackets 6 inch built into walls painted white in two cost after a primary cost of red land plinth a pair of 1/4" dia chrome plate pillar trape 1-1/2" dia P3	1.0	@ Rs: 4694.80	P.No: 4695.00
3	P/F 6"x2" or 6"x3" C.I floor tape.	3.0	@ Rs: 2042.43	P.No: 6073.00
4	P/F in position nyloon connection complete with 1/2" dia brass stop cock with pair brass nuts lining joints to nyloon coonections	2.0	@ Rs: 77.85	P No: 894.00
5	P/F 4" dia C.I soil and vent pipe i/c cutting fitting and extra painting to match the colour of the building	12.0	@Rs. 333.21	P.RFT 3999.00
6	P/F 4"x4" dia C.I branch of the required degree with access doors rubber washer 3/8" thick and bolts and unts and extra painting to match the colour of the building.	2.0	@ Rs: 270.60	P/No 541.20
7	Providing G.I pipe specials and clamps etc i/c fixing cutting fitting complete two coats of after cleaning the pipe etc with white zink paint with pigment to machh the colour of lthe building and testing pressure head of 200' and handling.			
(A)	1/2" dia	25.00	@ Rs: 73.21	PRft 1830.00
(B)	3/4" dia	50.00	@ Rs: 95.79	PRft 4790.00
8	Providing and fixing 4" dia C.I terminal guard i/c extra painting to match the colour of the colour of the building.	2.0	@ Rs: 389.70	PRft 779.00
9	Providing and fixing full way gun metal vallues with whelds threaded of flanged ends with rubber washing.(ii)3/4" (Light pattern)	1.0	@ Rs: 197.12	P No 197.00
10	P/F C:P.Bross bib cock 1/2 " Dia.	2.00	@ Rs: 337.92	P.No 676.00
11	Providing RCC pipe with colors class"B" & dying trenches to required depth & fixing in position & Cement Morter 1:1 & test staff (a) 4"Dia Refilling with excavted staff.			
	4"Dia	24.00	@ Rs: 146.57	Each 3518.00
	6"Dia	12.00	@ Rs: 199.25	Each 2391.00
12	S/F Conceled stop cock of superior quality with C.P head 1/2"Dia	2.00	@ Rs: 478.28	P.No 957.00

S.No	Description	Qty:	Rate		Amount
13	S/F Long bib-cock of superior quality with C.P head 1/2" Dia	1.00	@ Rs: 1109.46	P.No	1109.00
14	P/F approved quality AC Motor pumping set(Javed Engineering) Made etc.	1 No.	@ Rs: 5115	P.No:	5115.00
15	S/F Fibre glass tank of approved quality and design and wall thickness as specified i/c the cost of nuts and bolts and fixing in plate form of cement concrete 1:2:6 and making connection for inlet-outlet and over flow pipe etc complete. (250 Gallons).	1.0	@Rs: 21989.61	P.Gallans	13193.00
16	Hand pump all accessoried i/c fitting and fixing with local made coir strainer with wooden shoe i/c the complete.				
A	<u>Filter.</u>	10.0	@ Rs: 76.05	P.Rft	761.00
B	<u>G.I pipe</u>	40.0	@Rs: 38.95	P.Rft	3506.00
C	<u>Machine</u>	1 No.	@Rs: 1441.65	P.No:	1442.00
TOTAL					#####



SCHEDULE " B "

S.No: 65

NAME OF WORK:- **PROVISION OF MISSING FACILITIES IN EXISTING
ELEMENTARY SCHOOLS (2016-17 PROGRAMME). AT GBPS
HAMZO JATOI (1-C/R) TALUKA LARKANO.**

S.No:	Description	Qty:	Rate	Unit	Amount
1	Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).	816.00	@ Rs: 3176/25	% 0 Cft	Rs: 2,591.00 (Rs: three thous: one hund: seventy hund: twenty five only)
2	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No: P/).	245.00	@ Rs: 8694/95	% Cft	Rs: 21,302.00 (Rs: eight thous: six hund: ninty four & ninty five only)
3	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)	665.00	@ Rs:11948/36	%Cft	Rs: 79,456.00 (Rs: eleven thous: nine hund: eighty five & thirty six only)
4	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).	533.00	@ Rs:337/-	P.Cft	Rs: 179,621.00 (Rs: three hund: thirty seven only)
5	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)	26.00	@ Rs:5001/70	P.Cwt	Rs: 130,044.00 (Rs: five thous: one & seventy only)
6	Suppying and filling sand under floor and plugging in walls.(S.I.No: 29 P/25).	1272.00	@ Rs: 1141/25	%Cft	Rs: 14,516.00 (Rs: one thous: one hund: forty one & twenty five only)
7	Extra lead 3.0 miles	1272.00	@ Rs: 579/41	%Cft	Rs: 7,370.00 (Rs: five hund: sevnty nine & fourty one only)
8	Providing and laying single per layer of polythene sheet 0.13 mm thick for water proffing as per specification and instruction of Engineer incharge. (S.I.No: 38 P/37).	163.00	@ Rs:10/70	P.Sft	Rs: 1,744.00 (Rs: ten & seventy only)



XEN

S.No	Description	Qty:	Rate	Unit	Amount
9	Dry rammed brick or stone ballast 1 1/2" to 2" gauge. (S.I.No.2 P/14).				
		137.00	@ Rs: 3327/50	% Cft	Rs: 4,558.00
			(Rs: three thous: two hund: twenty seven & fifty only)		
10	Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).				
		1077.00	@ Rs:12674/36	% Cft	Rs: 136,502.00
			(Rs: twelve thous: six hund: seventy four & thirty six only)		
11	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: P.).				
		28.00	@ Rs:228/90	P.Rft	Rs: 6,409.00
			(Rs: two hund: twenty eight & ninty only)		
12	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: 29 P. 98).				
		114.00	@ Rs: 240/50	P.Rft	Rs: 27,417.00
			(Rs: two hund: forty & fifty only)		
13	Suppling M.S square, bar 5/8" dia (Sch: of matrial).				
		1.00	@ Rs: 3350/-	P.Cwt	Rs: 3,550.00
			(Rs: three thous: three hund; fifty only)		
14	Cutting and fixing iron bars for barred windows. (S.I.No.18 P/97).				
		26.00	@ Rs: 28/23	P.Bar	Rs: 733.00
			(Rs: twenty eight & twenty five only)		
15	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar paneiled and glazed (b) 1-3/4" thick. (Only Shutters).				
		72.00	@ Rs: 902/93	P.Sft	Rs: 65,010.00
			(Rs: nine hud: two & ninty three only)		
16	Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).				
		2013.00	@ Rs:2206/60	% Sft	Rs: 44,418.00
			(Rs: two thous: two hund: six & sixty only)		
17	Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).				
		1981.00	@ Rs:2197/52	% Sft	Rs: 43,532.00
			(Rs: two thous: one hund: ninty seven & twenty two only)		



S.No	Description	Qty:	Rate	Unit	Amount
18	Cement pointing striking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).	629.00	@ Rs:1287/44	% Sft	Rs: 8,097.00
					(Rs: one thous: two hund: eighty seven & forty four only)
19	Notice board made with cement. (S.I.No: 1 P/94)	32.00	@ Rs: 58/11	P.Sft	Rs: 1,859.00
					(Rs: fifty eight & eleven only)
20	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing and dividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).	440.00	@ Rs: 4411/82	% Sft	Rs: 19,412.00
					(Rs: four thous: four hund: eleven & eighty two only)
(B)	<u>1-1/2" Thick</u>	716.00	@ Rs: 2548/29	% S.ft	Rs: 18,245.00
					(Rs: two thous: five hund: forty eight & twenty nine only)
21	Providing and fixing ornamental cement jalli 2" thick. (1:2:4) with out steel. (S.I.No.11 P/17).	59.00	@ Rs:226/02	P.Sft	Rs: 13,335.00
					(Rs: two hund; twenty six & two only)
22	Two Coats of bituman laid hot using 34 Lbs for % Sft. Ober roof and blinded with sand at one Cft. Per % Sft. (S.I.No: 13 P/34).	716.00	@ Rs:1887/40	% Sft	Rs: 13,513.00
					(Rs: one thous: eight hund; eighty seven & fourteen only)
23	Primary coat of chalk distempering. (S.I.No.23 P/57).	2320.00	@ Rs:442/75	% Sft	Rs: 10,271.00
					(Rs: four hund; forty two & seventy five only)
24	Distempering three coats. (S.I.No.24 (c) P/53).	2320.00	@ Rs:1079/65	% Sft	Rs: 25,047.00
					(Rs: one thos: seventy nine & sixty five only)
(B)	<u>Two coats.</u>	440.00	@ Rs:1043/90	% Sft	Rs: 4,593.00
					(Rs: ten hund; forty three & ninty only)

[Handwritten signature]
JLEN

S.No:	Description	Qty:	Rate	Unit	Amount
25	Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of pairs and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).	317.00	@ Rs: 1948/10	%Sft	Rs: 6,175.00
					(Rs: one thous: nine hund: fourty eight & ten only)
26	Preparing surface and painting of doors and windows any type (including edges) (ii) Each subsequent coat of paint. (S.I.No.5 (c) P/69).	207.00	@ Rs:2116/41	%Sft	Rs: 4,380.00
					(Rs: two thous: one hund: sixteen & fourty one only)
				G.Total:	Rs: 893,700.0

[Handwritten signature]
[Stamp]

SCHEDULE " B "

S.No:

NAME OF WORK:-

INTEGRATED REHABILITATION OF PRIMARY / MIDDLE
/ELEMENTARY SCHOOLS (2016-17 PROGRAMME)
AT GBPS MIAN LAL TALUKA LARKANO.

S.No:	Description	Qty:	Rate	Unit	Amount
1	Dismantling cement concrete plain 1:2:4. (S.I.No.19 © P/10).	118.00	@ Rs: 3327/50	% Cft	Rs: 2,926.00 (Rs: three thous: two hund: twenty seven & fifty only)
2	Dismantling cement concrete reinforced separating reinfor cement from concrete cleaning and straightening the same. (S.I.No.20 P/10).	331.00	Rs 5445/-	% Cft	Rs: 18,022.00 (Rs: five thous: four hund: forty five only)
3	Dismantling brick work in lime or cement mortar. (S.I.No.13 P/10).	11.00	@ Rs: 1285/63	% Cft	Rs: 141.00 (Rs: one two hund: eighty five & sixty three only)
4	Remoning cement or lime plaster. (S.i.No.53 P/13).	1056.00	@ Rs:121/-	% Sft	Rs: 1,278.00 (Rs: one hund: twenty one only)
5	Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).	91.00	@ Rs: 3176/25	% 0 Cft	Rs: 289.00 (Rs: three thous: one hund: seventy hund: twenty five only)
6	Cement concrete brick or stone ballast 1-1/2 " to 2" guage (c) Ratio 1:5:10. (S.I.No: 4 (c) P/ 14).	30.00	@ Rs: 8694/95	% Cft	Rs: 2,608.00 (Rs: eight thous: six hund: ninty four & ninty five only)
(B)	<u>Ratio: 1:6:12.</u>	90.00	@ Rs: 8122/95	% Cft	Rs: 7,310.00 (Rs: eight thous: one hund: twenty two & ninty five only)
7	Pacca brick work in foundation and plinth in cement sand mortar ration 1:6 (S.I.No: P/)	77.00	@ Rs: 11948/36	% Cft	Rs: 9,200.00 (Rs: eleven thuos: nine hund: forty eight & thirty six only)
8	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).	395.00	@ Rs:337/-	P.Cft	Rs: 133,115.00 (Rs: three hund: thirty seven only)



XEN

S.No:	Description	Qty:	Rate	Unit	Amount
9	Fabrication of Top steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars. (S.I.No: 7 P/18).	17.63	@ Rs: 5001/70	P.CWt	Rs: 88,180.00 (Rs: five thous: one & seventy only)
10	Supplying and filling sand under floor and plugging in walls.(S.I.No: 29 P/25).	468.00	@ Rs: 1141/25	% Cft	Rs: 5,341.00 (Rs: one thous: one hund: forty one & twenty five only)
11	Extra Lead 3.0 Miles	468.00	@ Rs: 579/41	% 0.Cft	Rs: 2,712.00 (Rs: five hund: sevnty nine & fourty one only)
12	Pacca brick work in Ground floor in cement sand mortar Ratio 1:6 (S.I.No: 5 (i) (e) P.25).	124.00	@ Rs: 12674/36	% Cft	Rs: 15,716.00 (Rs: tweleve thous: six hund: seventy four & thirty six only)
13	Pacca brick work other than building including striking of joints upto 20ft height in cemen sand mortar. (S.I.No: 7 (i) (e) P.26).	38.00	@ Rs: 12346/75	% Cft	Rs: 4,692.00 (Rs: tweleve thous: three hund: forty six & seventy five or)
14	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: 29 P. 92).	18.00	@ Rs:228/90	P.Rft	Rs: 4,120.00 (Rs: two hund: twenty eight & ninty only)
15	P/F G.I frame chowkhats of size 7" x2" or 4" x 3" for Windows using 20 gauge G.I sheet i/c solded hignes and fixing at site with necessary hold fosts filling with cement sand repairing i/c all carriage tools and planst used in making and fixing .(S.I.No: P/).	20.00	@ Rs: 240/50	P.Rft	Rs: 7,215.00 (Rs: two hund: forty & fifty only)
16	M.S barred windows squars bars 5/8" dia.	28.00	@ Rs: 3550/-	P.Sft	Rs: 994.00 (Rs: three thous: five hund: fifty only)
17	Cutting and fixing iron bars for barred windows.	6.00	@ Rs:28/23	P.Cwt	Rs: 170.00 (Rs: twenty eight & twenty three only)


XEN

S.No:	Description	Qty:	Rate	Unit	Amount
18	Applying floating coat of cement 1/32" thick. (S.I.No.14 P/59).	1056.00	@ Rs: 660/- (Rs: six hund: sixty only)	% Sft	Rs: 6,969.00
19	Cement plaster (1:6) upto 12' ft: height 1/2" thick. (S.I.No: 13 (b) P.58).	1116.00	@ Rs: 2206/60 (Rs: two thous: two hund: six & sixty only)	% Sft	Rs: 24,625.00
20	Cement plaster 1:4 upto 12' ft; height 3/8" thick. (S.I.No: 11 (a) P.58).	1116.00	@ Rs: 2197/52 (Rs: two thous: one hund: ninty seven & twenty two only)	% S.ft	Rs: 24,524.00
21	Cement pointing striking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).	110.00	@ Rs:1287/44 (Rs: one thous: two hund: eighty seven & forty four only)	% Sft	Rs: 1,413.00
22	First Class deodar wood wrought, joinery in doors and windows etc, fixed in position i/c chowkats hold fasts hinges, iron tower bolts. Chocks cleats, handles and cords with hooks, etc 1 3/4" thick (S.I.No: 7 (b) P. 57) (Only Shutters).	8.00	@ Rs: 902/93 (Rs: nine hund: two & ninty three only)	P.Sft	Rs: 7,223.00
23	Notice board made with cement. (S.I.No: 1 P/94)	32.00	@ Rs: 58/11 (Rs: fifty eight & eleven only)	P.Sft	Rs: 1,860.00
24	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing and dividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).	300.00	@ Rs: 4411/82 (Rs: four thous: four hund: eleven & eighty two only)	% Sft	Rs: 13,235.00
(B)	<u>2"Thick</u>	742.00	@ Rs:3275/50 (Rs: three thous: two hund: seventy five & fifty only)	% S.ft	Rs: 24,304.00
25	Supplying and fixing in position iron/steel grill of 3/4"x1/4" size flate iron of approved design i/c painting three coats etc complete (weight not to be less than 3.7 lbs/Sq.foot of finished grill).(S.I.No.26 P/92).	12.00	@ Rs:180/50 (Rs: one hund: eighty & fifty only)	P. Sft	Rs: 2,166.00

XEN

S.No:	Description	Qty:	Rate	Unit	Amount
26	White washing three coats. (S.I.No.26 (c) P/53).	900.00	@ Rs:829/95	% Sft	Rs: 7,470
					(Rs: eight hund: twenty nine & ninty five only)
27	Distemping three coats. (S.I.No.24 (c) P/53).	5915.00	@ Rs:1079/65	% Sft	Rs: 63,861
					(Rs: one thos: seventy nine & sixty five only)
28	Preparing surface and painting of doors and windows any type (including edges) (ii) Each subsequent coat of paint. (S.I.No.5 (c) P/69).	304.00	@ Rs:2116/41	% Sft	Rs: 6,433
					(Rs: two thous: one hund: sixteen & fourty one only)
29	Painting guard bars , gates iron bars gratings railings i/c standard barse etc: smiler open works.	96.00	@ Rs:1270/83	% S.ft	Rs: 1,220
					(Rs: one thous: two hund: seventy & eighty three only)
			G.Total:		Rs: 489,332

D
XEN

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

PART-B

2 S/F long bib-cock of superior quality with C.P head 1/2" dia

1.00 @ Rs: 1384/24 P.No Rs: 1,384.00
(Rs: one thous: three hund; eighty four & twenty four only)

3 S/F fibre glass tank of approved qulity and design and wall thickness as apecoified i/c the cost of nute and bolts and fixing in plate iron of cement concerte 1:2:7 and making and commoction for inlet- outlet and over flow pipe etc complete (200 gallons).

1.00 @ Rs:17590/- P.No: Rs: 17,590.00
(Rs: seventeen thous: five hund: ninty one & sixty one only)

Total: Rs: 18,974.00

N.S.I

1 P/F UPVC pipe SCH-40 on surface by using clips/saddles (of approved quality & material), etc. paid separately or.recessed in masonry, C.C or RCC upto 60 ft height and making good with C.C i/c curing, finishing etc complete . 3/4" dia (R.A.,Approved).

3/ 4" Dia 25.00 @ Rs: 78/01 P.No Rs: 1,950.00
(Rs: sevnty eight & One only)

2 P/F Bend/ Elbow (90 degree) of Sch- 40 PVC of namet or Equivalent make of approved quality and design of verious sizes fixed to UPVC pipe/fittings paid seperately using approved adhesive compound (AGM or WELDON, made USA).

(a) 4" Dia 2.00 @ Rs: 425/45 P.No Rs: 850.00
(Rs: four hund: twenty five & fourty five only)

(b) 3/4" Dia 5.00 @ Rs: 103/05 P.No Rs: 515.00
(Rs: one hund; three & five only)

3 Providing & Fixing approved quality A.C motor Mono block set made 1-1/4" x 1" suction and delivery 1 H.Power single phase motor (Diamond /Siemens make or equal) i/c the cost of C.I fitting nuts, bolts etc complete. (R.A).

1.00 @ Rs:14201/- P.No: Rs: 14,201.00
(Rs: fourteen thous: two hund: one only)

N.S.I Rs: 17,516.00

S.I Rs: 18,974.00

G.Total: Rs: 36,490.00


XEN

SCHEDULE " B "

S.No: 67

OF WORK:-

**INTEGRATED REHABILITATION OF PRIMARY / MIDDLE
/ELEMENTARY SCHOOLS (2016-17 PROGRAMME)
AT GBPS BHEDA TALUKA LARKANO.**

S.No:	Description	Qty:	Rate	Unit	Amount
1	Removing cement or lime plaster. (S.i.No.53 P/13).	658.00	@ Rs:121/-	% Sft	Rs: 796.00
			(Rs: one hund: twenty one only)		
2	Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).	85.00	@ Rs: 3176/25	% 0 Cft	Rs: 270.00
			(Rs: three thous: one hund: seventy six & twenty five only)		
3	Cement concrete brick or stone ballast 1-1/2 " to 2" guage (c) Ratio 1:5:10. (S.I.No: 4 (c) P/ 14).	298.00	@ Rs: 8694/95	% Cft	Rs: 25,911.00
			(Rs: eight thous: six hund: ninty four & ninty five only)		
4	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)	171.00	@ Rs:11948/36	% Cft	Rs: 20,432.0
			(Rs: eleven thous: nine hund: forty eight & thirty six only)		
5	Supplying and filling sand under floor and plugging in walls:(S.I.No: 29 P/25).	9007.00	@ Rs: 1141/25	% Cft	Rs: 102,792.00
			(Rs: one thous: one hund: forty one & twenty five only)		
6	Extra lead 3 miles	9007.00	@ Rs: 579/41	% Cft	Rs: 52,187.0
			(Rs: five hund: sevnty nine & fourty one only)		
7	Pacca brick work other than building including striking of joints upto 20' ft: height in (e) cement sand mortar 1:6 (S.I.No.7 (e) P/21).	71.00	@ Rs:12346/65	% Cft	Rs: 8,766.00
			(Rs: tweleve thous: three forty six & sixty five only)		
8	Applying floating coat of cement 1/32" thick. (S.I.No.14 P/59).	658.00	@ Rs: 660/-	% Sft	Rs: 4,343.00
			(Rs: six hund: sixty only)		

XEN

S.No:	Description	Qty:	Rate	Unit	Amount
9	Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).	1523.00	@ Rs:2206/60 (Rs: two thous: two hund: six & sixty only)	% Sft	Rs: 33,607.0
10	Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).	1523.00	@ Rs:2197/52 (Rs: two thous: one hund: ninty seven & twenty two only)	% Sft	Rs: 33,468.0
11	Supplying and fixing in position iron/steel grill of 3/4"x1/4" size flate iron of approved design i/c painting three coats etc complete (weight not to be less than 3.7 lbs/Sq.foot of finished grill).(S.I.No.26 P/92).	153.00	@ Rs:180/50 (Rs: one hund: eighty & fifty only)	P. Sft	Rs: 27,617.0
12	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing anddividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).	776.00	@ Rs: 4411/82 (Rs: four thous: four hund: eleven & eighty two only)	% Sft	Rs: 34,236.00
13	Cement pointing strucking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).	425.00	@ Rs:1287/44 (Rs: one thous: two hund: eighty seven & fourty four only)	% Sft	Rs: 5,472.00
14	Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).	7.00	@ Rs:12674/36 (Rs: tweleve thous: six hund: seventy four & thirty six only)	% Cft	Rs: 887.00
15	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).	15.00	@ Rs:337/- (Rs: three hund: thirty seven only)	P.Cft	Rs: 5,055.00
16	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)	0.602	@ Rs:5001/70 (Rs: five thous: one & seventy only)	P.Cwt	Rs: 3,011.00
17	First Class deodar wood wrought, joinery in doors and windows etc, fixed in position i/c chowkats hold fasts hinges, iron tower bolts. Chocks cleats, handles and cords with hooks, etc 1 3/4" thick (S.I.No: 7 (b) P. 57) (Only Shutters).	8.00	@ Rs: 902/93 (Rs: nine hund: two & ninty three only)	P. Sft	Rs: 7,223.00


XEN

S.No:	Description	Qty:	Rate	Unit	Amount
18	White washing three coats. (S.I.No.26 (c) P/53).	886.00	@ Rs:829/95	% Sft	Rs: 7,353.00 (Rs: eight hund: twenty nine & ninty five only)
19	Primary coat of chalk under distempring.	4666.00	@ Rs: 442/75	% S.ft	Rs: 20,659.00 (Rs: four hund; fourty tow & seventy five only)
20	Distempering two coats. (S.I.No.24 (b) P/53).	4666.00	@ Rs:1043/90	% Sft	Rs: 48,708.00 (Rs: ten hund; forty three & ninty only)
21	Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of pairs and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).	2946.00	@ Rs: 1948/10	% Sft	Rs: 44,145.0 (Rs: one thous: nine hund: fourty eight & ten only)
22	Preparing surface and painting of doors and windows any type (including edges) (ii) Each subsequent coat of paint. (S.I.No.5 (c) P/69).	374.00	@ Rs:2116/41	% Sft	Rs: 7,915.00 (Rs: two thous: one hund: sixteen & fourty one only)
23	Painting guard bars , gates iron bars gratings railings i/c standard barsees etc: smiler open works.	576.00	@ Rs:1270/83	% S.ft	Rs: 7,320.00 (Rs: one thous: two hund: seventy & eighty three only)
G.Total:					Rs: 502,173.0


XEN

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

PART-B

- 1 S/F fibre glass tenk of approved qulity and design and wall thickness as apecoified i/c the cost of nute and bolts and fixing in plate iron of cement concerte 1:2:7 and making and commoction for inlet- outlet and over flow pipe etc complete (250 gallons).

1.00 @ Rs:21989/61 P.No: Rs: 21,989.00
(Rs: Twenty One thous: nine hund: eighty nine & Sixty only)

- 2 S/F long bib-cock of superior quality with C.P head 1/2" dia

5.00 @ Rs: 1384/24 P.No Rs: 6,921.00
(Rs: one thous: three hund; eighty four & twenty four only)

G.Total: Rs: 28,910.00


XEN

SCHEDULE " B "

S.No: 68

NAME OF WORK:-

**INTEGRATED REHABILITATION OF PRIMARY / MIDDLE
/ELEMENTARY SCHOOLS (2016-17 PROGRAMME)
AT GBPS GHULAM BHUTTO TALUKA LARKANO.**

S.No:	Description	Qty:	Rate	Unit	Amount
1	Supplying and filling sand under floor and plugging in walls. (S.I No: 29 P/25).	8389.00	@ Rs: 1141/25	% Cft	Rs: 95,761.00
					(Rs: one thous: one hund: forty one & twenty five only)
2	Cement concrete brick or stone ballast 1-1/2 " to 2" guage (c) Ratio 1:5:10. (S.I.No: 4 (c) P/ 14).	490.07	@ Rs: 8694/95	% Cft	Rs: 42,611.00
					(Rs: eight thous: six hund: ninty four & ninty five only)
3	Pacca brick work in foundation and plinth in cement sand mortar ratio. 1:6. (S.I.No.4 (1) (e) P/20)	447.49	@ Rs:11948/36	% Cft	Rs: 53,468.00
					(Rs: eleven thous: nine hund: eighty five & thirty six only)
4	Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51)	427.02	@ Rs:2206/60	% Sft	Rs: 9,423.00
					(Rs: two thous: two hund: six & sixty only)
5	Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).	427.02	@ Rs:2197/52	% Sft	Rs: 9,384.00
					(Rs: two thous: one hund: ninty seven & twenty two only)
6	Cement Concerate plain including placing compacting finishing and curing complete (including screening and washing at stone aggregate without Ratio. 1:2:4.(S.I.No: 5 (f) P/ 15).	27.73	@ Rs: 14429/25	%Cft	Rs: 4,001.00
					(Rs: fourteen thous: four hund: twenty nine & twenty five on
7	Laying floors of approved coloured glazed tiles 1/4" thick laid in white cement and pigment on a bed of 3/4" thick cement mortar 1:2 (S.I. No. 25 P/42).	598.77	@ Rs:27747/06	% Sft	Rs: 166,141.0
					(Rs: twenty seven thous: seven hund forty seven & six onl
8	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing anddividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).	1507.00	@ Rs: 4411/82	% Sft	Rs: 66,486.00
					(Rs: four thous: four hund: eleven & eighty two only)


XEN

S.No:	Description	Qty:	Rate	Unit	Amount
9	Providing and laying 2" thick topping cement concrete (1:2:4) including surface finishing and dividing into pannels (S.I.No.16 (c) P/41).	280.52	@ Rs: 3275/50	% S.ft	Rs: 9,188.00 (Rs: three thous: two hund; seventy five & fifty only)
10	First Class deodar wood wrought, joinery in doors and windows etc, fixed in position i/c chowkats hold fasts hinges, iron tower bolts. Chocks cleats, handles and cords with hooks, etc 1 3/4" thick (S.I.No: 7 (b) P. 57) (Only Shutters).	99.00	@ Rs: 902/93	P.Sft	Rs: 89,390.00 (Rs: nine hund: two & ninty three only)
11	White washing three coats. (S.I.No.26 (c) P/53).	161.58	@ Rs:829/95	%Sft	Rs: 1,341.00 (Rs: eight hund: twenty nine & ninty five only)
12	Primary coat of chalk under distemping.	573.26	@ Rs: 442/75	% S.ft	Rs: 2,538.00 (Rs: four hund; forty tow & seventy five only)
13	Distemping three coats. (S.I.No.24 (c) P/53).	573.26	@ Rs:1079/65	%Sft	Rs: 8,855.00 (Rs: one thos: seventy nine & sixty five only)
14	Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of pairs, and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).	1483.24	@ Rs: 1948/10	%Sft	Rs: 28,895.0 (Rs: one thous: nine hund: forty eight & ten only)
15	Preparing surface and painting of doors and windows any type (including edges) (ii) Each subsequent coat of paint. (S.I.No.5 (c) P/69).	175.00	@ Rs:2116/41	%Sft	Rs: 3,704.00 (Rs: two thous: one hund: sixteen & fourty one only)
G.Total:					Rs: 591,186.0


XEN

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

PART-B

1	P/f squatting type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern wit internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less than clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.	5.00	@ Rs: 4802/60	Each	Rs: 24,013.00
			(Rs: four thous: eight hund; two & sxitly only)		
2	S/F long bib-cock of superior quality with C.P head 1/2" dia	8.00	@ Rs: 1384/24	P.No	Rs: 11,074.00
			(Rs: one thous: three hund; eighty four & twenty four only)		
3	P/f water pumping set 3 HP mono block single phase 220 volls with 1 1/2"x1 1/4" suntire delivery (60 ft head i/c making c.c 1:3:6 plater form of required size fixing with units + hoolls E.S.I.No: 23P/33).	1.00	@ Rs:15254/48	P.No:	Rs: 15,254.00
			(Rs: fifteen thous: two hund: fifty four & foudy eight only)		
4	S/F fibre glass tenk of approved qulity and design and wall thickness as apecoified i/c the cost of nute and bolts and fixing in plate iron of cement concerte 1:2:7 and making and commoction for inlet- outlet and over flow pipe etc complete (250 gallons).	1.00	@ Rs:21989/61	P.No:	Rs: 21,990.00
			(Rs: Twenty One thous: nine hund: eighty nine & Sixty only)		
Total:					Rs: 72,331.00

N.S.I

1	P/F UPVC pipe SCH-40 on surface by using clips/saddles (of approved quality & material), etc. paid separately or recessed in masonry, C.C or RCC upto 60 ft height and making good with C.C i/c c uring, finishing etc complete . 3/4" dia (R.A. Approved).				
	<u>(a) 4" Dia</u>	56.00	@ Rs: 397/77	P.No	Rs: 22,271.00
			(Rs: three hund: ninty seven & seventy seven only)		
	<u>(b) 3/ 4" Dia</u>	93.00	@ Rs: 78/01	P.No	Rs: 7,285.00
			(Rs: sevnty eight & One only)		
	<u>(c) 1" Dia</u>	40.00	@ Rs: 97/91	P.No	Rs: 3,916.00
			(Rs: ninety seven & ninty one only)		


XEN

S.No:	Description	Qty:	Rate	Unit	Amount
2	P/F Bend/ Elbow (90 degree) of Sch- 40.PVC of namet or Equivalent make of approved quality and design of verious sizes fixed to UPVC pipe/fittings paid seperately using approved adhesive compound (AGM or WELDON, made USA).				
	(a) 3/4" Dia	20.00	@ Rs: 103/05	P.No	Rs: 2,061.00
			(Rs: one hund; three & five only)		
	(b) 1" Dia	10.00	@ Rs: 226/-	P.Rft	Rs: 2,260.00
			(Rs: two hund; twenty six only)		
3	P/F TEE of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of verious sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D_1784 type 1 grade TEE 1. Rate includes all costs of labour, material cartage.				
	3/4" Dia	20.00	@ Rs: 110/40	P.No	Rs: 2,208.00
			(Rs: one hund; ten & fourteen only)		
4	P/F COUPLING / SCOKET of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of verious sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I)				
	3/4" Dia	10.00	@ Rs:98/15	P.No	Rs: 981.00
			(Rs: ninty eight & fifteen only)		
			N.S.I	Rs:	40,982.00
			S.I	Rs:	72,331.00
			G.Total:	Rs:	113,313.00


XEN

SCHEDULE " B "

S.No: 69

NAME OF WORK:- **INTEGRATED REHABILITATION OF PRIMARY / MIDDLE /
ELEMENTARY SCHOOLS (2016-17 PROGRAMME). AT GBPS
CHAKAR KALHORO TALUKA LARKANO.**

S.No:	Description	Qty:	Rate	Unit	Amount
1	Dismantling cement concrete reinforced separating reinfor cement from concrete cleaning and straightening the same. (S.I.No.20 P/10).	31.00	Rs 5445/- (Rs: five thous: four hund: forty five only)	% Cft	Rs: 1,688.00
2	Dismantling cement concrete plain 1:2:4. (S.I.No.19 © P/10).	366.00	@ Rs: 3327/50 (Rs: three thous: two hund: twenty seven & fifty only)	% Cft.	Rs: 12,179.00
3	Dismantling brick work in lime or cement mortor. (S.I.No.13 P/10).	139.00	@ Rs: 1285/63 (Rs: one two hund: eighty five & sixty three only)	% Cft	Rs: 1,787.00
4	Removing cement or lime plaster. (S.i.No.53 P/13).	2690.00	@ Rs:121/- (Rs: one hund: twenty one only)	% Sft	Rs: 3,255.00
5	Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).	688.00	@ Rs: 3176/25 (Rs: three thous: one hund: seventy hund: twenty five only)	% 0 Cft	Rs: 2,185.00
6	Cement concrete brick or stone ballast 1-1/2 " to 2" guage (c) Ratio 1:5:10. (S.I.No: 4 (c) P/ 14)	142.00	@ Rs: 8694/95 (Rs: eight thous: six hund: ninty four & ninty five only)	% Cft	Rs: 12,347.00
(B)	Ratio: 1:6:12.	292.00	@ Rs: 8122/95 (Rs: eight thous: one hund: twenty two & ninty five only)	% Cft	Rs: 23,719.00
7	Pacca brick work in foundation and plinth in cement sand mortar ratio. 1:6. (S.I.No.4 (1) (e) P/20)	553.00	@ Rs:11948/36 (Rs: eleven thous: nine hund: eighty five & thirty six only)	% Cft	Rs: 66,074.00


XEN

S.No:	Description	Qty:	Rate	Unit	Rs.
8	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).	142.00	@ Rs:337/-	P.Cft	Rs: 47,854.00
					(Rs: three hund: thirty seven only)
9	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars. (S.I.No.8 (b) P/16)	8.00	@ Rs:5001/70	P.Cwt	Rs: 40,013.00
					(Rs: five thous: one & seventy only)
10	Supplying and filling sand under floor and plugging in walls. (S.I.No: 29 P/25).	5366.00	@ Rs: 1141/25	% Cft	Rs: 61,239.00
					(Rs: one thous: one hund: forty one & twenty five only)
11	Extra Lead 3.0 Miles	5366.00	@ Rs: 579/41	% O.Cft	Rs: 31,091.00
					(Rs: five hund: sevnty nine & fourty one only)
12	Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e)-P/20).	173.00	@ Rs:12674/36	% Cft	Rs: 21,927.00
					(Rs: twelve thous: six hund: seventy four & thirty six only)
13	Pacca brick work other than building including striking of joints upto 20' ft: height in (e) cement sand mortar 1:6 (S.I.No.7 (e) P/21).	204.00	@ Rs:12346/65	% Cft	Rs: 25,187.00
					(Rs: twelve thous: three forty six & sixty five only)
14	P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welding and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repairing jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: P/)	32.00	@ Rs:228/90	P.Rft	Rs: 7,324.00
					(Rs: two hund: twenty eight & ninty only)
15	P/F G.I frame chowkhats of size 7" x2" or 4" x 3" for Windows using 20 gauge G.I sheet i/c solded hignes and fixing at site with necessary hold fosts filling with cement sand repairing i/c all carriage tools and planst used in making and fixing. (S.I.No: P/)	6.00	@ Rs: 240/50	P.Rft	Rs: 1,443.00
					(Rs: two hund: forty & fifty only)


 HEN

S.No:	Description	Qty:	Rate	Unit	Amount
16	First Class deodar wood wrought, joinery in doors and windows etc, fixed in position i/c chowkats hold fasts hinges, iron tower bolts. Chocks cleats, handles and cords with hooks, etc 1 3/4" thick (S.I.No: 7 (b) P. 57) (Only Shutters).	35.00	@ Rs: 902/93 (Rs: nine hund: two & ninty three only)	P.Sft	Rs: 31,602.00
17	Applying floating of cement 1/32" thick.. (S.I.No.14 P/53).	2690.00	@ Rs:660/- (Rs: six hund: sixty only)	% Sft	Rs: 17,754.00
18	Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).	3492.00	@ Rs:2206/60 (Rs: two thous: two hund: six & sixty only)	% Sft	Rs: 77,054.00
19	Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).	3492.00	@ Rs:2197/52	% Sft	Rs: 76,737.00
20	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing anddividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).	899.00	@ Rs: 4411/82 (Rs: four thous: four hund: eleven & eighty two only)	% Sft	Rs: 39,662.00
(B)	2"Thick	1105.00	@ Rs: 3275/50 (Rs: three thous: two hund; seventy five & fifty only)	% S.ft	Rs: 36,194.00
21	Cement pointing strucking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).	435.00	@ Rs:1287/44 (Rs: one thous: two hund: eighty seven & fourty four only)	% Sft	Rs: 5,600.00
22	Notice board made with cement. (S.I.No: 1 P/94).	32.00	@ Rs: 58/11 (Rs: fifty eight & eleven only)	P.Sft	Rs: 1,860.00
23	Supplying and fixing in position iron/steel grill of 3/4"x1/4" size flate iron of approved . design i/c painting three coats etc complete (weight not to be less than 3.7 lbs/Sq.foot of finished grill).(S.I.No.26 P/92).	6.00	@ Rs:180/50 (Rs: one hund: eighty & fifty only)	P. Sft	Rs: 1,083.0

A
XEN

S.No:	Description	Qty:	Rate	Unit	Amount
24	Making and fixing steel grated door with 1/16" thick sheeting including angle iron frame 2"x2" 3/8" 3/4" square bars 4" centre to centre with locking arrangement. (S.I.No.24P/91).	24.00	@ Rs:726/72	P. Sft	Rs: 17,441.00 (Rs: seven hund: twenty six & seventy two only)
25	Two Coats of bituman laid hot using 34 Lbs for % Sft. Ober roof and blinded with sand at one Cft. Per % Sft. (S.I.No: 13 P/34).	998.00	@ Rs:1887/40	% Sft	Rs: 18,836.00 (Rs: one thous: eight hund; eighty seven & fourteen only)
26	Providing and laying HALLA or pettern tiles glazed 8"x8"x1/4" on floor or wall facing in required pat specification jointed in white cement and pigment over a base of 1:2 grey cement motar 3/4" thick washing and filling of joints with slurry of white cement and pigment in desired shape with finishing cost of wax polish etc. complete including cutting tiles to proper profile (S.I.No: 62 P.47).	21.00	@ Rs: 34520/31	% Sft	Rs: 7,249.00 (Rs: thirty four thous: five hund: twenty & thirty one only)
27	White washing three coats. (S.I.No.26 (c) P/53).	640.00	@ Rs:829/95	% Sft	Rs: 5,311.00 (Rs: eight hund: twenty nine & ninty five only)
28	Distemping three coats. (S.I.No.24 (c) P/53).	2208.00	@ Rs:1079/65	% Sft	Rs: 23,838.00 (Rs: one thos: seventy nine & sixty five only)
29	Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of pairs and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).	1789.00	@ Rs: 1948/10	% Sft	Rs: 34,851.0 (Rs: one thous: nine hund: forty eight & ten only)
30	Preparing surface and painting of doors and windows any type (including edges) (ii) Each subsequent coat of paint. (S.I.No.5 (c) P/69).	430.00	@ Rs:2116/41	% Sft	Rs: 9,100.00 (Rs: two thous: one hund: sixteen & fourty one only)
31	Painting guard bars , gates iron bars gratings railings i/c standard barsed etc: smiler open works.	96.00	@ Rs:1270/83	% S.ft	Rs: 1,220.00 (Rs: one thous: two hund: seventy & eighty three only)
G.Total:					Rs: 756,504.0


XEN

S.No	Description	Qty:	Rate	Unit	Amount
PART-B					
1	P/f squatting type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern with internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less than clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.	2.00	@ Rs: 4802/60	Each	Rs: 9,605.00 (Rs: four thous: eight hund; two & sixty only)
2	Add: Extra for labour for providing and fixing of erthern wire padestal white or coloured glazed	2.00	@ Rs: 2533/47	P.No:	Rs: 5,069.00 (Rs: four thous: five hund; thirty three & forty seven only)
3	P/F in position nyloon connections complete with 1/2" dia brass stop cock with pair of brass nuts lining joints to nyloon connections.	2.00	@ Rs: 447/15	P.No:	Rs: 894.00 (Rs: four hund: forty seven & fifteen only)
4	S/F long bib-cock of superior quality with C.P head 1/2" dia	2.00	@ Rs: 1384/24	P.No	Rs: 2,768.00 (Rs: one thqus: three hund; eighty four & twenty four only)
5	S/F concealed stop cock of superior quality with C.P head 1/2" dia.	2.00	@ Rs: 889/46	P.No	Rs: 1,778.00 (Rs: eight hund; eighty nine forty six only)
6	P/f water pumping set 3 HP unonablock single phase 220 volls with 1 1/2"x1 1/4" suntire delivery i/c making c.c 1:3:6 plater form of required size fixing with units + hools E.S.I.No: 23P/33).	1.00	@ Rs:15254/48	P.No:	Rs: 15,254.00 (Rs: fifteen thous: two hund: fifty four & fouty eight only)
7	S/F fibre glass tenk of approved qulity and design and wall thickniess as apecoified i/c the cost of nute and bolts and fixing in plate iron of cement concerte 1:2:7 and making and commoction for inlet- outlet and over flow pipe etc complete (200 gallons).	1.00	@ Rs: 17591/61	P.No:	Rs: 17,591.00 (Rs: seventeen thous: five hund: ninty one & sixty one only)
Total:					Rs: 52,959.00

J
XEN

S.No:	Description	Qty:	Rate	Unit	Amount
	<u>N.S.I</u>				
1	P/F UPVC pipe SCH-40 on surface by using clips/saddles (of approved quality & material), etc. paid separately or recessed in masonry, C.C or RCC upto 60 ft height and making good with C.C i/c c uring, finishing etc complete . 3/4" dia (R.A.,Approved).				
	<u>(a) 4" Dia</u>	5.00	@ Rs: 397/77	P.No	Rs: 1,988.00
			(Rs: three hund: ninty seven & seventy seven only)		
	<u>(b) 3/ 4" Dia</u>	20.00	@ Rs: 78/01	P.No	Rs: 1,560.00
			(Rs: sevnty eight & One only)		
2	P/F Bend/ Elbow (90 degree) of Sch- 40 PVC of namet or Equivalent make of approved quality and design of verious sizes fixed to UPVC pipe/fittings paid seperately using approved adhesive compound (AGM or WELDON, made USA).				
	<u>(a) 4" Dia</u>	2.00	@ Rs: 425/45	P.No	Rs: 850.00
			(Rs: four hund: twenty five & fourty five only)		
	<u>(b) 3/4" Dia</u>	5.00	@ Rs: 103/05	P.No	Rs: 515.00
			(Rs: one hund; three & five only)		
5	Hand pump all accessories i/c fitting and fixing with local made coir strainer with wooden shoe i/c the complete.				
	<u>(a) Filter</u>	10.00	@ Rs: 76/05	P.Rft	Rs: 760.00
			(Rs: seventy six & five only)		
	<u>(b) G.I Pipe</u>	60.00	@ Rs: 38/95	P.Rft	Rs: 2,337.00
			(Rs: thrity eight & ninty five only)		
	<u>(C) Machine</u>	10.00	@ Rs: 1441/65	Each	Rs: 1,442.00
			(Rs: one thous: four-hund: fourty one & sixty five only)		
	N.S.I				Rs: 9,452.00
	S.I				Rs: 52,959.00
	G.Total:				Rs: 62,411.00


XEN

SCHEDULE " B "

S.No: 70

NAME OF WORK:- INTEGRATED REHABILITATION OF PRIMARY / MIDDLE / ELEMENTARY SCHOOLS (2016-17 PROGRAMME) AT GBPS NEW NAZAR MUHALLA TALUKA LARKANO.

S.No	Description	Qty	Rate	Unit	Amount
1	Dismantling cement concrete plain 1:2:4. (S.I.No.19 © P/10).	292.00	@ Rs: 3327/50	% Cft	Rs: 9,71,164
					(Rs: three thous: three hund: twenty seven & fifty only)
2	Removing cement or lime plaster. (S.i.No.53 P/13).	987.00	@ Rs:121/-	% Sft	Rs: 1,19,427
					(Rs: one hund: twenty one only)
3	Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).	51.00	@ Rs:12674/36	% Cft	Rs: 6,46,574
					(Rs: twelve thous: six hund: seventy four & thirty six only)
4	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).	47.00	@ Rs:337/-	P.Cft	Rs: 15,839
					(Rs: three hund: thirty seven only)
5	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)	2.098	@ Rs:5001/70	P.Cwt	Rs: 10,494
					(Rs: five thous: one & seventy only)
6	Applying floating coat of cement 1/32" thick. (S.I.No.14 P/59).	987.00	@ Rs: 660/-	% Sft	Rs: 6,51,164
					(Rs: six hund: sixty only)
7	Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.i.No.13 (b) P/51).	1145.00	@ Rs:2206/60	% Sft	Rs: 25,263
					(Rs: two thous: two hund: six & sixty only)
8	Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).	1145.00	@ Rs:2197/52	% Sft	Rs: 25,160
					(Rs: two thous: one hund: ninty seven & twenty two only)
9	Cement Concerate plain including placing compacting finishing and curing complete (including screening and washing at stone aggregate without Ratio. 1:2:4.(S.I.No: 5 (f) P/ 15).	71.00	@ Rs: 14429/25	%Cft	Rs: 10,244
					(Rs: fourteen thous: four hund: twenty nine & twenty five only)


XEN

S.No:	Description	Qty:	Rate	Unit	Amount
10	Laying floors of approved coloured glazed tiles 1/4" thick laid in white cement and pigment on a bed of 3/4" thick cement mortar 1:2. (S.I. No: 25 P/42).	751.00	@ Rs:27747/06	% Sft	Rs: 208,380.00 (Rs: twenty seven thous: seven hund forty seven & six)
11	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing and dividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).	930.00	@ Rs: 4411/82	% Sft	Rs: 41,030.00 (Rs: four thous: four hund: eleven & eighty two only)
(B)	<u>2" Thick</u>				
		1617.00	@ Rs: 3275/50	% S.ft	Rs: 52,965.00 (Rs: three thous: two hund; seventy five & fifty only)
12	Two Coats of bituman laid hot using 34 Lbs for % Sft. Ober roof and blinded with sand at one Cft. Per % Sft. (S.I.No: 13 P/34).	1617.00	@ Rs:1887/40	% Sft	Rs: 30,519.00 (Rs: one thous: eight hund; eighty seven & fourteen only)
13	Making and fixing steel grated door with 1/16" thick sheeting including angle iron frame 2"x2" 3/8" and 3/4" square bars 4" centre to centre with locking arrangement. (S.I.No.24P/91).	24.00	@ Rs:726/72	P. Sft	Rs: 17,441.00 (Rs: seven hund: twenty six & seventy two only)
14	Cement pointing strucking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).	216.00	@ Rs:1287/44	% Sft	Rs: 2,781.00 (Rs: one thous: two hund: eighty seven & forty four only)
15	Notice board made with cement. (S.I.No: 1 P/94)	64.00	@ Rs: 58/11	P.Sft	Rs: 3,719.00 (Rs: fifty eight & eleven only)
16	First Class deodar wood wrought, joinery in doors and windows etc, fixed in position w/c chowkats hold fasts hinges, iron tower bolts. Chocks cleats, handles and cords with hocks, etc 1 3/4" thick (S.I.No: 7 (b) P. 57) (Only Shutters).	18.00	@ Rs: 902/93	P.Sft	Rs: 16,253.00 (Rs: nine hund: two & ninty three only)
17	White wash two coats.	2514.00	@ Rs:425/84	% Sft	Rs: 10,706.00 (Rs: four hund: twenty five & eighty four only)

D
XEN

S.No:	Description	Qty:	Rate	Unit	Amount
18	Distemparing three coats. (S.I.No.24 (c) P/53).				
		8855.00	@ Rs:1079/65	% Sft	Rs: 95,603.00
			(Rs: one thus: seventy nine & sixty five only)		
19	Painting doors and windows any type. (ii) Each subsequent coat. (S.I.No.4 (c) (ii) P/76).				
		808.00	@ Rs:1160/06	% Sft	Rs: 8,941.00
			(Rs: one thous: one hund; sixty & six only)		
20	Painting guard bars , gates iron bars gratings railings i/c standard barsees etc: smiler open works.				
		203.00	@ Rs:1270/83	% S.ft	Rs: 2,580.00
			(Rs: one thous: two hund: seventy & eighty three only)		
21	Preparing the surface and painting with weather coat of approved make to old weather coat surface. (S.I.No:39 P/55).				
		2902.00	@ Rs:1498/48	% Sft	Rs: 43,486.00
			(Rs: one thous: four hund; ninty eight & forty eight only)		
G.Total:					Rs: 645,298.00


XEN

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

PART-B

- 1 P/f squatting type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern with internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less than clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.

2.00	@ Rs: 4802/60	P.No:	Rs:	9,605.00
	(Rs: four thous: eight hund; two & sxity only)			

- 2 P/F & fixing 22" x 16" lavatory basin in white glazed earthen ware complete with and i/c the cost of W.I or C.I cantilever brackets 6 inches built into walls painted white in 2 coats after a primary cost of red lead paint & pair of 1/2" dia chrome-brass waster of approved pattern 1-1/4" dia malleable iron of cp bars traps. Malleable iron or brass unions & making requisite number of holes in walls plinth and floor for piep connection and making good in c.c 1:2:4 (foreign equivalent). (S.I.No: 13 P/3).

1.00	@ Rs: 4928/-	P.Each	Rs:	4,928.00
	(Rs: four thous: nine hund; twenty eight only)			

- 3 Add: Extra for labour for providing and fixing of erthern wire padestal white or coloured glazed

1.00	@ Rs: 2533/47	P.No:	Rs:	23,533.00
	(Rs: four thous: five hund; thirty three & fourty seven only)			

- 4 P/F in position nylon connections complete with 1/2" dia brass stop cock with pair of brass nuts in joints to nylon connections.

4.00	@ Rs: 447/15	P.No:	Rs:	1,789.00
	(Rs: four hund: forty seven & fifteen only)			

- 5 P/F 15"x12" beveled edge mirror of belgium glass complete with 1/8" thick hard board and C.P screws fixed to wooden pleat (a) Standard pattern. (S.I.No.3 (a) P/7).

1.00	@ Rs:2376/-	P.Each	Rs:	2,376.00
	(Rs: two thous: three hund; seventy six only)			

- 6 S/F conceled stop cock of superior quality with C.P head 1/2" dia.

4.00	@ Rs: 889/46	P.No	Rs;	3,558.00
	(Rs: eight hund; eighty nine fourty six only)			

- 7 S/F long bib-cock of superior quality with C.P head 1/2" dia

6.00	@ Rs: 1384/24	P.No	Rs:	8,305.00
	(Rs: one thous: three hund: eighty four & twenty four only)			

- 8 S/F Swan type piller cock of superior quality etc:

1.00	@ Rs: 877/80	P.No	Rs:	877.00
	(Rs: eight hund; seventy seven & eighty only)			

S.No:	Description	Qty:	Rate	Unit	Amount
9	P/f water pumping set 3 HP unonablock single phase 220 volls with 1 1/2"x1 1/4" suntire delivery (60 ft head i/c making c.c 1:3:6 plater form of required size fixing with units + hauls E.S.I.No: 23P/33).	1.00	@ Rs: 15254/48	P.No:	Rs: 15,254.00
			(Rs: fifteen thous: two hund: fifty four & fouty eight only)		
			G.Total:		Rs: 70,225.00

N.S.I

- 1 Hand pump all accessoried i/c fitting and fixing with local made coir strainer with wooden shoe i/c the complete.

(a) Filter 10.00 @ Rs: 76/05 P.Rft Rs: 760.00
(Rs: seventy six & five only)

(b) G.I Pipe 80.00 @ Rs: 38/95 P.Rft Rs: 3,116.00
(Rs: thrity eight & ninty five only)

(C) Machine 1.00 @ Rs: 1441/65 Each Rs: 1,442.00
(Rs: one thous: four hund: fourty one & sixty five only)

- 2 P/F UPVC Pipe (AGM) SCH: 40 (E) on surface using Clips/ Saddle of approved quality and Material etc paid separatly recessed in Masonry, C.C or R-C-C upto 60' height and making good with C.C i/c cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement of class 12 & 5 B in accordance with AS + MD 1784 type grade 1 rate I/C all cost of labour, material charges Scaffolding Ladders etc complete (N.S.I).

(a) 4" Dia 12.00 @ Rs: 397/77 P.Rft Rs: 4,773.00
(Rs: three hund: ninty seven & seventy seven only)

(b) 3/4" Dia 40.00 @ Rs: 78/01 P.Rft Rs: 3,120.00
(Rs: sevnty eight & One only)

- 3 P/F Bend/ Elbow (90 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of verious sizes fixed to UPVC pipe/fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per class 12454-B In accordance Incharge. Specifications of the material should meet the requirements of material, cartage, scaffolding / ladders etc. complete. (N.S.I)

(a) 3/4" Dia 25.00 @ Rs: 103/05 P.No Rs: 2,576.00
(Rs: one hund: three & five only)

(b) 4" Dia 4.00 @ Rs: 425/45 P.No Rs: 1,702.00
(Rs: four hund: twenty five & fourty five only)

S.No.	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

4 P/F TEE of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA; in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D_ 1784 type 1 grade TEE'1. Rate includes all costs of labour, material cartage.

(a) 3/4" Dia	9.00	@ Rs: 110/40	P.No	Rs:	993.00
(Rs: one hund; ten & fourteen only)					

(c) 4" Dia	2.00	@ Rs:712/75	P.No	Rs:	1,426.00
(Rs: seven hund: twelve & seventy five only)					

5 P/F COUPLING / SCOKET of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA; in ORANGE colour) upto 60 ft height as per-instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I)

(a) 3/4" Dia	15.00	@ Rs:98/15	P.No	Rs:	1,472.00
(Rs: ninty eight & fifteen only)					

Total:				Rs:	21,380.00
---------------	--	--	--	-----	------------------

S.I				Rs:	70,225.00
------------	--	--	--	-----	------------------

G.Total:				Rs:	91,605.00
-----------------	--	--	--	-----	------------------

SCHEDULE 'B'

7/

Name of Work:- Integrated Rehabilitation of Primary / Elemenary Schools Taluka Larkano
(2016-17 Progg)at: GBMS Wapda Colony Taluka Larkano

SN	ITEM OF WORK	Qty:	Rate	Unit	Amount
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	80.00	@ Rs: 910.0	P.Point	Rs: 72,800.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 129 P 15).	6.00	@ Rs: 742.0	P.Point	Rs: 4,452.00
3	Wiring for Call beel with 1/1.13 (3/029) PVC insulated wire in 20mm(3/4")PVC conduit recessed in the coloumns as required (S.I.No: 128 P 15)	3.00	@ Rs: 1764.0	P.Point	Rs: 5292.0
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	81.00	@ Rs: 171.0	P.Meter	Rs: 13,851.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7.044} Copper conductor in 1" dia PVC conduit on surface.(S.I.No: 6 P 1).	70.00	@ Rs: 305.0	P.Meter	Rs: 21,350.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7.052}(10mm2) Copper conductor in 1" dia PVC conduit on surface (S.I.No: 6 P 1).	65.00	@ Rs: 428.0	P.Meter	Rs: 27,820.00
5	Providing & Fixing A.C one way S.P 5ampswitch flush type (S.I.No: 219 P 33)	32.00	@ Rs: 54.0	P.Each	Rs: 1,728.00
14	Fixing A.C or D.C Electric beel 200/250 Volts 70 MM (S.I.No:19 P 12).	3.00	@ Rs: 150.70	P.Each	Rs: 452.0
15	P/F flush type electric beel push button (S.I.No: 23 P 12)	3.00	@ Rs: 25.19	P.Each	Rs: 76.0
6	Providing & Fixing 2 pin 5 amps plug & socket flush type.(S.I.No: 225 P 33).	6.00	@ Rs: 83.0	P.Each	Rs: 498.00
7	Providing & Fixing Brass Battern holder..(S.I.No: 232 P 33)	19.00	@ Rs: 70.0	P.Each	Rs: 1,368.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals .(S.I.No: 228 P 33)	13.00	@ Rs: 72.0	P.Each	Rs: 936.00
9	Providing and fixing brass ceiling fan 56" (good quality).	20.00	@ Rs: 3185.0	P.Each	Rs: 63,700.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet.(S.I.No: 18 P11)	1.00	@ Rs: 156.97	P.Each	Rs: 157.00
11	P/F Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	10.00	@ Rs: 948.0	P.Each	Rs: 9,480.00
12	P/F Circuit breakers 15,20,30,40,50,60,75 & 100 Amps (T P (XS-100 NS on a prepared board as required (S.I.No: 207 P 31).	2.00	@ Rs: 9261.0	P.Each	Rs: 18,522.00
TOTAL					242,482.00



SN	ITEM OF WORK	Qty:	Rate	Unit	Amount.
----	--------------	------	------	------	---------

(Part - B) N.S.I

1	Fixing A.C ceiling fan regulator on S.W board.	22.00	@ Rs: 109.56	P.Each	Rs: 2,410.00
2	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.	22.00	@ Rs: 169.21	P.Each	Rs: 3,723.00
3	P/F main panel board double shutter to accommodate heavy duty circuit breakers bus bar in painting.	6.00	@ Rs: 1089.50	P.Sq.ft.	Rs: 6,537.00
4	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal, etc, i.c making the pit 12" deep by excavation of all type of soil. Earth Plate to be connected with No.8 S.W.G bare copper wire run in 1/2" dia C.I pipe straight from the earth upto metallic electrical assembly i/c providing necessary tee.	1.00	@ Rs: 3084.40	P.Each	Rs: 3,084.00
5	P/F Energy saver superior quality i/c fixing on extg. holder etc complete.	50.00	@ Rs: 596.40	P.Each	Rs: 29,820.00
6	P/F wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.	14.00	@ Rs: 596.40	P.Each	Rs: 8,350.00
7	P/F hinged type double S.W board accommodate main or sub-main control switches and for other similar jobs.	25.00	@ Rs: 140.26	P.Each	Rs: 3,506.00

Part 'B' TOTAL: Rs: **57,430.0**

Part 'A' TOTAL: Rs: **242,482.0**

TOTAL: Rs: **299,912.0**


XEN

Schedule-B

Name of Work:- **INTEGRATED REHABILITATION OF PRIMARY / MIDDLE /
ELEMENTARY SCHOOLS TALUKA RATODERO (08 UNITS) @ GBPS
PANJOO LORIR TALUKA RATODERO DISTRICT LARKANA.**

S #	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.	492.00	@ Rs: 3,176.25	% OCft	Rs: 1,563
	(Thirty one Hundred seventy six rup: & twenty five paisa only)				
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10.(S.I No. 3(d) P/14)	390.00	@ Rs: 8,694.95	% Cft	Rs: 33,910
	(Eighty six hund: ninty four rup: & ninty five paisa only)				
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	678.00	@ Rs: 11,948.36	% Cft	Rs: 81,010
	(Eleven thousand nine hund: forty eight rup: & thirty six paisa only)				
4	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)	781.00	@ Rs. 2,206.60	% Cft	Rs. 17,234
	(Twenty tow hund: six rup: & sixty paisa only)				
5	Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)	781.00	@ Rs: 2,197.52	% Sft	Rs: 17,163
	(Twenty one hund: ninty seven rup: & fifty two paisa only)				
6	Making Notice board made with cement.	64.00	@ Rs: 58.11	P. Sft	Rs: 3,719
	(Fifty eight rupees & eleven paisa only)				
7	Cement concrete plain i/c placing, compacting, finishing & curing complete i/c screening & washing of stone aggregate without shuttering. Ratio 1:3:6.	11.00	@ Rs. 14,429.25	% Cft	Rs. 1,587
	(Fourteen thousand four hund: twenty nine rup: & twenty paisa only)				
8	Lying floor of approved white glazed tile 1/4" thick in white cement 1:2 over 3/4" thick cement mortar 1:2 complete.(S.I No. 23 P/45)	69.00	@ Rs. 27,678.86	% Cft	Rs. 19,098
	(Twenty seven thousand six hund:seventy eighty rup: & eighty six paisa only)				

XEN

S #	Description	Qty	Rate	Unit	Amount
9	White glazed tiles 1/4" thick dodo jointed in white cement & laid over 1:2 cement sand mortar 3/4" thick i/c finishing.(S.I No.24 P/45)	298.00	@ Rs. 28,253.61	% Cft	Rs. 84,196
	(Twenty seven thousand seven hund: forty seve rupp: & six paisa only)				
10	Providing and fixing iron steel grill door with angle iron frame of 1 1/2" x 1 1/2" x 1/4" and flat iron of 3/4" x 1/4" with approved design and locking arrangement embeded in Masonry as per instructions of Engineer in charg.(S.I No. 31 P No. 93)	213.00	@ Rs: 231.60	P. Sft	Rs: 49,331
	(Two Hund: Thirty One rupees & Sixty paisa only)				
11	Two coats of Bitumen laid hot using 34lbs, for % over with sand of one 3/4" thick. (S.I No. 13 P/34)	1325.00	@ Rs. 1,887.40	% Sft	Rs. 25,008
	(Eighteen hundred eighty seven rupees & forty paisa only)				
12	Providing and Laying 1" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)	760.00	@ Rs: 4,411.82	% Sft	Rs: 33,530
	(Forry four hundred eleven rup: & eighty two paisa only)				
(B)	2" Thick C.C.	104.00	@ Rs: 3,275.50	% Sft	Rs: 3,407
	(Thirty two hundred seventy five rup: & fifty paisa only)				
13	P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools and pla	36.00	@ Rs: 228.90	P. Rft	Rs: 8,240
	(Two hundred twenty eight rupees & ninty paisa only)				
14	P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools and pla	240.00	@ Rs: 240.50	P. Rft	Rs: 57,720
	(Two hundred forty rupees & fifty paisa only)				
15	1" class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25 P/60)	187.00	@ Rs: 902.93	P. Sft	Rs: 168,848
	(Nine hund: two rup: & ninty three paisa only)				
16	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)	11.00	@ Rs: 337.00	P.Cft	Rs: 3,707
	(Three hundred Thirty seven rup: only)				


XEN

S #	Description	Qty	Rate	Unit	Amount
17	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I .No. 8 (b) P/16)	0.491	@ Rs: 5,001.70	P.Cwt	Rs: 2,456
	(Five thousand one rup: & seventy paisa only)				
18	Primary coat of chalk distemper(S.I No. 23 P/53)	529.00	@ Rs: 442.75	% Sft	Rs: 2,342
	(Four hundred forty two rupees & seventy five paisa only)				
19	Distempering two coats.(S.I No. 24(b) P/54)	529.00	@ Rs: 1,043.90	% Sft	Rs: 5,522
	(One thousand forty three rup: & ninty paisa only)				
20	Preparing surface & painting with weather coat i/c rubbing the surface with rubbing brick / sand paper filling the voids with chalk / plaster then painting with weather coat of approved make(New surface)(S.I No.38 (a) P/55)	2511.00	@ Rs: 1,948.10	% Sft	Rs: 48,917
	(Nineteen hundred forty eight rupees & ten paisa only)				
21	Prepairng surface and painting of doors and widows any type, (including edges) (3 coats) (new surface) (S.I.No: 4 (c) P. 76 (ii)),	374.00	@ Rs: 2,116.41	% Sft	Rs: 7,915
	(Twenty one hundred sixteen rup & forty one paisa only)				
22	Preparing surface & painting Guard bars, gates / iron bars gating rakings i/c standard braces etc & similar open work.	96.00	@ Rs. 1,270.83	% Sft	Rs. 1,220
	(Twelve Hundred seventy rupees & eithy three paisa only)				
23	Supply and fixing sand under floor including plugging in to walls	1900.00	@ Rs: 1,141.05	% Cft	Rs: 21,680
	(Eleven hundred forty one rupees & five paisa only)				
Total Rs.					699,322


XEN

S.#	Description	Rate	Unit	Qty	Amount
PART - B					
1	P/F squatting type white glazed earthen ware W.C pan of with i/c cost of flushing cistern with internal fitting & flush pipe with bend making good in cement concrete 1:2:4. (i) W.C not less than 19" clear opening b/w flushing & 6 gallons flushing tank with	2.00 @ Rs: 4,846.80	P. No.	Rs.	9,694
		(Forty eight hundred forty six rup: & eighty paisa only)			
2	P/F 22"x16" lavatory basin in white glazed earthen ware complete with & i/c the cost of W.I & C.I cantilever brackets 6 inches built into walls painted white in two coats after a primary cost of red lead painted & pair of 1/2" dia etc & making requisite n	1.00 @ Rs: 4,694.80	P. No.	Rs.	4,695
		(Forty six hundred ninty four rupees & eighty paisa only)			
3	P/F 6"x6" C.I Floor Trap of the approved self cleaning & C.I secured down grating holes in walls plinth & floor for pipe connection & making good in C.C 1:2.4.	3.00 @ Rs: 2,042.40	P. No.	Rs.	6,127
		(Two thousand Forty Two rup: Forty Three Pessa only)			
4	P/F in position Nyloon connections complete with 1/2" dia brass stop cock with pair of brass nuts lining joints to Nyloon connections.	2.00 @ Rs: 447.15	P. No.	Rs.	894
		(Four hundred forty seven rup: & fifteen paisa only)			
5	P/F 4" dia C.I soil vent pipe i/c cutting, fitting & extra painting to match the colour of the building.	12.00 @ Rs: 666.21	P. Rft	Rs.	7,995
		(Six hundred Sixty Six rup: & Twenty One paisa only)			
6	P/F 4"x4"x4" dia C.I branch of the required degree with access doors, rubber washer 1/4" thick & bolts & nuts & extra painting to match the colour of the building.	2.00 @ Rs: 270.60	P. No.	Rs.	541
		(Two hundred seventy rupees & sixty paisa only)			
7	Providing G.I pipe specials & clamps etc i/c fixing, cutting & fitting complete two coats of after cleaning the pipe etc with white zink paint with pigment to match the colour of the				
(A)	<u>1/2" dia</u>	12.00 @ Rs: 76.21	P. Rft	Rs.	915
		(Seventy Three rupees & twenty paisa only)			
(B)	<u>3/4" dia</u>	25.00 @ Rs: 95.79	P. Rft	Rs.	2,395
		(Ninty five rupees seventy nine paisa only)			
8	P/F 4" dia C.I terminal guard i/c extra painting to match the colour of the building.	2.00 @ Rs: 689.70	P. No.	Rs.	1,379
		(Three hundred eighty nine rupees & seventy paisa only)			
9	P/F full way gun metal valves with whelds threaded of flanged endswith rubber washing	1.00 @ Rs: 197.12	P. No.	Rs.	197
		(one hundred ninty seven rupees & twelve paisa only)			
10	S/F C.P brass bib cock 1/2" dia standard pattern.	1.00 @ Rs: 667.92	P. No.	Rs.	668
		(Three hundred thirty seven rupees & ninty two paisa only)			

XEN

SCHEDULE-B

Name of work: Integrated Rehabilitaiton of Primary / Middle / Elementary Schools Taluka Dokri & Bakrani At: GBPS Ghazi Jhatiyal Taluka Dokri (C.Wall +Toilet)

S.No	Discription	Quantity	@RS:	Rate	Unit	Rs:	Amount.
1	Dismenlin Pacca brick work in cement mortor	372.00	@Rs: 1285.63	%CFT Rs:			4,783 (Rs: Twolve thousand Eighty Five & P.S Sixty Three only)
2	Dismenlin C C plain 1:2:4. (S.I.No 19 (c) P/11).	159.00	@Rs: 3327.50	P.SFT Rs:			5,291 (Rs: Three thousand Three Hundred Twenty Seven & P.S Fift
3	Removing Cement or Lime Plaster	1459.00	@Rs: 121.00	%CFT Rs:			1,765 (Rs: One Hunared Twenty One only)
4	Dismenling 2nd Class Tiles Roofing Consisting	1144.00	@Rs: 378.13	%CFT Rs:			4,326 (Rs: One Hunared Twenty One only)
5	Excavation in foundation of building bridges and other structure member with excavated lead upto one chain and lift upto 5" ft in ordingay soil (S I No: 18p4).	325.00	@Rs: 3176.25	%0CF Rs:			1,032 (Three Thousand One Hund:Sevnty Six & P.S Twenty Five
6	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P/16).	298.00	@Rs: 8694.95	%CFT Rs:			25,911 (Eight Thousand Six Hund:Ninty Four & P.S Ninty five only)
7	Pacca brick work in foundation and plinth in cement sand mortor ration 1:6 (S.I No 4 (C) 23	803.00	@Rs: 11948.36	%SFT Rs:			95,945 (Eleven Thousand Nine Hund: Fourty Eight & P.S Thirty Si:
8	S/F sand floor and plugging into walls (S.I.No 29 P/31).	1826.00	@Rs: 1141.25	%CFT Rs:			20,839 (Rs:One Thousand One Hund: Fourty One & P.S Twenty Five
9	Pacca brick work in Ground floor i/c striking of joints cement sand mortor Ratio 1:6 (S.I No 5 (C) P/24)	119.00	@Rs: 12674.36	%CFT Rs:			15,082 (Twlove thousand Six Hundred Sevnty Four & Thirty Six or
10	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast: laid in position complete in all respect ratio 1:2:4 (S.I No. 6 (a) P/18)	125.00	@Rs: 337.00	P.CFT Rs:			42,125 (Three Hundred Thirty Seven only)
11	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/20)	5.580	@Rs: 5001.70	P.CWI Rs:			27,909 (Five Thousand One &P.S Seventy).
12	Pacca brick work in other than building i/c striking of joints cement sand mortor Ratio 1:6 (S.I No 5 (C) F	373.00	@Rs: 12346.65	%CFT Rs:			46,053 (Tolve Thousand Three Hundred Fourty Six & P.S Sixty Five



S.No	Description	Quantity	@RS:	Rate	Unit	Rs:	Amount.
13	Cement plaster 1:6 upto 20' ft; height 1/2" thick. (S.I No.13 P/57)	3043.00	@Rs: 2206.60	%SFT	Rs:	67,147	(Two hundred Three Hund: Fifty Six & P.S Seventy Eight or
14	Cement plaster 1:4 upto 20' ft; height 3/8" thick. (S.I No: 11(a) P 57)	3043.00	@Rs: 2197.52	%SFT	Rs:	66,871	(Two Twousand One Hund: Ninty Seven & P.S Fifty Two oni
15	Cement pointing and striking of joints on walls ratio 1: 2 (S.I No. 19 (a) P/53)	990.00	@Rs: 1287.44	%CFT	Rs:	12,746	(Twolve Thousand Eighty Seven & P.S Fourty Four only)
11	Supplying Girders at site of work(Sch: of Material)	3.535	@Rs: 3575 00	P.RFT	Rs:	12,638	(Three Thousand Eight Hundred Fifty only)
12	Supplying T-iron at site of work (Sch: of Material).	8.642	@Rs: 3850.00	P.RFT	Rs:	33,272	(Three Thousand Three Hundred Seventy Five only)
13	First class tiles roofing consisting of 4" earth and 1" plaster with Gobri leaping over 1/4" thick cement pla 1:6 with 34lbs: of bituumen coating sand blinded provided over 2 layers of tiles 12"x6" 1 1/4" laid in 1:6 cer mortar with 1/4" thick sand of tiles complete i/c currin etc complete (S.I.No 1 P/38)	1144.00	@Rs: 11443.10	%SFT	Rs:	130,909	(Rs.Eleven thousand Four Hundred Fourty Three & P.S Ten)
14	P/L 1" thick cement concrete topping 1:2.4 i/c surface finishing and dividing into paenls Ration 3' thick. (S	994.00	@Rs: 4411.82	%SFT	Rs:	43,853	(Rs: Four Thousand Four Hundred Eleven & P.S Eighty Two
15	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4thicks.(Only Shutters)	18.00	@Rs: 902.93	%CFT	Rs:	16,253	(Nine Hundraed Two P.S Ninty Three only)
16	White wash three coats (S.I.No 26 (c) 59).	968.00	@Rs: 829.95	P.SFT	Rs:	8,034	(Rs: Four Hundred Twenty Five & P.S Eighty Four only)
17	Primary coat of chalk under distemping (S.I No: 23 P 59)	7307.00	@Rs: 442.75	%SFT	Rs:	32,352	(Four Hundred Fourty Two & P.S Seventy Five only)
18	Distemping three coats, (S I No 24 (b) P/59)	7307.00	@Rs: 1079.65	%SFT	Rs:	78,890	(Rs: One Thousand Seventy Nine & P.S Sixty Five only)
19	Painting doors & Window any type.	374.00	@Rs: 2116.41	%CFT	Rs:	7,915	(Rs: One Two Thousand one Hund: Sixteen & P.S Fourty Or
20	Preparing surface painting guards bars gates iron grating railing i/c standards brass etc similar open work (S I No 4 d P/76 ii)	96.00	@Rs: 1270.83	%CFT	Rs:	1,220	(Rs: Five Hundred Eighty Five & Fifty Four only)

Grand Total:- Rs: 803,161


XEN

Part B

- 1 P/F Squating type white glass W.C pan of i/c coat of finishing cistring with internal fitting & Flush Pipe between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thur
2.0 @ Rs: 4846.60 P.No: Rs: 9694.00
- 2 P/F & 22"x16" Lavatory basin in white glazed earthen ware complete with & i/c the cost of W.I conntilever brackets 6 inch built into walls painted white in two cost after a primary cost of red land plinth a pair of 1/4" dia chrome plate pillar trape 1-1/2" dia P3
1.0 @ Rs: 4694.80 P.No: Rs: 4695.00
- 3 P/F 6"x2" or 6"x3" C.I floor tape
3.0 @ Rs: 2042.43 P.No: Rs: 6073.00
- 4 P/F in position nyloon connection complete with 1/2" dia brass stop cock with pair brass nuts lining joints to nyloon coonections
2.0 @ Rs: 77.85 P.No: Rs: 894.00
- 5 P/F 4" dia C.I soil and vent pipe i/c cutting fitting and extra painting to match the colour of t
12.0 @Rs: 333.21 P.RFT Rs: 3999.00
- 6 P/F 4"x4" dia C.I branch of the required degree with access doors rubber washer 3/8" thick and bolts and unts and extra painting to match the colour of the building.
2.0 @ Rs: 270.60 P/No Rs: 541.20
- 7 Providing G.I pipe specials and clamps etc i/c fixing cutting fitting complete two coats of after cleaning the pipe etc with white zink paint with pigment to machi the colour of lthe building and testing pressure head of 200' and handling.
(A) 1/2" dia
25.00 @ Rs: 73.21 PRft Rs: 1830.00
(B) 3/4" dia
50.00 @ Rs: 95.79 PRft Rs: 4790.00
- 8 Providing and fixing 4" dia C.I terminal guard i/c extra painting to match the colour of the colour of the building.
2.0 @ Rs: 389.70 PRft Rs: 779.00
- 9 Providing and fixing full way gun metal valves with whelds threaded of flanged ends with rubber washing.(ii)3/4" (Light pattern)
1.0 @ Rs: 197.12 P.No Rs: 197.00
- 10 P/F C P Brass bib cock 1/2 " Dia
2.00 @ Rs: 337.92 P No Rs: 676.00
- 11 Providing RCC pipe with colors class"B" & dying trenches to required depth & fixing in position & Cement Morter 1:1 & test staff (a) 4"Dia Refilling with excavted staff.
4"Dia
24.00 @ Rs: 146.57 Each Rs: 3518.00
6"Dia
12.00 @ Rs: 199.25 Each Rs: 2391.00


XEN

12	S/F Conceled stop cock of superior quality with C.P head 1/2"Dia				
	2.00	@ Rs: 478.28	P.No	Rs:	957.00
13	S/F Long bib-cock of superior quality with C.P head 1/2" Dia				
	1.00	@ Rs: 1109.46	P.No	Rs:	1109.00
11	P/F approved quality AC Motor pumping set(Javed Engineering) Made etc.				
	1 No.	@ Rs: 5115	P.No:	Rs:	5115.00
15	S/F Fibre glass tank of approved quality and design and wall thickness as specified i/c the cost of nuts and bolts and fixing in plate form of cement concrete 1:2:6 and making connection for inlet-outlet and over flow pipe etc complete. (250 Gallons).				
	1.0	@Rs: 21989.61	P.Gallan:	Rs:	13193.00
16	Hand pump all accessoried i/c fitting and fixing with local made coir strainer with wooden shoe i/c the complete.				
A	<u>Filter.</u>				
	10.0	@ Rs: 76.05	P.Rft	Rs:	761.00
B	<u>G.I pipe</u>				
	40.0	@Rs: 38.95	P.Rft	Rs:	3506.00
C	<u>Machine</u>				
	1 No.	@Rs: 1441.65	P.No:	Rs:	1442.00
					TOTAL Rs: 64131.00


XEN

SCHEDULE "B"

**IMPROVEMENT/PROVISION OF MISSING FACILITIES IN
FIELD OFFICES OF EDUCATION & LITERACY DEPARTMENT
DISTRICT LARKANA @ TEC (FEMALE) OFFICE RATODERO**

S.No:	Description	Qty:	Rate	Unit	Amount
1	Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).	816.00	@ Rs: 3176/25	% 0 Cft	Rs: 2,591.00 (Rs: three thous: one hund: seventy hund: twenty five only)
2	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No: P/).	245.00	@ Rs: 8694/95	% Cft	Rs: 21,302.00 (Rs: eight thous: six hund: ninty four & ninty five only)
3	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)	665.00	@ Rs:11948/36	% Cft	Rs: 79,456.00 (Rs: eleven thous: nine hund: eighty five & thirty six only)
4	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).	533.00	@ Rs:337/-	P.Cft	Rs: 179,621.00 (Rs: three hund: thirty seven only)
5	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)	26.00	@ Rs:5001/70	P.Cwt	Rs: 130,044.00 (Rs: five thous: one & seventy only)
6	Supplying and filling sand under floor and plugging in walls.(S.I.No: 29 P/25).	1272.00	@ Rs: 1141/25	% Cft	Rs: 14,516.00 (Rs: one thous: one hund: forty one & twenty five only)
7	Extra lead 3.0 miles	1272.00	@ Rs: 579/41	% Cft	Rs: 7,370.00 (Rs: five hund: sevnty nine & fourty one only)
8	Providing and laying single per layer of polythene sheet 0.13 mm thick for water proffing as per specification and instruction of Engineer incharge. (S.I.No: 38 P/37).	13.00	@ Rs:10/70	P.Sft	Rs: 1,744.00 (Rs: ten & seventy only)

S.No:	Description	Qty:	Rate	Unit	Amount
9	Dry rammed brick or stone ballast 1 1/2" to 2" guage. (S.I.No.2 P/14).				
		137.00	@ Rs: 3327/50	% Cft	Rs: 4,558.00
			(Rs: three thous: two hund: twenty seven & fifty only)		
10	Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).				
		1077.00	@ Rs:12674/36	% Cft	Rs: 136,502.00
			(Rs: twelve thous: six hund: seventy four & thirty six only)		
11	P/F G.I Frame / Chowkats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:8 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: P.).				
		28.00	@ Rs:228/90	P.Rft	Rs: 6,409.00
			(Rs: two hund: twenty eight & ninty only)		
12	P/F G.I Frame / Chowkats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:8 and repairing the jambs. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: 29 P. 98).				
		114.00	@ Rs: 240/50	P.Rft	Rs: 27,417.00
			(Rs: two hund: forty & fifty only)		
13	Suppling M.S square, bar 5/8" dia (Sch: of matrial).				
		1.00	@ Rs: 3350/-	P.Cwt	Rs: 3,550.00
			(Rs: three thous: three hund; fifty only)		
14	Cutting and fixing iron bars for barred windows. (S.I.No.18 P/97).				
		26.00	@ Rs: 28/23	P.Bar	Rs: 733.00
			(Rs: twenty eight & twenty five only)		
15	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1 3/4" thick. (Only Shutters).				
		72.00	@ Rs: 902/93	P.Sft	Rs: 65,010.00
			(Rs: nine hud: two & ninty three only)		
16	Cement plaster 1:5 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).				
		2013.00	@ Rs:2206/60	% Sft	Rs: 44,418.00
			(Rs: two thous: two hund: six & sixty only)		
17	Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).				
		1981.00	@ Rs:2197/52	% Sft	Rs: 43,532.00
			(Rs: two thous: one hund: ninty seven & twenty two only)		

S.No:	Description	Qty:	Rate	Unit	Amount
18	Cement pointing strucking joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).	829.00	@ Rs:1287/44	% Sft	Rs: 8,097.00
					(Rs: one thous: two hund: eighty seven & forty four only)
19	Notice board made with cement. (S.I.No: 1 P/94)	31.00	@ Rs: 58/11	P.Sft	Rs: 1,859.00
					(Rs: fifty eight & eleven only)
20	Providing and laying 1" thick topping cement concrete (1:2:4) including surface finishing and dividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).	440.00	@ Rs: 4411/82	% Sft	Rs: 19,412.00
					(Rs: four thous: four hund: eleven & eighty two only)
(B)	<u>1-1/2" Thick</u>	716.00	@ Rs: 2548/29	% S.ft	Rs: 18,245.00
					(Rs: two thous: five hund: forty eight & twenty nine only)
21	Providing and fixing ornamental cement jalli 2" thick. (1:2:4) with out steel. (S.I.No.11 P/17).	59.00	@ Rs:226/02	P.Sft	Rs: 13,335.00
					(Rs: two hund; twenty six & two only)
22	Two Coats of bituman laid hot using 34 Lbs for % Sft. Ober roof and blinded with sand at one Cft. Per % Sft. (S.I.No: 13 P/34).	715.00	@ Rs:1887/40	% Sft	Rs: 13,513.00
					(Rs: one thous: eight hund; eighty seven & fourteen only)
23	Primary coat of chalk distemping. (S.I.No.23 P/57).	2320.00	@ Rs:442/75	% Sft	Rs: 10,271.00
					(Rs: four hund; forty two & seventy five only)
24	Distemping three coats. (S.I.No.24 (c) P/53).	2320.00	@ Rs:1079/65	% Sft	Rs: 25,047.00
					(Rs: one thos: seventy nine & sixty five only)
(B)	<u>Two coats.</u>	440.00	@ Rs:1043/90	% Sft	Rs: 4,593.00
					(Rs: ten hund; forty three & ninty only)


XEN

S.No:	Description	Qty:	Rate	Unit	Amount
25	Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of paris and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).	317.00	@ Rs: 1948/10	%Sft	Rs: 6,175.00
					(Rs: one thous: nine hund: fourty eight & ten only)
26	Preparing surface and painting of doors and windows any type (including edges) (ii) Each subsequent coat of paint. (S.I.No.5 (c) P/69).	207.00	@ Rs:2116/41	%Sft	Rs: 4,380.00
					(Rs: two thous: one hund: sixteen & fourty one only)
				G.Total:	Rs: 893,700.00


XEN

Schedule-B**Rehabilitation of High /Higher Secondary Schools in Sindh
(2008-09 Programme) @ GBHS. (Main) Ratodero(Balance
Work) Taluka Ratodero District Larkano**

75

Name of
Work:-

257

S #	Description	Qty	Rate	Unit	Amount
1	Dismantling cement concrete reinforced separating reinforcement from concrete cleaning & straightening the same. (S.I No. 20 P/10)	34.00	@ Rs. 5,445.00	% Cft (Fifty four hundred & forty five rupees only)	Rs. 1,851
2	Dismantling brick work in lime or cement mortar. (S.I No.13 P/10)	143.00	@ Rs: 1,285.63	% Cft (Twelve hundred eighty five rup & sixty three paisa only)	Rs: 1,838
3	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.	126.00	@ Rs: 3,176.25	% 0Cft (Thirty one Hundred seventy six rup: & twenty five paisa only)	Rs: 400
4	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10. (S.I. No. 4 © P/14)	132.00	@ Rs: 8,694.95	% Cft (Eighty six hund: ninty four rup: & ninty five paisa only)	Rs: 11,477
5	Pacca brick work in Ground Floor i/c striking of joints in cement sand mortar ratio 1:6.	398.00	@ Rs. 12,674.36	% Cft (Twelve thousand six hundred seventy four rup: & thity six paisa only)	Rs. 50,444
6	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	285.00	@ Rs: 11,948.36	% Cft (Eleven thousand nine hund: forty eight rup: & thirty six paisa only)	Rs: 34,053
7	Supply and fixing sand under floor including plugging in to walls	726.00	@ Rs: 1,141.25	% Cft (Eleven hundred forty one rupees & twenty five paisa only)	Rs: 8,285
8	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)	45.00	@ Rs: 337.00	P.Cft (Three hundred Thirty seven rup: only)	Rs: 15,165
9	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I .No. 8 (b) P/16)	2.209	@ Rs: 5,001.70	P.Cwt (Five thousand one rup: & seventy paisa only)	Rs: 11,049
10	Making & fixing steel gated doors with 1 1/6" thick sheeting i/c angle iron frame 2"x2"x3/4" and square bars 4" centre to cement.	36.00	@ Rs. 726.72	P. Sft (Seven hundred twenty six rupees & seventy two paisa only)	Rs. 26,162



S #	Description	Qty	Rate	Unit	Amount
11	Providing and Laying 3" thick topping cement concrete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)	336.00	@ Rs: 4,411.82	% Sft	Rs: 14,821
	(Forry four hundred eleven rup: & eighty two paisa only)				
12	Providing & lying HALLA or pattern tiles glazed 8"x8"x1/4" on floor or wall facing in required floor & pattern of STILE specification jointed in white cement & pigment over a base of 1:2 grey cement mortar 3/4" thick etc i/c the cost of polish & cutting	96.00	@ Rs: 34,520.31	% Sft	Rs: 33,139
	(Thirty four thousand five hundred twenty rupees & thirty one paisa only)				
13	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)	773.00	@ Rs. 2,206.60	% Cft	Rs. 17,057
	(Twenty tow hund: six rup: & sixty paisa only)				
14	Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)	773.00	@ Rs: 2,197.52	% Sft	Rs: 16,987
	(Twenty one hund: ninty seven rup: & fifty two paisa only)				
15	Galvanized wire guage fixing to chowkats 3/4" deodar stips and screws (S.I No. 14 (C) P/69).	66.00	@ Rs. 190.72	P. Sft	Rs. 12,588
	(One hundred Ninety rupees & seventy two paisa only)				
16	Deodar wood dedo or picture rail 3" x1 1/4" as per approved design including mouldind and fixed in place, cost of screws, nail plugs & painting (S.I No. 31 P-61).	62.00	@ Rs. 354.60	P. Sft	Rs. 21,985
	(Three hundred Fifty Four rupees & Sixty paisa only)				
17	Two coats of Bitumen laid hot using 34lbs, for % over with sand of one 3/4" thick. (S.I No. 13 P/34)	1916.00	@ Rs. 1,887.40	% Sft	Rs. 36,163
	(Eighteen hundred eighty seven rupees & forty paisa only)				
18	1 st class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25 P/60)	88.00	@ Rs: 902.93	P. Sft	Rs: 79,458
	(Nine hund: two rup: & ninty three paisa only)				
19	Dismantling cement concrete reinforced separating reinforcement from concrete cleaning & straightening the same. (S.I No. 22 P/10)	788.00	@ Rs: 3,327.50	% Cft	Rs: 26,221
	(Thirty three hundred twenty seven rup:& fifty paisa only)				
20	Cement concrete plain i/c placing, compacting, finishing & curing complete i/c screening & washing of stone aggregate without shuttering. Ratio 1:3:6.	161.00	@ Rs. 14,429.25	% Cft	Rs. 23,231
	(Fourteen thousand four hund: twenty nine rup: & twenty paisa only)				
21	Providing & lying HALLA or pattern tiles glazed 6"x6"x1/4" on floor or wall facing in required floor & pattern of STILE specification jointed in white cement & pigment over a base of 1:2 grey cement mortar 3/4" thick etc i/c the cost of polish	883.00	@ Rs. 30,509.77	% Sft	Rs. 269,401
	(Thirty thousand five hund: nine rupees & seventy seven paisa only)				


XEN

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

22 Preparing surface & painting doors & windows etc complete. (Old Surface)

2762.00 @ Rs. 1,498.48 % Sft Rs. 41,388
 Twenty on hundred sixteen rupees & forty one paisa only)

23 Painting doors & Windows any type (Old surface).(S.I No. 4 (c) P/67)

760.00 @ Rs: 1,212.21 % Sft Rs: 9,213
 (Twelve hundred twelve rup :& twenty one paisa only)

24 Preparing surface & painting Guard bars, gates / iron bars gating rakings i/c standard braces etc & similar open work.

72.00 @ Rs. 1,270.83 % Sft Rs. 915
 (Twelve Hundred seventy rupees & eithy three paisa only)

Total Rs: 763,294


 XEN

S.#	Description	Rate	Unit	Qty	Amount
-----	-------------	------	------	-----	--------

PART - B

1	P/F squatting type white glazed earthen ware W.C pan of with i/c cost of flushing cistern with internal fitting & flush pipe with bend making good in cement concrete 1:2:4.(i) W.C not less than 19" clear opening b/w flushing & 6 gallons flushing tank with	5.00 @ Rs: 4,846.80	P. No.	Rs.	24,234
		(Forty eight hundred forty six rup: & eighty paisa only)			
2	P/F 22"x16" lavatory basin in white glazed earthen ware complete with & i/c the cost of W.I & C.I cantilever brackets 6 inches built into walls painted white in two coats after a primary cost of red lead painted & pair of 1/2" dia etc & making requisite n	1.00 @ Rs: 4,694.80	P. No.	Rs.	4,695
		(Forty six hundred ninty four rupees & eighty paisa only)			
6	P/F 6"x6" C.I Floor Trap of the approved self cleaning & C.I secured down grating holes in walls plinth & floor for pipe connection & making good in C.C 1:2:4.	5.00 @ Rs: 2,042.43	P. No.	Rs.	10,212
		(Two thousand forty two rup:& forty three paisa only)			
4	P/F in position Nyloon connections complete with 1/2" dia brass stop cock with pair of brass nuts lining joints to Nyloon connections.	5.00 @ Rs: 447.15	P. No.	Rs.	2,236
		(Four hundred forty seven rup: & fifteen paisa only)			
5	P/F 4" dia C.I soil vent pipe i/c cutting, fitting & extra painting to match the colour of the building.	24.00 @ Rs: 666.21	P. Rft	Rs.	15,989
		(Three hundred thirty three rup: & nineteen paisa only)			
6	P/F 4"x4"x4" dia C.I branch of the required degree with access doors, rubber washer 1/4" thick & bolts & nuts & extra painting to match the colour of the building.	5.00 @ Rs: 270.60	P. No.	Rs.	1,353
		(Two hundred seventy rupees & sixty paisa only)			
7	Providing G.I pipe specials & clamps etc i/c fixing, cutting & fitting complete two coats of after cleaning the pipe etc with white zink paint with pigment to match the colour of the building & testing the pressure head of 200" & handling.				
(A)	1" dia	50.00 @ Rs: 76.21	P. Rft	Rs.	3,811
		(Seventy Six rupees & twenty one paisa only)			
(B)	6/4" dia	75.00 @ Rs: 95.79	P. Rft	Rs.	7,184
		(Ninty five rupees seventy nine paisa only)			
8	P/F 4" dia C.I terminal guard i/c extra painting to match the colour of the building.	1.00 @ Rs: 689.70	P. No.	Rs.	690
		(Six hundred eighty nine rupees & seventy paisa only)			


XEN

S.#	Description	Rate	Unit	Qty	Amount
9	P/F full way gun metal valves with whelds threabed of flanged endswith rubber washing 6/4" standard pattern.	1.00 @ Rs: 197.12	P. No.	Rs.	197
	(one hundred ninty seven rupees & twelve paisa only)				
10	S/F C.P.brass bib cock 1/2" dia standard pattern.	5.00 @ Rs: 337.92	P. No.	Rs.	1,690
	(Three hundred thirty seven rupees & ninty two paisa only)				
11	Providing RCC pipe with collars class "B" & digging the benches to required depth & fixing in				
(A)	<u>4" Dia</u>	60.00 @ Rs: 146.57	P. Rft	Rs.	8,794
	(One hundred forty six rupees & fifty seven paisa only)				
(B)	<u>6" Dia</u>	40.00 @ Rs: 199.25	P. Rft	Rs.	7,970
	(One hundred & Ninty nine paisa only)				
12	S/F concealed stop cock of superior quality with C.P head 1/2" dia.	5.00 @ Rs: 478.28	P. No.	Rs.	2,391
	(Four hundred Seventy eight rupees & twenty eight paisa only)				
16	S/F long bib cock of superior quality with C.P head 1/2" dia.	5.00 @ Rs: 1,109.46	P. No.	Rs.	5,547
	(Eleven hundred nine rupees & forty six paisa only)				
14	P/F approved quality A.C motor pumping set (Javed Engineering) made 1-1/4" 1" section &	1.00 @ Rs: 5,115.00	P. No.	Rs.	5,115
	(Fifty one hundred fifteen rupees only)				
15	S/F Fibre Glass Tank of approved quality & design & wall thickness as specified i/c the cost of nuts, bolts & fixing in plate form of cement concrete 1:2:6 & making connection for inlet-outlet & over flow pipe etc complete. (150 Gallons).	150.00 @ Rs: 87.95	P. Gallon	Rs.	13,193
	(Eighty Seven rupees & ninety five paisa only)				
16	Hand pump with all accessories i/c fitting & fixing with local made coir strainer with wooden shoe etc complete.				
(a)	Filter	10.00 @ Rs: 76.05	P. No.	Rs.	761
	(Seventy six rupees & five paisa only)				
(b)	G.I Pipe	70.00 @ Rs: 68.95	P. Rft	Rs.	4,827
	(Thirty eight rupees & ninty five paisa only)				
(c)	Machine	1.00 @ Rs: 1,441.60	P. No.	Rs.	1,442
	(Fourteen hundred forty one rup: & sixty paisa only)				
	Total Rs.				122,329
	N.S.I Rs.				10,824
	Total S.I Rs.				111,505



Schedule-B

76

**REHABILITATION OF EXISTING HIGH / HIGHER SECONDARY SCHOOLS IN
SINDH (250 UNITS) (2008-09 PROGRAMME) (12 UNITS FOR DISTRICT
LARKANO) @ GGHS. GARHI GHUDA BUX BHUTTO TALUKA RATODERO
DISTRICT LARKANO.**

Name of Work:-

S #	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.	354.00	@ Rs: 3,176.25	% 0Cft	Rs: 1,124
	(Thirty one Hundred seventy six rup: & twenty five paisa only)				
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10.(S.I No. 3(d) P/14)	549.36	@ Rs: 8,694.95	% Cft	Rs: 47,767
	(Eighty six hund: ninty four rup: & ninty five paisa only)				
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	146.49	@ Rs: 11,948.36	% Cft	Rs: 17,503
	(Eleven thousand nine hund: forty eight rup: & thirty six paisa only)				
4	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)	74.00	@ Rs: 337.00	P.Cft	Rs: 24,938
	(Three hundred Thirty seven rup: only)				
5	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I .No. 8 (b) P/16)	3.48	@ Rs: 5,001.70	P.Cwt	Rs: 17,410
	(Five thousand one rup: & seventy paisa only)				
6	Pacca brick work other than building i/c striking of joints in cement sand mortar ratio 1:6.	126.00	@ Rs. 12,346.65	% Cft	Rs. 15,557
	(Twelve thousand three hund: forty six rup: & sixty five paisa only)				
7	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)	989.50	@ Rs. 2,206.60	% Cft	Rs. 21,834
	(Twenty tow hund: six rup: & sixty paisa only)				
8	Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)	989.50	@ Rs: 2,197.52	% Sft	Rs: 21,744
	(Twenty one hund: ninty seven rup: & fifty two paisa only)				
9	Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)	236.25	@ Rs: 1,287.44	% Sft	Rs: 3,042
	(Twelve hundred eighty seven rupees & forty for paisa only)				

XEN

S #	Description	Qty	Rate	Unit	Amount
10	Preparing surface & painting doors & windows etc complete. (New Surface)	701.60	@ Rs. 1,948.10	% Sft	Rs. 13,668
	(Nineteen Hundred Forty Eight rupees & Ten paisa only)				
11	Supply and fixing sand under floor including plugging in to walls	1420.25	@ Rs. 1,141.25	% Cft	Rs: 16,209
	(Eleven hundred forty one rupees & twenty five paisa only)				
12	Providing and Laying 3" thick topping cement concrete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)	613.75	@ Rs. 4,411.82	% Sft	Rs: 27,078
	(Forry four hundred eleven rup: & eighty two paisa only)				
(B) 2" Thick First Floor					
		42.00	@ Rs. 3,275.50	% Sft	Rs: 1,376
	(Thirty two hundred seventy five rup: & fifty paisa only)				
13	Providing & lying HALLA or pattern tiles glazed 8"x8"x1/4" on floor or wall facing in required floor & pattern of STILE specification jointed in white cement & pigment over a base of 1:2 grey cement mortar 3/4" thick etc i/c the cost of polish & cutting	42.00	@ Rs. 34,520.31	% Sft	Rs: 14,499
	(Thirty four thousand five hundred twenty rupees & thirty one paisa only)				
14	P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools and pla	17.00	@ Rs. 228.90	P. Rft	Rs: 3,891
	(Two hundred twenty eight rupees & ninty paisa only)				
15	P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools and pla	180.00	@ Rs. 240.50	P. Rft	Rs: 43,290
	(Two hundred forty rupees & fifty paisa only)				
16	1 st class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25 P/60)	50.00	@ Rs. 902.93	P. Sft	Rs: 45,147
	(Nine hund: two rup: & ninty three paisa only)				
17	Primary coat of chalk distemper(S.I No. 23 P/53)	153.00	@ Rs. 442.75	% Sft	Rs: 677
	(Four hundred forty two rupees & seventy five paisa only)				

**J
XEN**

S #	Description	Qty	Rate	Unit	Amount
18	Distempring Two Coats (S.I No. 24 ©P/53)	153.00	@ Rs. 1,043.90	% Sft	Rs: 1,597
	(One thousand Seventy nine rup: & sixty five paisa only)				
16	Supply & Fixing in Position iron/steer grill of 3/4" X 1/4" Size flat iron of approved design including painting 3 coats etc. complete (weight not to be less than 3.7 Lbs./Sq. Foot of finished grill).(S.I No. 26 P/92)	3.00	@ Rs. 180.50	P. Sft	Rs: 542
	(One hundre eighty rupees & fifty paisa only)				
17	Cement concrete plain i/c placing, compacting, finishing & curing complete i/c screening & washing of stone aggregate without shuttering. Ratio 1:3:6.	3.40	@ Rs. 14,429.25	% Cft	Rs. 491
	(Fourteen thousand four hund: twenty nine rup: & twenty paisa only)				
18	Lying floor of approved white glazed tile 1/4" thick in white cement 1:2 over 3/4" thick cement mortar 1:2 complete.(S.I No. 23 P/45)	20.00	@ Rs. 27,678.86	% Cft	Rs. 5,536
	(Twenty seven thousand six hund:seventy eighty rup: & eighty six paisa only)				
19	White glazed tiles 1/4" thick dodo jointed in white cement & laid over 1:2 cement sand mortar 3/4" thick i/c finishing.(S.I No.24 P/45)	54.00	@ Rs. 28,253.61	% P.Cwt	Rs. 15,257
	(Twenty seven thousand seven hund: forty seve rupp: & six paisa only)				
20	Preparing surface & painting Guard bars, gates / iron bars gating rakings i/c standard braces etc & similar open work.	35.00	@ Rs. 1,270.83	% Sft	Rs. 445
	(Twelve Hundred seventy rupees & eihthy three paisa only)				
21	Two coats of Bitumen laid hot using 34lbs, for % over with sand of one 3/4" thick. (S.I No. 13 P/34)	700.00	@ Rs. 1,887.40	% Sft	Rs. 13,212
	(Eighteen hundred eighty seven rupees & forty paisa only)				

Total Rs: 373,831


XEN

S.#	Description	Rate	Unit	Qty	Amount
PART - B					
1	P/F squatting type white glazed earthen ware W.C pan of with i/c cost of flushing cistern with internal fitting & flush pipe with bend making good in cement concrete 1:2:4.(i) W.C not less than 19" clear opening b/w flushing & 6 gallons flushing tank with	2.00 @ Rs: 4,846.80	P. No.	Rs.	9,694
	(Forty eight hundred forty six rup: & eighty paisa only)				
2	P/F 22"x16" lavatory basin in white glazed earthen ware complete with & i/c the cost of W.I & C.I cantilever brackets 6 inches built into walls painted white in two coats after a primary cost of red lead painted & pair of 1/2" dia etc & making requisite n	2.00 @ Rs: 4,694.80	P. No.	Rs.	9,390
	(Forty six hundred ninty four rupees & eighty paisa only)				
3	P/F 6"x6" C.I Floor Trap of the approved self cleaning & C.I secured down grating holes in walls plinth & floor for pipe connection & making good in C.C 1:2:4.	2.00 @ Rs: 2,042.46	P. No.	Rs.	4,085
	(Two thousand fourty two rup: forty six pessa only)				
4	P/F in position Nyloon connections complete with 1/2" dia brass stop cock with pair of brass nuts lining joints to Nyloon connections.	2.00 @ Rs: 447.15	P. No.	Rs.	894
	(Four hundred forty seven rup: & fifteen paisa only)				
5	P/F 4" dia C.I soil vent pipe i/c cutting, fitting & extra painting to match the colour of the building.	4.00 @ Rs: 666.21	P. Rft	Rs.	2,665
	(Six hundred Sixty Six rup: & Twenty One paisa only)				
6	P/F 4"x4"x4" dia C.I branch of the required degree with access doors, rubber washer 1/4" thick & bolts & nuts & extra painting to match the colour of the building.	1.00 @ Rs: 270.60	P. No.	Rs.	270
	(Two hundred seventy rupees & sixty paisa only)				
7	Providing G.I pipe specials & clamps etc i/c fixing, cutting & fitting complete two coats of after cleaning the pipe etc with white zink paint with pigment to match the colour of the				
(A)	<u>1/2" dia</u>	12.00 @ Rs: 76.21	P. Rft	Rs.	915
	(Seventy six rupees & twenty paisa only)				
(B)	<u>6/4" dia</u>	20.00 @ Rs: 95.79	P. Rft	Rs.	1,916
	(Ninty five rupees seventy nine paisa only)				
8	P/F 4" dia C.I terminal guard i/c extra painting to match the colour of the building.	1.00 @ Rs: 689.70	P. No.	Rs.	690
	(Three hundred eighty nine rupees & seventy paisa only)				
9	P/F full way gun metal valves with whelds threabed of flanged endswith rubber washing 6/4" standard pattern.	1.00 @ Rs: 197.12	P. No.	Rs.	197
	(one hundred ninty seven rupees & twelive paisa only)				



S.#	Description	Rate	Unit	Qty	Amount
10	S/F C.P brass bib cock 1/2" dia standard pattern. 2.00 @ Rs: 337.92 P. No. Rs. (Three hundred thirty seven rupees & ninty two paisa only)				676
11	Providing RCC pipe with collars class "B" & digging the benches to required depth & fixing in position i/c cutting, fitting & jointing with mexphalt composition & cement mortar 1:1 & testing with water pressure to a head of 4" ft above the top of the high				
(A)	<u>4" Dia</u> 12.00 @ Rs: 146.57 P. Rft Rs. (One hundred forty six rupees & fifty seven paisa only)				1,759
(B)	<u>6" Dia</u> 20.00 @ Rs: 199.25 P. Rft Rs. (One hundred Ninety nine rupees & twenty five paisa only)				3,985
12	S/F concealed stop cock of superior quality with C.P head 1/2" dia. 1.00 @ Rs: 478.28 P. No. Rs. (Four hundred Seventy eight rupees & twenty eight paisa only)				478
13	S/F long bib cock of superior quality with C.P head 1/2" dia. 1.00 @ Rs: 1,109.46 P. No. Rs. (Eleven hundred nine rupees & forty six paisa only)				1,109
14	P/F approved quality A.C motor pumping set (Javed Engineering) made 1-1/4" 1" section & delivery with base & complying 1 H.Power single phase motor (Siemens make) 60" ft head of 2800 KPM i/c the cost of C.I fitting nuts, bolts & the cost of 1:2:4 plate f 1.00 @ Rs: 5,115.00 P. No. Rs. (Fifty one hundred fifteen rupees only)				5,115
15	S/F Fibre Glass Tank of approved quality & design & wall thickness as specified i/c the cost of nuts, bolts & fixing in plate form of cement concrete 1:2:6 & making connection for inlet-outlet & over flow pipe etc complete. (250 Gallons). 1.00 @ Rs: 21,988.00 P. Gallon Rs. (Twenty one thousand nine hundred eighty nine rup: & sixty one paisa only)				21,988
16	Hand pump with all accessories i/c fitting & fixing with local made coir strainer with wooden shoe etc complete.				
(a)	<u>Filter.</u> 10.00 @ Rs: 76.05 P. No. Rs. (Seventy six rupees & five paisa only)				761
(b)	<u>G.I Pipe.</u> 70.00 @ Rs: 68.95 P. Rft Rs. (Thirty eight rupees & ninty five paisa only)				4,827
(c)	<u>Machine.</u> 1.00 @ Rs: 1,441.60 P. No. Rs. (Fourteen hundred forty one rup: & sixty paisa only)				1,442

Total Rs. 72,853

N.S.I Rs. 10,824

Grand Total	Rs. (S.I)	71,014
-------------	-----------	--------


XEN

SCHEDULE 'B'

77

Name of Work:- Improvement of existing Public School in Larkano Division (2015-16 Progg:)
at: Public School Larkano (Electric Work)

SNo:	EM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4")PVC conduit recessed in the columns as required (S.I.No: 124 P 15).	222.00	@ Rs: 1130.0	P.Point	Rs: Rs: 250860.0
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4")PVC conduit recessed in the columns as required (S.I. No: 126 P 15).	18.00	@ Rs: 985.0	P.Point	Rs: Rs: 17730.0
3	Wiring for Call bell with 1/1.13 (3/029) PVC insulated wire in 20mm(3/4")PVC conduit recessed in the columns as required (S.I.No: 128 P 15)	4.00	@ Rs: 1764.0	P.Point	Rs: 7056.0
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029} Copper conductor in 3/4" PVC conduit recessed in the wall or colour as required.(S.I.No: 24 P 4)	300.00	@ Rs: 222.0	P.Meter	Rs: Rs: 66600.0
5	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/044}(6mm2)Copper conductor in 1" PVC conduit recessed in the wall or colour as required.(S.I.No: 26 P 4)	300.00	@ Rs: 341.0	P.Meter	Rs: Rs: 102300.0
6	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-/052}(10mm2) Copper cond. dia PVC conduit on surface.	100.00	@ Rs: 428.0	P.Meter	Rs: Rs: 42800.0
7	Providing & Fixing A.C one way S.P 10/15 amps switch flush type (S.I.No: 219 P33).	150.00	@ Rs: 58.0	P.Each	Rs: Rs: 8700.0
8	Providing & Fixing 2 pin 5 amps plug & socket flush type. (S.I.No: 225 P 33).	18.00	@ Rs: 83.0	P.Each	Rs: Rs: 1494.0
9	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	30.00	@ Rs: 162.0	P.Each	Rs: Rs. 4860.0
10	Providing & Fixing Bras batten holder. (S.I.No: 232 P 33).	132.00	@ Rs: 70.0	P.Each	Rs: Rs: 9240.0
11	P/Fixing Brase Baklite Coiling rose with two terminals .(S.I.No: 228 P 33)	54.00	@ Rs: 72.0	P.Each	Rs: Rs: 3888.0
12	Providing and fixing brass ceiling fan 56" (good quality).(S.I.No: 235 P 34)	54.00	@ Rs: 3185.0	P.Each	Rs: 171990.0
13	Providing and fixing brass Bracket fan 18" (good quality).(S.I.No: 235 P 34)	35.00	@ Rs: 2791.0	P.Each	Rs: 97685.0
13	Fixing A.C or D.C Electric beel 200/250 Volts 70 MM (S.I.No:19 P 12).	4.00	@ Rs: 150.70	P Each	Rs: Rs: 603.0


XEN

SNo:	EM OF WOF	Qty:	Rate	Unit	Amount.
14	P/F flush type electric bell push button.(S.I.No: 23 P 12)	4.00 @ Rs: 25.19	P.Each	Rs: Rs:	101.0
18	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or coloumns & covered with plastic sheet.(S.I.No: 18 P11)1st Add:)	40.00 @ Rs: 156.97	P.Each	Rs: Rs:	6279.0
20	P/F Cirecuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	29.00 @ Rs: 948.02	P.Each	Rs: Rs:	27493.0
21	P/F Cirecuit breakers100 Amps triple pole including fixing on a prepared board necessary connection. (S.I.No: 81 P 22)	6.00 @ Rs: 9138.25	P.Each	Rs: Rs:	54829.0
23	P/F Cirecuit breakers 400 amp T P setting 250- 400 amps (XS-630 CI) on a prepared board as required (S.I.No: 210 P 31).	1.00 @ Rs: 39401.0	P.Each	Rs: Rs:	39401.0
TOTAL: Rs:					913,909

PART B

15	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 (b)P 14).	54.00 @ Rs: 109.56	P.Each	Rs: Rs:	5916.0
16	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 10 P 14).	54.00 @ Rs: 169.21	P.Each	Rs: Rs:	9137.0
17	P/F main panel board double shutter to accommodate heavey duty circuit breakers sub bar in painting. (S.I.No: 8 P 13).	7.50 @ Rs: 1089.55	P.Sq.ft.	Rs: Rs:	8171.0
19	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc.i/c making the and charcoal.etc i.c making the pit 12" depth be excavation of all type of soil.Earth palte to be connected with No 8S.W.G bare copper wire run in 1/2" dia G.I pipe straight from the earth upto metallic electrical assarary i.c providing necessary tee.(S.I.No: 1 P 27).	1.00 @ Rs: 3084.42	P.Each	Rs: Rs:	3084.0
22	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	100.00 @ Rs: 596.40	P.Each	Rs: Rs:	59640
TOTAL: Rs: Rs:					85948.0
TOTAL: Rs: Rs:					913909.0
TOTAL: Rs: Rs:					999857.0


XEN

SCHEDULE 'B'

78

Name of Work:- Construction/Re-Construction of Existing offices for field officers of Education & Literacy
Department in Larkana Division (3 units)(2014-15 Progg:) at: Directorate of School Education,
Larkana (Electric Work)

SNo:	EM OF WORK	Qty:	Rate	Unit	Amount.
1	Wiring for light or fan point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4")PVC conduit recessed in the columns as required (S.I.No: 124 P 15).	222.00	@ Rs: 1130.0	P.Point	Rs: Rs: 250860.0
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4")PVC conduit recessed in the columns as required (S.I. No: 126 P 15).	18.00	@ Rs: 985.0	P.Point	Rs: Rs: 17730.0
3	Wiring for Call bell with 1/1.13 (3/029) PVC insulated wire in 20mm(3/4")PVC conduit recessed in the columns as required (S.I.No: 128 P 15)	4.00	@ Rs: 1764.0	P.Point	Rs: 7056.0
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7(.029) Copper conductor in 3/4" PVC conduit recessed in the wall or coloum as required.(S.I.No: 24 P 4)	300.00	@ Rs: 222.0	P.Meter	Rs: Rs: 66600.0
5	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7(.044)(6mm ²)Copper conductor in 1" PVC conduit recessed in the wall or coloum as required.(S.I.No: 26 P 4)	300.00	@ Rs: 341.0	P Meter	Rs: Rs: 102300.0
6	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7(.052)(10mm ²) Copper conductor in 1 1/2" dia PVC conduit on surface.	100.00	@ Rs: 428.0	P.Meter	Rs: Rs: 42800.0
7	Providing & Fixing A.C one way S.P 10/15 amps switch flush type (S.I.No: 219 P33).	150.00	@ Rs: 58.0	P.Each	Rs: Rs: 8700.0
8	Providing & Fixing 2 pin 5 amps plug & socket flush type. (S.I.No: 225 P 33).	18.00	@ Rs: 83.0	P.Each	Rs: Rs: 1494.0
9	Providing & Fixing 3 pin 10/15 amps plug & socket flush type. (S.I.No: 227 P 33).	30.00	@ Rs: 162.0	P.Each	Rs: Rs: 4860.0
10	Providing & Fixing Bras batten holder. (S.I.No: 232 P 33).	134.00	@ Rs: 70.0	P.Each	Rs: Rs: 9380.0
11	P/Fixing Brase Baklite Ceiling rose with two terminals. (S.I.No: 228 P 33)	54.00	@ Rs: 72.0	P.Each	Rs: Rs: 3888.0
12	Providing and fixing brass ceiling fan 56" (good quality) (S.I.No: 235 P 34)	54.00	@ Rs: 3185.0	P.Each	Rs: 171990.0
13	Providing and fixing brass Bracket fan 18" (good quality).(S.I.No: 235 P 34)	35.00	@ Rs: 2791.0	P.Each	Rs: 97685.0
13	Fixing A.C or D.C Electric beel 200/250 Volts 70 MM (S.I.No:19 P 12).	4.00	@ Rs: 150.70	P.Each	Rs: Rs: 603.0



S.No:	EM OF WOF	Qnty:	Rate	Unit	Amount.
4	P/F flush type electric bell push button.(S.I.No: 23 P 12)	4.00 @ Rs: 25.19	P.Each	Rs: Rs:	101.0
18	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or columns & covered with plastic sheet.(S.I.No: 18 P11)1st Add:)	40.00 @ Rs: 156.97	P.Each	Rs: Rs:	6279.0
20	P/F Cirecuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	29.00 @ Rs: 948.02	P.Each	Rs: Rs:	27493.0
21	P/F Cirecuit breakers 100 Amps triple pole including fixing on a prepared board necessary connection. (S.I.No: 81 P 22)	6.00 @ Rs: 9138.25	P.Each	Rs: Rs:	54829.0
23	P/F Cirecuit breakers 400 amp T P setting 250- 400 amps (XS-630 CI) on a prepared board as required (S.I.No: 210 P 31).	1.00 @ Rs: 39401.0	P.Each	Rs: Rs:	39401.0
TOTAL:Rs:					914,049

PART B

15	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 (b)P 14).	54.00 @ Rs: 109.56	P.Each	Rs: Rs:	5916.0
16	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 10 P 14).	54.00 @ Rs: 169.21	P.Each	Rs: Rs:	9137.0
17	P/F main panel board double shutter to accommodate heavy duty circuit breakers sub bar in painting. (S.I.No: 8 P 13).	7.50 @ Rs: 1089.55	P.Sq.ft.	Rs: Rs:	8171.0
19	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc.i/c making the and charcoal.etc i.c making the pit 12" depth be excavation of all type of soil.Earth palte to be connected with No.8S.W.G bare copper wire run in 1/2" dia G.I pipe straight from the earth upto metallic electrical assary i.c providing necessary tee.(S.I.No: 1 P 27).	1.00 @ Rs: 3084.42	P.Each	Rs: Rs:	3084.0
22	P/F Energy saver superior quality i/c fixing on extg: holder etc complete.(S.I.No: 6 P 33)	100.00 @ Rs: 596.40	P.Each	Rs: Rs:	59640
TOTAL:					Rs: Rs: 85948.0
TOTAL:					Rs: Rs: 914049.0
TOTAL:					Rs: Rs: 999997.0


XEN