

**OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION-II,  
EDUCATION & LITERACY DEPARTMENT, GOVERNMENT OF SINDH, KARACHI**

Tender form issued to M/S. \_\_\_\_\_, Government Contractor,  
and charged Rs. 3,000/= Vide D.R. No. \_\_\_\_\_, Dated: \_\_\_\_\_

EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION-II  
KARACHI

NAME OF WORK: **ESTABLISHMENT OF CADET COLLEGE AT GADAP TOWN KARACHI  
(EXTERNAL DEVELOPMENT ACADEMIC SIDE)**

I/We hereby tender for execution of the works of Government of Sindh (herein before / after) referred to as Government of Sindh, specified in the under written memorandum within the time modified in each memorandum at:

Part-A:	@ _____	(Above / Below),
Part-B:	@ _____	(Above / Below),
Part-C:	@ _____	(Above / Below),
Part-D:	@ _____	(Above / Below),
Part-E:	@ _____	(Above / Below),
Part-F:	@ _____	(Above / Below),

The estimate carried out & according to all respect with the specification design / drawing & instruction, in writing referred to rule-I here of the clause-12 of the annexed condition of the contract & agreement, that when material for the work are provided by the Government such materials & rates to paid for then shall be as provided in Schedule-B here to:

**GENERAL DESCRIPTION:**

i)	Estimated Cost	:-	Rs. 15,000,000/=
ii)	Earnest Money 2%	:-	Rs. 300,000/=
iii)	Security Deposit (8%) in/c Earnest Money (2%) Total (10%)	:-	Rs. 1,500,000/=
iv)	Income Tax (7.50%)	:-	Rs. 1,125,000/=
v)	Time allowed for completion of work	:-	06 MONTHS

EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION-II  
KARACHI

**CONTRACTOR'S UNDERTAKING**

I/We have offered that above rates after taking into consideration all the terms and conditions as per B-I, printed tender & this memorandum and shall be base to fill-up & completed the B-I, tender form co, as to complete the agreement. In case of failure, the Department will be at liable to take action against me/us.

xxix) Schedule-A: Nil  
xxx) Schedule-B: Attached herewith

Call Deposit / Pay Order bearing NO. \_\_\_\_\_, Dated: \_\_\_\_\_, Amounting to Rs. \_\_\_\_\_,

Bank: \_\_\_\_\_, Branch: \_\_\_\_\_ is enclosed herewith  
as desired on account of Security Deposit.

(SIGNATURE OF CONTRACTOR)

**SCHEDULE - B**

**NAME OF WORK:-**

**ESTABLISHMENT OF CADET COLLEGE AT GADAP TOWN KARACHI  
EXTERNAL DEVELOPMENT ACCADEMIC SIDE**

S.No	Description of Item	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges and other structure in/c degebillng dressing, refilling around structure with excavated earth watering and ramming lead upto 5ft (b) in ordinary soil (S.I.No.18/P-4)	10461.00	3176.25	%ocft	33,227.00
2	Cement Concrete brick or stone ballast 1-1/2" to 2" guage ratio 1:4:8 (S.I.No.4b/P-15)	17429.00	9416.28	%cft	1,641,163.00
3	P/F Teak wood wrought framed and fixed in place in/c chowkhats hold fast, tower, bolts chooks cleats handle cord with hooks and cost of nail and scew etc complete a) Pannelled or pannelled and glazed or fully glazed 2" thick (S.I.No.3a P-75).	720.00	2557.08	P.Sft	1,841,098.00
4	Filling watering and ramming earth in floor with new earth excavated from outside lead upto one chain and left upto 5 feet (S.I.No.22 P-4)	29618.00	3630.00	%ocft	107,513.00
<b>Total Rs:-</b>					<b>3,623,001.00</b>

\_\_\_\_\_ % Below / Above

Contractor Signature

**NON SCHEDULE ITEM**

1	Carriageb of 100 Cft 5 Tons of all materials like stone aggregate, Spawl, coal, lime surkhi etc. B.G rail fastening points and crossing bridges Girders, Pipes, Sheets rail, M.S barsetc 1000 Nos. of 10" x 5" x 3" or 1000 Nos. tiles 12" x 6" x 2" or 150 Cft of timber or 100 Maunds of fuel wood by trucks or any other means owned by the contractors. (S.I.No.1Page-2 Carriage of Materials Vol:-1 Part-1 Sixth Edition 2011) (15 Miles).	29618.00	1065.00	P.Each	315,432.00
2	P/L American / Dhaka grass over a bed of 12" thick sweet the items in/c laying of sweet earth in required grade compacting using manure / urea / watering the rate also in/c watering and maintaining of gross etc complete (R.A Approved).	22875.00	49.5	P.Each	1,132,313.00
<b>Total Rs:-</b>					<b>1,447,745.00</b>

\_\_\_\_\_ % Below / Above

Contractor Signature

**CHECKED**

DEPUTY SECRETARY  
Education  
Division-II

**EXECUTIVE ENGINEER**  
EDUCATION WORKS DIVISION-II  
EDUCATION & LITERACY DEPARTMENT  
GOVT. OF SINDH KARACHI.

**SCHEDULE ITEM 20% BELOW**

- 1 P/F cement paving blocks flooring having size of 197 x 97 x 80(mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 psi in/c filling the joints with hill sand and laying in specified manner / patter and design etc complete (S.I.No.74 P-50)

29618.00 248.17 P.Sft 7,350,299.00

Total Rs:-

7,350,299.00

% Below / Above

Contractor Signature

**SCHEDULE ITEM OF Edge Block**

- 1 Providing & Fixing Precast Edge Block 3750 PSI Industrial made size 6 inches thick x 12 inches long x 12 inches high in/c the cost of carriage, excavation from work for haunching 2250 PSI lean oncrete 2250 PSI concrete for hunching 1:4 sand mortar (S.I.No.14 P-16 Highway)


11500.00 297.01 P.Sft 3,415,615.00

Total Rs:-

3,415,615.00

% Below / Above

Contractor Signature

  
**EXECUTIVE ENGINEER**  
EDUCATION WORKS DIVISION-II  
EDUCATION & LITERACY DEPARTMENT  
GOVT. OF SINDH KARACHI.