

SCHEDULE-B

NAME OF WORK:- ESTABLISHMENT OF CADET COLLEGE AT GADAP TOWN (Horse Astabal)

S.No.	Description	Qty	Rate	Unit	Amount.
1	Excavation in foundation of building bridges and other structure in/c degebilling dressing, refilling around structure with excavated earth watering and ramming lead upto 5ft (b) in ordinary soil (S.I.No.18/P-4)	4944.00	3176.25	%Ocft	15,703.00
2	Cutting Hard Rock such as granite ballast hard lime stone or sand stone etc with chisels and hammers for small foundation (S.I.No.19 P-4)	4032.00	28672.05	%Ocft	115,606.00
3	Cement concrete brick or stone ballast 1.5" to 2" gauge (d) Ratio 1:4:8, (S.I.No. 4(d)/C-4)	4172.00	9416.28	%Cft	392,847.00
4	Erection and removal of centering for Reinforced or Plain cement concrete works of Partal wood (2nd class). (a) Vertical.(S.I.No. 18(a)/C-4)	912.00	3127.41	%Cft	28,522.00
5	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate without shuttering) (h) Ratio 1:3:6 (S.I.No. 5(h)/C-4)	306.00	12595.00	%Cft	38,541.00
6	Filling watering and ramming earth in floor with new earth excavated from outside lead upto one chain and left upto 5 feet (S.I.No.22 P-5)	11440.00	3630.00	%0cft	41,527.00
7	R.C.C work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms, moulds, lifting, shuttering, curing, rendering and finishing the exposed surface (including screening and washing of shingle (a) R.C.C work in roof slab, beams, columns, rafts, lintels and other structural	6987.00	337.00	P.Cft	2,354,619.00
8	P/L 1:3:6 cement concrete solid block masonry wall 6" above in thiskness set in 1:6 cement mortor in G.Floor Super structure in/c racking out joint and curing etc complete (S.I.NO.23/P-19)	1054.00	14621.44	%Cft	154,110.00
9	Cement plaster 1:4 upto 20 height 3/4" thick (S.I.No.11-d P-52)	2021.00	3191.76	%sft	64,505.00
10	P/L 2" thick topping cement concrete 1:2:4 in/c surface finishing and dividing into pannels pannels (S.I.No.16c P-42)	5720.00	3275.50	%sft	187,359.00
11	Two coats of bitumen laid hot using 34 lbs for % Sft over roof and blinded with sand @ 1 Cft per % Sft. (S.I.No. 13/ P-35)	5720.00	1887.40	%sft	107,959.00
12	P/L 3" thick topping cement concrete 1:2:4 in/c surface finishing and dividing into pannels pannels (S.I.No.16b P-46)	5720.00	4411.82	%sft	252,356.00
13	Reinforced cement concrete spout in/c fixing in position 2-1/2 x 6"x 5" (S.I.No.13 P-18)	5.00	261.50	Each	1,308.00

S.No.	Description	Qty	Rate	Unit	Amount.
14	Primary Coat of chalk under distemper (S.I.No.23/P-23)	13876.00	442.75	%sft	61,436.00
15	Distemping three coats (S.I.No.24© P-54)	13876.00	1079.65	%sft	149,812.00
Total Rs:-					3,966,210.00

_____ % Below / Above

Contractor Signature

NON SCHEDULE ITEM

- 1 Carriage of 100 Cft 5 Tons of all materials like stone aggregate, Spawl, coal, lime surkhi etc. B.G rail fastening points and crossing bridges Girders, Pipes, Sheets rail, M.S barsetc 1000 Nos. of 10" x 5" x 3" or 1000 Nos. tiles 12" x 6" x 2" or 150 Cft of timber or 100 Maunds of fuel wood by trucks or any other means owned by the contractors. (S.I.No.1Page-2 Carriage of Materials Vol:-1 Part-1 Sixth Edition 2011) (15 Miles).

11440.00 1065.00 %Cft 121,836.00

Total Rs:- 121,836.00

_____ % Below / Above

Contractor Signature

CHECKED

DRAFTSMAN
Education Works Division-II


SCHEDULE ITEM 10% ABOVE

- 1 Fabrication of Tor steel reinforcement for cement concrete including cutting, 374.30 5001.70 P.Cwt 1,872,136.00
- 2 S/F in position iron / steel grill of 3/4" x 1/4" size flate iron of approved design in/c 1672.00 180.50 P.Sft 301,796.00

Total Rs:- 2,173,932.00

_____ % Below / Above

Contractor Signature


EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION-II
EDUCATION & LITERACY DEPARTMENT
GOVT. OF SINDH KARACHI.