

**OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION-II,  
EDUCATION & LITERACY DEPARTMENT, GOVERNMENT OF SINDH, KARACHI**

Tender form issued to M/S. \_\_\_\_\_, Government Contractor,  
and charged Rs. 3,000/= Vide D.R. No. \_\_\_\_\_, Dated: \_\_\_\_\_

EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION-II  
KARACHI

**NAME OF WORK:** ESTABLISHMENT OF CADET COLLEGE AT GADAP TOWN KARACHI  
(GARRIAGE FOR STAFF VEHICLE)

I/We hereby tender for execution of the works of Government of Sindh (herein before / after) referred to as Government of Sindh, specified in the under written memorandum within the time modified in each memorandum at:

Part-A:	@ _____ (Above / Below),
Part-B:	@ _____ (Above / Below),
Part-C:	@ _____ (Above / Below),
Part-D:	@ _____ (Above / Below),
Part-E:	@ _____ (Above / Below),
Part-F:	@ _____ (Above / Below),

The estimate carried out & according to all respect with the specification design / drawing & instruction, in writing referred to rule-I here of the clause-12 of the annexed condition of the contract & agreement, that when material for the work are provided by the Government such materials & rates to paid for then shall be as provided in Schedule-B here to:

**GENERAL DESCRIPTION:**

i)	Estimated Cost	:-	Rs. 2,500,000/=
ii)	Earnest Money 2%	:-	Rs. 50,000/=
iii)	Security Deposit (8%) in/c Earnest Money (2%) Total (10%)	:-	Rs. 250,000/=
iv)	Income Tax (7.50%)	:-	Rs. 187,500/=
v)	Time allowed for completion of work	:-	06 MONTHS

EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION-II  
KARACHI

**CONTRACTOR'S UNDERTAKING**

I/We have offered that above rates after taking into consideration all the terms and conditions as per B-I, printed tender & this memorandum and shall be base to fill-up & completed the B-I, tender form co, as to complete the agreement. In case of failure, the Department will be at liable to take action against me/us.

iii) Schedule-A: Nil  
iv) Schedule-B: Attached herewith

Call Deposit / Pay Order bearing NO. \_\_\_\_\_, Dated: \_\_\_\_\_, Amounting to Rs. \_\_\_\_\_,

Bank: \_\_\_\_\_, Branch: \_\_\_\_\_ is enclosed herewith  
as desired on account of Security Deposit.

(SIGNATURE OF CONTRACTOR)

## SCHEDULE - B

NAME OF WORK:-

ESTABLISHMENT OF CADET COLLEGE AT GADAP TOWN (Garriage For Staff Vehicle)

S.No.	Description	Qty	Rate	Unit	Amount.
1	Excavation in foundation of building bridges and other structure in/c degebillng dressing, refilling around structure with excavated earth watering and ramming lead upto 5ft (b) in ordinary soil (S.I.No.18/P-4)	2616.00	3176.25	%Ocf	8,309.00
2	Cutting Hard Rock such as granite ballast hard lime stone or sand stone etc with chisels and hammers for small foundation (S.I.No.19 P-5)	654.00	28672.05	%Ocf	18,752.00
3	Cement concrete brick or stone ballast 1.5" to 2" gauge (d) Ratio 1:4:8. (S.I.No. 4(d)/C-4)	1027.00	9416.28	%Cft	96,705.00
4	Erection and removal of centering for Reinforced or Plain cement concrete works of Partial wood (2nd class). (a) Vertical.(S.I.No. 18(a)/C-4)	1088.00	3127.41	%Cft	34,026.00
5	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate without shuttering) (h) Ratio 1:3:6 (S.I.No. 5(h)/C-4)	364.00	12595.00	%Cft	45,846.00
6	Filling watering and ramming earth in floor with new earth excavated from outside lead upto one chain and left upto 5 feet (S.I.No.22 P-5)	6000.00	3630.00	%0cf	21,780.00
7	R.C.C work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms, moulds, lifting, shuttering, curing, rendering and finishing the exposed surface (including screening and washing of shingle (a) R.C.C work in roof slab, beams, columns, rafts, lintels and other structural members laid in situ or precast laid in position. Complete in all respects (i) Ratio 1:2:4 90 lbs. (S.I.No. 6(b)/i/C-4)	1834.00	337.00	P.Cft	618,058.00
8	P/L 1:3:6 cement concrete solid block masonry set in 1:6 cement sand mortar in plinth and foundation in/c racking out joint curing etc complete (S.I.No.21/P-22).	120.00	14268.53	%Cft	17,122.00
9	P/L 1:3:6 solid block masonry wall 6" above set in 1:6 cement mortar in ground floor super structure I/c raking out joints etc complete. S.I.No: 23/Chapter-4)	979.00	14621.44	%Cft	143,144.00
10	P/L 1:3:6 solid block masonry wall 6" below set in 1:6 cement mortar in ground floor super structure I/c raking out joints etc complete. S.I.No: 23/Chapter-4)	204.00	15771.01	%Cft	32,173.00
11	Cement plaster 1:4 upto 20' height 3/4" thick (S.I.No.11-d P-52)	4424.00	3191.76	%sft	141,203.00
12	P/L 2" thick topping cement concrete 1:2:4 in/c surface finishing and dividing into pannels pannels (S.I.No.16c P-42)	900.00	3275.50	%sft	29,480.00
13	Reinforced cement concrete spout in/c fixing in position 2-1/2 x 6"x 5" (S.I.No.14 P-18)	4.00	261.50	Each	1,046.00

CHECKED

DRAFTSMAN  
Division-II

Education

S.No.	Description	Qty	Rate	Unit	Amount.
14	Two coats of bitumen laid hot using 34 lbs for % Sft over roof and blinded with sand @ 1 Cft per % Sft. (S.I.No. 13/ P-35)	900.00	1887.40	%sft	16,987.00
15	Primary Coat of chalk under distemper (S.I.No.23/P-23)	5324.00	442.75	%sft	23,572.00
16	Distemping three coats (S.I.No.24© P-54)	5324.00	1079.65	%sft	57,481.00
Total Rs:-					1,305,683.00

\_\_\_\_\_ % Below / Above

Contractor Signature

#### SCHEDULE ITEM 20% BELOW

1	P/F cement paving blocks flooring having size of 197 x 97 x 80(mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 psi in/c filling the joints with hill sand and laying in specified manner / patter and design etc complete (S.I.No.74 P-50)	1400.00	248.17	P.Sft	347,438.00
Total:-					347,438.00

\_\_\_\_\_ % Below / Above

Contractor Signature

**CHECKED**  
**DRAFTSMAN**  
**Education Division-II**

#### SCHEDULE ITEM 10% ABOVE

1	Fabrication of Tor steel reinforcement for cement concrete including cutting, bending, laying in position, making joints and fastening including cost of binding wire (also includes removal of rust from bars. (S.I.No. (9/Chapter-4)	98.25	5001.70	P.Cwt	491,417.00
2	Providing & Fixing G.I Sheet rolling shutter using 2 guage G.I sheet for shutter side iron channel of 12 guage for rolling on 2" dia G.I pipe in/cbracket of 20 guage spring of requisite size and rolling pully, greating, all carriage T&P required for making and fixing in masonry bor etc complete (S.I.No.33 P-94)	605.00	264.96	P.Sft	160,301.00
Total:-					651,718.00

\_\_\_\_\_ % Below / Above

Contractor Signature

**EXECUTIVE ENGINEER**  
**EDUCATION WORKS DIVISION-II**  
**EDUCATION & LITERACY DEPARTMENT**  
**GOVT. OF SINDH KARACHI.**