

**OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION-II,
EDUCATION & LITERACY DEPARTMENT, GOVERNMENT OF SINDH, KARACHI**

Tender form issued to M/S. _____, Government Contractor,
and charged Rs. 3,000/= Vide D.R. No. _____, Dated: _____

EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION-II
KARACHI

NAME OF WORK: ESTABLISHMENT OF CADET COLLEGE AT CADAP TOWN KARACHI
(FOOTBALL GROUND)

I/We hereby tender for execution of the works of Government of Sindh (herein before / after) referred to as Government of Sindh, specified in the under written memorandum within the time modified in each memorandum at:

Part-A:	@ _____	(Above / Below),
Part-B:	@ _____	(Above / Below),
Part-C:	@ _____	(Above / Below),
Part-D:	@ _____	(Above / Below),
Part-E:	@ _____	(Above / Below),
Part-F:	@ _____	(Above / Below),

The estimate carried out & according to all respect with the specification design / drawing & instruction, in writing referred to rule-I here of the clause-12 of the annexed condition of the contract & agreement, that when material for the work are provided by the Government such materials & rates to paid for then shall be as provided in Schedule-B here to:

GENERAL DESCRIPTION:

i)	Estimated Cost	:-	Rs. 22,000,000/=
ii)	Earnest Money 2%	:-	Rs. 440,000/=
iii)	Security Deposit (8%) in/c Earnest Money (2%) Total (10%)	:-	Rs. 2,200,000/=
iv)	Income Tax (7.50%)	:-	Rs. 1,650,000/=
v)	Time allowed for completion of work	:-	06 MONTHS

EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION-II
KARACHI

CONTRACTOR'S UNDERTAKING

I/We have offered that above rates after taking into consideration all the terms and conditions as per B-I, printed tender & this memorandum and shall be base to fill-up & completed the B-I, tender form co. as to complete the agreement. In case of failure, the Department will be at liable to take action against me/us.

xxi) Schedule-A: Nil
xxii) Schedule-B: Attached herewith

Call Deposit / Pay Order bearing NO. _____, Dated: _____, Amounting to Rs. _____,
Bank: _____, Branch: _____ is enclosed herewith
as desired on account of Security Deposit.

(SIGNATURE OF CONTRACTOR)

SCHEDULE - B


NAME OF WORK:-

**ESTABLISHMENT OF CADET COLLEGE AT GADAP TOWN KARACHI
(ADP. NO.) Football Ground.)**

S.No	Description of Item	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges and other structure in/c degebilling dressing, refilling around structure with excavated earth watering and ramming lead upto 5ft (b) in ordinary soil (S.I.No.18/P-4)	6500.00	3176.25	%ocft	20,646.00
2	Cutting Hard Rock such as granite ballast hard lime stone or sand stone etc with chisels and hammers for small foundation (S.I.No.19 P-5)	20000.00	28672.05	%cft	573,441.00
3	Cement Concrete brick or stone ballast 1-1/2" to 2" guage ratio 1:4:8 (S.I.No.4b,/P-15)	5950.00	9416.28	%0cft	560,269.00
4	R.C.C work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms, moulds, lifting, shuttering, curing, rendering and finishing the exposed surface (including screening and washing of shingle (a) R.C.C work in roof slab, beams, columns, rafts, lintels and other structural members laid in situ or precast laid in position. Complete in all respects (i) Ratio 1:2:4 90 lbs. (S.I.No. 6(a)/i/C-4)	5700.00	337.00	P.cwt	1,920,900.00
5	Errection and removal of centering for R.C.C or plain cement concrete work of Partial wood (2nd class) (S.I.NO.18-P-21) (vertical)	33250.00	3127.41	%cft	1,039,864.00
6	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate without shuttering) (h) Ratio 1:3:6 (S.I.No. 5(h)/C-4)	7875.00	12595.00	%cft	991,856.00
7	Filling watering and ramming earth in floor with surplus earth from foundation lead upto one chain and left upto 5 feet (S.I.No.21 P-5)	2166.67	1512.50	%ocft	3,277.00
8	Filling watering and ramming earth in floor with new earth excavated from outside lead upto one chain and left upto 5 feet (S.I.No.21 P-4)	342200.00	3630.00	%ocft	1,242,186.00
9	Cement Plaster 1:3:6 upto 12" height 3/4" thick (S.I.No.11P-52) (Only Block Masonary Work)	13325.00	3191.76	% sft	425,302.00
10	P/L 1:3:6 cement concrete solid block masonry set in 1:6 cement sand mortar in plinth and foundation in/c racking out joint curing etc complete (S.I.No.21/P-22).	14850.00	14268.53	%Cft	2,118,877.00
					8,896,618.00

_____ % Below / Above

Contractor Signature


EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION-II
EDUCATION & LITERACY DEPARTMENT
GOVT. OF SINDH KARACHI

NON -SCHEDULE ITEM

1	Carriage of 100 Cft 5 Tons of all materials like stone aggregate, Spawl, coal, lime surkhi etc. B.G rail fastening points and crossing bridges Girders, Pipes, Sheets rail, M.S barsetc 1000 Nos. of 10" x 5" x 3" or 1000 Nos. tiles 12" x 6" x 2" or 150 Cft of timber or 100 Maunds of fuel wood by trucks or any other means owned by the contractors. (S.I.No.1Page-2 Carriage of Materials Vol:-I Part-I Sixth Edition 2011) (30 Miles).	342200.00	1065.00	%cft	3,644,430.00
2	P/F floor for Marble tile of China, Verona of Badal Block (12" x 12") fine dressed on the surface without winding in ground floor laid 1" thick (Average) lime mortar 1:2 one lime tow sand setting the tile with grey cement slurry in/c curring rubbing & polishing etc complete in/c the cost of mortar 1" thick (R/A approved).	5400.00	301.00	P.Sft	1,625,400.00
3	P/F Foot ball Goals post with Net etc complete (M.R)	2.00	200000.0	Each	400,000.00
4	P/L American / Dhaka grass over a bed of 12" thick sweet the items in/c laying of sweet earth in required grade compacting using manure / urea / watering the rate also in/c watering and maintaining of gross etc complete (R.A Approved).	68000.00	49.50	P.Sft	3,366,000.00
					9,035,830.00

SCHEDULE ITEM 20% BELOW

1	P/F 3/8" thick marble tiles of approved quality and colour and shade 8" x 4" or 6" x 4" in dado skirting and facing removal / tucking of existing plaster surface etc over 1/2" thick base of cement mortar 1:3 setting and washing the tiles with white cement slurry cement finishing cleaning and polishing etc complete for new work (S.I.No.68/P-55)	2250.00	186.04	P.Sft	418,590.00
					418,590.00

_____ % Below / Above

Contractor Signature

CHECKED
DRAFTSMAN
Education Division-II

SCHEDULE ITEM 10% ABOVE ON STEEL

1	Fabrication of Tor steel reinforcement for cement concrete including cutting, bending, laying in position, making joints and fastening including cost of binding wire (also includes removal of rust from bars. (S.I.No. 7(b)/C-4)				
	Tor Steel	305.36	5001.70	P.cwt	1,527,319.00
					1,527,319.00

_____ % Below / Above

Contractor Signature

EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION-II
EDUCATION & LITERACY DEPARTMENT
GOVT. OF SINDHICARACHI