

**CONSTRUCTION OF ROAD FROM LARKANA RASHEED WAGGAN ROAD @ NAZAR MUHALLA  
ALONGWITH SIM NALA (BOTH SIDES) TO MURAD SHAH MILE: 1/2-3/4**

**(I/C M.STRUCTURE)  
BILL OF QUANTITIES**

**PART-B (iv) 3.0' FT: SPAN CULVERT. (04 Nos.)**

Item	Qty's	Description of Item	Rate	Unit	Amount
1	2	3	4	5	6
1	1,514 Cft:	Excavation in foundation of building bridge other structure i/c dag belling dressing refilling around the structure with excavated earth watering and remaining lead upto one chain and left upto 5.0' ordinary soil.	3176.25	P.0% Cft:	4,809
2	247 Cft:	Cement concrete with bricks are stone plaster 1½" to 2" guage ratio 1:2:4	9416.28	P.% Cft:	23,258
3	1,440 Cft:	Pucca Brick work in foundation and plinth i/c cement sand mortor	12501.41	P.% Cft:	180,020
4	53 Cft:	Cement concrete plain i/c placing compacting finishing curing complete i/c screening washing of stone aggregate with out suhttering ratio 1:2:4:	14429.25	P.% Cft:	7,648
5	58 Sft:	Erection and removal of centering for R.C.C or plain cement work (2 <sup>nd</sup> : class) for partal wood vertical (S.I.No:18)(b) P-20).	3127.41	P.% Sft:	1,814
6	9.17 Cwt:	Fabrication of m/s reinforcement cement concrete including cutting binding laying in position making joints & fastening of i/c binding wire also removal rust from bars.	4820.20	P.% Cwt:	44,201
7	138 Cft:	Reinforced cement concrete work including all labour and	337.00	P.%	46,506
8	1,036 Sft:	Cement Plaster (1:3) upto 20' height 1½" thick.	2344.59	P.% Sft:	24,290
<b>TOTAL</b>					<b>332,546</b>

% Above / Below on the rates of CSR.

Rs.

Amount to be added / deducted on the

Total Rs.

\_\_\_\_\_ x 4 = Rs. \_\_\_\_\_

Total Amount in words. \_\_\_\_\_

Contractor

**CHECKED**

**Divisional Head Draftsman**  
office of the  
**Executive Engineer**  
**Provincial Highway Division**  
Larkana

**Executive Engineer,**  
Provincial Highways Division  
Larkana