

CONSTRUCTION OF ROAD FROM LARKANA RASHEED WAGGAN ROAD @ NAZAR MUHALLA  
ALONGWITH SIM NALA (BOTH SIDES) TO MURAD SHAH MILE: 1/2-3/4  
(I/C M.STRUCTURE)  
**BILL OF QUANTITIES**

**PART-B (ii) 10' RFT: BRIDGE**

Item No.	Qty's	Description of Item to be executed at site	Rate	Unit	Amount in Rs.
1	2	3	4	5	6
1	6,655 Cft:	Excavation in foundation of building bridge other structure i/cs dagbelling dressing refilling around the structure with excavated earth watering and remaining lead upto one chain and left upto 5.0' ordinary soil.	3176.25	P.0% Cft:	21,138
2	1,540 Cft:	Extra wet earth.	1058.75	P.0% Cft:	1,630
3	2,436 Cft:	Extra fro slash of Duldal i/c Dewatering (Below bed level).	2420.00	P.0% Cft:	5,895
4	1,312 Cft:	Cement concrete with bricks are stone plaster 1½" to 2" guage ratio 1:2:4	9416.28	P.0% Cft:	123,542
5	3,729 Cft:	Pucca Brick work in foundation and plinth i/c cement sand mortor	12501.41	P.0% Cft:	466,178
6	131 Cft:	Cement concrete plain i/c placing compacting finishing curing complete i/c screening washing of stone aggregate with out suhttering ratio 1:2:4:	14429.25	P.0% Cft:	18,902
7	39 Sft:	Erection and removal of centering for R.C.C or plain cement work (2 <sup>nd</sup> : class) for partal wood vertical (S.I.No:18)(b) P-20).	3127.41	P.0% Sft:	1,220
8	33.28 Cwt:	Fabrication of m/s reinforcement cement concrete including cutting binding laying in position making joints & fastening of i/c binding wire also removal rust from bars.	4820.20	P.0% Cwt:	160,416
9	733 Rft:	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle) R.C.C work in roof slab, beams columns rafts, lintels and other structural member laid in situ or pre cast laid in position complete in all respects. Ratio (1:2:4) 90 lbs: cement 2 cft: sand 4 cft: shingle 1/8 to ¼ gauge.	337.00	P.0% Rft:	247,021
10	1,056 Sft:	Cement Plaster (1:3) upto 20' height 1½" thick.	2344.59	P.0% Sft:	24,759
TOTAL					1,070,601

% Above / Below on the rates of CSR.

Rs.

Amount to be added / deducted on the


Total Rs.

Total Amount in words.

Contractor

**CHECKED**

**Divisional Head Draftsman**  
office of the  
**Executive Engineer**  
**Provincial Highway Division**  
Larkano

  
**Executive Engineer,**  
Provincial Highways Division  
Larkano