

Issued to Mr. \_\_\_\_\_  
Vide D.R. No. \_\_\_\_\_ dated \_\_\_\_\_.

## TENDER FOR WORKS

I/We hereby tender for the execution, for the Government of Sindh/ Chancellor of Sindh Agriculture University, Tando Jam (hereinbefore and hereinafter referred to as "University of the work specified in the underwritten memorandum within the time specified in such memorandum at \_\_\_\_\_ % above/below Part-I, and at \_\_\_\_\_ %Above/Below Part-II, and at \_\_\_\_\_ %Above/Below Part-III the estimated rates entered in schedule "B" memorandum showing items of work to be carried out) and in accordance in all respects with the Specifications, designs, drawings and instructions in written referred to in Rule 1 hereof and in clause 13 of the annexed conditions of contract and agree that when materials for the work are provided by the University such materials and rates to be paid for them shall be as provided in schedule, A, hereto.

### M E M O R A N D U M

- (a) General Description: **Construction of Additional Infrastructure compound wall around academic area**  
(b) Estimate cost. Rs:  
(c) Earnest money. Rs: **3%**  
(d) Security deposit i/c earnest money. Rs: **10.**  
(e) Percentage if any to be deducted Rs:  
From bills (Rupees \_\_\_\_\_) percent.  
(f) Time allowed for the completion of work from date of written order to commence **09 month(s)**.

Should this tender be accepted I/We hereby agree to abide by and fulfill all the terms and provisions of the conditions of contract annexed hereto so far as applicable, and in default there of to forfeit and pay to University the sums of money mentioned in the said conditions.

Receipt No. \_\_\_\_\_ dated \_\_\_\_\_ from the \_\_\_\_\_ Bank at \_\_\_\_\_ in respect of the sum of Rs. \_\_\_\_\_ is herewith forwarded presenting the earnest Money / (a) the full value of which is to be absolutely forfeited to University should I/We not deposit the full amount of security deposit specified in the above memorandum, in accordance with clause 1 (A) of the said conditions, otherwise the said sum of Rs. \_\_\_\_\_ shall be retained by University on account of such security deposit as aforesaid / or (b) the full value of which shall be retained by University on account of the security deposit in clause (B) of the condition.

Dated the \_\_\_\_\_ day of \_\_\_\_\_ 2016

**CONTRACTOR**

The above tender is hereby accepted by me on behalf of the Governor of Sindh/Chancellor, Sindh Agriculture University Tando Jam.

Dated: \_\_\_\_\_.

**PROJECT DIRECTOR  
SINDH AGRICULTURE UNIVERSITY  
TANDOJAM**

# SINDH AGRICULTURE UNIVERSITY, TANDOJAM

## Construction of Compound wall around Academic Area

### SUMMARY OF COST

#### SCHEDULE ITEM

1) CIVIL WORKS Rs. 37,875,536.24

Below/ above \_\_\_\_\_ Rs.

Schedule items: \_\_\_\_\_

TOTAL = Rs.

Total Schedule Items: Rs.

Say : Rs.

**Schedule-"B"**  
**Construction of Compound wall around Academic Area**  
**Sindh Agriculture University, Tando Jam.**

S.#	Item	Quantity	Rate	Unit	Amount
<b>A-Schedule Items</b>					
1-	Excavation in foundation of buildings bridges and other structures i/c dag belling, dressing, refilling around the structure with excavated earth watering and ramming. lead upto one chain and lift upto 5 ft. (b) In Ordinary soil ( S.Item No. 18-b, Page No. 4 )	47706 Cft	%0 Cft	3,176.25	151,526.18
2-	C.c brick or stone ballast 1 1/2" to 2" gauge ratio 1:4:8 ( S.Item No. 4 ( b ), Page No. 17 )	6270 Cft	% Cft	9,416.28	590,400.76
3-	Fabrication of deformed steel reinforcement for cement concrete i/c cutting, bending, laying in position. Making joints and fastenings i/c cost of binding wire. <u>Tor Steel</u> ( S.Item No. 8-b, Page No. 17 )	1995 Cwt	P. Cwt	5,001.70	9,978,391.50
4-	Reinforced cement concrete work in all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid seperately. This rate also i/c all kinds of forms, moulds, lifting, shuttering, curing, rendering and finishing the exposed surface. (i/c screening and washing of shingle). (b) RCC work in roof slabs, beams, columns, rafts, lintels and other structural mambbers laid in situ or pre-cast laid in position complete in all respects. (i) Ratio 1:2:4, 90 lbs cement, 2 cft sand, 4 cft shingle 1/8" to 1/4" gauge. ( S.Item No. 6-a-l), Page No. 19 )	36120 Cft	P. Cft	337.00	12,172,440.00
7-	Pacca brick work other than building including striking of joints upto 20 feet height in 1:6 ( S.Item No. 7-l-e, Page No. 22 )	46616 Cft	% Cft	12,346.65	5,755,514.36
10-	Cement plaster 1:6, 3/8" thick in cement sand mortar. ( S.Item No. 13-a, Page No. 52 )	63790 Sft	% Sft	2,122.72	1,354,083.09
11-	Cement plaster 1:4 up-to 20 ft height 3/8" thick in cement sand mortar. ( S.Item No. 11-a, Page No. 52 )	63790 Sft	% Sft	2,197.52	1,401,798.01
11-	Cement pointing struck jints on walls Ratio 1:2. ( S.Item No. 19 (a) , Page No. 53 ) @ Rs. 1287/44, % Sft	63790 Sft	% Sft	1,287.44	821,257.98

S.#	Item	Quantity	Rate	Unit	Amount
11-		67061 Sft	% Sft	2,306.10	1,546,493.72
11-		3135 Sft	% Sft	43.26	1,356.20
12-	Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of paris and than painting with weather coat of approved make. 3-coats ( S.Item No. 25, Page No. 54 )	159749 Sft	% Sft	2,567.95	4,102,274.45
Total Rs.					37,875,536.24
Premium @ -----% Above/below					
A-Total Amount of schedule Items					