

OFFICE OF THE TOWN COMMITTEE KHIPRO**DISTRICT SANGHAR**Ph: 0235-875985 TC/KPO/ 67 2016Khipro, Date: 13-12-2016**TENDER NOTICE:-**

With the permission of Local Government Department of Sindh vide letter No. SOG(LG)/3-40/2016 (Sgr) Karachi dated 29-08-2016, sealed tenders are hereby invited from all the interested contractor / firms / parties as per SPPRA Rules 2010, for the Financial Year 2016-2017 in connection to execute following development schemes with in jurisdiction to Town Committee Khipro District Sanghar.

S. #	Name of Work	Estimate Cost	Call Deposit	Tender Fee	Period
1.	Repair & Maintenance of Drain at Murad Colony T.C Khipro	972,000/=	19,440/=	1000/-	6 Months
2.	Providing & Lining Earth Filling at Hayat Colony T.C Khipro	998,300/=	19,966/=	1000/-	6 Months
3.	Repair & Maintenance of Drain at Deewan Colony T.C Khipro	972,000/=	19,440/=	1000/-	6 Months
4.	Construction of culverts at Ward no.3,4,& 6 T.C Khipro	951,600/=	19,032/=	1000/-	6 Months
5.	Construction C.C Road at Murad Colony T.C Khipro	983,900/=	19,678/=	1000/-	6 Months
6.	Construction of R.C.C Slabs over Open Surface Drain at Khipro City.	935,300/=	18,706/=	1000/-	6 Months
7.	Repair & Maintenance of Drain at Safar Colony T.C Khipro	972,000/=	19,440/=	1000/-	6 Months

TERMS & CONDITIONS:-

1. The Public form along with schedule-B for development works will be issued to the contractor from very first day after publication in news paper till dated the 30-12 -2016 at time 10:00am against mentioned tender fee, (non-refundable).
2. The Tender document along with schedule-B and 2% earnest money shown against the work will be submitted by the contractors on dated 30-12 -2016 till 12:00pm and same will be opened on similar date at 1:00 pm by the Town Officer Town Committee Khipro before the contractors / firms / interested parties or their authorized repetitive
3. No any condition or over written tender will be accepted.
4. No any contractor / party / firm will be allowed to participate without NTN certificate issued by the FBR , Certificate issued by SBR, at least Three years relevant experience, and filling the other requirement as per SPPRA Rules 2010 (Amended 2013).
5. Incase if any intermits is pointed out by the SPPRA / Government of Sindh for correction same will be received / incorrect in shape of corrigendum and will be displayed on notice board 03 days before receiving and opening of tenders for General Information out the contractor on public, which may please be noted clearly.

TOWN OFFICER
TOWN COMMITTEE KHIPRO

C.C to:-

1. The Secretary Local Government Department, Sindh Karachi for information.
2. The Secretary Information Technology Department, Govt. of Sindh with a request for Placement of the tender notice on the website of Govt. of Sindh.
3. The Managing Director Sindh Public Procurement Regulatory Authority Karachi.
4. The Deputy Commissioner Sangar for information.
5. The Director Local Government Shaheed Benazirabad (Nawabshah Division)


TOWN OFFICER
TOWN COMMITTEE KHIPRO

OFFICE OF THE TOWN OFFICER TOWN COMMITTEE KHIPRO
DISTRICT SANGHAR

No. TCK/KPO/ 65 / 2016

Dated: 08/12 / 2016

NOTIFICATION

In pursuance of Rule-31 of the Sindh Public Procurement Rules Complaint Redressal Committee Comprising of following officers constituted as under to resolve complaints of aggrieved bidders.

- | | | |
|----|---|----------------|
| 1. | Chairman Town Committee
Khipro. | Chairman (CRC) |
| 2. | Mr. Nazir Ahmed Palejo.
Executive Engineer
Highways Division Sanghar. | Member(CRC) |
| 3. | Accounts Officer
District Sanghar. | Member(CRC) |

TORs

- To perform according to the Rule -31 of SPPRA, 2010.
- Perform any other function canceling and incidental to the above.


**TOWN OFFICER
TOWN COMMITTEE
KHIPRO**

Copy F.w.cs for information and necessary action to :-

1. The All Members of the CRC Committee.
2. Office orders file.


**TOWN OFFICER
TOWN COMMITTEE
KHIPRO**

☎ 021-99212973
☎ 021-99211537



**GOVERNMENT OF SINDH
LOCAL GOVERNMENT
DEPARTMENT**

Karachi, dated 29th August, 2016

NOTIFICATION

No.SOG(LG)/3-40/2016: With the approval of Competent Authority, Procurement Committee is hereby constituted with the following composition alongwith TORs for development works/Schemes for the year 2016-17 of Town Committee, Khipro, district Sanghar, for smooth functioning of Government work :-

- | | |
|--|------------------|
| ○ Assistant Director, Local Government, Sanghar | Chairman |
| ○ Town Officer, Town Committee, Khipro | Member |
| ○ Sub-Engineer, Town Committee, Khipro | Member |
| ○ Sub-Engineer, Public Health Engineering, Sanghar | Member |
| ○ Accountant, Town Committee, Khipro | Member/Secretary |

Functions and Responsibilities of Procurement Committee

- ❖ Preparing bidding documents;
- ❖ Carrying-out technical as well as financial evaluation of the bids;
- ❖ Preparing evaluation report as provided in Rule-45;
- ❖ Making recommendations for the award of contract to the competent authority; and
- ❖ Perform any other function ancillary and incidental to the above.


**-BAQAULLAH UNNAR-
SECRETARY TO GOVERNMENT OF SINDH**

No.SOG(LG)/ 3-40 /2016.

Karachi, dated the 29th August - 2016.

A copy is forwarded for information and necessary action to:-

1. The Director, Local Government, Shaheed Benazirabad.
2. The Assistant Director, Local Government, Shaheed Benazirabad.
3. The Assistant Director, Local Fund Audit, Shaheed Benazirabad.
4. The Town Officer, Town Committee, Khipro.
5. The Sub-Engineer, Town Committee, Khipro.
6. The Sub-Engineer, Public Health Engineering, Sanghar.
7. The Accountant, Town Committee, Khipro.
8. PS to Minister, Local Government and Housing Town Planning.
9. PS to Secretary, Local Government and Housing Town Planning Department.
10. PA to Deputy Secretary (Gen.), Local Government Department.


SECTION OFFICER (GEN./DDO)

OFFICE OF THE TOWN COMMITTEE KHIPRO DISTRICT SANGHAR
ANNUAL PROCUREMENT PLAN
(WORKS, GOODS & SERVICES)

Financial year 2016-2017

Sr.No	Description of Procurement	Quantity (where applicable)	Estimated unit cost (where applicable)	Estimated total cost	Funds allocated	Source of funds (ADPI/ Non ADP)	Proposed procurement method	Timing of procurements			Remarks
								1st Qtr	2nd Qtr	3rd Qtr	
1	Repair & Maintenance of Drain at Murad Colony T.C Khipro	N/A	0.972 M	0.972 M		OZT SHARE 2016-17	Single stage Envelop				All Procurements will be made as per SPPRA Rules-2010 (Amended 2013)
2	Providing & Lining Earth Filling at Hayat Colony T.C Khipro	N/A	0.998 M	0.998 M		OZT SHARE 2016-17	Single stage Envelop				do
3	Repair & Maintenance of Drain at Deewan Colony T.C Khipro	N/A	0.972 M	0.972 M		OZT SHARE 2016-17	Single stage Envelop				do
4	Construction of culverts at Ward no.3,4, & 6 T.C Khipro	N/A	0.951 M	0.951 M		OZT SHARE 2016-17	Single stage Envelop				do
5	Construction C.C Road at Murad Colony T.C Khipro	N/A	0.983 M	0.983 M		OZT SHARE 2016-17	Single stage Envelop				do
6	Construction of R.C.C Slabs over Open Surface Drain at Khipro City.	N/A	0.935 M	0.935 M		OZT SHARE 2016-17	Single stage Envelop				do
7	Repair & Maintenance of Drain at Safar Colony T.C Khipro	N/A	0.972 M	0.972 M		OZT SHARE 2016-17	Single stage Envelop				do



TOWN OFFICER
TOWN COMMITTEE KHIPRO
DISTRICT SANGHAR

BIDDING DATA.

- 1.1 Name of Procuring Agency: Town Committee Khipro District Sanghar
2. Brief Description Of Work: Work No: (1) Repair & Maintenance of Drain at Murad Colony T.C Khipro.
3. (a) Procuring Agency Address: Town Committee Khipro District Sanghar.
(b) Engineer's address Office of the Engineer Town Committee Khipro District Sanghar.
4. Estimated Cost Rs: 972,000/=
5. Amount of Bid Security: 2% of Bid Amount Rs: 19,440/=
6. Time Period of Bid Validity: NIL
7. Security Deposit Including Bid Security: 10%
8. Percentage, if any , to be deducted from bills:- 8%
9. Venue, Date & Time of Bid Opening:
Venue: Office of The Town Committee Khipro.
Date: / /2016.
Time: @ :00 PM
10. Time of completion from written order to commence: 06 Months
11. Deposit receipt No. Date: Amount : (In Words)

12. Liquidity Damages:- Rs. NIL

Authority Issuing Bidding Documents

ENGINEER
Town Committee Khipro.

BIDDING DATA.

- 1.1 Name of Procuring Agency: Town Committee Khipro District Sanghar
2. Brief Description Of Work: Work No: (2) Providing & Lining Earth Filling at Hayat Colony T.C Khipro.
3. (a) Procuring Agency Address: Town Committee Khipro District Sanghar.
(b) Engineer's address Office of the Engineer Town Committee Khipro District Sanghar.
4. Estimated Cost Rs: 998,300/=
5. Amount of Bid Security: 2% of Bid Amount Rs: 19,966/=
6. Time Period of Bid Validity: NIL
7. Security Deposit Including Bid Security: 10%
8. Percentage, if any , to be deducted from bills:- 8%
9. Venue, Date & Time of Bid Opening:
Venue: Office of The Town Committee Khipro.
Date: / /2016.
Time: @ :00 PM
10. Time of completion from written order to commence: 06 Months
11. Deposit receipt No. Date: Amount : (In Words)
12. Liquidity Damages:- Rs. NIL

Authority Issuing Bidding Documents

ENGINEER
Town Committee Khipro.

BIDDING DATA.

- 1.1 Name of Procuring Agency: Town Committee Khipro District Sanghar
2. Brief Description Of Work: Work No: (3) Repair & Maintenance of Drain at Deewan Colony T.C Khipro
3. (a) Procuring Agency Address: Town Committee Khipro District Sanghar.
(b) Engineer's address Office of the Engineer Town Committee Khipro District Sanghar.
4. Estimated Cost Rs: 972,000/=
5. Amount of Bid Security: 2% of Bid Amount Rs: 19,440/=
6. Time Period of Bid Validity: NIL
7. Security Deposit Including Bid Security: 10%
8. Percentage, if any , to be deducted from bills:- 8%
9. Venue, Date & Time of Bid Opening:
Venue: Office of The Town Committee Khipro.
Date: / /2016.
Time: @ :00 PM
10. Time of completion from written order to commence: 06 Months
11. Deposit receipt No. Date: Amount : (In Words)
12. Liquidity Damages:- Rs. NIL

Authority Issuing Bidding Documents

ENGINEER
Town Committee Khipro.

BIDDING DATA.

- 1.1 Name of Procuring Agency: Town Committee Khipro District Sanghar
2. Brief Description Of Work: Work No: (4) Construction of culverts at Ward no.3,4,& 6 T.C Khipro
3. (a) Procuring Agency Address: Town Committee Khipro District Sanghar.
(b) Engineer's address Office of the Engineer Town Committee Khipro District Sanghar.
4. Estimated Cost Rs: 951,600/=
5. Amount of Bid Security: 2% of Bid Amount Rs: 19,032/=
6. Time Period of Bid Validity: NIL
7. Security Deposit Including Bid Security: 10%
8. Percentage, if any , to be deducted from bills:- 8%
9. Venue, Date & Time of Bid Opening:
Venue: Office of The Town Committee Khipro.
Date: / /2016.
Time: @ :00 PM
10. Time of completion from written order to commence: 06 Months
11. Deposit receipt No. Date: Amount : (In Words)
12. Liquidity Damages:- Rs. NIL

Authority Issuing Bidding Documents

ENGINEER
Town Committee Khipro.

BIDDING DATA.

- 1.1 Name of Procuring Agency: Town Committee Khipro District Sanghar
2. Brief Description Of Work: Work No: (5) Construction C.C Road at Murad Colony T.C Khipro
3. (a) Procuring Agency Address: Town Committee Khipro District Sanghar.
(b) Engineer's address Office of the Engineer Town Committee Khipro District Sanghar.
4. Estimated Cost Rs: 983,900/=
5. Amount of Bid Security: 2% of Bid Amount Rs: 19,678/=
6. Time Period of Bid Validity: NIL
7. Security Deposit Including Bid Security: 10%
8. Percentage, if any , to be deducted from bills:- 8%
9. Venue, Date & Time of Bid Opening:
Venue: Office of The Town Committee Khipro.
Date: / /2016.
Time: @ :00 PM
10. Time of completion from written order to commence: 06 Months
11. Deposit receipt No. Date: Amount : (In Words)
12. Liquidity Damages:- Rs. NIL

Authority Issuing Bidding Documents

ENGINEER
Town Committee Khipro.

BIDDING DATA.

- 1.1 Name of Procuring Agency: Town Committee Khipro District Sanghar
2. Brief Description Of Work: Work No: (6) Construction of R.C.C Slabs over Open Surface Drain at Khipro City.
3. (a) Procuring Agency Address: Town Committee Khipro District Sanghar.
(b) Engineer's address Office of the Engineer Town Committee Khipro District Sanghar.
4. Estimated Cost Rs: 935,300/=
5. Amount of Bid Security: 2% of Bid Amount Rs: 18,706/=
6. Time Period of Bid Validity: NIL
7. Security Deposit Including Bid Security: 10%
8. Percentage, if any , to be deducted from bills:- 8%
9. Venue, Date & Time of Bid Opening:
Venue: Office of The Town Committee Khipro.
Date: / /2016.
Time: @ :00 PM
10. Time of completion from written order to commence: 06 Months
11. Deposit receipt No. Date: Amount : (In Words)
12. Liquidity Damages:- Rs. NIL

Authority Issuing Bidding Documents

ENGINEER
Town Committee Khipro.

BIDDING DATA.

- 1.1 Name of Procuring Agency: Town Committee Khipro District Sanghar
2. Brief Description Of Work: Work No: (7) Repair & Maintenance of Drain at Safar Colony T.C Khipro
3. (a) Procuring Agency Address: Town Committee Khipro District Sanghar.
(b) Engineer's address Office of the Engineer Town Committee Khipro District Sanghar.
4. Estimated Cost Rs: 972,000/=
5. Amount of Bid Security: 2% of Bid Amount Rs: 19,440/=
6. Time Period of Bid Validity: NIL
7. Security Deposit Including Bid Security: 10%
8. Percentage, if any , to be deducted from bills:- 8%
9. Venue, Date & Time of Bid Opening:
Venue: Office of The Town Committee Khipro.
Date: / /2016.
Time: @ :00 PM
10. Time of completion from written order to commence: 06 Months
11. Deposit receipt No. Date: Amount : (In Words)
12. Liquidity Damages:- Rs. NIL

Authority Issuing Bidding Documents

ENGINEER
Town Committee Khipro.

SCHEDULE "B"/BILLS QUANTITY

NIT NO. TC-KHIPRO/ 67 /2016 Dated _____ -2016

SCHEME NO. 01

NAME OF WORK: MAINTENANCE & REPAIR OF SURFACE DRAIN AT ^{MURAD} ~~ASAT~~ COLONY T.C KHIPRO.

NAME OF AGENCY: _____

S.NO	ITEM OF WORKS	RATE	UNIT	AMOUNT
------	---------------	------	------	--------

1 EXCAVATION

Excavation in foundation of Building, Bridges and other structures including dagbelling dressing, refilling around structure with excavated earth, watering and ramming. lead upto 5.00 ft. (In Ordinary soil)

Schedule of Rate Vol: III Part - II = item 18 (b) Page 4&5

Qty. 3500 Cft. @ Rs 3176.25 Per %0 Cft. Rs. 11,117 /=

2 CEMENT CONCRETE RATIO 1:4:8

Cement Concrete brick or stone ballast 1 1/2" to 2" gauge. Ratio 1:4:8

Schedule of Rate Vol: III Part - II = item 4 (b) Page 17

Qty. 1750 Cft. @ Rs 9416.28 Per % Cft. Rs. 164,785 /=

3 PUCCA BRICK WORK RATIO 1:4

Pucca brick work in foundation and plinth in cement sand mortar Ratio 1:4

Schedule of Rate Vol: III Part - II = item 4 (i-c) Page 24

Qty. 2625 Cft. @ Rs 12501.41 Per % Cft. Rs. 328,162 /=

4 Canute block

Construction of standard open surface drain Canute block 1:2:4 etc complet

Qty. 700 Rft. @ Rs 72.20 Per Rft. Rs. 50,540 /=

5 BRICK ON EDGE FLOORING

Brick on edge flooring laid in 1:6 cement mortar over a bed, 3/4" thick cement mortar Ratio 1:6

Schedule of Rate Vol: III Part - II = item 9 Page 47

Qty. 1400 Sft. @ Rs 5256.63 Per % Sft. Rs. 73,593 /=

S.NO	ITEM OF WORKS	RATE	UNIT	AMOUNT
------	---------------	------	------	--------

6 CEMENT PLASTER RATIO 1:3

Cement Plaster 1:3 upto 20.0' height. 1/2" thick.

Schedule of Rate Vol: III Part - II = item 10 (b) Page 58

Qty.	6650	Sft.	@ Rs	2344.59	Per % Sft.	Rs.	155,915	/=
Total						Rs.	784,112	/=

I am agreed to do above said work at the _____ % above/Below of S.R

CONTRACTOR

Engineer,
Town Committee
Khipro

SCHEDULE "B"/BILLS QUANTITY

NIT-NO. TC-KHIPRO/ 67 /2016 Dated _____ - -2016

SCHEME NO. 02

NAME OF WORK:

CONSTRUCTION OF EARTH WORK AT HAYAT COLONY T.C
KHIPRO.

NAME OF AGENCY:

S.No	Items	No	Length	Breadth	Depth	Quantity	Amount
1	Borrow pit excavation undressed lead upto 100' ft (b) ordinary soil.(G.S.I.No: 3 (a) P-1)						
						133190.00 2117.50 P.‰ Cft	282029.83
2	Extra lead for 2 Miles Lead						
						133190.00 5025.20 P.‰ Cft	669306.39
3	Laying earth 6" layers leveling dressing watering for compacton (Soft Ordinary or Hard Soil) (G.S.I.No: 13 (b) P-3)						
						133190.00 354.00 P.‰ Cft	47149.26
						TOTAL	998485.47

I am agreed to do above said work at the _____ % above/Below of S.R

CONTRACTOR

Engineer,
Town Committee
Khipro

Shoaib Shafi

SCHEDULE "B"/BILLS QUANTITY

NIT NO. TC-KHIPRO/ 67 /2016 Dated _____ -2016

SCHEME NO. 03

NAME OF WORK: MAINTENANCE & REPAIR OF SURFACE DRAIN AT DEWAN COLONY T.C KHIPRO.

NAME OF AGENCY: _____

S.NO	ITEM OF WORKS	RATE	UNIT	AMOUNT
------	---------------	------	------	--------

1 EXCAVATION

Excavation in foundation of Building, Bridges and other structures including dagbelling dressing, refilling around structure with excavated earth, watering and ramming lead upto 5.00 ft. (In Ordinary soil)

Schedule of Rate Vol: III Part - II = item 18 (b) Page 4&5

Qty. 3500 Cft. @ Rs 3176.25 Per %0 Cft. Rs. 11,117 /=

2 CEMENT CONCRETE RATIO 1:4:8

Cement Concrete brick or stone ballast 1 1/2" to 2" gauge. Ratio 1:4:8

Schedule of Rate Vol: III Part - II = item 4 (b) Page 17

Qty. 1750 Cft. @ Rs 9416.28 Per % Cft. Rs. 164,785 /=

3 PUCCA BRICK WORK RATIO 1:4

Pucca brick work in foundation and plinth in cement sand mortar Ratio 1:4

Schedule of Rate Vol: III Part - II = item 4 (i-c) Page 24

Qty. 2625 Cft. @ Rs 12501.41 Per % Cft. Rs. 328,162 /=

4 Canute block

Construction of standard open surface drain Canute block 1:2:4 etc complet

Qty. 700 Rft. @ Rs 72.20 Per Rft. Rs. 50,540 /=

4 BRICK ON EDGE FLOORING

Brick on edge flooring laid in 1:6 cement mortar over a bed, 3/4" thick cement mortar Ratio 1:6

Schedule of Rate Vol: III Part - II = item 9 Page 47

Qty. 1400 Sft. @ Rs 5256.63 Per % Sft. Rs. 73,593 /=

S.NO	ITEM OF WORKS	RATE	UNIT	AMOUNT
------	---------------	------	------	--------

5 CEMENT PLASTER RATIO 1:3

Cement Plaster 1:3 upto 20.0' height. 1/2" thick.

Schedule of Rate Vol: III Part - II = Item 10 (b) Page 58

Qty.	6650	Sft.	@ Rs	2344.59	Per % Sft.	Rs.	155,915	/=
Total							Rs.	784,112
								/=

I am agreed to do above said work at the _____ % above/Below of S.R

CONTRACTOR

Engineer,
Town Committee
Khipro

SCHEDULE "B"/BILLS QUANTITY

NIT NO. TC-KHIPRO/ 67 /2016 Dated _____ - -2016

SCHEME NO. 04

NAME OF WORK: CONSTRUCTION OF CULVERTS AT WARD NO 3,4,6 T.C KHIPRO

NAME OF AGENCY: _____

S.No	Items	No	Length	Breadth	Depth	Quantity	Amount
1	Excavation in foundation building bridges and other structures including level dressing refilling around structure with excavated earth watering and ramming lead upto 5' ft height (GSI No. 1 page- 38)						
			151.25	3176.25		P.%o Cft	480.41
2	Cement Concrete brick or stone ballast 1 1/2" to 2" in ratio (1:5:10) etc complete (S.I.No: 4C, P-15)						
			30.25	8694.50		P.% Cft	2630.09
3	Cement Concrete palin (1:2:4) i/c placing compacting finishing and curing complete i/c screening & washing of stone aggregate without shuttering (G.S.I.No:5, P-17)						
			11.00	11288.75		P.% Cft	1241.76
4	Pacca Brick work in foundation and plinth in cement sand mortar (1:6) (GSI No. 4 (I) Page – 23)						
			88.35	11948.36		P.% Cft	10555.78
5	Reinforced Cement Concrete work i/c all labour & material except the cost of steel reinforced & its labour for bending & binding which will be paid separately this rate also i/c all kinds of forms moulds lifting shuttering curing rendering & finishing the exposed surface i/c screening & washing of shingle.(a) R.C. work in roof slab, beams columns rafts lintels & other structural members laid in situ or pre-cast laid in position completed in all respects Ratio (1:2:4) 90 lbs cement 2 Cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I.No: 6 , P-18)						
			41.25	337.00		P .Cft	13901.25

S.No	Items	No	Length	Breadth	Depth	Quantity	Amount
------	-------	----	--------	---------	-------	----------	--------

- 6 Fabrication of mild steel reinforced for cement concrete i/c cutting, bending, laying, in position making joints & fastenings i/c cost of binding wire also i/c removal of rust from bars (G.S.I. No: 7 (ii), P-20)

2.03 5001.70 P .Cwt 10131.79

- 7 Cement plaster (1:4) upto 20' ft height ½" thick (GSI No. 13 (b) Page- 58)

131.82 2206.60 P.% Sft 2908.63

TOTAL 41849.71

Add 19 No. Culverts = 795144.43

I am agreed to do above said work at the _____ % above/Below of S.R

CONTRACTOR

Engineer,
Town Committee
Khipro

SCHEDULE "B"/BILLS QUANTITYNIT NO. TC-KHIPRO/ 67 /2016 Dated _____ -2016SCHEME NO. 05NAME OF WORK: CONSTRUCTION OF C.C ROAD MURAD COLONY T.C KHIPRO.

NAME OF AGENCY: _____

S#	DESCRIPTION	No.	L	B	D/H	TOTAL
1	Barrow pit excavated undressed lead up to 100 ft (a) Ordinary soil.					
		14560 Cft	@	Rs. 2117.5	P.%0 Cft	Rs. 30831
2	Cement con crete brick or stone bllast 1-1/2" to 2" guage ratio 1:4:8					
		3120 Cft	@	Rs. 9416.28	P.%0 Cft	Rs. 293788
3	Cement concrete plain i/c placing compacting finishing curing complete (i/c screening and washing of stone aggregate without shuttering (GSI No. 5 (i) P-18)					
		2309 Cft	@	Rs. 14429.25	P.%0 Cft	Rs. 333171
4	Erection and removing centering for RCC in plain cement concrete work (GSI No. 5 P-18)					
		603 Cft	@	Rs. 3127.41	P.%0 Cft	Rs. 18858
Total						Rs. 676648.40

I am agreed to do above said work at the _____ % above/Below of S.R

CONTRACTOR

Engineer,
Town Committee
Khipro

SCHEDULE "B"/BILLS QUANTITY

NIT NO. TC-KHIPRO/ 67 /2016 Dated _____ -2016

SCHEME NO. 06

NAME OF WORK: CONSTRUCTION OF R.C.C SLABS OVER OPEN SURFACE DRAINS T.C KHIPRO.

NAME OF AGENCY: _____

S.NO	ITEM OF WORKS	RATE	UNIT	AMOUNT
------	---------------	------	------	--------

1 6 FEBRICATION

Febrication of mild steel reinforcement for cement concrete including cutting, bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars.)

Schedule of Rate Vol: III Part - II = Item 7 (II- a) Page 20

Qty. 73.66 Cwt. @ Rs 4820.20 Per Cwt.

Rs. 355,059 /=

2 0 R.C.C. WORK. RATIO 1:2:4

Reinforced cement concrete work including all labour and materials except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle).R.C.work in roof slab, beams, columns rafts, lintels and other structural members laid in situ or precast laid in position complete in all respects. Ratio (1:2:4) 90 lbs cement 2 Cft. sand 4 Cft. Shingle 1/8" to 1/4" gauge

Schedule of Rate Vol: III Part - II = Item 6 - a (I) Page 18 & 19

Qty. 1500 Cft. @ Rs 337.00 Per Cft.

Rs. 505,500 /=

Total

Rs. 860,559 /=

I am agreed to do above said work at the _____ % above/Below of S.R

CONTRACTOR

Engineer,
Town Committee
Khipro

SCHEDULE "B"/BILLS QUANTITY

NIT NO. TC-KHIPRO/ 67 /2016 Dated _____ -2016

SCHEME NO. 07

NAME OF WORK: MAINTENANCE & REPAIR OF SURFACE DRAIN AT Safar colony T.C Khipro.

NAME OF AGENCY: _____

S.NO	ITEM OF WORKS	RATE	UNIT	AMOUNT
------	---------------	------	------	--------

1 EXCAVATION

Excavation in foundation of Building, Bridges and other structures including dagbelling dressing, refilling around structure with excavated earth, watering and ramming lead upto 5.00 ft. (In Ordinary soil)

Schedule of Rate Vol: III Part - II = Item 18 (b) Page 4&5

Qty. 3500 Cft. @ Rs 3176.25 Per %0 Cft. Rs. 11,117 /=-

2 CEMENT CONCRETE RATIO 1:4:8

Cement Concrete brick or stone ballast 1 1/2" to 2" gauge. Ratio 1:4:8

Schedule of Rate Vol: III Part - II = Item 4 (b) Page 17

Qty. 1750 Cft. @ Rs 9416.28 Per % Cft. Rs. 164,785 /=-

3 PUGCA BRICK WORK RATIO 1:4

Pucca brick work in foundation and plinth in cement sand mortar Ratio 1:4

Schedule of Rate Vol: III Part - II = Item 4 (1-c) Page 24

Qty. 2625 Cft. @ Rs 12501.41 Per % Cft. Rs. 328,162 /=-

4 Canute block

Construction of standard open surface drain Canute block 1:2 1/2 c/c completed

Qty. 700 Rft. @ Rs 72.20 Per Rft. Rs. 50,540 /=-

5 BRICK ON EDGE FLOORING

Brick on edge flooring laid in 1:6 cement mortar over a bed, 3/4" thick cement mortar Ratio 1:6

Schedule of Rate Vol: III Part - II = Item 9 Page 47

Qty. 1400 Sft. @ Rs 5256.63 Per % Sft. Rs. 73,593 /=-

S.NO	ITEM OF WORKS	RATE	UNIT	AMOUNT
------	---------------	------	------	--------

6 CEMENT PLASTER RATIO 1:3

Cement Plaster 1:3 upto 20.0' height. 1/2" thick.

Schedule of Rate Vol: III Part - II = Item 10 (b) Page 58

Qty. 6650 Sft. @ Rs 2344.59 Per % Sft.

Rs. 155,915 /=

Total

Rs. 784,112 /=

I am agreed to do above said work at the _____ % above/Below of S.R

CONTRACTOR

Engineer,
Town Committee
Khalpi

Shoaib Shafi