

OFFICE OF THE EXECUTIVE ENGINEER (BUILDINGS) DIVISION,
DISTRICT JAMSHORO

Add: Opposite Irrigation Work Shop Near NADRA Office Kotri, Taluka Kotri, District Jamshoro.

E-mail: m_aslam_tanloy@yahoo.com Phone 022-3874164.

No. XEN/(B)/TC/G-55/03.

Jamshoro Dated. 02-01-2017.

NOTICE INVITING TENDERS

Sealed Tenders on Standard Bidding Documents are invited from the Interested Firms / Agencies / Contractors Under SPP Rules - 2010 for the following works:-

Sr. No.	Name of Schemes / Sectors	Estimate Cost (In Million)	Earnest Money	Cost of Printing & Providing Documents	Time of Completion
Annual Development Program for year (2016-17)					
1	ADP 9, Construction of Office of Assistant Engineer, Public Health Engineering, Sub Division Kotri, Taluka Kotri, District Jamshoro.				
	Part - A (Remaining Work)	4.000	5%	3000	12 Months
	Part - B (Electric Work)	0.500	5%	750	06 Months
2	ADP. 11, Renovation / Extension of Room of Defunct District Council Residential Quarters near Zila Nazim Office, Taluka Kotri (Electric Work).	0.300	5%	500	06 Months
3	ADP. 12, Renovation / Extension of Room of Defunct District Council Residential Quarters near GPS Kotri, Taluka Kotri (Electric Work).	0.300	5%	500	06 Months
4	ADP. 15, Construction of Assistant Commissioner Office / Bungalow at Kotri, Taluka Kotri, District Jamshoro (Electric Work).	0.500	5%	750	06 Months
5	ADP. 112, Rehabilitation of Sewerage Line Labour Squire and CC Block Labour Squire, Taluka Kotri (Remaining Work).	1.200	5%	2000	12 Months
6	ADP. 223, Repair & Renovation of Imam Bargah Abul Fazal Abbas Bhattai Colony, Taluka Kotri (Electric Work).	0.300	5%	500	06 Months
7	ADP. 411, Up-Gradation of Government Dispensary to Basic Health Unit Behar Colony (G+3) Phase - I Taluka Kotri, District Jamshoro (Electric Work).	0.600	5%	1000	06 Months
8	ADP. 413, Construction of Government Dispensary at Village Mohammad Ishaque Khoso, Taluka Kotri.				
	Part - A (Remaining Work)	5.000	5%	3000	12 Months
	Part - B (Electric Work)	0.500	5%	750	06 Months
9	ADP. 433, Remaining Work of BHU at Village Din Mohammad Aqlani, Taluka T.B. Khan, District Jamshoro (Electric Work).	0.300	5%	500	06 Months
10	ADP. 434, Up-Gradation of Service of Taluka Hospital Thana Bula Khan, District Jamshoro (Electric Work).	0.600	5%	1000	06 Months
11	ADP. 435, Renovation / Rehabilitation of Taluka Hospital Thana Bula Khan, District Jamshoro.				
	Part - A (Remaining Work)	3.000	5%	3000	12 Months
	Part - B (Electric Work)	0.800	5%	1500	06 Months

05
02-01-17

Sr. No.	Name of Schemes / Sectors	Estimate Cost (In Million)	Earnest Money	Cost of Printing & Providing Documents	Time of Completion
12	ADP. 436, Up-Gradation of BHU to the Level of 20 Badded RHC at Thana Ahmed Khan (Ward Block / Indoor Block) T.B. Khan.				
	Part - A (Remaining Work)	3.000	5%	3000	12 Months
	Part - B (Electric Work)	0.800	5%	1500	06 Months
13	ADP. 437, Up-Gradation of BHU to the Level of 20 Badded RHC at Sari Taluka T.B. Khan (Ward Block / Indoor Block).				
	Part - A (Remaining Work)	3.000	5%	3000	12 Months
	Part - B (Electric Work)	0.800	5%	1500	06 Months
14	ADP. 438, Rehabilitation / Construction of Basic Health Unit at Toung Sharif Taluka Thana Bula Khan.				
	Part - A (Remaining Work)	3.000	5%	3000	12 Months
	Part - B (Electric Work)	0.800	5%	1500	06 Months
15	ADP. 439, Up-Gradation of BHU to the Level of 20 Badded RHC at Mole Taluka T.B. Khan (Ward Block / Indoor Block).				
	Part - A (Remaining Work)	3.000	5%	3000	12 Months
	Part - B (Electric Work)	0.800	5%	1500	06 Months
16	Construction of Hall & Verandah @ Premises of T.T.C Collage, Taluka Kotri, District Jamshoro.				
	Part - A (Civil Work)	2.500	5%	2000	12 Months
	Part - B (Electric Work)	0.500	5%	750	06 Months

Tender will be issued to the contractors on payment of cost of printing and providing documents shown above (Non Refundable) upto **23-01-2017**, from the office of undersigned. Tender will be received back on **23-01-2017**, at 01 :00 P.M and tender will be opened on **23-01-2017**, at 02:00 P.M in presence of contractor or their representative who wish to remain present before committee, comprises over the Superintending Engineer (Works & Services) Department Jamshoro & Executive Engineer Buildings (Division) Works & Services Jamshoro & Executive Engineer Public Health Engineering Division, District Jamshoro.

Conditional tender / tenders not with the Call deposit from any recognized Bank in Pakistan equal to 2% of the bid will not be entertained.

Blank Tender forms / description of work / scheme can be had from the office of the undersigned on any working day.

"The applicant must be registered with Federal Board of Revenue (FBR) and Sindh Revenue of Board, when certificate should be attached alongwith tender form at the time of submission of bid".

"The Government Contractor (s) have to submit an affidavit that all documents / information presented by him is correct / accurate.

[In case of holiday the tender will be opened on the next working day].

"The Procuring Agency may reject all or any bids subject to the relevant provision of SPP Rules" 2010.

[The place of tenders issued & opening is Executive Engineer Buildings Division (W&S) Jamshoro at Kotri Opposite Irrigation Work Shop, Taluka Kotri].

Sr. No.	Name of Schemes / Sectors	Estimate Cost (In Million)	Earnest Money	Cost of Printing & Providing Documents	Time of Completion
---------	---------------------------	----------------------------	---------------	--	--------------------

In case of no response the issue and opening date of tender will be as under.

Second Attempt Tender will be issued upto **08-02-2017** at 01:00 PM received and Opened on **08-02-2017** (02:00 PM).


Note: This NIT can be seen on Sindh Govt Web Site at www.sindh.gov.pk.

Note: This NIT can be seen on SPPRA Web Site at www.pprasindh.gov.pk.

EXECUTIVE ENGINEER (BUILDINGS)
DIVISION (WORKS & SERVICES)
DISTRICT JAMSHORO

Copy f.w.cs for kind information and necessary action:-

- 1 The Secretary to Government of Sindh Information Technology Department, 1st Floor Sindh Secretariat No. 06, Karachi, for information and necessary action.
- 2 The Director information Advertisement, Public relation Department, Govt of Sindh Block 96 Sindh Secretariat Building Karachi alongwith six copies for publication and inseration in three leading news papers i.e. Urdu, English, Sindhi.
- 3 The Managing Director Sindh Public Procurement Regulatory Authority, Services General Administration & Coordination Department, Barrack No. 8, Sindh Secretariat No. 4-A, Court Road Karachi, for information and necessary action.
- 4 The Deputy Commissioner District Jamshoro for information.
- 5 The Superintending Engineer (W&S) Jamshoro for information with a request to kindly regularize the action taken by the undersigned in the interest of public service.
- 6 Copy for Notice Board.


EXECUTIVE ENGINEER (BUILDINGS)
DIVISION (WORKS & SERVICES)
DISTRICT JAMSHORO



**GOVERNMENT OF SINDH
WORKS & SERVICES DEPARTMENT**

Karachi, dated: 7 March, 2016.

NOTIFICATION

No.E&A(W&S)3-9/91-2016(Jamshoro): With the approval of Competent Authority, a Complaint Redressal Committees with the following composition, in terms of Rule-31 of Sindh Public Procurement Rules-2010 (Amended 2013), is hereby constituted in the Office of Executive Engineer, Buildings Division, Jamshoro for the purpose of redressal of grievances and settlement of disputes, if any, arises between procuring agency and bidders:-

- | | |
|---|----------|
| 1. Chief Engineer (Buildings), Hyderabad. | Chairman |
| 2. District Accounts Officer or his representative. | Member |
| 3. An independent professional from the relevant field
(Technical Expert) from Market privately, who is well versed
with procurement process under SPPRA Rules, 2010. | Member |

2. The Functions & Responsibilities of the Committee will be same as specified in Rules-31 (4) and (5) of Sindh Public Procurement Rules-2010 (Amended 2013).


SECRETARY TO GOVT. OF SINDH

No.E&A(W&S)3-9/91-2016(Jamshoro)

Karachi, dated the 7 March, 2016.

A copy is forwarded for information to:-

1. The Accountant General, Sindh, Karachi.
2. The Managing Director, SPPRA, Karachi.
3. The Chief Engineer (Highways), Hyderabad.
4. The Chairman / Members of the Committee.
5. The Deputy Director (Monitoring), PM&E Cell, W&SD.
6. P.S to Secretary, W&S Department.
7. Notification file.


SECTION OFFICER (GENERAL)
FOR SECRETARY TO GOVT. OF SINDH



**GOVERNMENT OF SINDH
WORKS & SERVICES DEPARTMENT**

Karachi dated the 5th October, 2016.

NOTIFICATION

No.E&A(W&S)3-9/91/2013 : In partial modification of this Department's Notification of even number dated 05-08-2014 and with the approval of Competent Authority, Procurement Committee, in terms of Rule-7 of Sindh Public Procurement Rules-2010 (Amended 2013), is hereby constituted for procurement of "Goods / Works" in the Office of **Executive Engineer, Highways/Buildings Division JAMSHORO** excluding, procurement involving foreign exchange, with the following composition:-

1.	Superintending Engineer (W&S), Jamshoro	Chairman
2.	Executive Engineer (Highways/Buildings), Jamshoro	Member
3.	Executive Engineer, Public Health Engineering Division, Jamshoro	Member

2. The Functions & Responsibilities of the Committee will be same as specified in Rule-7 & 8 of Sindh Public Procurement Rules-2010.


SECRETARY TO GOVT. OF SINDH

No.E&A(W&S)3-9/2013

Karachi, dated the 5th October, 2016.

A copy is forwarded for information to:-

1. The Accountant General, Sindh, Karachi.
2. The Managing Director, SPPRA, Karachi.
3. The Chief Engineer (Buildings), Hyderabad.
4. The Chairman / Members of the Committee.
5. The Deputy Director (Monitoring), PM&E Cell, W&SD.
6. P.S to Minister, Works & Services Sindh.
7. P.S to Secretary, W&S Department.
8. Notification file.


**SECTION OFFICER (GENERAL)
FOR SECRETARY TO GOVT. OF SINDH**

**ANNUAL PROCUREMENT PLAN
FINANCIAL YEAR 2016-2017**

ANNUAL PROCUREMENT PLAN CURRENT FINANCIAL YEAR 2016-2017
UNDER THE OFFICE OF THE EXECUTIVE ENGINEER BUILDINGS DIVISION WORKS & SERVICES DEPARTMENT JAMSHORO

Sr. No.	Description of Procurement	Quantity Where Applicable	Estimated Unit Cost Applicable	Estimated Total Cost	Funds Allocated	Source of Funds (ADP / Non ADP)	Proposed Procurement Method	Timing of Procurements				Remarks
								1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	
1	ADP 9. Construction of Office of Assistant Engineer, Public Health Engineering, Sub Division Kotri, Taluka Kotri, District Jamshoro. Part - A (Remaining Work) Part - B (Electric Work)	3	4.0000	4.0000	4.0000	ADP	Single - Stage One Envelop Procedure.	-	-	-	-	
2	ADP 11. Renovation / Extension of Room of Defunct District Council Residential Quarters near Zila Nazim Office, Taluka Kotri (Electric Work)	N/A	0.5000	0.5000	0.5000	ADP	Single - Stage One Envelop Procedure.	-	-	-	-	
3	ADP 12. Renovation / Extension of Room of Defunct District Council Residential Quarters near GPS Kotri, Taluka Kotri (Electric Work)	N/A	0.3000	0.3000	0.3000	ADP	Single - Stage One Envelop Procedure.	-	-	-	-	
4	ADP 15. Construction of Assistant Commissioner Office / Bungalow at Kotri, Taluka Kotri, District Jamshoro (Electric Work)	N/A	0.5000	0.5000	0.5000	ADP	Single - Stage One Envelop Procedure.	-	-	-	-	
5	ADP 112. Rehabilitation of Sewerage Line Labour Squire and CC Block Labour Squire, Taluka Kotri (Remaining Work)	N/A	1.2000	1.2000	1.2000	ADP	Single - Stage One Envelop Procedure.	-	-	-	-	
6	ADP 223. Repair & Renovation of Imam Bargah Abul Fazal Abbas Bhattai Colony, Taluka Kotri (Electric Work)	N/A	0.3000	0.3000	0.3000	ADP	Single - Stage One Envelop Procedure.	-	-	-	-	
7	ADP 411. Up-Gradation of Government Dispensary to Basic Health Unit Behar Colony (G+3) Phase - I Taluka Kotri, District Jamshoro (Electric Work).	N/A	0.6000	0.6000	0.6000	ADP	Single - Stage One Envelop Procedure.	-	-	-	-	
8	ADP 413. Construction of Government Dispensary at Village Mohammad Ichhaque Khoso, Taluka Kotri. Part - A (Remaining Work) Part - B (Electric Work)	N/A	5.0000	5.0000	5.0000	ADP	Single - Stage One Envelop Procedure.	-	-	-	-	
9	ADP 433. Remaining Work of BHU at Village Din Mohammad Aqlani, Taluka T.B. Khan, District Jamshoro (Electric Work)	N/A	0.3000	0.3000	0.3000	ADP	Single - Stage One Envelop Procedure.	-	-	-	-	

Sr. No.	Description of Procurement	Quantity Where Applicable	Estimated Unit Cost Applicable	Estimated Total Cost	Funds Allocated	Source of Funds (ADP / Non ADP)	Proposed Procurement Method	Timing of Procurements				Remarks
								1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	
1	2	3	4	5	6	7	8	9	10	11	12	13
10	ADP - 434. Up-Gradation of Service of Taluka Hospital Thana Bula Khan, District Jamsoro (Electric Work).	N/A	0.6000	0.6000	0.6000	ADP	Single - Stage One Envelop Procedure	-	-	-	-	
11	ADP - 435. Renovation / Rehabilitation of Taluka Hospital Thana Bula Khan, District Jamsoro. Part - A (Remaining Work)	N/A	3.0000	3.0000	3.0000	ADP	Single - Stage One Envelop Procedure.	-	-	-	-	
12	ADP - 436. Up-Gradation of BHU to the Level of 20 Badded RHC at Thana Ahmed Khan (Ward Block / Indoor Block) T.B. Khan. Part - B (Electric Work)	N/A	0.8000	0.8000	0.8000	ADP	Single - Stage One Envelop Procedure.	-	-	-	-	
13	ADP - 437. Up-Gradation of BHU to the Level of 20 Badded RHC at Sarf Taluka T.B. Khan (Ward Block / Indoor Block). Part - A (Remaining Work)	N/A	3.0000	3.0000	3.0000	ADP	Single - Stage One Envelop Procedure.	-	-	-	-	
14	ADP - 438. Rehabilitation / Construction of Basic Health Unit at Toung Sharif Taluka Thana Bula Khan. Part - A (Remaining Work)	N/A	0.8000	0.8000	0.8000	ADP	Single - Stage One Envelop Procedure.	-	-	-	-	
15	ADP - 439. Up-Gradation of BHU to the Level of 20 Badded RHC at Mole Taluka T.B. Khan (Ward Block / Indoor Block). Part - A (Remaining Work)	N/A	3.0000	3.0000	3.0000	ADP	Single - Stage One Envelop Procedure.	-	-	-	-	
16	Construction of Hall & Verandah @ Premises of T.T.C Collage, Taluka Kotri, District Jamsoro. Part - A (Civil Work)	N/A	2.5000	2.5000	2.5000	ADP	Single - Stage One Envelop Procedure.	-	-	-	-	
	Part - B (Electric Work)	N/A	0.5000	0.5000	0.5000	ADP	Single - Stage One Envelop Procedure.	-	-	-	-	



EXECUTIVE ENGINEER (BUILDINGS)
Division (Works & Services),
District Jamsoro

BIDDING DATA

(This section should be filled in by the Office of the Executive Engineer Buildings Division, Works & Services Jamshoro before issuance of the bidding documents).

- (a) Name of Procuring Agency:- The Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro.
- (b) Brief Description of Works:- ADP. 9, Construction of Office of Assistant Engineer, Public Health Engineering, Sub Division Kotri, Taluka Kotri, District Jamshoro Part - A (Remaining Work).
- (c) Procuring Agency Address:- Office of the Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro Opposite Irrigation Work Shop at Kotri.
- (d) Estimated Cost:- Rs. 4.000 (Million)
- (e) Amount of Bid Security:- Rs. 200000/-
- (f) Period of Bid Validity (Days):- (90 Days)
- (g) Security Deposit (i/c Bid Security):- (11 %).
- (h) Percentage, if any, to be deducted from bills:- (7.5% Income Tax Deduction & 6% Security Deposit)
- (i) Deadline for submission of Bids alongwith time:- 23-01-2017 @ 01:00 (P.M).
- (j) Venue, Time, and Date of Bid Opening:- 23-01-2017 @ 02:00 (P.M).
- (k) Time for completion from written order of Commence:- 12 Months
- (l) Liquidity Damages:- (01% On Estimated Cost).

BIDDING DATA

(This section should be filled in by the Office of the Executive Engineer Buildings Division, Works & Services Jamshoro before issuance of the bidding documents).

- (a) Name of Procuring Agency:- The Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro.
- (b) Brief Description of Works:- ADP. 9, Construction of Office of Assistant Engineer, Public Health Engineering, Sub Division Kotri, Taluka Kotri, District Jamshoro Part - B (Electric Work).
- (c) Procuring Agency Address:- Office of the Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro Opposite Irrigation Work Shop at Kotri.
- (d) Estimated Cost:- Rs. 0.500 (Million)
- (e) Amount of Bid Security:- Rs. 25000/-
- (f) Period of Bid Validity (Days):- (90 Days)
- (g) Security Deposit (i/c Bid Security):- (11 %).
- (h) Percentage, if any, to be deducted from bills:- (7.5% Income Tax Deduction & 6% Security Deposit)
- (i) Deadline for submission of Bids alongwith time:- 23-01-2017 @ 01:00 (P.M).
- (j) Venue, Time, and Date of Bid Opening:- 23-01-2017 @ 02:00 (P.M).
- (k) Time for completion from written order of Commence:- 06 Months
- (l) Liquidity Damages:- (01% On Estimated Cost).

BIDDING DATA

(This section should be filled in by the Office of the Executive Engineer Buildings Division, Works & Services Jamshoro before issuance of the bidding documents).

- (a) Name of Procuring Agency:- The Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro.
- (b) Brief Description of Works:- ADP. 11, Renovation / Extension of Room of Defunct District Council Residential Quarters near Zila Nazim Office, Taluka Kotri (Electric Work).
- (c) Procuring Agency Address:- Office of the Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro Opposite Irrigation Work Shop at Kotri.
- (d) Estimated Cost:- Rs. 0.300 (Million)
- (e) Amount of Bid Security:- Rs. 15000/-
- (f) Period of Bid Validity (Days):- (90 Days)
- (g) Security Deposit (i/c Bid Security):- (11 %).
- (h) Percentage, if any, to be deducted from bills:- (7.5% Income Tax Deduction & 6% Security Deposit)
- (i) Deadline for submission of Bids alongwith time:- 23-01-2017 @ 01:00 (P.M).
- (j) Venue, Time, and Date of Bid Opening:- 23-01-2017 @ 02:00 (P.M).
- (k) Time for completion from written order of Commence:- 06 Months
- (l) Liquidity Damages:- (01% On Estimated Cost).

BIDDING DATA

(This section should be filled in by the Office of the Executive Engineer Buildings Division, Works & Services Jamshoro before issuance of the bidding documents).

- (a) Name of Procuring Agency:- The Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro.
- (b) Brief Description of Works:- ADP. 12, Renovation / Extension of Room of Defunct District Council Residential Quarters near GPS Kotri, Taluka Kotri (Electric Work).
- (c) Procuring Agency Address:- Office of the Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro Opposite Irrigation Work Shop at Kotri.
- (d) Estimated Cost:- Rs. 0.300 (Million)
- (e) Amount of Bid Security:- Rs. 15000/-
- (f) Period of Bid Validity (Days):- (90 Days)
- (g) Security Deposit (i/c Bid Security):- (11 %).
- (h) Percentage, if any, to be deducted from bills:- (7.5% Income Tax Deduction & 6% Security Deposit)
- (i) Deadline for submission of Bids alongwith time:- 23-01-2017 @ 01:00 (P.M).
- (j) Venue, Time, and Date of Bid Opening:- 23-01-2017 @ 02:00 (P.M).
- (k) Time for completion from written order of Commence:- 06 Months
- (l) Liquidity Damages:- (01% On Estimated Cost).

BIDDING DATA

(This section should be filled in by the Office of the Executive Engineer Buildings Division, Works & Services Jamshoro before issuance of the bidding documents).

- (a) Name of Procuring Agency:- The Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro.
- (b) Brief Description of Works:- ADP. 15, Construction of Assistant Commissioner Office / Bungalow at Kotri, Taluka Kotri, District Jamshoro (Electric Work).
- (c) Procuring Agency Address:- Office of the Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro Opposite Irrigation Work Shop at Kotri.
- (d) Estimated Cost:- Rs. 0.500 (Million)
- (e) Amount of Bid Security:- Rs. 25000/-
- (f) Period of Bid Validity (Days):- (90 Days)
- (g) Security Deposit (i/c Bid Security):- (11 %).
- (h) Percentage, if any, to be deducted from bills:- (7.5% Income Tax Deduction & 6% Security Deposit)
- (i) Deadline for submission of Bids alongwith time:- 23-01-2017 @ 01:00 (P.M).
- (j) Venue, Time, and Date of Bid Opening:- 23-01-2017 @ 02:00 (P.M).
- (k) Time for completion from written order of Commence:- 06 Months
- (l) Liquidity Damages:- (01% On Estimated Cost).

BIDDING DATA

(This section should be filled in by the Office of the Executive Engineer Buildings Division, Works & Services Jamshoro before issuance of the bidding documents).

- (a) Name of Procuring Agency:- The Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro.
- (b) Brief Description of Works:- ADP. 112, Rehabilitation of Sewerage Line Labour Squire and CC Block Labour Squire, Taluka Kotri (Remaining Work).
- (c) Procuring Agency Address:- Office of the Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro Opposite Irrigation Work Shop at Kotri.
- (d) Estimated Cost:- Rs. 1.2000 (Million)
- (e) Amount of Bid Security:- Rs. 60000/-
- (f) Period of Bid Validity (Days):- (90 Days)
- (g) Security Deposit (i/c Bid Security):- (11 %).
- (h) Percentage, if any, to be deducted from bills:- (7.5% Income Tax Deduction & 6% Security Deposit)
- (i) Deadline for submission of Bids alongwith time:- 23-01-2017 @ 01:00 (P.M).
- (j) Venue, Time, and Date of Bid Opening:- 23-01-2017 @ 02:00 (P.M).
- (k) Time for completion from written order of Commence:- 12 Months
- (l) Liquidity Damages:- (01% On Estimated Cost).

BIDDING DATA

(This section should be filled in by the Office of the Executive Engineer Buildings Division, Works & Services Jamshoro before issuance of the bidding documents).

- (a) Name of Procuring Agency:- The Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro.
- (b) Brief Description of Works:- ADP. 223, Repair & Renovation of Imam Bargah Abul Fazal Abbas Bhattai Colony, Taluka Kotri (Electric Work).
- (c) Procuring Agency Address:- Office of the Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro Opposite Irrigation Work Shop at Kotri.
- (d) Estimated Cost:- Rs. 0.3000 (Million)
- (e) Amount of Bid Security:- Rs. 15000/-
- (f) Period of Bid Validity (Days):- (90 Days)
- (g) Security Deposit (i/c Bid Security):- (11 %).
- (h) Percentage, if any, to be deducted from bills:- (7.5% Income Tax Deduction & 6% Security Deposit)
- (i) Deadline for submission of Bids alongwith time:- 23-01-2017 @ 01:00 (P.M).
- (j) Venue, Time, and Date of Bid Opening:- 23-01-2017 @ 02:00 (P.M).
- (k) Time for completion from written order of Commence:- 06 Months
- (l) Liquidity Damages:- (01% On Estimated Cost).

BIDDING DATA

(This section should be filled in by the Office of the Executive Engineer Buildings Division, Works & Services Jamshoro before issuance of the bidding documents).

- (a) Name of Procuring Agency:- The Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro.
- (b) Brief Description of Works:- ADP. 411, Up-Gradation of Government Dispensary to Basic Health Unit Behar Colony (G+3) Phase - I Taluka Kotri, District Jamshoro (Electric Work).
- (c) Procuring Agency Address:- Office of the Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro Opposite Irrigation Work Shop at Kotri.
- (d) Estimated Cost:- Rs. 0.6000 (Million)
- (e) Amount of Bid Security:- Rs. 30000/-
- (f) Period of Bid Validity (Days):- (90 Days)
- (g) Security Deposit (i/c Bid Security):- (11 %).
- (h) Percentage, if any, to be deducted from bills:- (7.5% Income Tax Deduction & 6% Security Deposit)
- (i) Deadline for submission of Bids alongwith time:- 23-01-2017 @ 01:00 (P.M).
- (j) Venue, Time, and Date of Bid Opening:- 23-01-2017 @ 02:00 (P.M).
- (k) Time for completion from written order of Commence:- 06 Months
- (l) Liquidity Damages:- (01% On Estimated Cost).

BIDDING DATA

(This section should be filled in by the Office of the Executive Engineer Buildings Division, Works & Services Jamshoro before issuance of the bidding documents).

- (a) Name of Procuring Agency:- The Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro.
- (b) Brief Description of Works:- ADP. 413, Construction of Government Dispensary at Village Mohammad Ishaque Khoso, Taluka Kotri Part - A (Remaining Work).
- (c) Procuring Agency Address:- Office of the Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro Opposite Irrigation Work Shop at Kotri.
- (d) Estimated Cost:- Rs. 5.0000 (Million)
- (e) Amount of Bid Security:- Rs. 250000/-
- (f) Period of Bid Validity (Days):- (90 Days)
- (g) Security Deposit (i/c Bid Security):- (11 %).
- (h) Percentage, if any, to be deducted from bills:- (7.5% Income Tax Deduction & 6% Security Deposit)
- (i) Deadline for submission of Bids alongwith time:- 23-01-2017 @ 01:00 (P.M).
- (j) Venue, Time, and Date of Bid Opening:- 23-01-2017 @ 02:00 (P.M).
- (k) Time for completion from written order of Commence:- 12 Months
- (l) Liquidity Damages:- (01% On Estimated Cost).

BIDDING DATA

(This section should be filled in by the Office of the Executive Engineer Buildings Division, Works & Services Jamshoro before issuance of the bidding documents).

- (a) Name of Procuring Agency:- The Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro.
- (b) Brief Description of Works:- ADP. 413, Construction of Government Dispensary at Village Mohammad Ishaque Khoso, Taluka Kotri Part - B (Electric Work).
- (c) Procuring Agency Address:- Office of the Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro Opposite Irrigation Work Shop at Kotri.
- (d) Estimated Cost:- Rs. 0.5000 (Million)
- (e) Amount of Bid Security:- Rs. 25000/-
- (f) Period of Bid Validity (Days):- (90 Days)
- (g) Security Deposit (i/c Bid Security):- (11 %).
- (h) Percentage, if any, to be deducted from bills:- (7.5% Income Tax Deduction & 6% Security Deposit)
- (i) Deadline for submission of Bids alongwith time:- 23-01-2017 @ 01:00 (P.M).
- (j) Venue, Time, and Date of Bid Opening:- 23-01-2017 @ 02:00 (P.M).
- (k) Time for completion from written order of Commence:- 06 Months
- (l) Liquidity Damages:- (01% On Estimated Cost).

BIDDING DATA

(This section should be filled in by the Office of the Executive Engineer Buildings Division, Works & Services Jamshoro before issuance of the bidding documents).

- (a) Name of Procuring Agency:- The Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro.
- (b) Brief Description of Works:- ADP, 433, Remaining Work of BHU at Village Din Mohammad Aqlani, Taluka T.B. Khan, District Jamshoro (Electric Work).
- (c) Procuring Agency Address:- Office of the Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro Opposite Irrigation Work Shop at Kotri.
- (d) Estimated Cost:- Rs. 0.3000 (Million)
- (e) Amount of Bid Security:- Rs. 15000/-
- (f) Period of Bid Validity (Days):- (90 Days)
- (g) Security Deposit (i/c Bid Security):- (11 %).
- (h) Percentage, if any, to be deducted from bills:- (7.5% Income Tax Deduction & 6% Security Deposit)
- (i) Deadline for submission of Bids alongwith time:- 23-01-2017 @ 01:00 (P.M).
- (j) Venue, Time, and Date of Bid Opening:- 23-01-2017 @ 02:00 (P.M).
- (k) Time for completion from written order of Commence:- 06 Months
- (l) Liquidity Damages:- (01% On Estimated Cost).

BIDDING DATA

(This section should be filled in by the Office of the Executive Engineer Buildings Division, Works & Services Jamshoro before issuance of the bidding documents).

- (a) Name of Procuring Agency:- The Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro.
- (b) Brief Description of Works:- ADP. 434, Up-Gradation of Service of Taluka Hospital Thana Bula Khan, District Jamshoro (Electric Work).
- (c) Procuring Agency Address:- Office of the Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro Opposite Irrigation Work Shop at Kotri.
- (d) Estimated Cost:- Rs. 0.6000 (Million)
- (e) Amount of Bid Security:- Rs. 30000/-
- (f) Period of Bid Validity (Days):- (90 Days)
- (g) Security Deposit (i/c Bid Security):- (11 %).
- (h) Percentage, if any, to be deducted from bills:- (7.5% Income Tax Deduction & 6% Security Deposit)
- (i) Deadline for submission of Bids alongwith time:- 23-01-2017 @ 01:00 (P.M).
- (j) Venue, Time, and Date of Bid Opening:- 23-01-2017 @ 02:00 (P.M).
- (k) Time for completion from written order of Commence:- 06 Months
- (l) Liquidity Damages:- (01% On Estimated Cost).

BIDDING DATA

(This section should be filled in by the Office of the Executive Engineer Buildings Division, Works & Services Jamshoro before issuance of the bidding documents).

- (a) Name of Procuring Agency:- The Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro.
- (b) Brief Description of Works:- ADP. 435, Renovation / Rehabilitation of Taluka Hospital Thana Bula Khan, District Jamshoro Part - A (Remaining Work).
- (c) Procuring Agency Address:- Office of the Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro Opposite Irrigation Work Shop at Kotri.
- (d) Estimated Cost:- Rs. 3.000 (Million)
- (e) Amount of Bid Security:- Rs. 150000/-
- (f) Period of Bid Validity (Days):- (90 Days)
- (g) Security Deposit (i/c Bid Security):- (11 %).
- (h) Percentage, if any, to be deducted from bills:- (7.5% Income Tax Deduction & 6% Security Deposit)
- (i) Deadline for submission of Bids alongwith time:- 23-01-2017 @ 01:00 (P.M).
- (j) Venue, Time, and Date of Bid Opening:- 23-01-2017 @ 02:00 (P.M).
- (k) Time for completion from written order of Commence:- 12 Months
- (l) Liquidity Damages:- (01% On Estimated Cost).

BIDDING DATA

(This section should be filled in by the Office of the Executive Engineer Buildings Division, Works & Services Jamshoro before issuance of the bidding documents).

- (a) Name of Procuring Agency:- The Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro.
- (b) Brief Description of Works:- ADP. 435, Renovation / Rehabilitation of Taluka Hospital Thana Bula Khan, District Jamshoro Part - B (Electric Work).
- (c) Procuring Agency Address:- Office of the Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro Opposite Irrigation Work Shop at Kotri.
- (d) Estimated Cost:- Rs. 0.8000 (Million)
- (e) Amount of Bid Security:- Rs. 40000/-
- (f) Period of Bid Validity (Days):- (90 Days)
- (g) Security Deposit (i/c Bid Security):- (11 %).
- (h) Percentage, if any, to be deducted from bills:- (7.5% Income Tax Deduction & 6% Security Deposit)
- (i) Deadline for submission of Bids alongwith time:- 23-01-2017 @ 01:00 (P.M).
- (j) Venue, Time, and Date of Bid Opening:- 23-01-2017 @ 02:00 (P.M).
- (k) Time for completion from written order of Commence:- 06 Months
- (l) Liquidity Damages:- (01% On Estimated Cost).

BIDDING DATA

(This section should be filled in by the Office of the Executive Engineer Buildings Division, Works & Services Jamshoro before issuance of the bidding documents).

- (a) Name of Procuring Agency:- The Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro.
- (b) Brief Description of Works:- ADP. 436, Up-Gradation of BHU to the Level of 20 Badded RHC at Thana Ahmed Khan (Ward Block / Indoor Block) T.B. Khan Part - A (Remaining Work).
- (c) Procuring Agency Address:- Office of the Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro Opposite Irrigation Work Shop at Kotri.
- (d) Estimated Cost:- Rs. 3.000 (Million)
- (e) Amount of Bid Security:- Rs. 150000/-
- (f) Period of Bid Validity (Days):- (90 Days)
- (g) Security Deposit (i/c Bid Security):- (11 %).
- (h) Percentage, if any, to be deducted from bills:- (7.5% Income Tax Deduction & 6% Security Deposit)
- (i) Deadline for submission of Bids alongwith time:- 23-01-2017 @ 01:00 (P.M).
- (j) Venue, Time, and Date of Bid Opening:- 23-01-2017 @ 02:00 (P.M).
- (k) Time for completion from written order of Commence:- 12 Months
- (l) Liquidity Damages:- (01% On Estimated Cost).

BIDDING DATA

(This section should be filled in by the Office of the Executive Engineer Buildings Division, Works & Services Jamshoro before issuance of the bidding documents).

- (a) Name of Procuring Agency:- The Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro.
- (b) Brief Description of Works:- ADP. 436, Up-Gradation of BHU to the Level of 20 Badded RHC at Thana Ahmed Khan (Ward Block / Indoor Block) T.B. Khan Part - B (Electric Work).
- (c) Procuring Agency Address:- Office of the Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro Opposite Irrigation Work Shop at Kotri.
- (d) Estimated Cost:- Rs. 0.8000 (Million)
- (e) Amount of Bid Security:- Rs. 40000/-
- (f) Period of Bid Validity (Days):- (90 Days)
- (g) Security Deposit (i/c Bid Security):- (11 %).
- (h) Percentage, if any, to be deducted from bills:- (7.5% Income Tax Deduction & 6% Security Deposit)
- (i) Deadline for submission of Bids alongwith time:- 23-01-2017 @ 01:00 (P.M).
- (j) Venue, Time, and Date of Bid Opening:- 23-01-2017 @ 02:00 (P.M).
- (k) Time for completion from written order of Commence:- 12 Months
- (l) Liquidity Damages:- (01% On Estimated Cost).

BIDDING DATA

(This section should be filled in by the Office of the Executive Engineer Buildings Division, Works & Services Jamshoro before issuance of the bidding documents).

- (a) Name of Procuring Agency:- The Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro.
- (b) Brief Description of Works:- ADP. 437, Up-Gradation of BHU to the Level of 20 Badded RHC at Sari Taluka T.B. Khan (Ward Block / Indoor Block) Part - A (Remaining Work).
- (c) Procuring Agency Address:- Office of the Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro Opposite Irrigation Work Shop at Kotri.
- (d) Estimated Cost:- Rs. 3.000 (Million)
- (e) Amount of Bid Security:- Rs. 150000/-
- (f) Period of Bid Validity (Days):- (90 Days)
- (g) Security Deposit (i/c Bid Security):- (11 %).
- (h) Percentage, if any, to be deducted from bills:- (7.5% Income Tax Deduction & 6% Security Deposit)
- (i) Deadline for submission of Bids alongwith time:- 23-01-2017 @ 01:00 (P.M).
- (j) Venue, Time, and Date of Bid Opening:- 23-01-2017 @ 02:00 (P.M).
- (k) Time for completion from written order of Commence:- 12 Months
- (l) Liquidity Damages:- (01% On Estimated Cost).

BIDDING DATA

(This section should be filled in by the Office of the Executive Engineer Buildings Division, Works & Services Jamshoro before issuance of the bidding documents).

- (a) Name of Procuring Agency:- The Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro.
- (b) Brief Description of Works:- ADP. 437, Up-Gradation of BHU to the Level of 20 Badded RHC at Sari Taluka T.B. Khan (Ward Block / Indoor Block) Part - B (Electric Work).
- (c) Procuring Agency Address:- Office of the Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro Opposite Irrigation Work Shop at Kotri.
- (d) Estimated Cost:- Rs. 0.8000 (Million)
- (e) Amount of Bid Security:- Rs. 40000/-
- (f) Period of Bid Validity (Days):- (90 Days)
- (g) Security Deposit (i/c Bid Security):- (11 %).
- (h) Percentage, if any, to be deducted from bills:- (7.5% Income Tax Deduction & 6% Security Deposit)
- (i) Deadline for submission of Bids alongwith time:- 23-01-2017 @ 01:00 (P.M).
- (j) Venue, Time, and Date of Bid Opening:- 23-01-2017 @ 02:00 (P.M).
- (k) Time for completion from written order of Commence:- 06 Months
- (l) Liquidity Damages:- (01% On Estimated Cost).

BIDDING DATA

(This section should be filled in by the Office of the Executive Engineer Buildings Division, Works & Services Jamshoro before issuance of the bidding documents).

- (a) Name of Procuring Agency:- The Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro.
- (b) Brief Description of Works:- ADP. 438, Rehabilitation / Construction of Basic Health Unit at Toung Sharif Taluka Thana Bula Khan Part - A (Remaining Work).
- (c) Procuring Agency Address:- Office of the Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro Opposite Irrigation Work Shop at Kotri.
- (d) Estimated Cost:- Rs. 3.0000 (Million)
- (e) Amount of Bid Security:- Rs. 150000/-
- (f) Period of Bid Validity (Days):- (90 Days)
- (g) Security Deposit (i/c Bid Security):- (11 %).
- (h) Percentage, if any, to be deducted from bills:- (7.5% Income Tax Deduction & 6% Security Deposit)
- (i) Deadline for submission of Bids alongwith time:- 23-01-2017 @ 01:00 (P.M).
- (j) Venue, Time, and Date of Bid Opening:- 23-01-2017 @ 02:00 (P.M).
- (k) Time for completion from written order of Commence:- 12 Months
- (l) Liquidity Damages:- (01% On Estimated Cost).

BIDDING DATA

(This section should be filled in by the Office of the Executive Engineer Buildings Division, Works & Services Jamshoro before issuance of the bidding documents).

- (a) Name of Procuring Agency:- The Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro.
- (b) Brief Description of Works:- ADP. 438, Rehabilitation / Construction of Basic Health Unit at Toung Sharif Taluka Thana Bula Khan Part - B (Electric Work).
- (c) Procuring Agency Address:- Office of the Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro Opposite Irrigation Work Shop at Kotri.
- (d) Estimated Cost:- Rs. 0.8000 (Million)
- (e) Amount of Bid Security:- Rs. 40000/-
- (f) Period of Bid Validity (Days):- (90 Days)
- (g) Security Deposit (i/c Bid Security):- (11 %).
- (h) Percentage, if any, to be deducted from bills:- (7.5% Income Tax Deduction & 6% Security Deposit)
- (i) Deadline for submission of Bids alongwith time:- 23-01-2017 @ 01:00 (P.M).
- (j) Venue, Time, and Date of Bid Opening:- 23-01-2017 @ 02:00 (P.M).
- (k) Time for completion from written order of Commence:- 06 Months
- (l) Liquidity Damages:- (01% On Estimated Cost).

BIDDING DATA

(This section should be filled in by the Office of the Executive Engineer Buildings Division, Works & Services Jamshoro before issuance of the bidding documents).

- (a) Name of Procuring Agency:- The Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro.
- (b) Brief Description of Works:- ADP. 439, Up-Gradation of BHU to the Level of 20 Badded RHC at Mole Taluka T.B. Khan (Ward Block / Indoor Block) Part - A (Remaining Work).
- (c) Procuring Agency Address:- Office of the Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro Opposite Irrigation Work Shop at Kotri.
- (d) Estimated Cost:- Rs. 3.0000 (Million)
- (e) Amount of Bid Security:- Rs. 150000/-
- (f) Period of Bid Validity (Days):- (90 Days)
- (g) Security Deposit (i/c Bid Security):- (11 %).
- (h) Percentage, if any, to be deducted from bills:- (7.5% Income Tax Deduction & 6% Security Deposit)
- (i) Deadline for submission of Bids alongwith time:- 23-01-2017 @ 01:00 (P.M).
- (j) Venue, Time, and Date of Bid Opening:- 23-01-2017 @ 02:00 (P.M).
- (k) Time for completion from written order of Commence:- 12 Months
- (l) Liquidity Damages:- (01% On Estimated Cost).

BIDDING DATA

(This section should be filled in by the Office of the Executive Engineer Buildings Division, Works & Services Jamshoro before issuance of the bidding documents).

- (a) Name of Procuring Agency:- The Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro.
- (b) Brief Description of Works:- ADP. 439, Up-Gradation of BHU to the Level of 20 Badded RHC at Mole Taluka T.B. Khan (Ward Block / Indoor Block) Part - B (Electric Work).
- (c) Procuring Agency Address:- Office of the Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro Opposite Irrigation Work Shop at Kotri.
- (d) Estimated Cost:- Rs. 0.8000 (Million)
- (e) Amount of Bid Security:- Rs. 40000/-
- (f) Period of Bid Validity (Days):- (90 Days)
- (g) Security Deposit (i/c Bid Security):- (11 %).
- (h) Percentage, if any, to be deducted from bills:- (7.5% Income Tax Deduction & 6% Security Deposit)
- (i) Deadline for submission of Bids alongwith time:- 23-01-2017 @ 01:00 (P.M).
- (j) Venue, Time, and Date of Bid Opening:- 23-01-2017 @ 02:00 (P.M).
- (k) Time for completion from written order of Commence:- 06 Months
- (l) Liquidity Damages:- (01% On Estimated Cost).

BIDDING DATA

(This section should be filled in by the Office of the Executive Engineer Buildings Division, Works & Services Jamshoro before issuance of the bidding documents).

- (a) Name of Procuring Agency:- The Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro.
- (b) Brief Description of Works:- Construction of Hall & Verandah @ Premises of T.T.C Collage, Taluka Kotri, District Jamshoro Part - A (Civil Work).
- (c) Procuring Agency Address:- Office of the Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro Opposite Irrigation Work Shop at Kotri.
- (d) Estimated Cost:- Rs. 2.5000 (Million)
- (e) Amount of Bid Security:- Rs. 125000/-
- (f) Period of Bid Validity (Days):- (90 Days)
- (g) Security Deposit (i/c Bid Security):- (11 %).
- (h) Percentage, if any, to be deducted from bills:- (7.5% Income Tax Deduction & 6% Security Deposit)
- (i) Deadline for submission of Bids alongwith time:- 23-01-2017 @ 01:00 (P.M).
- (j) Venue, Time, and Date of Bid Opening:- 23-01-2017 @ 02:00 (P.M).
- (k) Time for completion from written order of Commence:- 12 Months
- (l) Liquidity Damages:- (01% On Estimated Cost).

BIDDING DATA

(This section should be filled in by the Office of the Executive Engineer Buildings Division, Works & Services Jamshoro before issuance of the bidding documents).

- (a) Name of Procuring Agency:- The Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro.
- (b) Brief Description of Works:- Construction of Hall & Verandah @ Premises of T.T.C Collage, Taluka Kotri, District Jamshoro Part - B (Electric Work).
- (c) Procuring Agency Address:- Office of the Executive Engineer (Buildings) Division Works & Services, Department, District Jamshoro Opposite Irrigation Work Shop at Kotri.
- (d) Estimated Cost:- Rs. 0.5000 (Million)
- (e) Amount of Bid Security:- Rs. 25000/-
- (f) Period of Bid Validity (Days):- (90 Days)
- (g) Security Deposit (i/c Bid Security):- (11 %).
- (h) Percentage, if any, to be deducted from bills:- (7.5% Income Tax Deduction & 6% Security Deposit)
- (i) Deadline for submission of Bids alongwith time:- 23-01-2017 @ 01:00 (P.M).
- (j) Venue, Time, and Date of Bid Opening:- 23-01-2017 @ 02:00 (P.M).
- (k) Time for completion from written order of Commence:- 06 Months
- (l) Liquidity Damages:- (01% On Estimated Cost).

Agreement 1.

Instructions to Bidders/ Executive Engineer Buildings Division Works & Services, District Jamshoro.
General Rules and Directions for the Guidance of Contractors.

This section of the bidding documents should provide the information necessary for bidders to prepare responsive bids, in accordance with the requirements of the **“Executive Engineer Buildings Division Works & Services, District Jamshoro”**. It should also give information on bid submission, opening and evaluation, and on the award of contract.

Matters governing the performance of the Contract or payments under the Contract, or matters affecting the risks, rights, and obligations of the parties under the Contract are included as Conditions of Contract and *Contract Data*.

The *Instructions to Bidders* will not be part of the Contract and will cease to have effect once the contract is signed.

1. All work proposed to be executed by contract shall be notified in a form of Notice Inviting Tender (NIT) / Invitation for Bid (IFB) hoisted on website of Authority and **“Executive Engineer Buildings Division Works & Services, District Jamshoro”** and also in printed media where ever required as per rules. NIT must state the description of the work, dates, time and place of issuing, submission, opening of bids, completion time, cost of bidding document and bid security either in lump sum or percentage of Estimated Cost/Bid Cost. The interested bidder must have valid NTN also.

2. Content of Bidding Documents must include but not limited to: Conditions of contract, Contract Data, specifications or its reference, Bill of Quantities containing description of items with scheduled / item rates with premium to be filled in form of percentage above/ below or on item rates to be quoted, Form of Agreement and drawings.

3. **Fixed Price Contracts:** The Bid prices and rates are fixed during currency of contract and under no circumstance shall any contractor be entitled to claim enhanced rates for any item in this contract.

4. The **“Executive Engineer Buildings Division Works & Services, District Jamshoro”** shall have right of rejecting all or any of the tenders as per provisions of SPP Rules 2010.

5. **Conditional Offer:** Any person who submits a tender shall fill up the usual printed form stating at what percentage above or below on the rates specified in Bill of Quantities for items of work to be carried out: he is willing to undertake the work and also quote the rates for those items which are based on market rates. Only one rate of such percentage, on all the Scheduled Rates shall be framed. Tenders, which propose any alternative in the works specified in the said form of invitation to tender or in the time allowed for carrying out the work, or which contain any other conditions, will be liable to rejection. No printed form of tender shall include a tender for more than one work, but if contractor wish to tender for two or more works, they shall submit a separate tender for each. The envelope containing the tender documents shall refer the name and number of the work.

6. All works shall be measured by standard instruments according to the rules.
7. Bidders shall provide evidence of their eligibility as and when requested by the Procuring Agency.
8. Any bid received by the Agency after the deadline for submission of bids shall be rejected and returned unopened to the bidder.
9. Prior to the detailed evaluation of bids, the “**Executive Engineer Buildings Division Works & Services, District Jamshoro**” will determine whether the bidder fulfills all codal requirements of eligibility criteria given in the tender notice such as registration with tax authorities, registration with PEC (where applicable), turnover statement, experience statement, and any other condition mentioned in the NIT and bidding document. If the bidder does not fulfill any of these conditions, it shall not be evaluated further.
10. Bid without bid security of required amount and prescribed form shall be rejected.
11. Bids determined to be substantially responsive shall be checked for any arithmetic errors. Arithmetical errors shall be rectified on the following basis:
 - (A) **In case of schedule rates**, the amount of percentage quoted above or below will be checked and added or subtracted from amount of bill of quantities to arrive the final bid cost.
 - (B) **In case of item rates**, .If there is a discrepancy between the unit rate and the total cost that is obtained by multiplying the unit rate and quantity, the unit rate shall prevail and the total cost will be corrected unless in the opinion of the Agency there is an obvious misplacement of the decimal point in the unit rate, in which case the total cost as quoted will govern and the unit rate corrected. If there is a discrepancy between the total bid amount and the sum of total costs, the sum of the total costs shall prevail and the total bid amount shall be corrected.
 - (C) Where there is a discrepancy between the amounts in figures and in words, the amount in words will govern.

CONDITIONS OF CONTRACT

Name of Work: - _____

Clause – 1: Commencement & Completion Dates of work. The contractor shall not enter upon or commence any portion or work except with the written authority and instructions of the Engineer-in-charge or of in subordinate-in-charge of the work. Failing such authority the contractor shall have no claim to ask for measurements of or payment for work.

The contractor shall proceed with the works with due expedition and without delay and complete the works in the time allowed for carrying out the work as entered in the tender shall be strictly observed by the contractor and shall reckoned from the date on which the order to commence work is given to the contractor. And further to ensure good progress during the execution of the wok, contractor shall be bound, in all in which the time allowed for completion of any work exceeds one month, to achieve progress on the prorate basis.

Clause – 2: Liquidated Damages. The contractor shall pay liquidated damages to the Agency at the rate per day stated in the bidding data for each day that the completion date is later than the Intended completion date; the amount of liquidated damage paid by the contractor to the Agency shall not exceed 10 per cent of the contract price. Agency may deduct liquidated damages from payments due to the contractor. Payment of liquidated damages does not affect the contractor's liabilities.

Clause – 3: Termination of the Contract.

(A) ““Executive Engineer Buildings Division Works & Services, District Jamshoro” may terminate the contract if either of the following conditions exits:-

- (i) Contractor causes a breach of any clause of the Contract;
- (ii) the progress of any particular portion of the work is unsatisfactory and notice of 10 days has expired;
- (iii) in the case of abandonment of the work owing to the serious illness or death of the contractor or any other cause.
- (iv) Contractor can also request for termination of contract if a payment certified by the Engineer is not paid to the contractor within 60 days of the date of the submission of the bill.

Name of Contractor. _____

(B) The ““Executive Engineer Buildings Division Works & Services, District Jamshoro” has power to adopt any of the following courses as may deem fit:-

- (i) to forfeit the security deposit available except conditions mentioned at A (iii) and (iv) above;
- (ii) to finalize the work by measuring the work done by the contractor.

**EXECUTIVE ENGINEER BUILDINGS
DIVISION JAMSHORO**

(C) In the event of any of the above courses being adopted by the “**Executive Engineer Buildings Division Works & Services, District Jamshoro**”, the contractor shall have:-

(i) no claim to compensation for any loss sustained by him by reason of his having purchased or procured any materials, or entered into any engagements, or made any advances on account of, or with a view to the execution of the work or the performance of the contract.

(ii) however, the contractor can claim for the work done at site duly certified by the executive engineer in writing regarding the performance of such work and has not been paid.

“**Executive Engineer Buildings Division Works & Services, District Jamshoro**” may invite fresh bids for remaining work.

Clause 4: Possession of the site and claims for compensation for delay. The Engineer shall give possession of all parts of the site to the contractor. If possession of site is not given by the date stated in the contract data, no compensation shall be allowed for any delay caused in starting of the work on account of any acquisition of land, water standing in borrow pits/ compartments or in according sanction to estimates. In such case, either date of commencement will be changed or period of completion is to be extended accordingly.

Clause -5: Extension of Intended Completion Date. The “**Executive Engineer Buildings Division Works & Services, District Jamshoro**” either at its own initiatives before the date of completion or on desire of the contractor may extend the intended completion date, if an event (which hinders the execution of contract) occurs or a variation order is issued which makes it impossible to complete the work by the intended completion date for such period as he may think necessary or proper. The decision of the Executive Engineer in this matter shall be final: where time has been extended under this or any other clause of this agreement, the date for completion of the work shall be the date fixed by the order giving the extension or by the aggregate of all such orders, made under this agreement.

When time has been extended as aforesaid, it shall continue to be the essence of the contract and all clauses of the contract shall continue to be operative during the extended period.

Clause -6: Specifications. The contractor shall execute the whole and every part of the work in the most substantial and work-man-like manner and both as regards materials and all other matters in strict accordance with the specifications lodged in the office of the Executive Engineer and initialed by the parties, the said specification being a part of the contract. The contractor shall also confirm exactly, fully and faithfully to the designs, drawing, and instructions in writing relating to the work signed by the Engineer-in-charge and lodge in his office and to which the contractor shall be entitled to have access at such office or on the site of work for the purpose of inspection during office hours and the contractor shall, if he so requires, be entitled at his own expense to make or cause to be made copies of the specifications, and of all such designs, drawings, and instructions as aforesaid.

Clause - 7: Payments.

(A) Interim / Running Bill. A bill shall be submitted by the contractor as frequently as the progress of the work may justify for all work executed and not included in any previous bill at least once in a month and the Engineer-in-charge shall take or cause to be taken the requisite measurements for the purpose of having the same verified and the

claim, as far as admissible, adjusted, if possible before the expiry of ten days from the presentation of the bill, at any time depute a subordinate to measure up the said work in the presence of the contractor or his authorized agent, whose countersignature to the measurement list will be sufficient to warrant and the Engineer-in-charge may prepare a bill from such list which shall be binding on the contractor in all respects.

The Engineer / **“Executive Engineer Buildings Division Works & Services, District Jamshoro”** shall pass/certify the amount to be paid to the contractor, which he considers due and payable in respect thereof, subject to deduction of security deposit, advance payment if any made to him and taxes.

All such intermediate payment shall be regarded as payments by way of advance against the final payment only and not as payments for work actually done and completed, and shall not preclude the Engineer-in-charge from recoveries from final bill and rectification of defects and unsatisfactory items of works pointed out to him during defect liability period.

(B) The Final Bill. A bill shall be submitted by the contractor within one month of the date fixed for the completion of the work otherwise Engineer-in-charge's certificate of the measurements and of the total amount payable for the works shall be final and binding on all parties.

Clause – 8: Reduced Rates. In cases where the items of work are not accepted as so completed, the Engineer-in-charge may make payment on account of such items at such reduced rates as he may consider reasonable in the preparation of final or on running account bills with reasons recorded in writing.

Clause – 9: Issuance of Variation and Repeat Orders.

(A) Agency may issue a Variation Order for procurement of works, physical services from the original contractor to cover any increase or decrease in quantities, including the introduction of new work items that are either due to change of plans, design or alignment to suit actual field conditions, within the general scope and physical boundaries of the contract.

(B) Contractor shall not perform a variation until the **“Executive Engineer Buildings Division Works & Services, District Jamshoro”** has authorized the variation in writing subject to the limit not exceeding the contract cost by of 15% on the same conditions in all respects on which he agreed to do them in the work, and at the same rates, as are specified in the tender for the main work. The contractor has no right to claim for compensation by reason of alterations or curtailment of the work.

(C) In case the nature of the work in the variation does not correspond with items in the Bill of Quantities, the quotation by the contractor is to be in the form of new rates for the relevant items of work, and if the Engineer-in-charge is satisfied that the rate quoted is within the rate worked out by him on detailed rate analysis, and then only he shall allow him that rate after approval from higher authority.

(D) The time for the completion of the work shall be extended in the proportion that the additional work bear to the original contract work.

(E) In case of quantities of work executed result the Initial Contract Price to be exceeded by more than 15%, and then Engineer can adjust the rates for those quantities causing excess the cost of contract beyond 15% after approval of Superintending Engineer.

(F) Repeat Order: Any cumulative variation, beyond the 15% of initial contract amount, shall be subject of another contract to be tendered out if the works are separable from the original contract.

Clause-10: Quality Control.

(A) Identifying Defects: If at any time before the security deposit is refunded to the contractor/during defect liability period mentioned in bid data, the Engineer-in-charge or his subordinate-in-charge of the work may instruct the contractor to uncover and test any part of the works which he considers may have a defect due to use of unsound materials or unskillful workmanship and the contractor has to carry out a test at his own cost irrespective of work already approved or paid.

(B) Correction of Defects: The contractor shall be bound forthwith to rectify or remove and reconstruct the work so specified in whole or in part, as the case may require. The contractor shall correct the notified defect within the Defects Correction Period mentioned in notice.

(C) Uncorrected Defects:

(i) In the case of any such failure, the Engineer-in-charge shall give the contractor at least 14 days notice of his intention to use a third party to correct a defect. He may rectify or remove, and re-execute the work or remove and replace the materials or articles complained of as the case may be at the risk and expense in all respects of the contractor.

(ii) If the Engineer considers that rectification/correction of a defect is not essential and it may be accepted or made use of; it shall be within his discretion to accept the same at such reduced rates as he may fix therefore.

Clause – 11:

(A) Inspection of Operations. The Engineer and his subordinates, shall at all reasonable times have access to the site for supervision and inspection of works under or in course of execution in pursuance of the contract and the contractor shall afford every facility for and every assistance in obtaining the right to such access.

(B) Dates for Inspection and Testing. The Engineer shall give the contractor reasonable notice of the intention of the Engineer-in-charge or his subordinate to visit the work shall have been given to the contractor, then he either himself be present to receive orders and instructions, or have a responsible agent duly accredited in writing present for that purpose, orders given to the contractor's duly authorized agent shall be considered to have the same force an effect as if they had been given to the contractor himself.

Clause – 12: Examination of work before covering up.

(A) No part of the works shall be covered up or put out of view/beyond the reach without giving notice of not less than five days to the Engineer whenever any such part of the works or foundations is or are ready or about to be ready for examination and the Engineer shall, without delay, unless he considers it unnecessary and advises the contractor accordingly, attend for the purpose of examining and measuring such part of the works or of examining such foundations;

(B) If any work is covered up or placed beyond the reach of measurement without such notice having been given, the same shall be uncovered at the contractor's expense, and in default thereof no payment or allowance shall be made for such work, or for the materials with which the same was executed.

Clause – 13: Risks. The contractor shall be responsible for all risks of loss of or damage to physical property or facilities or related services at the premises and of personal injury and death which arise during and in consequence of its performance of the contract, if any damage is caused while the work is in progress or become apparent within three months of the grant of the certificate of completion, final or otherwise, the

contractor shall make good the same at his own expense, or in default the Engineer may cause the same to be made good by other workmen, and deduct the expenses from retention money lying with the Engineer.

Clause-14: Measures for prevention of fire and safety measures. The contractor shall not set fire to any standing jungle, trees, bush-wood or grass without a written permit from the Executive Engineer. When such permit is given, and also in all cases when destroying, cutting or uprooting trees, bush-wood, grass, etc by fire, the contractor shall take necessary measures to prevent such fire spreading to or otherwise damaging surrounding property. The contractor is responsible for the safety of all its activities including protection of the environment on and off the site. Compensation of all damage done intentionally or unintentionally on or off the site by the contractor's labour shall be paid by him.

Clause-15:Sub-contracting. The contractor shall not subcontract the whole of the works, except where otherwise provided by the contract. The contractor shall not subcontract any part of the works without the prior consent of the Engineer. Any such consent shall not relieve the contractor from any liability or obligation under the contract and he shall be responsible for the acts, defaults and neglects of any subcontractor, his agents, servants or workmen as if these acts, defaults or neglects were those of the contractor, his agents' servants or workmen. The provisions of this contract shall apply to such subcontractor or his employees as if he or it were employees of the contractor.

Clause – 16: Disputes. All disputes arising in connection with the present contract, and which cannot be amicably settled between the parties, , the decision of the Superintending Engineer of the circle/officer/one grade higher to awarding authority shall be final, conclusive and binding on all parties to the contract upon all questions relating to the meaning of the specifications, designs drawings, and instructions, hereinbefore mentioned and as to the quality of workmanship, or materials used on the work or as to any other questions, claim, right, matter, or thing whatsoever in any way arising out of, or relating to the contract design, drawings, specifications, estimates, instructions, orders or these conditions or otherwise concerning the works, or the execution, of failure to execute the same, whether arising, during the progress of the work, or after the completion or abandonment thereof.

Clause –17: Site Clearance. On completion of the work, the contractor shall be furnished with a certificate by the Executive Engineer (hereinafter called the Engineer in-charge) of such completion, but neither such certificate shall be given nor shall the work be considered to be complete until the contractor shall have removed all temporary structures and materials brought at site either for use or for operation facilities including cleaning debris and dirt at the site. If the contractor fails to comply with the requirements of this clause then Engineer-in-charge, may at the expense of the contractor remove and dispose of the same as he thinks fit and shall deduct the amount of all expenses so incurred from the contractor's retention money. The contractor shall have no claim in respect of any surplus materials as aforesaid except for any sum actually realized by the sale thereof.

Clause –18: Financial Assistance /Advance Payment.

(A) **Mobilization advance** is not allowed.

(B) **Secured Advance against materials brought at site.**

(i) Secured Advance may be permitted only against imperishable materials/quantities anticipated to be consumed / utilized on the work within a period of three months from the date of issue of secured advance and definitely not for full quantities of materials for the entire work/contract. The sum payable for such materials on site shall not exceed 75% of the market price of materials;

(ii) Recovery of Secured Advance paid to the contractor under the above provisions shall be affected from the monthly payments on actual consumption basis, but not later than period more than three months (even if unutilized).

Clause –19: Recovery as arrears of Land Revenue. Any sum due to the Government by the contractor shall be liable for recovery as arrears of Land Revenue.

Clause –20: Refund of Security Deposit/Retention Money. On completion of the whole of the works (a work should be considered as complete for the purpose of refund of security deposit to a contractor from the last date on which its final measurements are checked by a competent authority, if such check is necessary otherwise from the last date of recording the final measurements), the defects notice period has also passed and the Engineer has certified that all defects notified to the contractor before the end of this period have been corrected, the security deposit lodged by a contractor (in cash or recovered in installments from his bills) shall be refunded to him after the expiry of three months from the date on which the work is completed.

Contractor:

**Divisional Accounts Officer
Buildings Jamshoro**

**Executive Engineer (Buildings)
Division Works & Services,
District Jamahoro**

**SCHEDULE-B
PART-A**

Name of work:

**ADP NO. 09, CONSTRUCTION OF OFFICE OF ASSISTANT PUBLIC HEALTH ENGINEERING
SUB DIVISION KOTRI, TALUKA KOTRI, DISTRICT JAMSHORO (PART-A REMAINING WORK)**

Description	Quantity	Rate	Unit	Amount
1 Reinforced cement concrete work i/c all labour and material except the cost of steel reinforcement and its labour for 90 lbs (S.I.No. 6 (a) (i) - P / 19)	2029 x @	337.00	P.Cft	= 683779
2 fabrication of mild Steel Reinforcement for Cement Concrete including cutting, bending,	117.76 x @	5001.70	P.Cwt	= 588978
3 Pacca Brick Work in Ground Floor cement Sand Mortar 1:6	2576 x @	12674.36	%Cft	= 326428
4 Supplying and fixing in position Aluminum channels framing for sliding windows & ventilator (Page 107 item 84)	120 x @	1647.69	%PSft	= 197723
5 Supplying and fixing in position Aluminum channels framing hinged doors or Alcop made with 5 mm thick tinted glass glazing Belgum and alpha japan locks I c handels stoppers (Page 107 item 83)	25 x @	1507.66	%PSft	= 36938
6 Providing & Fxing G. I frames / chowkats of size 7" x 2" or 4 1/2" x 3" for windows using 20 guage G.I sheet I/C	35 x @	240.50	P.Rft	= 8418
7 Providing & Fxing G. I frames / chowkats of size 7" x 2" or 4 1/2" x 3" for windows using 20 guage G.I sheet I/C	119 x @	228.90	P.Rft	= 27125
8 First Class Deador wood wrought joinery in door & windows etc. fixed in position including chowkats hold fasts hinge iron tower, bolts , chocks, cleats, handles & cords with hocks etc 1 3/4"	159 x @	902.93	P.Sft	= 143114
9 Providing and fixing iron/ steel grill using solid square bars of size 1/2" x 1/2" placed at 4" center to or pins including painting 3 coats with first coat of red oxide paint etc (S.I.NO.30/C-17).P94	120 x @	194.16	P.Sft	= 23299
10 Cement plaster 1:6 upto 20 height (b) 1/2" (S.I.No.13(b)/C-19)	7866 x @	2206.60	%Sft	= 173571

11 Cement plaster 1:4 upto 20 height (a) 3/8" thick (S.I.No.11(a)/C-9)	7866 x @	2197.52 %Sft	=	172857
12 Providing and laying tiles glazed 6" x 6" x 1/4" on floor or wall facing requires pattern of cleaning and cost of wax polish etc complete including cutting tiles the proper profile (S.I.No.61/C-8)	707 x @	30509.77 %Sft		215704
13 Providing and laying Hala or Patter tile Glazed 6" x 6" x 1/4" on floor or wall facing requires pattern of	135 x @	47651.56 %Sft		64330
14 Laying white marble flooring fine dressed on the surface without winding set in lime mortar 1:2 including rubbing and polishing of the joint 3/4" thick flooring (S.I.NO. 28 (a). pg. 42)	1344 x @	567.48 PSft		762445
15 Providing and fixing 3/8 inch thick marble tiles of approved quality and colour and shade size Item no 68 page 48	220 x @	186.00 PSft		40920
16 Providing & fixing approved motric lock (s.i.no. 21 .pg 10)	12 x @	1786.13 each		21434
17 Providing and laying topping cement concrete 1:2:4 including surface finishing and dividing into panels © 2" thick (S.I.No.16©/C-8	1301 x @	3275.50 %Sft		42627
18 Primary coat of chalk under distemper (S.I.No.23/C-9).	996 x @	442.75 %Sft	=	4409
19 Distempering C-3 Coats (S.I.No. 24© / C-9)	996 x @	1079.65 %Sft	=	10752
20 Preparing the surface with Matt finish i/c rubbing the surface with rubbing brick / sand paper bathy silicon carbide rubbing brick) filling voids with zink (S.I.NO.36 (A) pg. 54)	4136 x @	1989.62 %Sft	=	82291
21 Preparing the surface with weather coat i/c rubbing the surface with rubbing brick / sand paper filliing the voids with chalk/ plaster of paris and then painting wih weather coat	3879 x @	2567.95 %Sft	=	99611
22 Preparing new surface and painting of doors and windows any type including (I & II) 3 coats (S.I.NO. 5 © / I & II /C-11)	318 x @	2116.41 %Sft	=	6730
			=	<u>3733480</u>

Total Amount (a)

_____ % Above / Below on the Rates or Amount to be added / deducted on
basis of premium quoted Total (b)

Civil Work Rs. (a) _____ Rs. (+) _____ = Rs. _____

Tile / Marble Rs. _____ Rs. (-) _____ = Rs. _____

Fabrication Rs. (a) _____ Rs. (+) _____ = Rs. _____

Non-S Items Rs. (a) _____ Rs. (-) _____ = Rs. _____

Grant Total _____

Total (A)= a+b In Words & Figure _____

CONTRACTOR

EXECUTIVE ENGINEER (BUILDINGS)
DIVISION JAMSHORO

SCHEDULE - B

Part-B

Name of work:

**ADP NO. 09, CONSTRUCTION OF OFFICE OF ASSISTANT PUBLIC HEALTH ENGINEERING
SUB DIVISION KOTRI, TALUKA KOTRI, DISTRICT JAMSHORO (PART-A REMAINING WORK)**

Description	Quantity	Rate	Unit	Amount
1 Providing & fixing squatting type white Glazed Earthenware W.C Pan with front flush inlet & flushing rims and three gallons flushing tank with 4" dia C.I trap & C.I thumb (S.I.No.1)(B)/I.C.I	4 Nos	4802.60 Each	RS =	19210
2 . Providing and fixing 24" x 18" lavatory basin in white glazed earthenware complete with (Foreign or equivalent)(S.I.No.10/C-1).	4 Nos	4928.00 Each	RS =	19712
3 Add extra labour for providing and fixing earthenware pedestral white or colored glazed (foreign or equivalent). (S.I.No.11/c-1).	4 Nos	2533.47 Each	RS =	10134
4 Providing and fixing Stainless & Steel sink local made complete with C.I or W.I (S.I.No.19(b)/C-1).	1 Nos	5162.30 Each	RS =	5162
5 Providing and fixing 6" x 2" or 6" x 3" C.I floor trap of the approved self cleaning design with C.I good in cement concrete 1:2:4 (S.I.No.20/C-1)	6 Nos	2042.43 Each	RS =	12255
6 Providing and fixing in position nylon connections complete with 1/2" dia brass stop cock with pair of brass nuts and lining joints to nylon connections S.I.No.23/C-1	6 Nos	447.15 Each	RS =	2683
7 Providing and fixing bathroom accessories set (7 pieces) including tower rod, brush holder, brand) S.I No.25/C-6	4 Nos	8122.40 Each	RS =	32490
8 Providing and fixing 4" dia C.I Plain Bend of the required degree including extra painting to match the color of the building. (S.I.No. 10/C-3)	4 Nos	566.70 Each	RS =	2267
9 Providing G.I Pipes, specials and clamps etc including fixing, cutting and fitting complete with (i)1/2" dia. (S.I.No.1(i)/C-4, pg -12)				
1/2"	15	Rft	73.21 Each	RS = 1098
3/4"	15	Rft	95.79 Each	RS = 1437
1"	10	Rft	128.55 Each	RS = 1286
2"	10	Rft	233.00 Each	RS = 2330

3"	10	Rft	360.00 Each	RS	=	3600
4"	10	Rft	896.17 Each	RS	=	8962

10 Add extra labour for concealed G.I Pipe and fitting including making recess in the wall (i)1/2" dia. (S.I.No.1(i)/C-4, PG-12)

1/2"	15 Rft		7.82 P.Rft	RS	=	117
3/4"	15 Rft		8.45 P.Rft	RS	=	127
1"	10 Rft		9.96 P.Rft	RS	=	100

11 Providing G.I Pipes, specials and clamps etc including fixing, cutting and fitting complete with ITEM NO. (1) PG 14 CHAPT (WATER SERVICES EXTERNAL)

1/2"	15 Rft		64.88 Each	RS	=	973
3/4"	15 Rft		86.36 Each	RS	=	1295
1"	10 Rft		116.20 Each	RS	=	1162
2"	10 Rft		355.27 Each	RS	=	3553
3"	10 Rft		887.24 Each	RS	=	8872
4"	10 Rft		835.39 Each	RS	=	8354
						24210

12 Providing R.C.C Pipe with collars class"C" and digging the tranches to required and fixing thickness excavated stuff (item no. 37 PHSI pg-37)

9"	50 P.Rft		194.00 P.Rft	RS	=	9700
12"	50 P.Rft		330.00 P.Rft	RS	=	16500

13 Proving & laying UPVC pressure pipes of class "D" (equivalent make) fixing in trench i/c cutting fitting and jointing with Z joint with one rubber ring i/c testing with water to a head 61 meter or 200 ft

1"	10 Rft		28.00 P.Rft	RS	=	280
1-1/2"	20 Rft		44.00 P.Rft	RS	=	880
2"	20 Rft		66.00 P.Rft	RS	=	1320
3"	15 Rft		137.00 P.Rft	RS	=	2055
4"	10 Rft		226.00 P.Rft	RS	=	2260
5"	15 Rft		336.00 P.Rft	RS	=	5040
6"	12 Rft		486.00 P.Rft	RS	=	5832
8"	12 Rft		742.00 P.Rft	RS	=	8904
10"	10 Rft		1375.00 P.Rft	RS	=	13750

14 Supplying and fixing Long bib Cock of superior quality with C.P head 1/2 dia (S.I.No.159(a)/C-6).

4 Nos		1109.46 Each	RS	=	4438
-------	--	--------------	----	---	------

15 Supplying and fixing concealed stop cock of superior quality with C.P head 1/2" dia. S.I.No.13/(a)/C-6).

4 Nos		478.28 Each	RS	=	1913
-------	--	-------------	----	---	------

16 Supplying and fixing concealed wash basin mixture of superior quality with C.P head 1/2" dia. S.I.No.16/(a)/C-6).

1 Nos		2882.00 Each	RS	=	2882
-------	--	--------------	----	---	------

17 Supplying and fixing jet shower with rod of superior quality with C.P head 1/2" dia.

S.I.No.17/(a)/C-6).

2 Nos 1142.24 Each RS = 2284

18 Providing and fixing Handle Valves (China) (ii) 3/4" dia. (S.I.No.7 (ii)/C-6)

dia					
3/4"	6 Nos	271.92 Each	RS	=	1632
1/2"	4 Nos	200.42 Each	RS	=	802
1"	5 Nos	365.42 Each	RS	=	1827

19 Providing and fixing water pumping set 1 H.P 2800 RPM Single phase 220 volts, 1.25"x1" 40 ft head including base plato and also making C.C 1:3:6 plateform of required size and fixing with nuts and bolts etc complete in all respects (S.I.No. 11/Sub Head XI Water pumps of Electric S.O.R)

1 Nos 10469.00 Each RS = 10469

Total = 239946

Total Amount (a)

_____ % Above / Below on the Rates of CSR.

Amount to be added / deducted on basis of premium quoted Total (b)

W.S Rs. (a) _____ Rs. (+) _____ = Rs. _____

G.I Pipe / R.C.C Pipe Rs. _____ Rs. (-) _____ = Rs. _____

Non-S Items Rs. (a) _____ Rs. (-) _____ = Rs. _____

Grant Total _____

Total (A)= a+b In Words & Figure _____

CONTRACTOR

EXECUTIVE ENGINEER (BUILDINGS)
DIVISION JAMSHORO

SCHEDULE "B"

Construction of Office of the Assistant Engineer Public Health Engineering Sub-Division Kotri, Taluka Kotri District Jamshoro (Electric Work)

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
1	Wiring for light or fan point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-124 P-15)	50 NOS	1130.00	Per.Point	56500
2	Wiring for Plug point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit on surface as required. (S.NO:P-125 P-15)	10 NOS	669.00	Per.Point	6690
3	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.29 copper conductor in 3/4" dia PVC conduit on surface.(SNO:A-03 P-01)	115 P.MR	171.00	Per Mtr.	19665
4	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.44 copper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-12 P-02)	300 P.MR	341.00	Per Mtr.	102300
5	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp SP (TB-5S) on prepared board as required.(S.NO:P-203 P-31)	10 NOS	916.00	Per.Point	9160
6	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp DP (TB-5S) on prepared board as required.(S.NO:P-204 P-31)	2 NOS	2456.00	Per.Point	4912
7	Providing & Fixing Circuit Breaker 3.5.10.15.20.& 30 Amp TP (XS-30NS[NB]) on prepared board as required.(S.NO:P-205 P-31)	1 NOS	5301.00	Per.Point	5301
8	Providing & Fixing Bakelite ceiling Rose with two terminals.(S.NO:B-228 P-33)	20 NOS	72.00	Per.Point	1440
9	Providing & Fixing Brass Pendant Lamp holder .(S.NO:B-229 P-33)	20 NOS	74.00	Per.Point	1480
10	Providing & Fixing AmpMeters Size 96/96mm Direct 15A, 30A 50A.60A,&100 A as required & as per instruction of E.I.(S.NO:A-284 P-41)	1 NOS	1054.00	Per.No.	1054
11	Providing & Fixing VoltMeter Size 96/96mm 500 as required & as per instruction of E.I.(S.NO:B-285 P-41)	1 NOS	999.00	Per.No.	999
12	Providing & Fixing Three Pin 10/15 amp Plug & Socket flush type.(S.NO:A-227 P-33)	4 Nos	162.00	Per No.	648

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
13	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.36 copper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-11 P-02)	90 Per Mtr.	252.00	Per Mtr.	22680
14	Wiring for Call bell point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-128 P-15)	2 NOS	1764.00	Per.Point	3528
15	Construction of RCC Foundation as per following specification & instruction of E.I for 31ft/40ft long tubular pole Excavation of soft/hard soil 3'x3'x5.5' stone soiling 3'x3'x6" Making lean in the ratio of 1:4:8 Length of MS bolts 6 1/2' (3/4"dia) 4 nos & making thread on MS rod Template 16"x16"x1/4 Rings 1/4" dia round bar 4 nos to the welded with MS rod RCC foundation rotio 1:2:4 with apprpriate size 2'x2'x6.5' (S.NO:P-139 P-19)	3 Nos	15168.00	Per.Point	45504
16	Providing & Fixing Brass Ceiling Fan 56" (Good Quality) .(S.NO:B-235 P-34)	8 Nos	3185.00	Per No.	25480
17	Providing & Fixing One Way SP 10/15 amp switch surface type.(S.NO:A-218 P-33)	50 NOS	58.00	Per.Nos	2900
TOTAL RS:-					310241

((PART "B"))

1	Providing & Fixing Distribution Pannel Board of 3/4" thick sheeting double shutter to accommodate circuit breakers i/c painting with enamelled paint.	2 Sft	2436.04	P.Sft	4872
2	Providing & Fixing A.C or D.C Electric bell 200/250 Volts MM (2-3/4") gong .(Imported)	2 Nos	750.00	EACH	1500
3	Providing & Fixing Mild Steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C roof.	8 Nos	325.00	EACH	2600
4	P/F Energy Saver (18 to 24 watts) Superior Quality including Fixing on Existing holder etc complete.(Imported)	20 Nos	605.00	EACH	12100

S. NO	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
5	P/F Fancy Capsule Light with fancy Plastic body,holder,Saver etc complete (of approved make and design).	10 Nos	950.00	EACH	9500
6	P/F 1-40 watts Tube Light complete with 40 watts 4-0"long rod chock starter & putty with Philips components including necessary electric connection & Fixing on wall or ceiling etc complete (Philips).	6 Nos	1450.00	EACH	8700
7	S/F Exhaust Fan 280 mm (12") sweep with butterfly shutter for exhaust fan complete as required this rate also cutting wall or beam upto required size fixing exhaust fan with connection and finishing the hole with coment etc complete in all respects (1st: quality).	2 Nos	3150.00	EACH	6300
8	P/Installing Connecting & testing of road light fixture IP 66 rating lamp component SGP-338 philps appeared type with 25 volts SON-T lamp high priority amodized aluminum reflector highpressure die cost i/c hoisting complete with all installation accessories as approved by the Engineer parts shouls be Germany Make are equivalent quality	3 Nos	22000.00	Each	66000
9	P/I A.C Fancy road light Pole 20 ft hight to ground level with fancy arm bracket Impection window i/c (15x15") 4mm this squire pase plate 4 Nos 4mm round holes nut & bolts silver panint complete set (fancy Assambleed)changes of Loading tranportations changes fram factory to site.	3 Nos	26000.00	Each	78000

TOTAL RS:-	189572
-------------------	---------------

CONTRACTOR

EXECUTIVE ENGINEER (BUILDINGS)
DIVISION (W&S) DEPARTMENT
DISTRICT JAMSHORO.

SCHEDULE "B"**Renovation / Extension of Room of Defunct District Council Residential Quarters Near Zila
Nazim Office Taluka Kotri (Electric Work)**

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
1	Wiring for light or fan point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-124 P-15)	75 NOS	1130.00 (Rs:One thousand one hundred thirty only).	Per.Point	84750
2	Providing & Fixing One Way SP 10/15 amp switch surface type.(S.NO:A-218 P-33)	75 NOS	58.00 (Rs:Fifty eight only).	Per.Nos	4350
3	Wiring for Plug point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit on surface as required. (S.NO:P-125 P-15)	10 NOS	669.00 (Rs: Six hundred sixty nine only).	Per.Point	6690
4	Providing & Fixing Two Pin 5 amp Plug & Socket (S.NO:A-222 P-33)	10 NOS	80.00 (Rs: Eighty only).	Per.Nos	800
5	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.29 copper conductor in 3/4" dia PVC conduit on surface.(SNO:A-03 P-01)	150 P.MR	171.00 (Rs: One hundred Seventy one only).	Per Mtr.	25650
6	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.44 copper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-12 P-02)	150 P.MR	341.00 (Rs: Three hundred forty one only).	Per Mtr.	51150
7	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp SP (TB-5S) on prepared board as required.(S.NO:P-203 P-31)	12 NOS	916.00 (Rs:Nine hundred sixteen only).	Per.Point	10992
8	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp DP (TB-5S) on prepared board as required.(S.NO:P-204 P-31)	2 NOS	2456.00 (Rs:Two thousand four hundred fifty six only).	Per.Point	4912
9	Providing & Fixing Circuit Breaker 15.20.30.40.50.60.75 & 100 Amp TP (XS - 100NS) on prepared board as required.(S.NO:P-207 P-31)	1 Nos	9261.00 (Rs:Nine thousand two hundred sixty one only).	Per No.	9261
10	Providing & Fixing Bakelite ceiling Rose with two terminals.(S.NO:B-228 P-33)	30 NOS	72.00 (Rs:Seventy two only).	Per No.	2160
11	Providing & Fixing Brass Pendant Lamp holder .(S.NO:B-229 P-33)	35 NOS	74.00 (Rs:Seventy two only).	Per No.	2590

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
12	Providing & Fixing AmpMeters Size 96/96mm Direct 15A, 30A 50A.60A,&100 A as required & as per instruction of E.I.(S.NO:A-284 P-41)	1 NOS	1054.00 (Rs:One thousand fifty four only).	Per.No.	1054
13	Providing & Fixing VoltMeter Size 96/96mm 500 as required & as per instruction of E.I.(S.NO:B-285 P-41)	1 NOS	999.00 (Rs:Nine hundred ninty nine only).	Per.No.	999
14	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.36 copper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-11 P-02)	50 Per Mtr.	252.00 (Rs:two hundred fifty two only).	Per Mtr.	12600
15	Wiring for Call bell point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-128 P-15)	1 NOS	1764.00 (Rs:One thousand Seven hundred sixty four only).	Per No.	1764
16	Providing & Fixing Brass Ceiling Fan 56" (Good Quality) .(S.NO:B-235 P-34)	10 Nos	3185.00 (Rs:Three thousand one hundred eighty five only).	Per No.	31850

TOTAL RS:-	251572
-------------------	---------------

SCHEDULE "B"**Renovation / Extension of Room of Defunct District Council Residential Quarters Near Zila Nazim Office Taluka Kotri (Electric Work)**

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
((PART "B"))					
1	Providing & Fixing Distribution Pannel Board of 3/4" thick sheeting double shutter to accommodate circuit breakers i/c painting with enamelled paint.	2 Sft		P.Sft	
2	P/F. Surface type 3 pin 15 amper s.p surface type plug switch and shoe unit prepared on board etc complete	6 NOS		EACH	
3	Fixing A.C. ceiling fan Regulator on metal board recessed in the walls	10 Nos		EACH	
4	Providing & Fixing A.C or D.C Electric bell 200/250 Volts MM (2-3/4") gong .(Imported)	1 Nos		EACH	
5	Providing & Fixing Mild Steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C roof.	10 Nos		EACH	
6	P/F Energy Saver (18 to 24 watts) Superior Quality including Fixing on Existing holder etc complete.(Imported)	35 Nos		EACH	
7	Supply / Fixing LED Light 06 watts etc complete	12 Nos		Each	
8	P/F Fancy Capsule Light with fancy Plastic body,holder,Saver etc complete (of approved make and design).	10 Nos		EACH	
9	P/F 1-40 watts Tube Light complete with 40 watts 4-0"long rod chock starter & putty with Philips components including necessary electric connection & Fixing on wall or ceiling etc complete (Philips).	15 Nos		EACH	

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
10	P/Fixing Pilot Lamps	3 NOS		EACH	

TOTAL RS:-

Total Amount (a)

_____ % Above / Below on the Rates of CSR.

Amount to be added / deducted on basis of premium quoted Total (b)

PART"A"Schedule Item Rs. _____ Rs. (b) _____ = Rs. _____

PART"B"Non Schedule Item Rs. _____ Rs. (+) _____

Total (A)= a+b In Words & Figure _____

CONTRACTOR

EXECUTIVE ENGINEER (BUILDINGS)
DIVISION JAMSHORO

SCHEDULE "B"**Renovation / Extension of Room of Defunct District Council Residential Quarters Near GPS
Kotri Taluka Kotri (Electric Work)**

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
1	Wiring for light or fan point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-124 P-15)	75 NOS	1130.00 (Rs:One thousand one hundred thirty only).	Per.Point	84750
2	Providing & Fixing One Way SP 10/15 amp switch surface type.(S.NO:A-218 P-33)	75 NOS	58.00 (Rs:Fifty eight only).	Per.Nos	4350
3	Wiring for Plug point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit on surface as required. (S.NO:P-125 P-15)	10 NOS	669.00 (Rs: Six hundred sixty nine only).	Per.Point	6690
4	Providing & Fixing Two Pin 5 amp Plug & Socket (S.NO:A-222 P-33)	10 NOS	80.00 (Rs: Eighty only).	Per.Nos	800
5	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.29 copper conductor in 3/4" dia PVC conduit on surface.(SNO:A-03 P-01)	150 P.MR	171.00 (Rs: One hundred Seventy one only).	Per Mtr.	25650
6	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.44 conpper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-12 P-02)	150 P.MR	341.00 (Rs: Three hundred forty one only).	Per Mtr.	51150
7	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp SP (TB-5S) on prepared board as required.(S.NO:P-203 P-31)	12 NOS	916.00 (Rs:Nine hundred sixteen only).	Per.Point	10992
8	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp DP (TB-5S) on prepared board as required.(S.NO:P-204 P-31)	2 NOS	2456.00 (Rs:Two thousand four hundred fifty six only).	Per.Point	4912
9	Providing & Fixing Circuit Breaker 15.20.30.40.50.60.75 & 100 Amp TP (XS - 100NS) on prepared board as required.(S.NO:P-207 P-31)	1 Nos	9261.00 (Rs:Nine thousand two hundred sixty one only).	Per No.	9261
10	Providing & Fixing Bakelite ceiling Rose with two terminals.(S.NO:B-228 P-33)	30 NOS	72.00 (Rs:Seventy two only).	Per No.	2160
11	Providing & Fixing Brass Pendant Lamp holder .(S.NO:B-229 P-33)	35 NOS	74.00 (Rs:Seventy two only).	Per No.	2590

S. NO	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
12	Providing & Fixing AmpMeters Size 96/96mm Direct 15A, 30A 50A.60A,&100 A as required & as per instruction of E.I.(S.NO:A-284 P-41)	1 NOS	1054.00 (Rs:One thousand fifty four only).	Per.No.	1054
13	Providing & Fixing VoltMeter Size 96/96mm 500 as required & as per instruction of E.I.(S.NO:B-285 P-41)	1 NOS	999.00 (Rs:Nine hundred ninty nine only).	Per.No.	999
14	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.36 copper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-11 P-02)	50 Per Mtr.	252.00 (Rs:two hundred fifty two only).	Per Mtr.	12600
15	Wiring for Call bell point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-128 P-15)	1 NOS	1764.00 (Rs:One thousand Seven hundred sixty four only).	Per No.	1764
16	Providing & Fixing Brass Ceiling Fan 56" (Good Quality) .(S.NO:B-235 P-34)	10 Nos	3185.00 (Rs:Three thousand one hundred eighty five only).	Per No.	31850

TOTAL RS:-	251572
-------------------	---------------

SCHEDULE "B"

**Renovation / Extension of Room of Defunct District Council Residential Quarters Near GPS
Kotri Taluka Kotri (Electric Work)**

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
((PART "B"))					
1	Providing & Fixing Distribution Pannel Board of 3/4" thick sheeting double shutter to accommodate circuit breakers i/c painting with enamelled paint.	2 Sft		P.Sft	
2	P/F Surface type 3 pin 15 amper s.p surface type plug switch and shoe unit prepared on board etc complete	6 NOS		EACH	
3	Fixing A.C. ceiling fan Regulator on metal board recessed in the walls	10 Nos		EACH	
4	Providing & Fixing A.C or D.C Electric bell 200/250 Volts MM (2-3/4") gong .(Imported)	1 Nos		EACH	
5	Providing & Fixing Mild Steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C roof.	10 Nos		EACH	
6	P/F Energy Saver (18 to 24 watts) Superior Quality including Fixing on Existing holder etc complete.(Imported)	35 Nos		EACH	
7	Supply / Fixing LED Light 06 watts etc complete	12 Nos		Each	
8	P/F Fancy Capsule Light with fancy Plastic body,holder,Saver etc complete (of approved make and design).	10 Nos		EACH	
9	P/F 1-40 watts Tube Light complete with 40 watts 4-0"long rod chock starter & putty with Philips components including necessary electric connection & Fixing on wall or ceiling etc complete (Philips).	15 Nos		EACH	

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
--------	----------------	-------	------	------	--------

10	P/Fixing Pilot Lamps	3 NOS		EACH	
----	----------------------	----------	--	------	--

TOTAL RS:-	
-------------------	--

Total Amount (a)

_____ % Above / Below on the Rates of CSR.

Amount to be added / deducted on
basis of premium quoted Total (b)

PART "A" Schedule Item Rs. _____ Rs. (b) _____ = Rs. _____

PART "B" Non Schedule Item Rs. _____ Rs. (+) _____

Total (A) = a+b In Words & Figure _____

CONTRACTOR

EXECUTIVE ENGINEER (BUILDINGS)
DIVISION JAMSHORO

SCHEDULE "B"**Construction of Assistant Commissioner Office Bungalow at Kotri Taluka Kotri District
Jamshoro (Electric Work)**

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
1	Wiring for light or fan point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-124 P-15)	80 NOS	1130.00 (Rs:One thousand one hundred thirty only).	Per.Point	90400
2	Providing & Fixing One Way SP 10/15 amp switch surface type.(S.NO:A-218 P-33)	80 NOS	58.00 (Rs:Fifty eight only).	Per.Nos	4640
3	Wiring for Plug point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit on surface as required. (S.NO:P-125 P-15)	20 NOS	669.00 (Rs: Six hundred sixty nine only).	Per.Point	13380
4	Providing & Fixing Two Pin 5 amp Plug & Socket (S.NO:A-222 P-33)	20 NOS	80.00 (Rs: Eighty only).	Per.Nos	1600
5	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.29 copper conductor in 3/4" dia PVC conduit on surface.(SNO:A-03 P-01)	350 P.MR	171.00 (Rs: One hundred Seventy one only).	Per Mtr.	59850
6	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.44 conpper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-12 P-02)	285 P.MR	341.00 (Rs: Three hundred forty one only).	Per Mtr.	97185
7	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp SP (TB-5S) on prepared board as required.(S.NO:P-203 P-31)	15 NOS	916.00 (Rs:Nine hundred sixteen only).	Per.Point	13740
8	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp DP (TB-5S) on prepared board as required.(S.NO:P-204 P-31)	3 NOS	2456.00 (Rs:Two thousand four hundred fifty six only).	Per.Point	7368
9	Providing & Fixing Circuit Breaker 15.20.30.40.50.60.75 & 100 Amp TP (XS - 100NS) on prepared board as required.(S.NO:P-207 P-31)	1 Nos	9261.00 (Rs:Nine thousand two hundred sixty one only).	Per No.	9261
10	Providing & Fixing Bakelite ceiling Rose with two terminals.(S.NO:B-228 P-33)	30 NOS	72.00 (Rs:Seventy two only).	Per No.	2160
11	Providing & Fixing Brass Pendant Lamp holder .(S.NO:B-229 P-33)	40 NOS	74.00 (Rs:Seventy two only).	Per No.	2960

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
12	Providing & Fixing AmpMeters Size 96/96mm Direct 15A, 30A 50A.60A,&100 A as required & as per instruction of E.I.(S.NO:A-284 P-41)	1 NOS	1054.00 (Rs:One thousand fifty four only).	Per.No.	1054
13	Providing & Fixing VoltMeter Size 96/96mm 500 as required & as per instruction of E.I.(S.NO:B-285 P-41)	1 NOS	999.00 (Rs:Nine hundred ninty nine only).	Per.No.	999
14	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.36 copper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-11 P-02)	100 Per Mtr.	252.00 (Rs:two hundred fifty two only).	Per Mtr.	25200
15	Wiring for Call bell point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-128 P-15)	2 NOS	1764.00 (Rs:One thousand Seven hundred sixty four only).	Per No.	3528
16	Providing & Fixing Brass Ceiling Fan 56" (Good Quality) .(S.NO:B-235 P-34)	15 Nos	3185.00 (Rs:Three thousand one hundred eighty five only).	Per No.	47775

TOTAL RS:-	381100
-------------------	---------------

SCHEDULE "B"

**Construction of Assistant Commissioner Office Bungalow at Kotri Taluka Kotri District
Jamshoro (Electric Work)**

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
<u>((PART "B"))</u>					
1	Providing & Fixing Distribution Pannel Board of 3/4" thick sheeting double shutter to accommodate circuit breakers i/c painting with enamelled paint.	4 Sft		P.Sft	
2	P/F. Surface type 3 pin 15 amper s.p surface type plug switch and shoe unit prepared on board etc complete	8 NOS		EACH	
3	Fixing A.C. ceiling fan Regulator on metal board recessed in the walls	15 Nos		EACH	
4	Providing & Fixing A.C or D.C Electric bell 200/250 Volts MM (2-3/4") gong .(Imported)	2 Nos		EACH	
5	Providing & Fixing Mild Steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C roof.	15 Nos		EACH	
6	P/F Energy Saver (18 to 24 watts) Superior Quality including Fixing on Existing holder etc complete.(Imported)	40 Nos		EACH	
7	Supply / Fixing LED Light 06 watts etc complete	12 Nos		Each	
8	P/F Fancy Capsule Light with fancy Plastic body,holder,Saver etc complete (of approved make and design).	10 Nos		EACH	
9	P/F 1-40 watts Tube Light complete with 40 watts 4-0"long rod chock starter & putty with Philips components including necessary electric connection & Fixing on wall or ceiling etc complete (Philips).	15 Nos		EACH	

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
10	P/Fixing Pilot Lamps	6 NOS		EACH	
11	P/F.SNF (HPIT) Fixture (Philips) type complete with lamp bolts ingnitor chwok capactor further more 99% pure aluminum used for reflector & tempered glass with heat resistant gas kit ensuring 400 watts lights req:(philips or german made	2 Nos		Each	

TOTAL RS:-

Total Amount (a)

_____ % Above / Below on the Rates of CSR.

Amount to be added / deducted on basis of premium quoted Total (b)

PART"A"Schedule Item Rs. _____ Rs. (b) _____ = Rs. _____

PART"B"Non Schedule Item Rs. _____ Rs. (+) _____

Total (A)= a+b In Words & Figue _____

CONTRACTOR

EXECUTIVE ENGINEER (BUILDINGS)
DIVISION JAMSHORO

5

SCHEDULE B

**NAME OF WORK. REHABILITATION OF SEWERGE LINE LABOUR SQUIRE
AND CC BLOCK LABOUR SQUIRE TALUKA KOTRI DISTRICT JAMSHORO
ADP NO 112 (REVISED)**

PART A

**1 Dismantling of existing asphalt concrete road including base, sub base and disposal
of dismanteld material to designed placed.
item no 11 page 15 public health schedule**

1920 x 773.86 %Sft = 14858

2 Dismantling cement concrete plain (1:2:4) (S.I.NO. 19 (c), P/10)

145 x 3327.50 %Sft = 4832

3 Dismantling cement concrete plain stone ballast (1:4:8) (S.I.NO. 19 (a), P/10)

220 x 1663.75 %Sft = 3660

**4 Pacca Brick work in foundation and plinth in
cement sand mortar in 1:6
item 4 (e) page 20 chapter 5**

135 x 11948.36 %Cft = 16130

**5 Pacca Brick work in ground floor in
cement sand mortar in 1:6
item 5(E) page 21 chapter 5**

135 x 12674.36 %Cft = 17110

6 Cement plaster 1:4 upto 20 height (a) 1/2" thick (S.I.No.11(a)/C-9)

127 x 2283.93 %Sft = 2891

**7 Borrow Pit Excavtion undressed lead upto 100 ft in ordinary soil.
item 3 chapter 1 excation page 1**

5260 x 2117.50 O%Cft = 11138

**8 Dressing and levelling of earth work to designed section etc complete
ordinary or hard soil
item 11 (b) chapter 1 excation page 3**

5260 x 187.55 O%Cft = 987

9 Earth work compaction (soft ,ordinary or hard soil)
Compaction by rolling this does not include hire charges of the
roller etc Ordinary soil
Item 13 (c) chapter 1 excation page 3

5260 x 756.00 O%Cft = 3977

10 Excavtion in foundation of bulding, bridges and other structure including dag belling
refilling around strecture with excavated earth watering and ramming. lead upto
upto 5ft(b) in Ordinary or soft murum. (S.I.NO.18(b)/C-1

1400 x 3176.25 O%Cft = 4447

11 Cement concrete brick or stone ballast1.5 inch to2 inch guage.(b) Ratio 1:4:8. (S.I.No.4 (b) /C-4).

2980 x 9416.28 %Cft = 280605

12 Erection and removal of centering for reniforced or palin cement concrete works of partial wood
(2nd Class) (B) Vertical.

330 x 3127.41 %Sft = 10320

13 Cement concrete plain including placing , compacting finishing and curing complete
(including screening and washing of stone aggrete without shuttering (F) Ratio 1:2: 4

2073 x 14429.25 %Cft = 299046

14 Reinforced cement concrete work i/c all labour and material
except the cost of steel reinforcement and its labour for
bending and binding whidh will be paid separately. This rate
also includes of forms, moulds,lifting, shuttering, rendering
and finishing and finishing the exposed surface (i/c screening,
shingle (a) Rc work in roof slab, beams, columns, rafts,
lintals and other structural members laid in situ or precast
laid in position. Complete in all respects (1) Ratio 1:2:4,
90 lbs (S.I.No. 6 (a) (i) - P / 19)

92 x 337.00 P.Cft = 30962

15 Fabrication of Miled Steel Reinforcement for Cement Concrete including cutting, bending,
laying in position, making joints and fastly including cost of binding wire (also includes \
removal of rust from bars

6 x 5001.70 Pcwt = 28721

= 729683

Civil work Rs (a)	_____ Rs(+)	_____	=	RS	_____
Tile/ Marble Rs (b)	_____ Rs(-)	_____	=	RS	_____
Fabrication Rs (C)	_____ Rs(+)	_____	=	RS	_____
Non -S Items Rs (D)	_____ Rs(-)	_____	=	RS	_____

Grand Total

Total (A)= a+b in words and figure

EXECUTIVE ENGINEER (BUILDINGS)
 DIVISION (W&S) DEPARTMENT
 DISTRICT JAMSHORO

SCHEDULE B

**NAME OF WORK. REHABILITATION OF SEWERGE LINE LABOUR SQUIRE
AND CC BLOCK LABOUR SQUIRE TALUKA KOTRI DISTRICT JAMSHORO
ADP NO 112 (REVISED)**

PART B

- 1 Excavation of pipe line into trenches and pits in all kindof soils of morum i/c trimming & dressing sides to to true alignment and shape leveling of beds of trenches to correct level and grade cutting joint holes and disposal of surplus earth within a one chain as directed by Engineer incharge providing fence guards lights flags and temporary crossing for non vehicular traffic where ever required to lift upto 5' ft (1.52m) and lead upto one chain (30.50 mm) (P.H.S.I NO. 6 P/62)**

4720 x 4650.00 %Sft = 21948

- 2 Excavation of pipe line into trenches and pits in all kindof soils of morum i/c trimming & dressing sides to to true alignment and shape leveling of beds of trenches to correct level and grade cutting joint holes and disposal of surplus earth within a one chain as directed by Engineer incharge providing fence guards lights flags and temporary crossing for non vehicular traffic where ever required to lift upto 5' ft (1.52m) and lead upto one chain (30.50 mm) (P.H.S.I NO. 6 P/62)**

4720 x 10770.00 %Sft = 50834

- 3 Refilling the excavated stuff trench 6" thick layers i/c watering ramming to full compaction etc complete (P.H.S.I.NO. 24, P/53)**

8496 x 2760.00 %OCFT = 23449

= 96231

Sanitary item _____ = RS _____

G.I Pipe/ RCC Pipe _____ = RS _____

Grand Total

Total (A)= b+c in words and figure

CONTRACTOR

EXECUTIVE ENGINEER BUILDINGS
DIVISION JAMSHORO

SCHEDULE

NAME OF WORK. REHABILITATION OF SEWERGE LINE LABOUR SQUIRE
AND CC BLOCK LABOUR SQUIRE TALUKA KOTRI DISTRICT JAMSHORO
ADP NO 112 (REVISED)

PART C

- 1 Providing RCC Pipes & collars of class C and fixing in trench Including cutting & fitting and jointing with maxphalt composition and cement 1:1 including testing with water to headof 45 meter or i50 C class item no 37 PHSI d page 37

For Pipe Line 6 inch	230	x	189.00	PRft	=	43470
For Pipe Line 9 inch	250	x	194.00	PRft	=	48500
For Pipe Line 12 inch	90	x	330.00	PRft	=	29700
For Pipe Line 18 inch	50	x	481.00	PRft	=	24050
					=	145720

total amount(A)

_____ % Above / Below on the rate amount to be added /deducated on basis of premium Quoted total (B)

Sanitary item _____ Rs(+) _____ = RS _____

G.I Pipe/ RCC Pipe _____ Rs(+) _____ = RS _____

Grand Total

Total (A)= b+c in words and figure

CONTRACTOR

EXECUTIVE ENGINEER BUILDINGS
DIVISION JAMSHORO

SCHEDULE "B"**Repair & Renovation of Imam Bargah Abul Fazal Abbas Bhattai Colony Taluka Kotri. (Electric Work)**

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
1	Wiring for light or fan point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-124 P-15)	75 NOS	1130.00 (Rs:One thousand one hundred thirty only).	Per.Point	84750
2	Providing & Fixing One Way SP 10/15 amp switch surface type.(S.NO:A-218 P-33)	75 NOS	58.00 (Rs:Fifty eight only).	Per.Nos	4350
3	Wiring for Plug point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit on surface as required. (S.NO:P-125 P-15)	10 NOS	669.00 (Rs: Six hundred sixty nine only).	Per.Point	6690
4	Providing & Fixing Two Pin 5 amp Plug & Socket (S.NO:A-222 P-33)	10 NOS	80.00 (Rs: Eighty only).	Per.Nos	800
5	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.29 copper conductor in 3/4" dia PVC conduit on surface.(SNO:A-03 P-01)	150 P.MR	171.00 (Rs: One hundred Seventy one only).	Per Mtr.	25650
6	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.44 conpper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-12 P-02)	150 P.MR	341.00 (Rs: Three hundred forty one only).	Per Mtr.	51150
7	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp SP (TB-5S) on prepared board as required.(S.NO:P-203 P-31)	12 NOS	916.00 (Rs:Nine hundred sixteen only).	Per.Point	10992
8	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp DP (TB-5S) on prepared board as required.(S.NO:P-204 P-31)	2 NOS	2456.00 (Rs:Two thousand four hundred fifty six only).	Per.Point	4912
9	Providing & Fixing Circuit Breaker 15.20.30.40.50.60.75 & 100 Amp TP (XS - 100NS) on prepared board as required.(S.NO:P-207 P-31)	1 Nos	9261.00 (Rs:Nine thousand two hundred sixty one only).	Per No.	9261
10	Providing & Fixing Bakelite ceiling Rose with two terminals.(S.NO:B-228 P-33)	30 NOS	72.00 (Rs:Seventy two only).	Per No.	2160
11	Providing & Fixing Brass Pendant Lamp holder .(S.NO:B-229 P-33)	35 NOS	74.00 (Rs:Seventy two only).	Per No.	2590

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
12	Providing & Fixing AmpMeters Size 96/96mm Direct 15A, 30A 50A.60A,&100 A as required & as per instruction of E.I.(S.NO:A-284 P-41)	1 NOS	1054.00 (Rs:One thousand fifty four only).	Per.No.	1054
13	Providing & Fixing VoltMeter Size 96/96mm 500 as required & as per instruction of E.I.(S.NO:B-285 P-41)	1 NOS	999.00 (Rs:Nine hundred ninety nine only).	Per.No.	999
14	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.36 copper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-11 P-02)	50 Per Mtr.	252.00 (Rs:two hundred fifty two only).	Per Mtr.	12600
15	Wiring for Call bell point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-128 P-15)	1 NOS	1764.00 (Rs:One thousand Seven hundred sixty four only).	Per No.	1764
16	Providing & Fixing Brass Ceiling Fan 56" (Good Quality) .(S.NO:B-235 P-34)	10 Nos	3185.00 (Rs:Three thousand one hundred eighty five only).	Per No.	31850

TOTAL RS:-	251572
-------------------	---------------

SCHEDULE "B"

**Repair & Renovation of Imam Bargah Abul Fazal Abbas Bhattai Colony Taluka Kotri.
(Electric Work)**

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
<u>((PART "B"))</u>					
1	Providing & Fixing Distribution Pannel Board of 3/4" thick sheeting double shutter to accommodate circuit breakers i/c painting with enamelled paint.	2 Sft		P.Sft	
2	P/F. Surface type 3 pin 15 amper s.p surface type plug switch and shoe unit prepared on board etc complete	6 NOS		EACH	
3	Fixing A.C. ceiling fan Regulator on metal board recessed in the walls	10 Nos		EACH	
4	Providing & Fixing A.C or D.C Electric bell 200/250 Volts MM (2-3/4") gong .(Imported)	1 Nos		EACH	
5	Providing & Fixing Mild Steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C roof.	10 Nos		EACH	
6	P/F Energy Saver (18 to 24 watts) Superior Quality including Fixing on Existing holder etc complete.(Imported)	35 Nos		EACH	
7	Supply / Fixing LED Light 06 watts etc complete	12 Nos		Each	
8	P/F Fancy Capsule Light with fancy Plastic body,holder,Saver etc complete (of approved make and design).	10 Nos		EACH	
9	P/F 1-40 watts Tube Light complete with 40 watts 4-0"long rod chock starter & putty with Philips components including necessary electric connection & Fixing on wall or ceiling etc complete (Philips).	15 Nos		EACH	

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
10	P/Fixing Pilot Lamps	3 NOS		EACH	

TOTAL RS:-	
-------------------	--

Total Amount (a)

_____ % Above / Below on the Rates of CSR.

Amount to be added / deducted on
basis of premium quoted Total (b)

PART"A"Schedule Item Rs. _____ Rs. (b) _____ = Rs. _____

PART"B"Non Schedule Item Rs. _____ Rs. (+) _____

Total (A)= a+b In Words & Fiqure _____

CONTRACTOR

EXECUTIVE ENGINEER (BUILDINGS)
DIVISION JAMSHORO

SCHEDULE "B"**Up-Gradation of Government Dispensary to Basic Health Unit Behar Colony (G+3) Phase
Taluka Kotri District Jamshoro (Electric Work)**

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
1	Wiring for light or fan point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-124 P-15)	80 NOS	1130.00 (Rs:One thousand one hundred thirty only).	Per.Point	90400
2	Providing & Fixing One Way SP 10/15 amp switch surface type.(S.NO:A-218 P-33)	80 NOS	58.00 (Rs:Fifty eight only).	Per.Nos	4640
3	Wiring for Plug point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit on surface as required. (S.NO:P-125 P-15)	20 NOS	669.00 (Rs: Six hundred sixty nine only).	Per.Point	13380
4	Providing & Fixing Two Pin 5 amp Plug & Socket (S.NO:A-222 P-33)	20 NOS	80.00 (Rs: eighty only).	Per.Nos	1600
5	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.29 copper conductor in 3/4" dia PVC conduit on surface.(SNO:A-03 P-01)	250 P.MR	171.00 (Rs: One hundred Seventy one only).	Per Mtr.	42750
6	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.44 copper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-12 P-02)	285 P.MR	341.00 (Rs: Three hundred forty one only).	Per Mtr.	97185
7	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp SP (TB-5S) on prepared board as required.(S.NO:P-203 P-31)	13 NOS	916.00 (Rs:Nine hundred sixteen only).	Per.Point	11908
8	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp DP (TB-5S) on prepared board as required.(S.NO:P-204 P-31)	2 NOS	2456.00 (Rs:Two thousand four hundred fifty six only).	Per.Point	4912
9	Providing & Fixing Circuit Breaker 3.5.10.15.20.& 30 Amp TP (XS-30NS[NB]) on prepared board as required.(S.NO:P-205 P-31)	1 NOS	5301.00 (Rs:Five thousand three hundred one only).	Per.Point	5301
10	Providing & Fixing Bakelite ceiling Rose with two terminals.(S.NO:B-228 P-33)	26 NOS	72.00 (Rs:Seventy two only).	Per.Point	1872

S. NO	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
11	Providing & Fixing Brass Pendant Lamp holder.(S.NO:B-229 P-33)	30 NOS	74.00 (Rs:Seventy four only).	Per.Point	2220
12	Providing & Fixing AmpMeters Size 96/96mm Direct 15A, 30A 50A.60A,&100 A as required & as per instruction of E.I.(S.NO:A-284 P-41)	1 NOS	1054.00 (Rs:One thousand fifty four only).	Per.No.	1054
13	Providing & Fixing VoltMeter Size 96/96mm 500 as required & as per instruction of E.I.(S.NO:B-285 P-41)	1 NOS	999.00 (Rs:Nine hundred ninty nine only).	Per.No.	999
14	Providing & Fixing Three Pin 10/15 amp Plug & Socket flush type.(S.NO:A-227 P-33)	4 Nos	162.00 (Rs:one hundred sixty two only).	Per No.	648
15	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.36 copper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-11 P-02)	60 Per Mtr.	252.00 (Rs:two hundred fifty two only).	Per Mtr.	15120
16	Wiring for Call bell point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-128 P-15)	3 NOS	1764.00 (Rs:One thousand Seven hundred sixty four only).	Per.Point	5292
17	Construction of RCC Foundation as per following specification & instruction of E.I for 31ft/40ft long tubular pole Excavation of soft/hard soil 3'x3'x5.5' stone soiling 3'x3'x6" Making lean in the ratio of 1:4:8 Length of MS bolts 6 1/2' (3/4"dia) 4 nos & making thread on MS rod Template 16"x16"x1/4 Rings 1/4" dia round bar 4 nos to the welded with MS rod RCC foundation rotio 1:2:4 with appropriate size 2'x2'x6.5' (S.NO:P-139 P-19)	3 Nos	15168.00 (Rs:fifteen thousand one hundred sixty eight only).	Per.Point	45504
18	Providing & Fixing Brass Ceiling Fan 56" (Good Quality) .(S.NO:B-235 P-34)	12 Nos	3185.00 (Rs:Three thousand one hundred eighty five only).	Per No.	38220
TOTAL RS:-					383005

SCHEDULE "B"**Up-Gradation of Government Dispensary to Basic Health Unit Behar Colony (G+3) Phase
Taluka Kotri District Jamshoro (Electric Work)**

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
((PART "B"))					
1	Providing & Fixing Distribution Pannel Board of 3/4" thick sheeting double shutter to accommodate circuit breakers i/c painting with enamelled paint.	2 Sft		P.Sft	
2	Providing & Fixing A.C or D.C Electric bell 200/250 Volts MM (2-3/4") gong .(Imported)	3 Nos		EACH	
3	Providing & Fixing Mild Steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C roof.	12 Nos		EACH	
4	P/F Energy Saver (18 to 24 watts) Superior Quality including Fixing on Existing holder etc complete.(Imported)	30 Nos		EACH	
5	P/F Fancy Capsule Light with fancy Plastic body,holder,Saver etc complete (of approved make and design).	15 Nos		EACH	
6	P/F 1-40 watts Tube Light complete with 40 watts 4-0"long rod chock starter & putty with Philips components including necessary electric connection & Fixing on wall or ceiling etc complete (Philips).	16 Nos		EACH	
7	S/F Exhuast Fan 280 mm (12") sweep with butterfly shutter for exhuast fan complete as required this rate also cutting wall or beam upto reqiured size fixing exhuast fan with connection and finishing the hole with coment etc complete in all respects (1st: quality).	2 Nos		EACH	
8	P/Installing Connecting & testing of road light fixture IP 66 rating lamp component SGP-338 philps appeared type with 25 volts SON-T lamp high priority amodized aluminum reflector highpressure die cost i/c hoisting complete with all installation accessories as approved by the Engineer parts shouls be Germany Make are equivalent quality	3 Nos		Each	

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
--------	----------------	-------	------	------	--------

9	P/I A.C Fancy road light Pole 20 ft hight to ground level with fancy arm bracket Impection window i/c (15x15") 4mm this squire pase plate 4 Nos 4mm round holes nut & bolts silver panint complete set (fancy Assambleed)changes of Loading tranportations changes fram factory to site.	3 Nos		Each	
---	---	----------	--	------	--

TOTAL RS:-	
-------------------	--

Total Amount (a)

_____ % Above / Below on the Rates of CSR.

Amount to be added / deducted on basis of premium quoted Total (b)

PART"A"Schedule Item Rs. _____ Rs. (b) _____ = Rs. _____

PART"B"Non Schedule Item Rs. _____ Rs. (+) _____

Total (A)= a+b In Words & Fiqure _____

CONTRACTOR

EXECUTIVE ENGINEER (BUILDINGS)
DIVISION JAMSHORO

NAME OF WORK: ADP NO 413 CONSTRUCTION OF GOVERNMENT DISPENSARY AT VILLAGE
 MOHAMMAD ISHAQUE KHOSO TALUKA KOTRI DISTRICT JAMSHORO
 PART A REMAINING WORK

DESCRIPTION	QTY		RATE	UNIT		AMOUNT
1 Excavtion in rock, dressed to designed section , grades and profiles excaveted material disposed off within 100 ft lift upto 5ft . (a)Soft rock ,slate , schist or lateriate work with and crow bar item 6 page 2 chapter 1						
	3414	x	7260.00	O%Cft	=	24786
2 Cement concrete brick or stone ballast1.5 inch to2 inch guage.(b) Ratio 1:4:8. Item no 4 b chapter 4						
	2994	x	9416.28	%Cft	=	281950
3 Erection and removal of centering for reniforced or palin cement concrete works of partial wood (2nd Class) (B) Vertical.						
	3120	x	3127.41	%Sft	=	97575
4 Cement concrete plain including placing , compacting finishing and curing complete (including screening and washing of stone aggrete without shuttering (F) Ratio 1:2: 4						
	3753	x	14429.25	%Cft	=	541584
5 Filling watering and ramming earth in floors with surplus earth from foundation lead upto one chain and lift upto 5 ft.(S.I.No.21 /C-1)						
	2276	x	1512.50	%OCFT	=	3442
6 Filling ,wateringand ramming earth under floor with new earth (excavated from outside) lead upto one chain and lift upto 5ft . item no 22 page 4 chapter 1 General schedule						
	16047	x	3630.00	%OCFT	=	58251

7 Supplying and filling sand under floors and plugging in walls.(S.I.NO.29/C-5)

10698 x 1141.25 %Cft = 122091

8 Reinforced cement concrete work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes of forms, moulds, lifting, shuttering, rendering and finishing and finishing the exposed surface (i/c screening, shingle (a) Rc work in roof slab, beams, columns, rafts, lintals and other structural members laid in situ or precast laid in position. Complete in all respects (I) Ratio 1:2:4, 90 lbs (S.I.No. 6 (a) (i) - P / 19)

1571 x 337.00 P.Cft = 529371

9 Fabrication of Miled Steel Reinforcement for Cement Concrete including cutting, bending, laying in position, making joints and fastly including cost of binding wire (also includes \ removal of rust from bars Qty same as item no(08)

PCWT 98 x 5001.70 PCWT = 491053

10 Providing and laying 1:3:6 cement concrete solid block masonry wall Above 6" in thickness set in 1:6 cement sand mortar in ground floor super structure including raking out joints and curring etc complete.

%Cft 1980 x 14621.44 %Cft = 289534

11 Pacca Brick work in foudation and plinth in cement sand mortar in 1:6 item 4(E) page 20 chapter 5

%Cft 113 x 11948.36 %Cft = 13442

12 Pacca Brick work in ground floor in cement sand mortar in 1:6 item 5(E) page 21 chapter 5

%Cft 54 x 12674.36 %Cft = 6789

13 Providing and fixing Galvanized iron frames/chowkats of size 7" x 2" or 4.5" x 3" for doors using 20 guage

G.I sheet including welded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ration 1:6 and repairing the jams. The cost also include all carriage, tools and plants used in making and fixing (S.I.NO.29/C-17).

35 x 228.90 PCft = 8012

14 Providing and fixing Galvanized iron frames/chowkats of size 7" x 2" or 4.5" x 3" for windows using 20 guage G.I sheet including welded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ration 1:6 and repairing the jams. The cost also include all carriage, tools and plants used in making and fixing (S.I.NO.28/C-17).

12 x 240.50 PCft = 2886

15 First class deodar wood rought, joinry in doors and windows etc fixed in position including chowkats, hold fasts, hinges, iron tower bolts, chowks, cleates, handles and cords with hookd etc. Deodar panelled or panelled and glazed or fully glazed, (b) 1.75" thick (S.I.NO.7(b)/C-10).

39 x 902.93 %P.Sft = 35214

16 Supplying and fixing in postion Aluminum channels framing hinged doors or Alcop made with 5 mm thick tinted glass glazing Beligum and alpha japan locks l c handels stoppers

21 x 1507.66 %P.Sft = 31661

17 Supplying and fixing in postion Aluminum channels framing hinged doors or Alcop made with 5 mm thick tinted glass glazing Beligum and alpha japan locks l c handels stoppers

20 x 1647.69 %P.Sft = 32954

18 Provinding and fixing iron/ steel grill using solid square bars of size 1/2" x 1/2" placed at 4" center to center and frame of flat iron 3/4" x 1/4" including circle shape at 1-0 a part equivalent fitted with screws or pins including painting 3 coats with first coat of red oxide paint etc (S.I.NO.30/C-17).

20 x 194.16 %P.Sft = 3883

19 Provinding and fixing iron/ steel grill door with angle iron frame of 1-1/2" x1- 1/2"x1/4 inch flat iron 3/4" x 1/4" with approved design and locking arrngment embeded in masonry as per instruction of engineer incharge . Item 31 page 94

80 x 231.60 %P.Sft = 18528

20 Cement plaster 1:6 upto 20 height (b) 1/2" (S.I.No.13(b)/C-19)

8520 x 2206.60 %Sft = 188001

21 Cement plaster 1:4 upto 20 height (a) 3/8" thick (S.I.No.11(a)/C-9)

8520 x 2197.52 %Sft = 187227

22 Providing and laying topping cement concrete 1:2:4 including surface finishing and dividing into panels © 2" thick (S.I.No.16©/C-8)

89 x 3275.50 %Sft = 2903

23 Providing and laying tiles glazed 6" x 6" x 1/4" on floor or wall facing requires pattern of styles specification jointed in white cement and pigment over base of 1:2 gray cement mortar 3/4" thick including washing and filling of joints with slurry of white cement and pigment in desired shape with finishing cleaning and cost of wax polish etc complete including cutting tiles the proper profile (S.I.No.61/C-8)

949 x 30509.77 %Sft = 289538

24 Laying white marble flooring fine dressed on the surface winding set 1:2 in lime mortar 1:2 including rubbing and polishing of the joints. 3/4 inch(Marble)

616 x 567.48 %PSft = 349568

25 Providing and fixing cement paving blocks flooring having size of 197x97x80mm of city / quddra/ cobble shape with pigmented having strength between 5000psi to 8500 psi filling the joints with hill sand and laying in specified manner /patter and design etc
item 74 page 50 Building shedule

2565 x 248.17 %PSft = 636556

26 Painting new surface © preparing surface and painting of doors and windows any type including edges (I and II) 3 coats (S.I.No.5© /I and II / C-11).

78.00 x 2116.41 %Sft = 1651

27 Primary coat of chalk under distemper (S.I.No.23/C-9).

8520 x 442.75 %Sft = 37722

28 Distemping C-3 Coats (S.I.No. 24© / C-9)

8520 x 1079.65 %Sft = 91985

29 Making and fixing steel grated door frames 1/16" thick sheeting including angle frame 2 "x 2" 3/8 "x 3/4" Square bars 4" c/c with locking arrangement.

112 x 726.72 %PSft = 81393

30 Preparing new surface and painting Guard bars of gates of iron bars grating railing (including standers brasses etc) and smilar open work (I and II) 3 coats

224 x 1396.67 %PSft = 3129

TOTAL AMOUNT = 4462676

total amount(A)

_____ % Above / Below on the rate amount to be added /deducated on basis of premium Quoted total (B)

Civil work Rs (a) _____ Rs(+) _____ = RS _____

Tile/ Marble Rs (b) _____ Rs(-) _____ = RS _____

Fabrication Rs (C) _____ Rs(+) _____ = RS _____

Non -S Items Rs (D) _____ Rs(-) _____ = RS _____

Grand Total

Total (A)= a+b in words and figure

CONTRACTOR

EXECUTIVE ENGINEER BUILDINGS
DIVISION JAMSHORO

schedule B

**NAME OF WORK: ADP NO 413 CONSTRUCTION OF GOVERNMENT DISPENSARYAT VILLAGE
MOHAMMAD ISHAQUE KHOSO TALUKA KOTRI DISTRICT JAMSHORO
PART A REMAINING WORK**

PART B

- 1 Providing & fixing squatting type white Glazed Earthenware W.C P
with including the cost of flushing cisteran with internal fitting and flush pipe with
bend and making requisite number of holes in walls, plinth and floor for pipe connections and
making good in cement concrete. 1:2:4 .
(B) (i) W.C of not less than 19" clear opening between
flushing rims and three gallons flushing tank with 4" dia C.I trap & C.I thumble .
item no 1 (B) (i) page 1 Chapter Sanitary fittings

Nos	2	4802.60	Each	=	9605
-----	---	---------	------	---	------

- 2 Providing and fixing 24" x 18" lavatory basin in white glazed earthenware complete with
and including cost of W.I or C.I cantelever (6") built into walls, painted white into 2 coats after
primary coat of red lead paint, a pair of half inch dia rubber plug chrome plated
brass chain, 1-1/4 inch dia brass waist approved pattern, 1.5" inch dia malleable iron
or brass unions and making requisite number of holes
in walls, plainth and floor for pipe connection and making good in cement and concrete 1:2:4
Foreign or equivalent.
item no 10 page 3 chapter sanitary fittings

Nos	2	4928.00	Each	=	9856
-----	---	---------	------	---	------

- 3 Add extra labour for providing and fixing earthenware pedestral white or colored glazed
Foreign or equivalent.
item no 11 page 3 chapter sanitary fittings

Nos	2	2533.47	Each	=	5067
-----	---	---------	------	---	------

- 4 Supplying and fixing in postion brass bib cocks.
item no 1 ((i) & (II)) chapter 6 page 16

(B)

1/2 inch dia brass bib cock , standard pattern

Nos	10	337.92	Each	=	3379
-----	----	--------	------	---	------

(B)

3/4 inch dia brass bib cock , standard pattern

Nos	10	348.92	Each	=	3489
-----	----	--------	------	---	------

- 5 Supplying and fixing concealed stop cock of superior quality with C.P head 1/2" dia.
item no 11 (a) chapter 6 page 18

Nos	10	478.28	Each	=	4783
-----	----	--------	------	---	------

6 Providing and fixing Handle Valves (China) .
item no 5 (a) chapter 6 page 17

1/2 inch dia	10	200.42	Each	=	2004
3/4 inch dia	15	271.92	Each	=	4079
1 inch dia	10	365.42	Each	=	3654
TOTAL				=	45917

PART C

7 Providing G.I Pipes, specials and clamps etc including fixing, cutting and fitting complete with and including cost of breaking through walls and roof, making good etc. painting 2 coats after cleaning the pipes etc with white zink paint with pigment to match the colour of the building and testing with water to pressure head of 200 ft and handling
item no 1 page 12 chapter 4 (WATER SERVICES INTERNAL)

1/2 inch pipe	20	73.21	Each	=	1464
3/4 inch pipe	10	95.79	Each	=	958
1 inch pipe	8	128.55	Each	=	1028
2 inch pipe	6	233.00	Each	=	1398
3 inch pipe	5	360.40	Each	=	1802
4 inch pipe	7	896.17	Each	=	6273

8 Add extra labour for concealed G.I Pipe and fitting including making recess in the wall for pipes and making good in cement concrete etc complete.
item no 2 page 12 chapter 4 (WATER SERVICES INTERNAL)

1/2 inch pipe	5	7.82	Each	=	39
3/4 inch pipe	8	8.45	Each	=	68
1 inch pipe	6	9.96	Each	=	60

9 Providing G.I Pipes, specials and clamps etc including fixing, cutting and fitting complete with and including cost of breaking through walls and roof, making good etc. painting 2 coats after cleaning the pipes etc with white zink paint with pigment to match the colour of the building and testing with water to pressure head of 200 ft and handling
item no 1 page 14 chapter (WATER SERVICES EXTERNAL)

1/2 inch pipe	12	64.88	Each	=	779
3/4 inch pipe	14	86.36	Each	=	1209
1 inch pipe	10	116.20	Each	=	1162
2 inch pipe	5	355.27	Each	=	1776
3 inch pipe	6	887.24	Each	=	5323
4 inch pipe	7	835.39	Each	=	5848

10 Providing RCC Pipes & collars of class C and fixing in trench including cutting & fitting and jointing with maxphalt composition and cement 1:1 including testing with water to head of 45 meter or 150 C class item no 37 PHSI d page 37

9 inch dia	20	194.00	PRft	3880
12 inch dia	25	330.00	PRft	8250

11 Providing Laying UPVC pressure pipes of Class D (equivalent make) fixing in trench i/c cutting, fitting and jointing with Z joint with one rubber i/c testing with water to a head 122 meter or 400 ft item 3 (i) page 23 chapter finished item Public health

1 inch dia	10	28.00	PRft	280
1 -1/2 inch dia	12	44.00	PRft	528
2 inch dia	15	66.00	PRft	990
3 inch dia	20	137.00	PRft	2740
4 inch dia	30	226.00	PRft	6780
5 inch dia	10	336.00	PRft	3360
6 inch dia	15	486.00	PRft	7290
8 inch dia	15	742.00	PRft	11130
10 inch dia	40	1375.00	PRft	55000

TOTAL PART C 129415

total amount(A)

_____ % Above / Below on the rate amount to be added /deducted on basis of premium Quoted total (B)

Sanitary item _____ Rs(+) _____ = RS _____

G.I Pipe/ RCC Pipe _____ Rs(+) _____ = RS _____

Grand Total

Total (A)= b+c in words and figure

CONTRACTOR

EXECUTIVE ENGINEER BUILDINGS
DIVISION JAMSHORO

Schedule "B"

Construction of Government Dispensary at Village Mohammad Ishaque Khoso.
Taluka Kotri. District Jamshoro (Electric Work).

S. NO	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
1	Wiring for light or fan point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-124 P-15)	50 NOS	1130.00	Per.Point	56500
2	Wiring for Plug point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit on surface as required. (S.NO:P-125 P-15)	10 NOS	669.00	Per.Point	6690
3	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.29 copper conductor in 3/4" dia PVC conduit on surface.(SNO:A-03 P-01)	115 P.MR	171.00	Per Mtr.	19665
4	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.44 conpper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-12 P-02)	300 P.MR	341.00	Per Mtr.	102300
5	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp SP (TB-5S) on prepared board as required.(S.NO:P-203 P-31)	10 NOS	916.00	Per.Point	9160
6	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp DP (TB-5S) on prepared board as required.(S.NO:P-204 P-31)	2 NOS	2456.00	Per.Point	4912
7	Providing & Fixing Circuit Breaker 3.5.10.15.20.& 30 Amp TP (XS-30NS[NB]) on prepared board as required.(S.NO:P-205 P-31)	1 NOS	5301.00	Per.Point	5301
8	Providing & Fixing Bakelite ceiling Rose with two terminals.(S.NO:B-228 P-33)	20 NOS	72.00	Per.Point	1440
9	Providing & Fixing Brass Pendant Lamp holder .(S.NO:B-229 P-33)	20 NOS	74.00	Per.Point	1480
10	Providing & Fixing AmpMeters Size 96/96mm Direct 15A, 30A 50A.60A,&100 A as required & as per instruction of E.I.(S.NO:A-284 P-41)	1 NOS	1054.00	Per.No.	1054
11	Providing & Fixing VoltMeter Size 96/96mm 500 as required & as per instruction of E.I.(S.NO:B-285 P-41)	1 NOS	999.00	Per.No.	999
12	Providing & Fixing Three Pin 10/15 amp Plug & Socket flush type.(S.NO:A-227 P-33)	4 Nos	162.00	Per No.	648

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
13	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.36 copper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-11 P-02)	90 Per Mtr.	252.00	Per Mtr.	22680
14	Wiring for Call bell point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-128 P-15)	2 NOS	1764.00	Per.Point	3528
15	Construction of RCC Foundation as per following specification & instruction of E.I for 31ft/40ft long tubular pole Excavation of soft/hard soil 3'x3'x5.5' stone soiling 3'x3'x6" Making lean in the ratio of 1:4:8 Length of MS bolts 6 1/2' (3/4"dia) 4 nos & making thread on MS rod Template 16"x16"x1/4 Rings 1/4" dia round bar 4 nos to the welded with MS rod RCC foundation rotio 1:2:4 with apprpriate size 2'x2'x6.5' (S.NO:P-139 P-19)	3 Nos	15168.00	Per.Point	45504
16	Providing & Fixing Brass Ceiling Fan 56" (Good Quality) .(S.NO:B-235 P-34)	8 Nos	3185.00	Per No.	25480
17	Providing & Fixing One Way SP 10/15 amp switch surface type.(S.NO:A-218 P-33)	50 NOS	58.00	Per.Nos	2900
TOTAL RS:-					310241

((PART "B"))

1	Providing & Fixing Distribution Pannel Board of 3/4" thick sheeting double shutter to accommodate circuit breakers i/c painting with enamelled paint.	2 Sft	2436.04	P.Sft	4872
2	Providing & Fixing A.C or D.C Electric bell 200/250 Volts MM (2-3/4") gong .(Imported)	2 Nos	750.00	EACH	1500
3	Providing & Fixing Mild Steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C roof.	8 Nos	325.00	EACH	2600
4	P/F Energy Saver (18 to 24 watts) Superior Quality including Fixing on Existing holder etc complete.(Imported)	20 Nos	605.00	EACH	12100

S.NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
5	P/F Fancy Capsule Light with fancy Plastic body,holder,Saver etc complete (of approved make and design).	10 Nos	950.00	EACH	9500
6	P/F 1-40 watts Tube Light complete with 40 watts 4-0"long rod chock starter & putty with Philips components including necessary electric connection & Fixing on wall or ceiling etc complete (Philips).	6 Nos	1450.00	EACH	8700
7	S/F Exhaust Fan 280 mm (12") sweep with butterfly shutter for exhaust fan complete as required this rate also cutting wall or beam upto required size fixing exhaust fan with connection and finishing the hole with coment etc complete in all respects (1st: quality).	2 Nos	3150.00	EACH	6300
8	P/Installing Connecting & testing of road light fixture IP 66 rating lamp component SGP-338 philps appeared type with 25 volts SON-T lamp high priority amodized aluminum reflector highpressure die cost i/c hoisting complete with all installation accessories as approved by the Engineer parts shouls be Germany Make are equivalent qualitiv	3 Nos	22000.00	Each	66000
9	P/I A.C Fancy road light Pole 20 ft hight to ground level with fancy arm bracket Impection window i/c (15x15") 4mm this squire pase plate 4 Nos 4mm round holes nut & bolts silver panint complete set (fancy Assambleed)changes of Loading tranportations changes fram factory to site.	3 Nos	26000.00	Each	78000

TOTAL RS:-	189572
-------------------	---------------

CONTRACTOR

EXECUTIVE ENGINEER (BUILDINGS)
DIVISION (W&S) DEPARTMENT
DISTRICT JAMSHORO.

SCHEDULE "B"**Remaining Work of BHU at Village Din Muhammad Aqlani Taluka T.B.Khan
District Jamshoro. (Electric Work)**

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
1	Wiring for light or fan point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-124 P-15)	75 NOS	1130.00 (Rs:One thousand one hundred thirty only).	Per.Point	84750
2	Providing & Fixing One Way SP 10/15 amp switch surface type.(S.NO:A-218 P-33)	75 NOS	58.00 (Rs:Fifty eight only).	Per.Nos	4350
3	Wiring for Plug point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit on surface as required. (S.NO:P-125 P-15)	10 NOS	669.00 (Rs: Six hundred sixty nine only).	Per.Point	6690
4	Providing & Fixing Two Pin 5 amp Plug & Socket (S.NO:A-222 P-33)	10 NOS	80.00 (Rs: Eighty only).	Per.Nos	800
5	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.29 copper conductor in 3/4" dia PVC conduit on surface.(SNO:A-03 P-01)	150 P.MR	171.00 (Rs: One hundred Seventy one only).	Per Mtr.	25650
6	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.44 conpper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-12 P-02)	150 P.MR	341.00 (Rs: Three hundred forty one only).	Per Mtr.	51150
7	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp SP (TB-5S) on prepared board as required.(S.NO:P-203 P-31)	12 NOS	916.00 (Rs:Nine hundred sixteen only).	Per.Point	10992
8	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp DP (TB-5S) on prepared board as required.(S.NO:P-204 P-31)	2 NOS	2456.00 (Rs:Two thousand four hundred fifty six only).	Per.Point	4912
9	Providing & Fixing Circuit Breaker 15.20.30.40.50.60.75 & 100 Amp TP (XS - 100NS) on prepared board as required.(S.NO:P-207 P-31)	1 Nos	9261.00 (Rs:Nine thousand two hundred sixty one only).	Per No.	9261
10	Providing & Fixing Bakelite ceiling Rose with two terminals.(S.NO:B-228 P-33)	30 NOS	72.00 (Rs:Seventy two only).	Per No.	2160
11	Providing & Fixing Brass Pendant Lamp holder .(S.NO:B-229 P-33)	35 NOS	74.00 (Rs:Seventy two only).	Per No.	2590

S. NO	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
12	Providing & Fixing AmpMeters Size 96/96mm Direct 15A, 30A 50A.60A,&100 A as required & as per instruction of E.I.(S.NO:A-284 P-41)	1 NOS	1054.00 (Rs:One thousand fifty four only).	Per.No.	1054
13	Providing & Fixing VoltMeter Size 96/96mm 500 as required & as per instruction of E.I.(S.NO:B-285 P-41)	1 NOS	999.00 (Rs:Nine hundred ninety nine only).	Per.No.	999
14	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.36 copper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-11 P-02)	50 Per Mtr.	252.00 (Rs:two hundred fifty two only).	Per Mtr.	12600
15	Wiring for Call bell point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-128 P-15)	1 NOS	1764.00 (Rs:One thousand Seven hundred sixty four only).	Per No.	1764
16	Providing & Fixing Brass Ceiling Fan 56" (Good Quality) .(S.NO:B-235 P-34)	10 Nos	3185.00 (Rs:Three thousand one hundred eighty five only).	Per No.	31850

TOTAL RS:-	251572
-------------------	---------------

SCHEDULE "B"

**Remaining Work of BHU at Village Din Muhammad Aqlani Taluka T.B.Khan
District Jamshoro. (Electric Work)**

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
<u>((PART "B"))</u>					
1	Providing & Fixing Distribution Pannel Board of 3/4" thick sheeting double shutter to accommodate circuit breakers i/c painting with enamelled paint.	2 Sft		P.Sft	
2	P/F. Surface type 3 pin 15 amper s.p surface type plug switch and shoe unit prepared on board etc complete	6 NOS		EACH	
3	Fixing A.C. ceiling fan Regulator on metal board recessed in the walls	10 Nos		EACH	
4	Providing & Fixing A.C or D.C Electric bell 200/250 Volts MM (2-3/4") gong .(Imported)	1 Nos		EACH	
5	Providing & Fixing Mild Steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C roof.	10 Nos		EACH	
6	P/F Energy Saver (18 to 24 watts) Superior Quality including Fixing on Existing holder etc complete.(Imported)	35 Nos		EACH	
7	Supply / Fixing LED Light 06 watts etc complete	12 Nos		Each	
8	P/F Fancy Capsule Light with fancy Plastic body,holder,Saver etc complete (of approved make and design).	10 Nos		EACH	
9	P/F 1-40 watts Tube Light complete with 40 watts 4-0"long rod chock starter & putty with Philips components including necessary electric connection & Fixing on wall or ceiling etc complete (Philips).	15 Nos		EACH	

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
--------	----------------	-------	------	------	--------

10	P/Fixing Pilot Lamps	3 NOS		EACH	
----	----------------------	----------	--	------	--

TOTAL RS:-

Total Amount (a)

_____ % Above / Below on the Rates of CSR.

Amount to be added / deducted on
basis of premium quoted Total (b)

PART "A" Schedule Item Rs. _____ Rs. (b) _____ = Rs. _____

PART "B" Non Schedule Item Rs. _____ Rs. (+) _____

Total (A) = a+b In Words & Figure _____

CONTRACTOR

EXECUTIVE ENGINEER (BUILDINGS)
DIVISION JAMSHORO

SCHEDULE "B"**Up-Gradation of Service of Taluka Hospital Thana Bula Khan District Jamshoro.
(Electric Work)**

S. NO	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
1	Wiring for light or fan point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-124 P-15)	122 NOS	1130.00 (Rs:One thousand one hundred thirty only).	Per.Point	137860
2	Providing & Fixing One Way SP 10/15 amp switch surface type.(S.NO:A-218 P-33)	122 NOS	58.00 (Rs:Fifty eight only).	Per.Nos	7076
3	Wiring for Plug point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit on surface as required. (S.NO:P-125 P-15)	20 NOS	669.00 (Rs: Six hundred sixty nine only).	Per.Point	13380
4	Providing & Fixing Two Pin 5 amp Plug & Socket (S.NO:A-222 P-33)	20 NOS	80.00 (Rs: Eighty only).	Per.Nos	1600
5	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.29 copper conductor in 3/4" dia PVC conduit on surface.(SNO:A-03 P-01)	350 P.MR	171.00 (Rs: One hundred Seventy one only).	Per Mtr.	59850
6	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.44 conpper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-12 P-02)	285 P.MR	341.00 (Rs: Three hundred forty one only).	Per Mtr.	97185
7	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp SP (TB-5S) on prepared board as required.(S.NO:P-203 P-31)	15 NOS	916.00 (Rs:Nine hundred sixteen only).	Per.Point	13740
8	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp DP (TB-5S) on prepared board as required.(S.NO:P-204 P-31)	3 NOS	2456.00 (Rs:Two thousand four hundred fifty six only).	Per.Point	7368
9	Providing & Fixing Circuit Breaker 15.20.30.40.50.60.75 & 100 Amp TP (XS - 100NS) on prepared board as required.(S.NO:P-207 P-31)	1 Nos	9261.00 (Rs:Nine thousand two hundred sixty one only).	Per No.	9261
10	Providing & Fixing Bakelite ceiling Rose with two terminals.(S.NO:B-228 P-33)	65 NOS	72.00 (Rs:Seventy two only).	Per No.	4680
11	Providing & Fixing Brass Pendant Lamp holder .(S.NO:B-229 P-33)	40 NOS	74.00 (Rs:Seventy two only).	Per No.	2960

S. NO	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
12	Providing & Fixing AmpMeters Size 96/96mm Direct 15A, 30A 50A.60A,&100 A as required & as per instruction of E.I.(S.NO:A-284 P-41)	1 NOS	1054.00 (Rs:One thousand fifty four only).	Per.No.	1054
13	Providing & Fixing VoltMeter Size 96/96mm 500 as required & as per instruction of E.I.(S.NO:B-285 P-41)	1 NOS	999.00 (Rs:Nine hundred ninty nine only).	Per.No.	999
14	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.36 copper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-11 P-02)	100 Per Mtr.	252.00 (Rs:two hundred fifty two only).	Per Mtr.	25200
15	Wiring for Call bell point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-128 P-15)	2 NOS	1764.00 (Rs:One thousand Seven hundred sixty four only).	Per No.	3528
16	Providing & Fixing Brass Ceiling Fan 56" (Good Quality) .(S.NO:B-235 P-34)	34 Nos	3185.00 (Rs:Three thousand one hundred eighty five only).	Per No.	108290

TOTAL RS:-	494031
-------------------	---------------

SCHEDULE "B"**Up-Gradation of Service of Taluka Hospital Thana Bula Khan District Jamshoro.
(Electric Work)**

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
((PART "B"))					
1	Providing & Fixing Distribution Pannel Board of 3/4" thick sheeting double shutter to accommodate circuit breakers i/c painting with enamelled paint.	4 Sft		P.Sft	
2	P/F. Surface type 3 pin 15 amper s.p surface type plug switch and shoe unit prepared on board etc complete	8 NOS		EACH	
3	Fixing A.C. ceiling fan Regulator on metal board recessed in the walls	34 Nos		EACH	
4	Providing & Fixing A.C or D.C Electric bell 200/250 Volts MM (2-3/4") gong .(Imported)	2 Nos		EACH	
5	Providing & Fixing Mild Steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C roof.	34 Nos		EACH	
6	P/F Energy Saver (18 to 24 watts) Superior Quality including Fixing on Existing holder etc complete.(Imported)	40 Nos		EACH	
7	Supply / Fixing LED Light 06 watts etc complete	12 Nos		Each	
8	P/F Fancy Capsule Light with fancy Plastic body,holder,Saver etc complete (of approved make and design).	17 Nos		EACH	
9	P/F 1-40 watts Tube Light complete with 40 watts 4-0"long rod chock starter & putty with Philips components including necessary electric connection & Fixing on wall or ceiling etc complete (Philips).	15 Nos		EACH	

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
10	P/Fixing Pilot Lamps	6 NOS		EACH	
11	P/F.SNF (HPIT) Fixture (Philips) type complete with lamp bolts ingnitor chwok capactor further more 99% pure aluminum used for reflector & tempered glass with heat resistant gas kit ensuring 400 watts lights req:(philips or german made	2 Nos		Each	

TOTAL RS:-

Total Amount (a)

_____ % Above / Below on the Rates of CSR.

Amount to be added / deducted on basis of premium quoted Total (b)

PART"A"Schedule Item Rs. _____ Rs. (b) _____ = Rs. _____

PART"B"Non Schedule Item Rs. _____ Rs. (+) _____

Total (A)= a+b In Words & Figure _____

CONTRACTOR

EXECUTIVE ENGINEER (BUILDINGS)
DIVISION JAMSHORO

schedule B

NAME OF WORK:

RENOVATION / REHABILITATION OF TALUKA HOSPITAL THANA BULA KHAN,
TALUKA THANA BULA KHAN, DISTRICT JAMSHORO

DESCRIPTION	QUANTITY	RATE	UNIT	AMOUNT
1 Cement concrete plain including placing , compacting finishing and curing complete (including screening and washing of stone aggregate without shuttering (F) Ratio 1:2: 4 (S.I.NO. 5 (C) P-16)	765.60	Cft	14429.25	%Cft 110470.00
2 Supplying & fixing porcelain tile size 24" x 24" on the bed 3/4" thick mortar ratio 1:2 (R.A.A)	3590.25	Sft	466.00	PSft 1673057.00
3 Providing and laying tiles glazed 6" x 6" x 1/4" on floor or wall facing requires pattern of styles specification jointed in white cement and pigment over base of 1:2 gray cement mortar 3/4" thick including washing and filling of joints with slurry of white cement and pigment in desired shape with finishing cleaning and cost of wax polish etc complete including cutting tiles the proper profile (S.I.No.61/C-8)	2637	Sft	30509.77	%Sft 804466
4 Laying verona Marble Flooring fine dressed on the surface without winding set in lime mortar 1:2 i/c rubbing & polishing of the joint (a) 3/4" thick flooring (R.A.A)	1491.75	Sft	371.55	% Sft 554260.00
				<u>3142252.00</u>
Total Amount (a)				
	%	Above / Below on the rate of CSR		Amount to be Added / Deducted on basis of premium quoted Total (b)
Civil Work Rs. (a)		Rs. (+)	=	Rs.
Non- S items Rs. (a)		Rs. (+)	=	Rs.
				<u>Grand Total</u>
Total (A) = a + b in words & figure				

Contractor

EXECUTIVE ENGINEER (BUILDING)
DIVISION JAMSHORO

SCHEDULE "B"**Renovation / Rehabilitation of Taluka Hospital Thana Bula Khan District Jamshoro
(Electric Work)**

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
1	Wiring for light or fan point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-124 P-15)	185 NOS	1130.00 (Rs:One thousand one hundred thirty only).	Per.Point	209050
2	Providing & Fixing One Way SP 10/15 amp switch surface type.(S.NO:A-218 P-33)	185 NOS	58.00 (Rs: fifty eight only).	Per.Nos	10730
3	Wiring for Plug point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit on surface as required. (S.NO:P-125 P-15)	30 NOS	669.00 (Rs: Six hundred sixty nine only).	Per.Point	20070
4	Providing & Fixing Two Pin 5 amp Plug & Socket (S.NO:A-222 P-33)	30 NOS	80.00 (Rs: eighty only).	Per.Nos	2400
5	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.29 copper conductor in 3/4" dia PVC conduit on surface.(SNO:A-03 P-01)	250 P.MR	171.00 (Rs: One hundred Seventy one only).	Per Mtr.	42750
6	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.44 conpper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-12 P-02)	200 P.MR	341.00 (Rs: Three hundred forty one only).	Per Mtr.	68200
7	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp SP (TB-5S) on prepared board as required.(S.NO:P-203 P-31)	30 NOS	916.00 (Rs:Nine hundred sixteen only).	Per.Nos	27480
8	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp DP (TB-5S) on prepared board as required.(S.NO:P-204 P-31)	4 NOS	2456.00 (Rs:Two thousand four hundred fifty six only).	Per.Nos	9824
9	Providing & Fixing Circuit Breaker 15.20.30.40.50.60.75 & 100 Amp TP (XS - 100NS) on prepared board as required.(S.NO:P-207 P-31)	2 Nos	9261.00 (Rs:Nine thousand two hundred sixty one only).	Per No.	18522
10	Providing & Fixing Circuit Breaker 125.150.200 & 225 Amp TP (XS-225NS) on prepared board as required.(S.NO:P-208 P-31)	1 Nos	25541.00 (Rs:twenty five thousand five hundred forty one only).	Per No.	25541
11	Providing & Fixing Bakelite ceiling Rose with two terminals.(S.NO:B-228 P-33)	75 NOS	72.00 (Rs:Seventy two only).	Per No.	5400
12	Providing & Fixing Brass Pendant Lamp holder .(S.NO:B-229 P-33)	70 NOS	74.00 (Rs:Seventy two only).	Per No.	5180
13	Providing & Fixing AmpMeters Size 96/96mm Direct 15A, 30A 50A.60A,&100 A as required & as per instruction of E.I.(S.NO:A-284 P-41)	1 NOS	1054.00 (Rs:One thousand fifty four only).	Per.No.	1054

S. NO	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
14	Providing & Fixing VoltMeter Size 96/96mm 500 as required & as per instruction of E.I.(S.NO:B-285 P-41)	1 NOS	999.00 (Rs:Nine hundred ninty nine only).	Per.No.	999
15	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.36 copper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-11 P-02)	50 Per Mtr.	252.00 (Rs:two hundred fifty two only).	Per Mtr.	12600
16	Wiring for Call bell point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-128 P-15)	4 NOS	1764.00 (Rs:One thousand Seven hundred sixty four only).	Per No.	7056
17	Providing & Fixing Brass Ceiling Fan 56" (Good Quality) .(S.NO:B-235 P-34)	30 Nos	3185.00 (Rs:Three thousand one hundred eighty five only).	Per No.	95550
18	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.64 (16mm2)copper conductor in 3/4" dia PVC conduit on surface. (SNO:A-07 P-01)	70 P. Mtr.	605.00 (Rs:Six hundred five only).	Per Mtr.	42350

TOTAL RS:-	604756
-------------------	---------------

SCHEDULE "B"**Renovation / Rehabilitation of Taluka Hospital Thana Bula Khan District Jamshoro
(Electric Work)**

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
((PART "B"))					
1	Providing & Fixing Distribution Pannel Board of 3/4" thick sheeting double shutter to accommodate circuit breakers i/c painting with enamelled paint.	6 Sft		P.Sft	
2	P/F. Surface type 3 pin 15 amper s.p surface type plug switch and shoe unit prepared on board etc complete	8 NOS		EACH	
3	Fixing A.C. ceiling fan Regulator on metal board recessed in the walls	30 Nos		EACH	
4	Providing & Fixing A.C or D.C Electric bell 200/250 Volts MM (2-3/4") gong .(Imported)	4 Nos		EACH	
5	Providing & Fixing Mild Steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C roof.	30 Nos		EACH	
6	P/F Energy Saver (18 to 24 watts) Superior Quality including Fixing on Existing holder etc complete.(Imported)	70 Nos		EACH	
7	Supply / Fixing LED Light 06 watts etc complete	15 Nos		Each	
8	P/F Fancy Capsule Light with fancy Plastic body,holder,Saver etc complete (of approved make and design).	10 Nos		EACH	
9	P/F 1-40 watts Tube Light complete with 40 watts 4-0"long rod chock starter & putty with Philips components including necessary electric connection & Fixing on wall or ceiling etc complete (Philips).	40 Nos		EACH	
10	P/Fixing Pilot Lamps	6 NOS		EACH	

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
--------	----------------	-------	------	------	--------

11	P/F.SNF (HPIT) Fixture (Philips) type complete with lamp bolts ignitor chwok capacitor further more 99% pure aluminum used for reflector & tempered glass with heat resistant gas kit ensuring 400 watts lights req:(philips or german made	2 Nos		Each	
----	---	----------	--	------	--

TOTAL RS:-

Total Amount (a)

_____ % Above / Below on the Rates of CSR.

Amount to be added / deducted on basis of premium quoted Total (b)

PART"A"Schedule Item Rs. _____ Rs. (b) _____ = Rs. _____

PART"B"Non Schedule Item Rs. _____ Rs. (+) _____

Total (A)= a+b In Words & Figue _____

CONTRACTOR

EXECUTIVE ENGINEER (BUILDINGS)
DIVISION JAMSHORO

schedule B

NAME OF WORK:

**UP- GRADATION OF BHU TO THE LEVEL OF 20 BEDED RHC AT THANA AHMED KHAN
(WARD BLOCK / INDOOR BLOCK) TALUKA THANA BULA KHAN, DISTRICT JAMSHORO**

DESCRIPTION	QUANTIY	RATE	UNIT	AMOUNT
1 Cement concrete plain including placing , compacting finishing and curing complete (including screening and washing of stone aggrete without shuttering (F) Ratio 1:2: 4 (S.I.NO. 5 (C) P-16)	765.60	Cft	14429.25 %Cft	110470.00
2 Supplying & fixing porcelain tile size 24" x 24" on the bed 3/4" thick mortar ratio 1:2 (R.A.A)	3395.37	Sft	466.00 PSft	1582242.00
3 Providing and laying tiles glazed 6" x 6" x 1/4" on floor or wall facing requires pattern of styles specification jointed in white cement and pigment over base of 1:2 gray cement mortar 3/4" thick including washing and filling of joints with slurry of white cement and pigment in desired shape with finishing cleaning and cost of wax polish etc complete including cutting tiles the proper profile (S.I.No.61/C-8)	2637	Sft	30509.77 %Sft	804466
4 Laying verona Marble Flooring fine dressed on the surface without winding set in lime mortar 1:2 i/c rubbing & polishing of the joint (a) 3/4" thick flooring (R.A.A)	1491.75	Sft	371.55 % Sft	554260.00

3051438.00

Total Amount (a)

% Above / Below on the rate of CSR

Amount to be Added / Deducted
on basis of premium quoted Total (b)

Civil Work Rs. (a) _____ Rs. (+) _____ = Rs. _____

Non- S items Rs. (a) _____ Rs. (+) _____ = Rs. _____

Grand Total _____

Total (A) = a + b in words & figure _____

Contractor

EXECUTIVE ENGINEER (BUILDING)
DIVISION JAMSHORO

SCHEDULE "B"

**Up-Gradation to BHU to the Level of 20 Badded RHC at Thana Ahmed Khan
(Ward Block/Indoor Block) Taluka T.B. Khan (Electric Work)**

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
1	Wiring for light or fan point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-124 P-15)	185 NOS	1130.00 (Rs:One thousand one hundred thirty only).	Per.Point	209050
2	Providing & Fixing One Way SP 10/15 amp switch surface type.(S.NO:A-218 P-33)	185 NOS	58.00 (Rs: fifty eight only).	Per.Nos	10730
3	Wiring for Plug point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit on surface as required. (S.NO:P-125 P-15)	30 NOS	669.00 (Rs: Six hundred sixty nine only).	Per.Point	20070
4	Providing & Fixing Two Pin 5 amp Plug & Socket (S.NO:A-222 P-33)	30 NOS	80.00 (Rs: eighty only).	Per.Nos	2400
5	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.29 copper conductor in 3/4" dia PVC conduit on surface.(SNO:A-03 P-01)	250 P.MR	171.00 (Rs: One hundred Seventy one only).	Per Mtr.	42750
6	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.44 conpper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-12 P-02)	200 P.MR	341.00 (Rs: Three hundred forty one only).	Per Mtr.	68200
7	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp SP (TB-5S) on prepared board as required.(S.NO:P-203 P-31)	30 NOS	916.00 (Rs:Nine hundred sixteen only).	Per.Nos	27480
8	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp DP (TB-5S) on prepared board as required.(S.NO:P-204 P-31)	4 NOS	2456.00 (Rs:Two thousand four hundred fifty six only).	Per.Nos	9824
9	Providing & Fixing Circuit Breaker 15.20.30.40.50.60.75 & 100 Amp TP (XS - 100NS) on prepared board as required.(S.NO:P-207 P-31)	2 Nos	9261.00 (Rs:Nine thousand two hundred sixty one only).	Per No.	18522
10	Providing & Fixing Circuit Breaker 125.150.200 & 225 Amp TP (XS-225NS) on prepared board as required.(S.NO:P-208 P-31)	1 Nos	25541.00 (Rs:twenty five thousand five hundred forty one only).	Per No.	25541
11	Providing & Fixing Bakelite ceiling Rose with two terminals.(S.NO:B-228 P-33)	75 NOS	72.00 (Rs:Seventy two only).	Per No.	5400
12	Providing & Fixing Brass Pendant Lamp holder .(S.NO:B-229 P-33)	70 NOS	74.00 (Rs:Seventy two only).	Per No.	5180
13	Providing & Fixing AmpMeters Size 96/96mm Direct 15A, 30A 50A.60A,&100 A as required & as per instruction of E.I.(S.NO:A-284 P-41)	1 NOS	1054.00 (Rs:One thousand fifty four only).	Per.No.	1054

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
14	Providing & Fixing VoltMeter Size 96/96mm 500 as required & as per instruction of E.I.(S.NO:B-285 P-41)	1 NOS	999.00 (Rs:Nine hundred ninty nine only).	Per.No.	999
15	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.36 copper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-11 P-02)	50 Per Mtr.	252.00 (Rs:two hundred fifty two only).	Per Mtr.	12600
16	Wiring for Call bell point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-128 P-15)	4 NOS	1764.00 (Rs:One thousand Seven hundred sixty four only).	Per No.	7056
17	Providing & Fixing Brass Ceiling Fan 56" (Good Quality) .(S.NO:B-235 P-34)	30 Nos	3185.00 (Rs:Three thousand one hundred eighty five only).	Per No.	95550
18	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.64 (16mm ²)copper conductor in 3/4" dia PVC conduit on surface. (SNO:A-07 P-01)	70 P. Mtr.	605.00 (Rs:Six hundred five only).	Per Mtr.	42350

TOTAL RS:-	604756
-------------------	---------------

SCHEDULE "B"

**Up-Gradation to BHU to the Level of 20 Badded RHC at Thana Ahmed Khan
(Ward Block/Indoor Block) Taluka T.B. Khan (Electric Work)**

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
((PART "B"))					
1	Providing & Fixing Distribution Pannel Board of 3/4" thick sheeting double shutter to accommodate circuit breakers i/c painting with enamelled paint.	6 Sft		P.Sft	
2	P/F. Surface type 3 pin 15 amper s.p surface type plug switch and shoe unit prepared on board etc complete	8 NOS		EACH	
3	Fixing A.C. ceiling fan Regulator on metal board recessed in the walls	30 Nos		EACH	
4	Providing & Fixing A.C or D.C Electric bell 200/250 Volts MM (2-3/4") gong .(Imported)	4 Nos		EACH	
5	Providing & Fixing Mild Steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C roof.	30 Nos		EACH	
6	P/F Energy Saver (18 to 24 watts) Superior Quality including Fixing on Existing holder etc complete.(Imported)	70 Nos		EACH	
7	Supply / Fixing LED Light 06 watts etc complete	15 Nos		Each	
8	P/F Fancy Capsule Light with fancy Plastic body,holder,Saver etc complete (of approved make and design).	10 Nos		EACH	
9	P/F 1-40 watts Tube Light complete with 40 watts 4-0"long rod chock starter & putty with Philips components including necessary electric connection & Fixing on wall or ceiling etc complete (Philips).	40 Nos		EACH	
10	P/Fixing Pilot Lamps	6 NOS		EACH	

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
11	P/F.SNF (HPIT) Fixture (Philips) type complete with lamp bolts ingnitor chwok capactor further more 99% pure aluminum used for reflector & tempered glass with heat resistant gas kit ensuring 400 watts lights req:(philips or german made	2 Nos		Each	

TOTAL RS:-

Total Amount (a)

_____ % Above / Below on the Rates of CSR. Amount to be added / deducted on basis of premium quoted Total (b)

PART"A"Schedule Item Rs. _____ Rs. (b) _____ = Rs. _____

PART"B"Non Schedule Item Rs. _____ Rs. (+) _____

Total (A)= a+b In Words & Figure _____

CONTRACTOR

EXECUTIVE ENGINEER (BUILDINGS)
DIVISION JAMSHORO

schedule B

NAME OF WORK:

UP- GRADATION OF BHU TO THE LEVEL OF 20 BEDED RHC AT SARI

(WARD BLOCK / INDOOR BLOCK) TALUKA THANA BULA KHAN, DISTRICT JAMSHORO

DESCRIPTION	QUANTITY	RATE	UNIT	AMOUNT
1 Cement concrete plain including placing , compacting finishing and curing complete (including screening and washing of stone aggregate without shuttering (F) Ratio 1:2: 4 (S.I.NO. 5 (C) P-16)	765.60	Cft	14429.25 %Cft	110470.00
2 Supplying & fixing porcelain tile size 24" x 24" on the bed 3/4" thick mortar ratio 1:2 (R.A.A)	3590.25	Sft	466.00 PSft	1673057.00
3 Providing and laying tiles glazed 6" x 6" x 1/4" on floor or wall facing requires pattern of styles specification jointed in white cement and pigment over base of 1:2 gray cement mortar 3/4" thick including washing and filling of joints with slurry of white cement and pigment in desired shape with finishing cleaning and cost of wax polish etc complete including cutting tiles the proper profile (S.I.No.61/C-8)	2637	Sft	30509.77 %Sft	804466
4 Laying verona Marble Flooring fine dressed on the surface without winding set in lime mortar 1:2 i/c rubbing & polishing of the joint (a) 3/4" thick flooring (R.A.A)	1491.75	Sft	371.55 % Sft	554260.00
				<u>3142252.00</u>

Total Amount (a)

%

Above / Below on the rate of CSR

Amount to be Added / Deducted
on basis of premium quoted Total (b)

Civil Work Rs. (a)

Rs. (+)

= Rs.

Non- S items Rs. (a)

Rs. (+)

= Rs.

Grand Total

Total (A) = a + b in words & figure

Contractor

**EXECUTIVE ENGINEER (BUILDING)
DIVISION JAMSHORO**

SCHEDULE "B"

**Up-Gradation of BHU to the Level of Beded RHC at Sari Taluka T.B Khah
(Ward Block/Indoor Block) (Electric Work)**

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
1	Wiring for light or fan point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-124 P-15)	185 NOS	1130.00 (Rs:One thousand one hundred thirty only).	Per.Point	209050
2	Providing & Fixing One Way SP 10/15 amp switch surface type.(S.NO:A-218 P-33)	185 NOS	58.00 (Rs: fifty eight only).	Per.Nos	10730
3	Wiring for Plug point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit on surface as required. (S.NO:P-125 P-15)	30 NOS	669.00 (Rs: Six hundred sixty nine only).	Per.Point	20070
4	Providing & Fixing Two Pin 5 amp Plug & Socket (S.NO:A-222 P-33)	30 NOS	80.00 (Rs: eighty only).	Per.Nos	2400
5	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.29 copper conductor in 3/4" dia PVC conduit on surface.(SNO:A-03 P-01)	250 P.MR	171.00 (Rs: One hundred Seventy one only).	Per Mtr.	42750
6	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.44 copper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-12 P-02)	200 P.MR	341.00 (Rs: Three hundred forty one only).	Per Mtr.	68200
7	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp SP (TB-5S) on prepared board as required.(S.NO:P-203 P-31)	30 NOS	916.00 (Rs:Nine hundred sixteen only).	Per.Nos	27480
8	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp DP (TB-5S) on prepared board as required.(S.NO:P-204 P-31)	4 NOS	2456.00 (Rs:Two thousand four hundred fifty six only).	Per.Nos	9824
9	Providing & Fixing Circuit Breaker 15.20.30.40.50.60.75 & 100 Amp TP (XS - 100NS) on prepared board as required.(S.NO:P-207 P-31)	2 Nos	9261.00 (Rs:Nine thousand two hundred sixty one only).	Per No.	18522
10	Providing & Fixing Circuit Breaker 125.150.200 & 225 Amp TP (XS-225NS) on prepared board as required.(S.NO:P-208 P-31)	1 Nos	25541.00 (Rs:twenty five thousand five hundred forty one only).	Per No.	25541
11	Providing & Fixing Bakelite ceiling Rose with two terminals.(S.NO:B-228 P-33)	75 NOS	72.00 (Rs:Seventy two only).	Per No.	5400
12	Providing & Fixing Brass Pendant Lamp holder .(S.NO:B-229 P-33)	70 NOS	74.00 (Rs:Seventy two only).	Per No.	5180
13	Providing & Fixing AmpMeters Size 96/96mm Direct 15A, 30A 50A.60A,&100 A as required & as per instruction of E.I.(S.NO:A-284 P-41)	1 NOS	1054.00 (Rs:One thousand fifty four only).	Per.No.	1054

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
14	Providing & Fixing VoltMeter Size 96/96mm 500 as required & as per instruction of E.I.(S.NO:B-285 P-41)	1 NOS	999.00 (Rs:Nine hundred ninty nine only).	Per.No.	999
15	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.36 copper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-11 P-02)	50 Per Mtr.	252.00 (Rs:two hundred fifty two only).	Per Mtr.	12600
16	Wiring for Call bell point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-128 P-15)	4 NOS	1764.00 (Rs:One thousand Seven hundred sixty four only).	Per No.	7056
17	Providing & Fixing Brass Ceiling Fan 56" (Good Quality) .(S.NO:B-235 P-34)	30 Nos	3185.00 (Rs:Three thousand one hundred eighty five only).	Per No.	95550
18	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.64 (16mm2)copper conductor in 3/4" dia PVC conduit on surface. (SNO:A-07 P-01)	70 P. Mtr.	605.00 (Rs:Six hundred five only).	Per Mtr.	42350

TOTAL RS:-	604756
-------------------	---------------

SCHEDULE "B"

**Up-Gradation of BHU to the Level of Beded RHC at Sari Taluka T.B Khah
(Ward Block/Indoor Block) (Electric Work)**

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
((PART "B"))					
1	Providing & Fixing Distribution Pannel Board of 3/4" thick sheeting double shutter to accommodate circuit breakers i/c painting with enamelled paint.	6 Sft		P.Sft	
2	P/F. Surface type 3 pin 15 amper s.p surface type plug switch and shoe unit prepared on board etc complete	8 NOS		EACH	
3	Fixing A.C. ceiling fan Regulator on metal board recessed in the walls	30 Nos		EACH	
4	Providing & Fixing A.C or D.C Electric bell 200/250 Volts MM (2-3/4") gong .(Imported)	4 Nos		EACH	
5	Providing & Fixing Mild Steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C roof.	30 Nos		EACH	
6	P/F Energy Saver (18 to 24 watts) Superior Quality including Fixing on Existing holder etc complete.(Imported)	70 Nos		EACH	
7	Supply / Fixing LED Light 06 watts etc complete	15 Nos		Each	
8	P/F Fancy Capsule Light with fancy Plastic body,holder,Saver etc complete (of approved make and design).	10 Nos		EACH	
9	P/F 1-40 watts Tube Light complete with 40 watts 4-0"long rod chock starter & putty with Philips components including necessary electric connection & Fixing on wall or ceiling etc complete (Philips).	40 Nos		EACH	
10	P/Fixing Pilot Lamps	6 NOS		EACH	

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
--------	----------------	-------	------	------	--------

11	P/F.SNF (HPIT) Fixture (Philips) type complete with lamp bolts ingnitor chwok capactor further more 99% pure aluminum used for reflector & tempered glass with heat resistant gas kit ensuring 400 watts lights req:(philips or german made	2 Nos		Each	
----	---	----------	--	------	--

TOTAL RS:-

Total Amount (a)

_____ % Above / Below on the Rates of CSR.

Amount to be added / deducted on basis of premium quoted Total (b)

PART"A"Schedule Item Rs. _____ Rs. (b) _____ = Rs. _____

PART"B"Non Schedule Item Rs. _____ Rs. (+) _____

Total (A)= a+b In Words & Figure _____

CONTRACTOR

EXECUTIVE ENGINEER (BUILDINGS)
DIVISION JAMSHORO

schedule B

NAME OF WORK:

**UP- GRADATION OF BHU TO THE LEVEL OF 20 BEDED RHC AT TOUNG SHAREEF
(WARD BLOCK / INDOOR BLOCK) TALUKA THANA BULA KHAN, DISTRICT JAMSHORO**

DESCRIPTION	QUANTIY	RATE	UNIT	AMOUNT
1 Cement concrete plain including placing , compacting finishing and curing complete (including screening and washing of stone aggrete without shuttering (F) Ratio 1:2: 4 (S.I.NO. 5 (C) P-16)	765.60	Cft	14429.25 %Cft	110470.00
2 Supplying & fixing porcelain tile size 24" x 24" on the bed3/4" thick mortar ratio 1:2 (R.A.A)	3563.37	Sft	466.00 PSft	1660530.00
3 Providing and laying tiles glazed 6" x 6" x 1/4" on floor or wall facing requires pattern of styles specification jointed in white cement and pigment over base of 1:2 gray cement mortar 3/4" thick including washing and filling of joints with slurry of white cement and pigment in desired shape with finishing cleaning and cost of wax polish etc complete including cutting tiles the proper profile (S.I.No.61/C-8)	2637	Sft	30509.77 %Sft	804466
4 Laying verona Marble Flooring fine dressed on the surface without winding set in lime mortar 1:2 i/c rubbing & polishing of the joint (a) 3/4" thick flooring (R.A.A)	1491.75	Sft	371.55 % Sft	554260.00
				<u>3129726.00</u>

Total Amount (a)

%

Above / Below on the rate of CSR

Amount to be Added / Deducted
on basis of premium quoted Total (b)

Civil Work Rs. (a)

Rs. (+)

= Rs.

Non- S items Rs. (a)

Rs. (+)

= Rs.

Grand Total

Total (A) = a + b in words & figure

Contractor

EXECUTIVE ENGINEER (BUILDING)
DIVISION JAMSHORO

SCHEDULE "B"**Rehabilitation / Construction of Basic Health Unit at Toung Sharif Taluka Thana Bula Khan
District Jamshoro (Electric Work)**

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
1	Wiring for light or fan point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-124 P-15)	185 NOS	1130.00 (Rs:One thousand one hundred thirty only).	Per.Point	209050
2	Providing & Fixing One Way SP 10/15 amp switch surface type.(S.NO:A-218 P-33)	185 NOS	58.00 (Rs: fifty eight only).	Per.Nos	10730
3	Wiring for Plug point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit on surface as required. (S.NO:P-125 P-15)	30 NOS	669.00 (Rs: Six hundred sixty nine only).	Per.Point	20070
4	Providing & Fixing Two Pin 5 amp Plug & Socket (S.NO:A-222 P-33)	30 NOS	80.00 (Rs: eighty only).	Per.Nos	2400
5	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.29 copper conductor in 3/4" dia PVC conduit on surface.(SNO:A-03 P-01)	250 P.MR	171.00 (Rs: One hundred Seventy one only).	Per Mtr.	42750
6	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.44 conpper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-12 P-02)	200 P.MR	341.00 (Rs: Three hundred forty one only).	Per Mtr.	68200
7	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp SP (TB-5S) on prepared board as required.(S.NO:P-203 P-31)	30 NOS	916.00 (Rs:Nine hundred sixteen only).	Per.Nos	27480
8	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp DP (TB-5S) on prepared board as required.(S.NO:P-204 P-31)	4 NOS	2456.00 (Rs:Two thousand four hundred fifty six only).	Per.Nos	9824
9	Providing & Fixing Circuit Breaker 15.20.30.40.50.60.75 & 100 Amp TP (XS - 100NS) on prepared board as required.(S.NO:P-207 P-31)	2 Nos	9261.00 (Rs:Nine thousand two hundred sixty one only).	Per No.	18522
10	Providing & Fixing Circuit Breaker 125.150.200 & 225 Amp TP (XS-225NS) on prepared board as required.(S.NO:P-208 P-31)	1 Nos	25541.00 (Rs:twenty five thousand five hundred forty one only).	Per No.	25541
11	Providing & Fixing Bakelite ceiling Rose with two terminals.(S.NO:B-228 P-33)	75 NOS	72.00 (Rs:Seventy two only).	Per No.	5400
12	Providing & Fixing Brass Pendant Lamp holder .(S.NO:B-229 P-33)	70 NOS	74.00 (Rs:Seventy two only).	Per No.	5180
13	Providing & Fixing AmpMeters Size 96/96mm Direct 15A, 30A 50A.60A,&100 A as required & as per instruction of E.I.(S.NO:A-284 P-41)	1 NOS	1054.00 (Rs:One thousand fifty four only).	Per.No.	1054

S. NO	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
14	Providing & Fixing VoltMeter Size 96/96mm 500 as required & as per instruction of E.I.(S.NO:B-285 P-41)	1 NOS	999.00 (Rs:Nine hundred ninty nine only).	Per.No.	999
15	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.36 copper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-11 P-02)	50 Per Mtr.	252.00 (Rs:two hundred fifty two only).	Per Mtr.	12600
16	Wiring for Call bell point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-128 P-15)	4 NOS	1764.00 (Rs:One thousand Seven hundred sixty four only).	Per No.	7056
17	Providing & Fixing Brass Ceiling Fan 56" (Good Quality) .(S.NO:B-235 P-34)	30 Nos	3185.00 (Rs:Three thousand one hundred eighty five only).	Per No.	95550
18	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.64 (16mm2)copper conductor in 3/4" dia PVC conduit on surface. (SNO:A-07 P-01)	70 P. Mtr.	605.00 (Rs:Six hundred five only).	Per Mtr.	42350

TOTAL RS:-	604756
-------------------	---------------

SCHEDULE "B"**Rehabilitation / Construction of Basic Health Unit at Toung Sharif Taluka Thana Bula Khan
District Jamshoro (Electric Work)**

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
((PART "B"))					
1	Providing & Fixing Distribution Pannel Board of 3/4" thick sheeting double shutter to accommodate circuit breakers i/c painting with enamelled paint.	6 Sft		P.Sft	
2	P/F. Surface type 3 pin 15 amper s.p surface type plug switch and shoe unit prepared on board etc complete	8 NOS		EACH	
3	Fixing A.C. ceiling fan Regulator on metal board recessed in the walls	30 Nos		EACH	
4	Providing & Fixing A.C or D.C Electric bell 200/250 Volts MM (2-3/4") gong .(Imported)	4 Nos		EACH	
5	Providing & Fixing Mild Steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C roof.	30 Nos		EACH	
6	P/F Energy Saver (18 to 24 watts) Superior Quality including Fixing on Existing holder etc complete.(Imported)	70 Nos		EACH	
7	Supply / Fixing LED Light 06 watts etc complete	15 Nos		Each	
8	P/F Fancy Capsule Light with fancy Plastic body,holder,Saver etc complete (of approved make and design).	10 Nos		EACH	
9	P/F 1-40 watts Tube Light complete with 40 watts 4-0"long rod chock starter & putty with Philips components including necessary electric connection & Fixing on wall or ceiling etc complete (Philips).	40 Nos		EACH	
10	P/Fixing Pilot Lamps	6 NOS		EACH	

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
--------	----------------	-------	------	------	--------

11	P/F.SNF (HPIT) Fixture (Philips) type complete with lamp bolts ignitor chwok capacitor further more 99% pure aluminum used for reflector & tempered glass with heat resistant gas kit ensuring 400 watts lights req:(philips or german made	2 Nos		Each	
----	---	----------	--	------	--

TOTAL RS:-

Total Amount (a)

_____ % Above / Below on the Rates of CSR.

Amount to be added / deducted on basis of premium quoted Total (b)

PART"A"Schedule Item Rs. _____ Rs. (b) _____ = Rs. _____

PART"B"Non Schedule Item Rs. _____ Rs. (+) _____

Total (A)= a+b In Words & Figure _____

CONTRACTOR

EXECUTIVE ENGINEER (BUILDINGS)
DIVISION JAMSHORO

schedule B

NAME OF WORK:

**UP- GRADATION OF BHU TO THE LEVEL OF 20 BEDED RHC AT MOLE
(WARD BLOCK / INDOOR BLOCK) TALUKA THANA BULA KHAN, DISTRICT JAMSHORO**

DESCRIPTION	QUANTITY	RATE	UNIT	AMOUNT
Cement concrete plain including placing , compacting finishing and curing complete (including screening and washing of stone aggregate without shuttering (F) Ratio 1:2: 4 (S.I.NO. 5 (C) P-16)	765.60	Cft	14429.25 %Cft	110470.00
2 Supplying & fixing porcelain tile size 24" x 24" on the bed 3/4" thick mortar ratio 1:2 (R.A.A)	3002.25	Sft	466.00 PSft	1399049.00
3 Providing and laying tiles glazed 6" x 6" x 1/4" on floor or wall facing requires pattern of styles specification jointed in white cement and pigment over base of 1:2 gray cement mortar 3/4" thick including washing and filling of joints with slurry of white cement and pigment in desired shape with finishing cleaning and cost of wax polish etc complete including cutting tiles the proper profile (S.I.No.61/C-8)	2423	Sft	30509.77 %Sft	739175
4 Laying verona Marble Flooring fine dressed on the surface without winding set in lime mortar 1:2 i/c rubbing & polishing of the joint (a) 3/4" thick flooring (R.A.A)	1491.75	Sft	371.55 % Sft	554260.00
				<u>2802953.00</u>

Total Amount (a)

% Above / Below on the rate of CSR Amount to be Added / Deducted
on basis of premium quoted Total (b)

Civil Work Rs. (a) _____ **Rs. (+)** _____ **= Rs.** _____

Non- S items Rs. (a) _____ **Rs. (+)** _____ **= Rs.** _____

Grand Total _____

Total (A) = a + b in words & figure _____

Contractor

**EXECUTIVE ENGINEER (BUILDING)
DIVISION JAMSHORO**

SCHEDULE "B"**Up-Gradation to BHU to the Level of 20 Badded RHC at Mole Taluka Thana Bula Khan
(Ward Block/Indoor Block) (Electric Work)**

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
1	Wiring for light or fan point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-124 P-15)	185 NOS	1130.00 (Rs:One thousand one hundred thirty only).	Per.Point	209050
2	Providing & Fixing One Way SP 10/15 amp switch surface type.(S.NO:A-218 P-33)	185 NOS	58.00 (Rs: fifty eight only).	Per.Nos	10730
3	Wiring for Plug point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit on surface as required. (S.NO:P-125 P-15)	30 NOS	669.00 (Rs: Six hundred sixty nine only).	Per.Point	20070
4	Providing & Fixing Two Pin 5 amp Plug & Socket (S.NO:A-222 P-33)	30 NOS	80.00 (Rs: eighty only).	Per.Nos	2400
5	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.29 copper conductor in 3/4" dia PVC conduit on surface.(SNO:A-03 P-01)	250 P.MR	171.00 (Rs: One hundred Seventy one only).	Per Mtr.	42750
6	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.44 conpper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-12 P-02)	200 P.MR	341.00 (Rs: Three hundred forty one only).	Per Mtr.	68200
7	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp SP (TB-5S) on prepared board as required.(S.NO:P-203 P-31)	30 NOS	916.00 (Rs:Nine hundred sixteen only).	Per.Nos	27480
8	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp DP (TB-5S) on prepared board as required.(S.NO:P-204 P-31)	4 NOS	2456.00 (Rs:Two thousand four hundred fifty six only).	Per.Nos	9824
9	Providing & Fixing Circuit Breaker 15.20.30.40.50.60.75 & 100 Amp TP (XS - 100NS) on prepared board as required.(S.NO:P-207 P-31)	2 Nos	9261.00 (Rs:Nine thousand two hundred sixty one only).	Per No.	18522
10	Providing & Fixing Circuit Breaker 125.150.200 & 225 Amp TP (XS-225NS) on prepared board as required.(S.NO:P-208 P-31)	1 Nos	25541.00 (Rs:twenty five thousand five hundred forty one only).	Per No.	25541
11	Providing & Fixing Bakelite ceiling Rose with two terminals.(S.NO:B-228 P-33)	75 NOS	72.00 (Rs:Seventy two only).	Per No.	5400
12	Providing & Fixing Brass Pendant Lamp holder .(S.NO:B-229 P-33)	70 NOS	74.00 (Rs:Seventy two only).	Per No.	5180
13	Providing & Fixing AmpMeters Size 96/96mm Direct 15A, 30A 50A.60A,&100 A as required & as per instruction of E.I.(S.NO:A-284 P-41)	1 NOS	1054.00 (Rs:One thousand fifty four only).	Per.No.	1054

S. NO	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
14	Providing & Fixing VoltMeter Size 96/96mm 500 as required & as per instruction of E.I.(S.NO:B-285 P-41)	1 NOS	999.00 (Rs:Nine hundred ninty nine only).	Per.No.	999
15	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.36 copper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-11 P-02)	50 Per Mtr.	252.00 (Rs:two hundred fifty two only).	Per Mtr.	12600
16	Wiring for Call bell point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-128 P-15)	4 NOS	1764.00 (Rs:One thousand Seven hundred sixty four only).	Per No.	7056
17	Providing & Fixing Brass Ceiling Fan 56" (Good Quality) .(S.NO:B-235 P-34)	30 Nos	3185.00 (Rs:Three thousand one hundred eighty five only).	Per No.	95550
18	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.64 (16mm2)copper conductor in 3/4" dia PVC conduit on surface. (SNO:A-07 P-01)	70 P. Mtr.	605.00 (Rs:Six hundred five only).	Per Mtr.	42350

TOTAL RS:-

604756

SCHEDULE "B"**Up-Gradation to BHU to the Level of 20 Badded RHC at Mole Taluka Thana Bula Khan
(Ward Block/Indoor Block) (Electric Work)**

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
((PART "B"))					
1	Providing & Fixing Distribution Pannel Board of 3/4" thick sheeting double shutter to accommodate circuit breakers i/c painting with enamelled paint.	6 Sft		P.Sft	
2	P/F Surface type 3 pin 15 amper s.p surface type plug switch and shoe unit prepared on board etc complete	8 NOS		EACH	
3	Fixing A.C. ceiling fan Regulator on metal board recessed in the walls	30 Nos		EACH	
4	Providing & Fixing A.C or D.C Electric bell 200/250 Volts MM (2-3/4") gong .(Imported)	4 Nos		EACH	
5	Providing & Fixing Mild Steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C roof.	30 Nos		EACH	
6	P/F Energy Saver (18 to 24 watts) Superior Quality including Fixing on Existing holder etc complete.(Imported)	70 Nos		EACH	
7	Supply / Fixing LED Light 06 watts etc complete	15 Nos		Each	
8	P/F Fancy Capsule Light with fancy Plastic body,holder,Saver etc complete (of approved make and design).	10 Nos		EACH	
9	P/F 1-40 watts Tube Light complete with 40 watts 4-0"long rod chock starter & putty with Philips components including necessary electric connection & Fixing on wall or ceiling etc complete (Philips).	40 Nos		EACH	
10	P/Fixing Pilot Lamps	6 NOS		EACH	

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
--------	----------------	-------	------	------	--------

11	P/F.SNF (HPIT) Fixture (Philips) type complete with lamp bolts ingnitor chwok capactor further more 99% pure aluminum used for reflector & tempered glass with heat resistant gas kit ensuring 400 watts lights req:(philips or german made	2 Nos		Each	
----	---	----------	--	------	--

TOTAL RS:-	
-------------------	--

Total Amount (a)

_____ % Above / Below on the Rates of CSR.

Amount to be added / deducted on basis of premium quoted Total (b)

PART"A"Schedule Item Rs. _____ Rs. (b) _____ = Rs. _____

PART"B"Non Schedule Item Rs. _____ Rs. (+) _____

Total (A)= a+b In Words & Fiqure _____

CONTRACTOR

EXECUTIVE ENGINEER (BUILDINGS)
DIVISION JAMSHORO

SCHEDULE B

ESTIMATION

**NAME OF WORK: CONSTRUCTION OF HALL & VERANDAH @ PREMISES OF TTC COLLEGE
TALUKA KOTRI DISTRICT JAMASHORO**

DESCRIPTION	QTY		RATE	UNIT		AMOUNT
1 Excavtion in foundation of bulding, bridges and other structure including dag belling refilling around strecture with excavated earth watering and ramming. lead upto upto 5ft(b) in Ordinary or soft murum. (S.I.NO.18(b)/C-1						
	2896	x	3176.25	O%Cft	=	9198
2 Cement concrete brick or stone ballast1.5 inch to2 inch guage.(b) Ratio 1:4:8. (S.I.No.4 (b) /C-4).						
	1138	x	9416.28	%Cft	=	107157
3 Erection and removal of centering for reniforced or palin cement concrete works of partial wood (2nd Class) (B) Vertical.						
	916	x	3127.41	%Sft	=	28647
4 Cement concrete plain including placing , compacting finishing and curing complete (including screening and washing of stone aggrete without shuttering (F) Ratio 1:2: 4						
	1181	x	14429.25	%Cft	=	170409
5 Filling watering and ramming earth in floors with surplus earth from foundation lead upto one chain and lift upto 5 ft.(S.I.No.21 /C-1)						
	1931	x	1512.50	%OCFT	=	2920
6 Supplying and filling sand under floors and plugging in walls.(S.I.NO.29/C-5)						
	1712	x	1141.25	%Cft	=	19538

7 Reinforced cement concrete work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes of forms, moulds, lifting, shuttering, rendering and finishing and finishing the exposed surface (i/c screening, shingle (a) Rc work in roof slab, beams, columns, rafts, lintals and other structural members laid in situ or precast laid in position. Complete in all respects (1) Ratio 1:2:4, 90 lbs (S.I.No. 6 (a) (i) - P / 19)

1593 x 337.00 P.Cft = 536980

8 Fabrication of Miled Steel Reinforcement for Cement Concrete including cutting, bending, laying in position, making joints and fastly including cost of binding wire (also includes \ removal of rust from bars
Qty same as item no 7

100 x 5001.70 PCWT = 498111

9 Providing and laying 1:3:6 cement concrete solid block masonry wall Above 6" in thickness set in 1:6 cement sand mortar in ground floor super structure including raking out joints and curring etc complete.

704 x 14621.44 %Cft = 102960

10 Providing and fixing Galvanized iron frames/chowkats of size 7" x 2" or 4.5" x 3" for doors using 20 guage G.I sheet including welded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ration 1:6 and repairing the jams. The cost also include all carriage, tools and plants used in making and fixing (S.I.NO.29/C-17).

69 x 228.90 %P.Sft = 15794

11 Providing and fixing Galvanized iron frames/chowkats of size 7" x 2" or 4.5" x 3" for windows using 20 guage G.I sheet including welded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ration 1:6 and repairing the jams. The cost also include all carriage, tools and plants used in making and fixing (S.I.NO.28/C-17).

88 x 240.50 %PSft = 21164

12 First class deodar wood rough, joinry in doors and windows etc fixed in position including chowkats, hold fasts, hinges, iron tower bolts, chowks, cleates, handles and cords with hookd etc. Deodar panelled

or panelled and glazed or fully glazed, (b) 1.75" thick (S.I.NO.7(b)/C-10).

$$175 \quad x \quad 902.93 \quad \%P.Sft \quad = \quad 158013$$

13 Providing and fixing iron/ steel grill using solid square bars of size 1/2" x 1/2" placed at 4" center to center and frame of flat iron 3/4" x 1/4" including circle shape at 1-0 a part equivalent fitted with screws or pins including painting 3 coats with first coat of red oxide paint etc (S.I.NO.30/C-17).

$$88 \quad x \quad 231.60 \quad \%PSft \quad = \quad 20381$$

14 Pacca Brick work in foudation and plinth in cement sand mortar in 1:6
item 4(E) page 20 chapter 5

$$113 \quad x \quad 11948.36 \quad \%Cft \quad = \quad 13442$$

15 Pacca Brick work in ground floor in cement sand mortar in 1:6
item 5(E) page 21 chapter 5

$$113 \quad x \quad 12674.36 \quad \%Cft \quad = \quad 14259$$

16 Cement plaster 1:6 upto 20 height (b) 1/2" (S.I.No.13(b)/C-19)

$$4931 \quad x \quad 2206.60 \quad \%Sft \quad = \quad 108807$$

17 Cement plaster 1:4 upto 20 height (a) 3/8" thick (S.I.No.11(a)/C-9)

$$4931 \quad x \quad 2197.52 \quad \%Sft \quad = \quad 108360$$

18 Providing and laying topping cement concrete 1:2:4 including surface finishing and dividing into panels © 2" thick (S.I.No.16©/C-8

$$788 \quad x \quad 3275.50 \quad \%Sft \quad = \quad 25819$$

19 Primary Coat of Chalk Under Distemper.

$$4931 \quad x \quad 442.75 \quad \%Sft \quad = \quad 21832$$

20 Distemping C-3 Coats (S.I.No. 24© / C-9)

$$4931 \quad x \quad 1079.65 \quad \%Sft \quad = \quad 53238$$

21 Painting new surface © preparing surface and painting of doors and windows any type including edges (I and II) 3 coats (S.I.No.5© /I and II / C-11).

350.00 x 2116.41 %Sft = 7407

22 Making and fixing steel grated door frames 1/16" thick sheeting including angle frame 2 "x 2" 3/8 "x 3/4" Square bars 4" c/c with locking arrangement.

112 x 726.72 %PSft 81393

23 Preparing new surface and painting Guard bars of gates of iron bars grating railing (including standers brasses etc) and similar open work (I and II) 3 coats

224 x 1396.67 %Sft 3129

24 Fabrication of heavy steel work with angles , tees, flat iron and sheet iron for making trusses ,griders,tands etc and including cutting tanks etc including cutting, drilling riveting, handling assembling and fixing but excluding erection in postion.

26 x 4928.49 PCWT = 129373

total amount(A) = 2258330

_____ % Above / Below on the rate amount to be added /deducted on basis of premium Quoted total (B)

Civil work Rs (a)	Rs(+)	_____	=	RS	_____
Tile/ Marble Rs (b)	Rs(-)	_____	=	RS	_____
Fabrication Rs (C)	Rs(+)	_____	=	RS	_____
Non -S Items Rs (D)	Rs(-)	_____	=	RS	_____

Grand Total

Total (A)= a+b in words and figure

CONTRACTOR

EXECUTIVE ENGINEER BUILDINGS
DIVISION JAMSHORO

SCHEDULE B

ESTIMATION

NAME OF WORK: CONSTRUCTION OF HALL & VERANDAH @ PREMISES OF TTC COLLEGE
TALUKA KOTRI DISTRICT JAMASHORO
PART B

- 1 Providing & fixing squatting type white Glazed Earthenware W.C Pan
with including the cost of flushing cisteran with internal fitting and flush pipe with
bend and making requisite number of holes in walls, plinth and floor for pipe connections and
making good in cement concrete. 1:2:4 .

(B) (i) W.C of not less than 19" clear opening between
flushing rims and three gallons flushing tank with 4" dia C.I trap & C.I thumble .
item no 1 (B) (i) page 1 Chapter Sanitary fittings

1	4802.60	Each	=	4803
---	---------	------	---	------

- 2 Providing and fixing 24" x 18" lavatory basin in white glazed earthenware complete with
and including cost of W.I or C.I cantelever (6") built into walls, painted white into 2 coats after
primary coat of red lead paint, a pair of half inch dia rubber plug chrome plated
brass chain, 1-1/4 inch dia brass waist approved pattern, 1.5" inch dia malleable iron
or brass unions and making requisite number of holes
in walls, plainth and floor for pipe connection and making good in cement and concrete 1:2:4
Foreign or equivalent.

item no 10 page 3 chapter sanitary fittings

1	4928.00	Each	=	4928
---	---------	------	---	------

- 3 Add extra labour for providing and fixing earthenware pedestral white or colored glazed
Foreign or equivalent.

item no 11 page 3 chapter sanitary fittings

Nos	1	2533.47	Each	=	2533
-----	---	---------	------	---	------

- 4 Supplying and fixing in postion brass bib cocks.
item no 1 ((i) & (II)) chapter 6 page 16

(B)

1/2 inch dia brass bib cock , standard pattern

Nos	6	337.92	Each	=	2028
-----	---	--------	------	---	------

(B)

3/4 inch dia brass bib cock , standard pattern

Nos	6	348.92	Each	=	2094
-----	---	--------	------	---	------

- 5 Supplying and fixing concealed stop cock of superior quality with C.P head 1/2" dia.
item no 11 (a) chapter 6 page 18

Nos	5	478.28	Each	=	2391
-----	---	--------	------	---	------

6 Providing and fixing Handle Valves (China) .

Item no 5 (a) chapter 6 page 17

1/2 inch dia	5	200.42	Each	=	1002
3/4 inch dia	6	271.92	Each	=	1632
1 inch dia	8	365.42	Each	=	2923
TOTAL PART B					= 24333

PART C

7 Providing G.I Pipes, specials and clamps etc including fixing, cutting and fitting complete with and including cost of breaking through walls and roof, making good etc. painting 2 coats after cleaning the pipes etc with white zink paint with pigment to match the colour of the building and testing with water to pressure head of 200 ft and handling

Item no 1 page 12 chapter 4 (WATER SERVICES INTERNAL)

1/2 inch pipe	25	73.21	Each	=	1830
3/4 inch pipe	25	95.79	Each	=	2395
1 inch pipe	10	128.55	Each	=	1286
2 inch pipe	10	233.00	Each	=	2330
3 inch pipe	15	360.40	Each	=	5406
4 inch pipe	16	896.17	Each	=	14339

8 Add extra labour for concealed G.I Pipe and fitting including making recess in the wall for pipes and making good in cement concrete etc complete.

Item no 2 page 12 chapter 4 (WATER SERVICES INTERNAL)

1/2 inch pipe	25	7.82	Each	=	196
3/4 inch pipe	25	8.45	Each	=	211
1 inch pipe	10	9.96	Each	=	100

9 Providing G.I Pipes, specials and clamps etc including fixing, cutting and fitting complete with and including cost of breaking through walls and roof, making good etc. painting 2 coats after cleaning the pipes etc with white zink paint with pigment to match the colour of the building and testing with water to pressure head of 200 ft and handling

Item no 1 page 14 chapter (WATER SERVICES EXTERNAL)

1/2 inch pipe	25	64.88	Each	=	1622
3/4 inch pipe	30	86.36	Each	=	2591
1 inch pipe	3	116.20	Each	=	349
2 inch pipe	8	355.27	Each	=	2842
3 inch pipe	6	887.24	Each	=	5323
4 inch pipe	10	835.39	Each	=	8354

10 Providing RCC Pipes & collars of class C and fixing in trench including cutting & fitting and jointing with maxphalt composition and cement

1:1 including testing with water to head of 45 meter or i50 C class
 item no 37 PHSI d page 37

9 inch dia	5	194.00	PRft	970
12 inch dia	10	330.00	PRft	3300

11 Providing Laying UPVC pressure pipes of Class D (equivalent make) fixing in trench i/c cutting, fitting and jointing with Z joint with one rubber i/c testing with water to a head 122 meter or 400 ft
 item 3 (i) page 23 chapter finished item Public health

1 inch dia	7	28.00	PRft	196
1 -1/2 inch dia	6	44.00	PRft	264
2 inch dia	8	66.00	PRft	528
3 inch dia	12	137.00	PRft	1644
4 inch dia	5	226.00	PRft	1130
5 inch dia	10	336.00	PRft	3360
6 inch dia	40	486.00	PRft	19440
8 inch dia	40	742.00	PRft	29680
10 inch dia	40	1375.00	PRft	55000

TOTAL PART C 164684

total amount(A)

_____ % Above / Below on the rate amount to be added /deducted on basis of
 premium Quoted total (B)

Sanitary item _____ Rs(+) _____ = RS _____

G.I Pipe/ RCC Pipe _____ Rs(+) _____ = RS _____

Grand Total

Total (A)= b+c in words and figure

CONTRACTOR

EXECUTIVE ENGINEER BUILDINGS
 DIVISION JAMSHORO

SCHEDULE "B"

Construction of Hall & Verandah i/c Lav:Block @ Premises of T.T.C College Taluka Kotri District Jamshoro (Electric Work)

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
1	Wiring for light or fan point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-124 P-15)	30 NOS	1130.00	Per.Point	33900
2	Wiring for Plug point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit on surface as required. (S.NO:P-125 P-15)	6 NOS	669.00	Per.Point	4014
3	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.29 copper conductor in 3/4" dia PVC conduit on surface.(SNO:A-03 P-01)	190 P.MR	171.00	Per Mtr.	32490
4	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.44 copper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-12 P-02)	300 P.MR	341.00	Per Mtr.	102300
5	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp SP (TB-5S) on prepared board as required.(S.NO:P-203 P-31)	10 NOS	916.00	Per.Point	9160
6	Providing & Fixing Circuit Breaker 6.10.15.20.30.40.50 & 63 Amp DP (TB-5S) on prepared board as required.(S.NO:P-204 P-31)	2 NOS	2456.00	Per.Point	4912
7	Providing & Fixing Circuit Breaker 3.5.10.15.20.& 30 Amp TP (XS-30NS[NB]) on prepared board as required.(S.NO:P-205 P-31)	1 NOS	5301.00	Per.Point	5301
8	Providing & Fixing Bakelite ceiling Rose with two terminals.(S.NO:B-228 P-33)	15 NOS	72.00	Per.Point	1080
9	Providing & Fixing Brass Pendant Lamp holder .(S.NO:B-229 P-33)	10 NOS	74.00	Per.Point	740
10	Providing & Fixing AmpMeters Size 96/96mm Direct 15A, 30A 50A.60A,&100 A as required & as per instruction of E.I.(S.NO:A-284 P-41)	1 NOS	1054.00	Per.No.	1054
11	Providing & Fixing VoltMeter Size 96/96mm 500 as required & as per instruction of E.I.(S.NO:B-285 P-41)	1 NOS	999.00	Per.No.	999
12	Providing & Fixing Three Pin 10/15 amp Plug & Socket flush type.(S.NO:A-227 P-33)	4 Nos	162.00	Per No.	648

S.NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
13	Providing & Laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.36 copper conductor in 3/4" dia PVC conduit in the wall or column as required (SNO:B-11 P-02)	50 Per Mtr.	252.00	Per Mtr.	12600
14	Wiring for Call bell point with 3/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.NO:P-128 P-15)	1 NOS	1764.00	Per.Point	1764
15	Providing & Fixing Brass Ceiling Fan 56" (Good Quality) .(S.NO:B-235 P-34)	6 Nos	3185.00	Per No.	19110
16	Providing & Fixing One Way SP 10/15 amp switch surface type.(S.NO:A-218 P-33)	30 NOS	58.00	Per.Nos	1740

TOTAL RS:-	231812
-------------------	---------------

((PART "B"))

1	Providing & Fixing Distribution Pannel Board of 3/4" thick sheeting double shutter to accommodate circuit breakers i/c painting with enamelled paint.	2 Sft	2436.04	P.Sft	4872
2	Providing & Fixing A.C or D.C Electric bell 200/250 Volts MM (2-3/4") gong .(Imported)	1 Nos	750.00	EACH	750
3	Providing & Fixing Mild Steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C roof.	6 Nos	325.00	EACH	1950
4	P/F Energy Saver (18 to 24 watts) Superior Quality including Fixing on Existing holder etc complete.(Imported)	15 Nos	605.00	EACH	9075
5	P/F Fancy Capsule Light with fancy Plastic body,holder,Saver etc complete (of approved make and design).	10 Nos	950.00	EACH	9500
6	P/F 1-40 watts Tube Light complete with 40 watts 4-0"long rod chock starter & putty with Philips components including necessary electric connection & Fixing on wall or ceiling etc complete (Philips).	6 Nos	1450.00	EACH	8700

S. NO.	ITEMS OF WORKS	QNTY:	RATE	UNIT	AMOUNT
7	S/F Exhuast Fan 280 mm (12") sweep with butterfly shutter for exhuaast fan complete as required this rate also cutting wall or beam upto reqiured size fixing exhuaast fan with connection and finishing the hole with coment etc complete in all respects (1st: quality).	1 Nos	3150.00	EACH	3150
8	P/F.SNF (HPIT) Fixture (Philips) type complete with lamp bolts ingnitor chwok capactor further more 99% pure aluminum used for reflector & tempered glass with heat resistant gas kit ensuring 400 watts lights req:(philips or german made	2 Nos	14500.00	Each	29000

TOTAL RS:-	66997
-------------------	--------------

CONTRACTOR.

EXECUTIVE ENGINEER (BUILDINGS)
DIVISION (W&S) DEPARTMENT
DISTRICT JAMSHORO.