



# OFFICE OF THE DISTRICT MUNICIPAL CORPORATION, MALIR KARACHI.

16.DMC Malir / B.Q.Zone/E/E/

(Bin Qasim Zone)

Dated: 20/1/2017.

## TENDER NOTICE

The Tender is sealed covers are invited for the following work under SPPRA Rules-2010 from the firms having adequate experience in the relevant field. The tentative cost of work is under Rs: 1.00 Million.

S.No.	Name of Work	Amount	Earnest Money	Time Allowed	Tender Fee Non Refundable
1.	PATCH WORK OF METALLED ROAD FROM SIDEEQ-E-AKBAR MASJID TO TAXI STAND PHASE-2 UC- GULSHAN-E-HADEED	998200	20000	03 Month	1000
2.	PATCH WORK OF METALLED ROAD FROM BANK AL-HABIB TO C- ROAD PHASE-1,2 DOUBLE ROAD UC- GULSHAN-E-HADEED	998200	20000	03 Month	1000
3.	CONSTRUCTION OF METALLED ROAD FROM MEHFOOZ SHERMALL TO TCF OFFICE PHASE-2 UC -GULSHAN-E-HADEED	996800	20000	03 Month	1000
4.	CONSTRUCTION OF METALLED ROAD FROM MASHALLAH PAINT HOUSE PHASE-2 UC -GULSHAN-E-HADEED	999500	20000	03 Month	1000
5.	CONSTRUCTION OF METALLED ROAD FROM SINDH FURNITURE TO BANK ISLAMI PHASE-1 UC - GULSHAN-E-HADEED	877900	17558	03 Month	1000

Tender Processing Schedule shall be as follows:-

1-Receiving of Applications & Issuance of Tenders	27-01-2017 To 10-02-2017 (DURING OFFICE HOURS)	Executive Engineer, (B&R) Bin Qasim Zone DMC Malir, Karachi
2-Dropping of Tenders	13-02-2017 12:00 PM	In the office of the Executive Engineer, (B&R) Bin Qasim Zone, DMC Malir, Karachi
3-Opening of Tenders	13-02-2017 1:00 PM	Tender opening Committee in the office of Executive Engineer, (B&R) DMC Bin Qasim Zone, Malir, Karachi

### Terms & Conditions:

- The Tender Document will be issued to the Contractors on the submission of written request on their letterhead and on payment of non-refundable cost of tender price through pay order from any scheduled bank in favors of District Municipal Corporation, Malir Karachi as mentioned above each work.
- In case of any reason beyond our control, if the tenders are not responded on the above date, the next date of submission & opening of Tenders will be 01 - 03 -2017 at 01:00 PM and the tender documents will be available for sale from 14 - 02 -2017 To 28 - 02 2017
- In case the date of opening is declared as a public holiday by the government, the next official working day shall be deemed to the date for submission and opening of tenders of the same time as mentioned.
- Registration with income tax Department (NTN Copy) and Sindh Revenue Board.
- Documentary of work equivalent cost or above executed in last 3 years & Certificate of satisfactory completion showing date of start & completion from employer.
- List of machinery & equipment available with documentary proof of its ownership.
- 2% of specified amount against each work in shape of Pay Order/Bank draft in favor of District Municipal Corporation, Malir Karachi shall be attached with the tender documents.
- Tenders in unsealed covers / without 2% Earnest Money will not be entertained and discarded.
- The single envelop procedure adopted for tender work as per S.P.P.R.A Rules-2010.
- The total bid amount as well as the rates of items must be filled both in figure and words and incase any correction is made by the contractor himself then each correction must be initiated by the contractor otherwise the tenders are liable to be summarily rejected.
- If any fake documents are found then the tender is liable to be rejected-cancelled without any compensation but penalty as per rules.
- Tenders can be seen/download on Authority's web sites S.P.P.R.A [www.sppra.sindh.gov.pk](http://www.sppra.sindh.gov.pk).
- The procuring agency may reject all or any bid subject to the relevant provision of S.P.P.R.A Rules-2010.

EXECUTIVE ENGINEER (B&R)  
DISTRICT MUNICIPAL CORPORATION  
MALIR KARACHI

### DIRECTOR (CB) S.P.P.R.A, GOS.

With a request to upload on the website of S.P.P.R.A (Authority) A Soft copy (CD) is also enclosed.

Copy to:

- The Chairman, DMC Malir Karachi
- The Municipal Commissioner, DMC Malir Karachi.
- The Superintending Engineer, DMC Malir Karachi.
- The Accounts Officer DMC Malir Karachi.
- P.S. to Managing Director, S.P.P.R.A

EXECUTIVE ENGINEER (B&R)  
DISTRICT MUNICIPAL CORPORATION  
MALIR, KARACHI

688  
27-01-17

NAME OF WORK: - PATCH WORK OF METALLED ROAD FROM SIDEEQ-E-AKBAR MASJID  
TO TAXI STAND PHASE-2 UC- GULSHAN-E-HADEED

BILL OF QUANTITIES

(A) Description and rate of Items based on Composite Schedule of Rates.

S.NO	Quantities	Description of item to be executed at site	Rate	Unit	Amount in Rupees
1.	2.	3.	4.	5.	6.
1.	11200.0Sft	Making diagonal grooves of 1 ½" x 1 ½" at 2" ft center to center in road surface. (H.W Sch.P/14 I/7 )	Rs:146.41	%Sft	Rs:16398.00
2.	5040.0Cft	Providing and laying aggregate base course in proper grade and camber having CBR 80% as per AASHTO standard specification i/c spreading and compacting by approved mechanical means (Motor grader, Vibrator roller and smooth wheel roller etc watering to maintain the moisture content the compaction of each layer shall 100 percent to the mix dry density (Rate i/c all cost of material T&P and carriage upto(H.W.Sch.P/4 I/13 (B ).	Rs: 7606.09	% Cft	Rs:383347.00
3.	11200.0Sft	Providing 1 ½" thick (consolidated) premix carpet in proper camber and grade including supplying 10 cft: bajri, 4 cft: hill sand (of approved quality and grade) bitumen of 80-100penetration include mixing in mechanical mixer in required proportion including heating material and cleaning the road surface ( hill sand 2 cft: for mixing and 2 cft for dusting) (Rate includes all cost of material T&P and carriage upto 3 chains){H.S.I.No.21 P/8}	Rs:6165.84	%Sft	Rs:690574.00

Amount Total (a) **Rs: 10, 90,319.00**

\_\_\_\_\_%Above/Below On The Schedule Rates of CSR.

Amount to be Added/Deducted on the basis of premium quoted Total (b)

Total (A)= a + b in words &amp; Figures:

Contractor

Executive Engineer / Procuring Agency

## Summary of Bill of Quantities

Cost of Bid

Amount \_\_\_\_\_

1 (A) Cost based on composite Schedule of Rate

\_\_\_\_\_

2 (B) Cost of based on Non / Offered Schedule of Rates.

\_\_\_\_\_

TOTAL COST OF BID (C) = TOTAL (A) + Total (B)

\_\_\_\_\_

Contractor

Executive Engineer / Procuring Agency

NAME OF WORK: - PATCH WORK OF METALLED ROAD FROM BANK AL-HABIB TO C- ROAD  
PHASE-1,2 DOUBLE ROAD UC- GULSHAN-E-HADEED

BILL OF QUANTITIES

(A) Description and rate of Items based on Composite Schedule of Rates.

S.NO	Quantities	Description of item to be executed at site	Rate	Unit	Amount in Rupees
1.	2.	3.	4.	5.	6.
1.	11200.0Sft	Making diagonal grooves of 1 ½" x 1 ½" at 2" ft center to center in road surface. (H.W Sch.P/14 I/7 )	Rs:146.41	%Sft	Rs:16398.00
2.	5040.0Cft	Providing and laying aggregate base course in proper grade and camber having CBR 80% as per AASHTO standard specification i/c spreading and compacting by approved mechanical means (Motor grader, Vibrator roller and smooth wheel roller etc watering to maintain the moisture content the compaction of each layer shall 100 percent to the mix dry density (Rate i/c all cost of material T&P and carriage upto(H.W.Sch.P/4 I/13 (B ).	Rs: 7606.09	% Cft	Rs:383347.00
3.	11200.0Sft	Providing 1 ½" thick (consolidated) premix carpet in proper camber and grade including supplying 10 cft: bajri, 4 cft: hill sand (of approved quality and grade) bitumen of 80-100penetration include mixing in mechanical mixer in required proportion including heating material and cleaning the road surface ( hill sand 2 cft: for mixing and 2 cft for dusting) (Rate includes all cost of material T&P and carriage upto 3 chains)(H.S.I.No.21 P/8)	Rs:6165.84	%Sft	Rs:690574.00

Amount Total (a) **Rs: 10, 90,319.00**

\_\_\_\_\_%Above/Below On The Schedule Rates of CSR.

Amount to be Added/Deducted on the basis of premium quoted Total (b)

Total (A)= a + b in words &amp; Figures:

Contractor

Executive Engineer / Procuring Agency

## Summary of Bill of Quantities

Cost of Bid

Amount \_\_\_\_\_

1 (A) Cost based on composite Schedule of Rate

\_\_\_\_\_

2 (B) Cost of based on Non / Offered Schedule of Rates.

\_\_\_\_\_

TOTAL COST OF BID (C) = TOTAL (A) + Total (B)

\_\_\_\_\_

Contractor

Executive Engineer / Procuring Agency

NAME OF WORK: - CONSTRUCTION OF METALLED ROAD FROM MEHFOOZ SHERMAL TO TCF  
OFFICE PHASE-2 UC – GULSHAN-E-HADEED BIN QASIM ZONE

**BILL OF QUANTITIES**

(A) Description and rate of Items based on Composite Schedule of Rates.

S.NO	Quantities	Description of item to be executed at site	Rate	Unit	Amount in Rupees
1.	2.	3.	4.	5.	6.
1.	1322.0Cft	Earth work excavation of road side nalies i/c forming its banks of putting the same on embankment as directed cloud breaking dressing etc complete. (Trough work) (in ordinary Soil)	Rs:1437.00	%Oft	Rs:12807.00
2.	1322.Cft	Carriage of 100Cft / 5 Tons of all material like stone aggregate spawl coal lime -surkhi etc BG rail fastening & points & crossing Bridge Girder pipes sheets Rail M.s Bars etc or 1000 No. Tiles 12"x12" or 150 Cft of timber or 100 Mounds of fuel wood by truck or any other means owned by the contractors 3 mile lead etc...complete.	Rs.771.96	%Cft	Rs.10205.00
3.	1963.0Cft	Providing and laying aggregate base course in proper grade and camber having CBR 80% as per AASHTO standard specification i/c spreading and compacting by approved mechanical means (Motor grader, Vibrator roller and smooth wheel roller etc watering to maintain the moisture content the compaction of each layer shall 100 percent to the mix dry density ( Rate i/c all cost of material T&P and carriage up to(H.W.Sch.P/5 I/ 13(b)	Rs:7606.09	%Cft	Rs:149308.00
4.	10719.0Sft	1 ½"Thick Asphalt Concrete Wearing Course Plant Mix Laying mechanically to proper line and grade plant mixed Asphalt Concrete specified formula according to job mixed formula approved by the Engineer Incharge rolling and finishing to design Proper grade line level and comber etc (Machinery with POLs Cost ) (H.W Sch P/09 I/24(A)	Rs:7248.40	% Sft	Rs:776999.00

Amount Total (a) **Rs:9, 55,509.00**

\_\_\_\_\_%Above/Below On The Schedule Rates of CSR.

Amount to be Added/Deducted on the basis of premium quoted Total (b)

Total (A)= a + b in words &amp; Figures:

Contractor

Executive Engineer / Procuring Agency

(Cont.....Page No.02)

## Summary of Bill of Quantities

Cost of Bid

Amount \_\_\_\_\_

1 (A) Cost based on composite Schedule of Rate

\_\_\_\_\_

2 (B) Cost of based on Non / Offered Schedule of Rates.

\_\_\_\_\_

TOTAL COST OF BID (C) = TOTAL (A) + Total (B)

\_\_\_\_\_

Contractor

Executive Engineer / Procuring Agency

NAME OF WORK: - CONSTRUCTION OF METALLED ROAD FROM MASHALLAH PAINT  
HOUSE PHASE-2 UC –GULSHAN-E-HADEED

BILL OF QUANTITIES

(A) Description and rate of Items based on Composite Schedule of Rates.

S.NO	Quantities	Description of item to be executed at site	Rate	Unit	Amount in Rupees
1.	2.	3.	4.	5.	6.
1.	1322.0Cft	Earth work excavation of road side nalies i/c forming its banks of putting the same on embankment as directed cloud breaking dressing etc complete. (Trough work) (in ordinary Soil)	Rs:1437.00	%Oft	Rs:12807.00
2.	1322.Cft	Carriage of 100Cft / 5 Tons of all material like stone aggregate spawl coal lime -surkhi etc BG rail fastening & points & crossing Bridge Girder pipes sheets Rail M.s Bars etc or 1000 No. Tiles 12"x12" or 150 Cft of timber or 100 Mounds of fuel wood by truck or any other means owned by the contractors 3 mile lead etc...complete.	Rs.771.96	%Cft	Rs.10205.00
3.	2001.0Cft	Providing and laying aggregate base course in proper grade and camber having CBR 80% as per AASHTO standard specification i/c spreading and compacting by approved mechanical means (Motor grader, Vibrator roller and smooth wheel roller etc watering to maintain the moisture content the compaction of each layer shall 100 percent to the mix dry density ( Rate i/c all cost of material T&P and carriage up to(H.W.Sch.P/5 I/ 13(b)	Rs:7606.09	%Cft	Rs:152198.00



4.		<u>1 ½" Thick Asphalt Concrete Wearing Course Plant Mix</u> Laying mechanically to proper line and grade plant mixed Asphalt Concrete specified formula according to job mixed formula approved by the Engineer Incharge rolling and finishing to design Proper grade line level and comber etc (Machinery with POLs Cost ) (H.W Sch P/09 I/24(A)			
	10719.0Sft		Rs:7248.40	% Sft	Rs:776999.00

Amount Total (a) **Rs: 9, 58,399.00**

\_\_\_\_\_ %Above/Below On The Schedule Rates of CSR.

Amount to be Added/Deducted on the basis of premium quoted Total (b)

Total (A)= a + b in words & Figures:

Contractor

Executive Engineer / Procuring Agency

## Summary of Bill of Quantities

Cost of Bid

Amount \_\_\_\_\_

1 (A) Cost based on composite Schedule of Rate

\_\_\_\_\_

2 (B) Cost of based on Non / Offered Schedule of Rates.

\_\_\_\_\_

TOTAL COST OF BID (C) = TOTAL (A) + Total (B)

\_\_\_\_\_

Contractor

Executive Engineer / Procuring Agency

NAME OF WORK:- CONSTRUCTION OF METALLED ROAD FROM SINDH FURNITURE TO BANK  
ISLAMI PHASE-1 UC – GULSHAN-E-HADEED

BILL OF QUANTITIES

(A) Description and rate of Items based on Composite Schedule of Rates.

S.NO	Quantities	Description of item to be executed at site	Rate	Unit	Amount in Rupees
1.	2.	3.	4.	5.	6.
1.	2708.0Cft	Earth work excavation of road side nalies i/c forming its banks of putting the same on embankment as directed cloud breaking dressing etc complete. (Trough work) (in ordinary Soil)	Rs:1437.00	%Oft	Rs:38900.00
2.	2707.Cft	Carriage of 100Cft / 5 Tons of all material like stone aggregate spawl coal lime -surkhi etc BG rail fastening & points & crossing Bridge Girder pipes sheets Rail M.s Bars etc or 1000 No. Tiles 12"x12" or 150 Cft of timber or 100 Mounds of fuel wood by truck or any other means owned by the contractors 3 mile lead etc...complete.	Rs.771.96	%Cft	Rs.20897.00
3.	1803.0Cft	Providing and laying aggregate base course in proper grade and camber having CBR 80% as per AASHTO standard specification i/c spreading and compacting by approved mechanical means (Motor grader, Vibrator roller and smooth wheel roller etc watering to maintain the moisture content the compaction of each layer shall 100 percent to the mix dry density ( Rate i/c all cost of material T&P and carriage up to(H.W.Sch.P/5 I/ 13(b)	Rs:7606.09	%Cft	Rs:137138.00

4.		<u>1 ½" Thick Asphalt Concrete Wearing Course Plant Mix</u> Laying mechanically to proper line and grade plant mixed Asphalt Concrete specified formula according to job mixed formula according to job mixed formula approved by the Engineer Incharge rolling and finishing to design Proper grade line level and comber etc (Machinery with POLs Cost ) (H.W Sch P/09 I/24(A)			
	8937.05ft		Rs:7248.40	% Sft	Rs:647825.00

Amount Total (a) **Rs:8, 44,760.00**

\_\_\_\_\_ %Above/Below On The Schedule Rates of CSR.

Amount to be Added/Deducted on the basis of premium quoted Total (b)

Total (A)= a + b in words & Figures:

Contractor

Executive Engineer / Procuring Agency

## Summary of Bill of Quantities

Cost of Bid		Amount_____
1	(A) Cost based on composite Schedule of Rate	_____
2	(B) Cost of based on Non / Offered Schedule of Rates.	_____
TOTAL COST OF BID (C) = TOTAL (A) + Total (B)		_____

Contractor

Executive Engineer / Procuring Agency