

Schedule B

**Name of Scheme:- Rehabilitation of Various Primary School (Rural Areas) @ GBPS
Manahyoon Taluka Sehwan Distirct Jamshoro (Ext Dev)**

(A) Description and Rate of Item based on composite Schedule Rate.

Item No.	Quantity	Description of Item	Rate	Unit	Amount
1	505.00	Excavation in foundation of building, bridges and other structure including dagbelling dressing, refilling around structure with excavated earth, watering and ramming. Lead upto 5 ft (b) In ordinary soil. (S.I.No. 18(b)/C-1)	3176.25	%oCft	1604
2	717.00	Cement concrete brick or stone ballast 1." to 2" gauge 1:5:10.	8694.95	%Cft	62343
3	914.00	Pacca brick work in foundation and plinth in cement sand mortar 1:6	11948.36	%Cft	109208
4	73.00	R.C.C work including all labour and material except the cost of steel reinforcement and i/c cutting beding which will be paid s separately. R.C.C work in roof slab, beams, columns, rafts,precast Ratio 1:2:4	337.00	P.Cft	24601
5	3.250	Fabrication of miled steel reinforcement for cutting, bending and binding which will joint and fasteing wire removal of removal of rust from bars.	5001.70	P.Cwt	16256
6	14450.00	Filling watering and remainng earth under floor with new earth (Excavated from out side) lead upto one chain and lift upto 5 ft	3630.00	%0Cft	52454
7	1001.00	Cement Plaster 1/2" thick ration 1:6 (S.No.13 b/P.51)	2206.60	%Sft	22088
8	1001.00	Cement Plaster 3/8" thick ration 1:4 (S.No.11 a/P.51)	2197.52	%Sft	21997
9	48.00	Making & Fixing grated door with 1/16" thick sheeting i/c angle iron frame 2"x2" 3/8" square bars 4" center to center with locking arrangement.	726.72	P.Sft	34883
10		Providing and laying topping cement concret (1:2:4) i/c surface finishing and dividing into panels (d) (S.No.16 d/P.41)			
A	714.00	2" Thick	3275.50	%Sft	23387
B	842.00	3" Thick	4411.82	%Sft	37148
11	105.00	P/L Coloured cement tiles (Pattern 8"x8"x3/4") of approved shade and pattern laid flat in 1:2 grey cement mortar over a bed of 3/4" thick grey cement mortar 1;2	10964.99	%Sft	11513
12	32.00	Providing and laying Hala or pattern tiles glazed 6"x6"x1/2" on floor or wall facing in required pattern of Stile specification jointed in white cement and pigment over a base of 1:2 gray cement mortar 3/4" thick including washing and filling of joints with slurry of white cement and pigment in desired shape with finishing, cleaning and cost of waxpolish etc. S.No. 61/P47)	34520.31	%Sft	11046
13	64.00	Supplying and Fixing calligraphic (6x6)x1/4" size in required color and design of tile specification base of 1:2 grey cement mortor 3/4" above and i/c washing and filling of joints with solem white cement and pigment desired shape with finishing cleaning adn cost of wax polish etc complete	222.00	P.No	14208

Item No.	Quantity	Description of Item	Rate	Unit	Amount
14	96.00	Preparing New surface and painting guard bars gates of iron bars i/c standards braces etc and similar open work	1270.83	%Sft	1220

Total 443956

NSI 14208

N.S.I 429748

_____ % Above / Below on the Rates of CSR.

Amount to be added / deducted on basis of premium quoted Total (b)

Total a+b Rs. (a) _____ **Rs. (b)** _____ = Rs. _____

Febrication (a) _____ | _____ % _____ **Rs** _____ **Total Amount Rs** _____

Marble / Tile (a) _____ | _____ % _____ **Rs** _____ **Total Amount Rs** _____

Total (A)= a+b In Words & Figure _____

CONTRACTOR

**EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
JAMSHORO**