

M & R to External, Miscellenous, Internal Works at GOR-I (Kerb Stone, Pavers and Other Civil Works)

SCHEDULE - B

S.No	Description	Unit	Quantity	Rate	Amount
<u>SCHEDULE ITEM</u>					
1	Cement Plaster 1:4 upto 12' height. (d) 3/4" thick (only for block masonry). (S.I-11(d)/52)	%Sft	150.00	3191.76	4787.64
CHECKED TOTAL					4787.64
<u>NON-SCHEDULE ITEM</u>					
1	P/F cement paving block flooring having size of 60mm of city quddra cobble shape with natural colour having strength b/w 5000 psi to 8500 psi i/c. filling the joints with hill sand and laying over khakha & compacting with electric compactor as directed by the Engineer Incharge etc. complete.	Sft	19180.00		
2	Providing and kerb stone 12" x 6" x 18" including cutting required earth over a bed of curing and finishing etc. complete	Each	150.00		
3	Disposal of Debries concrete from site of work to out side city limits through mechanical means i/c. tractor trolley / trucks etc. complete.	Each	6.00		
4	P/F RCC manhole cover of 3' thickness embedded with angle iron frame 1-1/2" x 1-1/2" x 1-1/4" and bars of 3/8" dia mild steel placed at 6' i/c. both way i/c. handle in centre for lifting poured with C.C. 1:2:4 etc. complete.	Sft	35.00		
5	Providing and fixing PVC Pipe 2" dia including cutting making and jointing with switch pest with special approved quality including all cost of labour as directed by the Engineer Incharge etc. complete.	Rft	23.00		
6	Providing and fixing uPVC pipe 3" dia including cutting making and jointing with switch pest with special approved quality including all cost of labour as directed by the Engineer Incharge etc. complete.	Rft	60.00		
7	Providing and fixing uPVC Fitting 3" dia				
	a) Plug Tee	Each	3.00		
	b) Plain Bend	Each	5.00		
	c) Y-Tee	Each	4.00		
	d) Plug Bend	Each	6.00		

M & R to External, Miscellaneous, Internal Works at GOR-I (Kerb Stone, Pavers and Other Civil Works)

SCHEDULE - B

S.No	Description	Unit	Quantity	Rate	Amount
8	Providing and fixing uPVC pipe 4" dia including cutting making and jointing with switch pest with special approved quality including all cost of labour as directed by the Engineer Incharge etc. complete.	Rft	50.00		
9	Providing and fixing uPVC Fitting 4" dia				
	a) Plug Tee	Each	2.00		
	b) Plain Bend	Each	4.00		
	c) Y-Tee	Each	2.00		
	d) Plug Bend	Each	6.00		
TOTAL NON-SCH. ITEM					
GRAND TOTAL					

TERMS AND CONDITION

- Any typographical errors in the schedule B are subject to the correction with reference to the Schedule of rate General 2012 enforced from 12-07-2012 as approved by the SRC, Sindh Karachi.
- No. premium shall be paid on a Non Schedule Items.
- 100% well Graded crushed Bajri shall be used in items of work without any extra payment.
- No any items of excavated then the Quality Provided in the Schedule B without Prior of the Executive Engineer.
- All sample of items should be got approved by the Executive Engineer.

(CONTRACTOR)


(ASSISTANT ENGINEER)
 Provincial Buildings Sub-Division-I
 Karachi

(EXECUTIVE ENGINEER)
 Provincial Buildings Division-I
 Karachi