

BILL OF QUANTITIES

Discription and Rate of Items based on Composite Schedule of Rates

NAME OF WORK :- CONSTRUCTION OF MASJID OF BOARD OF INTERMEDIATE & SECONDARY EDUCATION SUKKUR.

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
PART "A" SCHEDULE ITEMS					
1	674	Excavation in foundation of building bridges and other structure including dressing refeling around structure with excavated earth watering and ramming lead upto one chain and lift upto 5ft (b) in ordinary soil.(C.S.I No:18 (b)P.5.	3176.25	%0Cft	2141
2	248	Cement concrete brick or stone ballast 11/2" to 2" guage ratio 1:4:8 (C.S.I No: 4 (b) Page No:15)	9416.28	%Cft	23343
3	435	Rein forced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid sepreately this rate also includes all kinds of forms moulds:lifting shuttering curing rending and finishing the exposed surface (including screening and washing of shingle) (a) RC work in slabe bams columns rafts lintels and other structural members laid in situ or pre cost laid in position complete in all respects. (I)Ratio (1:2:4) 90 Lbs cement 2 Cft. sand 4 Cft . shingle 1/8" to 1/4" guage.(C.S.I No:6 A (1) P.19).	337.00	P.Cft	146730
4	27.21	Fabrication of Tor steel reinforcement for cement concrete including cutting bending and laying in position making joints and fastings including cost of binding wire also includes removal of rust from bars (C.S.I No:7 B P.20).	5001.70	P.Cwt	136111
B	1.94	Fabrication of Mild steel reinforcement for cement concrete including cutting bending and laying in position making joints and fastings including cost of binding wire also includes removal of rust from bars (C.S.I No:8 A P.17).	4820.20	P.Cwt	9370
5	46	Pacca brick work in foundation and plinth in cement sand mortor ratio 1:6(C.S.I No:4 (e) P.21).	11948.36	%Cft	5484
6	568	Filling watering and raming earth in floor with surplus from foundation lead upto one chain and lift upto 5ft. (C.S.I No: 21 P.4).	1512.50	%0Cft	859
7	625	Filling watering and raming earth under floor with new earth excavated from outside lead upto on chain and lift upto 5ft. (C.S.I No: 22 P.4).	3630.00	%0Cft	2269
8	63	Supplying and filling sand under floor and plugging in walls .(C.S.I No:29 P.26).	1141.25	%Cft	713
9	625	Extra Lead three miles	579.41	%Cft	3621
10	160	Pacca brick work in ground floor in cement sand mortor ratio: (C.S.I No: 5 (e) Page No: 25)	12674.36	%Cft	20330
11	1361	Cement plaster upto 20' height 1/2" thick rario 1:6 (C.S.I No: 13 (b)Page No: 52).	2206.60	%Sft	30038
12	1361	Cement plaster upto 20' height 3/8" thick rario 1:4 (C.S.I No: 11 (a) Page No: 52).	2197.52	%Sft	29915
13	485	P/F clolour create to wall surface to provide durable crust and aestheics having thickness upto 3/4" with specified colour having water, fire and temite resistance (upto 2' -0 height). (C.S.I No. 44 P-56).	6319.50	%Sft	30637
14	16	Supplying & fixing in position aluminuim channels framing for hanged doors or alcop made with 5 mm thick tinted glass glazing (Belguim) and alpha Japan locks i/c handels stoppers etc deluxe model (Bronze) (C.S.I No. 83 (b) P-108).	1507.66	P.Sft	24424
15	21	Supplying and fixing in position Aluminium channels framing for sliding windows and ventilators of alco made with 5 mm thick tinted glass glazing (Belgium) & Aluminium glass Glazing (Blgium) & Aluminium fly screen i/c handles stoppers locking arrangement etc complete Deluxe model (Blonze) (C.S.I No:84 (b) P-108).	1647.69	P.Sft	34272
16	27	Suppling and fixing in position iron steel grill of 3/4"x 1/4" size flate iron of approved design i/c painting three coats etcomplete weightg not less than 3.7 lbs of finished grill (C.S.I No:26 P.93).	180.50	P.Sft	4910