

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
17	22	Providing and fixing iron collapsible gate with channel framing of section 3/4" x 5/16" at 4" l/c revitted with 3/4" x 1/8" flat iron patti placed diagonally and provided with top & bottom T- section 1" x 1" 1/8" along with rollers also l/c locking arrangement and fixing in floor/ceiling or wall etc. completed. (C.S.I No:32 P-94).	387.04	P.Sft	8360
18	83	Cement Concrete plain including placing compacting finishing and curing complete including screening complete and washing of stone aggregate without shuttering Ratio: 1:2:4. (C.S.I No. 5 (f) Page No:16)	14429.25	%Cft	11919
19	415	Providing and laying tiles glazed 6" x 6" x 1/4" on floor or wall facing in required colour and pattern of STILE specification jointed in white cement and pigment over a base of 1:2 grey cement mortar 3/4" thick including washing and filling of joints with slurry of white cement and pigment in desired shape with finishing, clearing and cost of wax polish etc. complete including cutting tiles to proper profile. (C.S.I No:60 P-47) .	30509.77	%Sft	126555
20	140	Laying white marble flooring fine dressed in the surface without winging sate in lie mortar 1:2 including rubbing and polishing of the joints(C.S.I No:28 (a) P-43) .	567.48	P.Sft	79447
21	16	Providing and fixing 3/8" thick marble tiles of approved quality and colour shade size 8" x 4/6" x 4" in dado skirting and facing removal / tucking of exiting plaster surface etc over 1/2" thick base of cement mortar 1:3 setting mortar base including filling the joints and washing of tiles with white cement slurry current finishing cleaning and polishing etc complete (for new work) (C.S.I No: 68 (i) P-49).	186.04	P.Sft	2902
22	265	Providing and laying single per layer of polithin 0.13mm thick for water proofing per specification and instructions of engineer incharge(C.S.I No:38 P.38).	10.70	P.Sft	2838
24	265	Single Layer Tiles 9" x 4 1/12" x 2" laid over 4" earth 1" mud plaster without bhoosa grouted with cement sand 1:3 on top of RCC Slab provided with 34 lbs bitumen coating sand blinded (C.S.I No: 5 P-34).	5310.35	%Sft	14083
25	265	Two coats of bitumen laid hot using 34"Lbs for 100sft over roof and blinded with sand at 1Sft per 100sft (C.S.I No:13 P.35).	1887.40	%Sft	5005
26	250	Supplying & Fixing false ceiling of plaster paris, in panels including making frame work of deodar wood including painting with soligia paint (C.S.I No: 52 P-64).	25293.42	%Sft	63234
27	6	First class deodar wood wrought joinery in doors and windows etc fixed insition i/c in chwoakts holds fasts hinges iron tower bolts chowkats cleats handles and cards with hooks etc deodar paneled or paned are fully glazed 1:3:4 (C.S.I No: 7 (b)Page No: 58).	1273.76	P.Sft	8152
28	15	P/L Halla pattern tiles glazed 6" x 6" x 1/4" of floor of walls facing required pattern stile specification jointed in white cement and pigment over a bases 1:2 gray cement mortar 3/4" thick l/c washing & filling of joints with slurry of white cement & pigment in desire shape with finishing cleaning and cost of wax polish etc complete i/c cutting tiles to proper profile. (C.S.I No: 61 P-48)	47651.56	%Sft	7148
29	7	Khapriel of cement concrete 12" x 8" x1"of approved designed / shape land flat in 1:2 gray cement mortar over a bed of 3/4" thick gray cement mortar 1:2 (C.S.I No:39 P-38).	8977.90	%Sft	646
30	13	Providing & fixing deodar almirah 9" - 12" depth including boxing with back shelves shutters brass fitting complete (CSI No.23 P-61)	1778.50	P.Sft	22409
31	56	Providing and lying 3" thick topping cement concrete 1:2:4. Including surface finishing dividing into panels (C.S.I No:16 (d) P-42) .	4411.82	%Sft	2462
32	19	Galvanized wire guaze fixed to chowkats with 3/4" deodar stips and screws. (C.S.I No. 14 (d) P-60).	190.72	P.Sft	3662
33	10	Providing and laying cement ornamental cement jalli 2" thick 1:2:4 without steel (C.S.I No:11 P.18).	226.02	P.Sft	2170
34	319	Preparing the surface and painting with matt finish i/c rubbing the surface with bathy (silicon carbide rubbing brick) filling the voids with zink/ chalj/ plaster of paris mixture , applying first coat premix making the surface smooth and then painting 3 coat with matt finish of aproved make etc complet (New Surface) Three Coat. (CSI No. 36 (C) Page No. 55).	3444.38	%Sft	10994