

BILL OF QUANTITIES

Discription and Rate of Items based on Composite Schedule of Rates

NAME OF WORK :- CONSTRUCTION OF BOUNDARY WALL OF BOARD OF INTERMEDIATE & SECONDARY EDUCATION SUKKUR.

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
PART "A" SCHEDULE ITEMS					
1	6660	Dismantling brick work in lime or cement plaster (C.S.I No:13 P-10).	1285.63	%Cft	85623
2	24000	Excavation in foundation of building bridges and other structure including dressing refeling around structure with excavated earth watering and ramming lead upto one chain and lift upto 5ft (b) in ordinary soil(C.S.I No:18 (b)P.5.	3176.25	%0Cft	76230
3	6000	Cement concrete brick or stone ballast 11/2" to 2" guage ratio 1:4:8 (C.S.I No: 4 (b) Page No:15)	9416.28	%Cft	564977
4	2800	Pacca brick work in foundation and plinth in cement sand mortor ratio 1:6(C.S.I No:4 (e) P.21).	11948.36	%Cft	334554
5	12750	Rein forced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid sepretely this rate also includes all kinds of forms moulds:lifting shuttering curing rending and finishing the exposed surface (including screening and washing of shingle) (a) RC work in slabe bams columns rafts lintels and other structural members laid in situ or pre cost laid in position complete in all respects. (I)Ratio (1:2:4) 90 Lbs cement 2 Cft. sand 4 Cft . shingle 1/8" to 1/4" guage.(C.S.I No:6 A (1) P.19).	337.00	P.Cft	4296750
6	683.036	Fabrication of Tor steel reinforcecment for cement concrete including cutting bending and laying in position making joints and fastings including cost of binding wire also includes removal of rust from bars (C.S.I No:7 B P.20).	5001.70	P.Cwt	3416341
7	17500	Cement Concrete plain including placing compacting finishing and curing complete including screening complete and washing of stone agreegate without shuttring Ratio: 1:2:4. (C.S.I No. 5 (a) Page No:18)	14429.25	%Cft	2525119
8	35000	Errection and removal of cuttering for R.C.C or plain Cemnet concrete work for partial wood vertical (C.S.I No. 18 (b) Page No:21)	3127.41	%Cft	1094594
9	22500	Pacca brick work other then building including stricking of joints up to feet height (C.S.I No: 7 (e) Page No: 26)	12346.65	%Cft	2777996
10	35000	Cement plaster upto 20' height 1/2" thick rario 1:6 (C.S.I No: 13 (b)Page No: 58).	2206.60	%Sft	772310
11	35000	Cement plaster upto 20' height 3/8" thick rario 1:4 (C.S.I No: 11 (b)Page No: 58).	2197.52	%Sft	769132
12	30000	Cement pointing stricking of joints of walls ratio 1:2 (C.S.I No: 19 (a) Page. 59)	1287.44	%Sft	386232
13	140	Preparing the surface and painting with weather coat l/c rubbing the surface with rubbing brick / sand Paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make. Three coats (CSI No. 38 (c) P. No. 56)	726.72	P.Sft	101741
14	70000	Destember three coats (C.S.I No:24 (c) P-54).	1079.65	%Sft	755755
			TOTAL :-		17957353

Amount Total (CSR)

Part "A"

% Above / Below _____

Total Amount _____

Total "A" _____