

Schedule B (Civil)

Name Of Work Repair & restoration of angular plateform (4 Nos) near RD 5, RD 9, RD 16 & in between RD 19 & 20 @ Haleii Lake District Thatta						
Description	Quantity	Rate	Unit	Amount		
01. Excavation in foundation of building, bridges and other structure including dagbelling dressing, refilling around structure with excavated earth, watering and ramming. Lead upto 5 ft (b) In ordinary soil. (S.I.No. 18(b)/P-4)	388.00	Cft	Rs. 3176.25	%oCft	Rs.	1232.00
02. Cement concrete brick or stone ballast 1.5" to 2" gauge (b) Ratio 1:4:8. (S.I.No. 4(b)/P-15)	330.00	Cft	Rs. 9416.28	%Cft	Rs.	31074.00
03. Erection and removal of centering for Reinforced or Plain cement concrete works of partial wood (2nd class). (b) Vertical. (S.I.No. 19(b)/ii/P-18)	1398.00	Sft	Rs. 3127.41	%Sft	Rs.	43721.00
04. Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate without shuttering) (f) Ratio 1:2:4 (S.I.No. 5(f)/P-16)	517.00	Cft	Rs. 14429.25	%Cft	Rs.	74599.00
05. Filling, watering and ramming earth in floors with surplus earth from foundation. Lead upto one chain and lift upto 5 ft. (S.I.No. 21/P-4)	259.00	Cft	Rs. 1512.50	%oCft	Rs.	392.00
06. Supplying and filling sand under floors and plugging in wells. (S.I.No. 29/P-26)	400.00	Cft	Rs. 1141.25	%Cft	Rs.	4565.00
07. Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13(b)/P-52)	624.00	Sft	Rs. 2206.60	%Sft	Rs.	13769.00
08. Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11(a)/P-52)	624.00	Sft	Rs. 2197.52	%Sft	Rs.	13713.00
09. Providing and laying tiles glazed 6"x6"x1/4" on floor or wall facing in required colour & pattern of Stile specification jointed in white cement and pigment over a base of 1:2 gray cement mortar 3/4" thick including washing and filling of joints with slurry of white cement and pigment in desired shape with finishing, cleaning and cost of wax polish etc complete including cutting tiles to proper profile. (S.I.No. 60/P-47)	1054.00	Sft	Rs. 30509.77	%Sft	Rs.	321573.00
10. Supplying and Fixing / Erecting G.I Pipe of 3.0" dia (ILL M Karachi) including cutting, welding, carriage etc complete including painting 3 coats with 1st coat of red oxide paint as per directions of Engineer Incharge (M.R)	488.00	Rft	Rs. 390.00	P.Rft	Rs.	190320.00
11. Asbestos cement corrugated sheet roofing including necessary over laps and G.I hooks, bolts, nuts screws, washers and bitumen washers etc (excluding valleys & ridges etc) (S.I.No. 28/P-37)	576.00	Sft	Rs. 12141.25	%Sft	Rs.	69934.00
12. Supplying & fixing Mosaic bench complete with polishing etc including fixing on floor etc complete (M.R)	4.00	No	Rs. 15000.00	P.No.	Rs.	60000.00

Total S.I except Steel Work, Marble, G.Tiles, Alcop D&W, F.Door, W.Guaze & P.Block

Total Steel Work

Total Marble, G.Tiles, Alcop D&W, F.Door, W.Guaze & P.Block

Total N.S.I

G.Total

_____ % Above / Below on the Rates of CSR

Amount to be added / deducted on basis of premium quoted Total (b)

Total a + b Rs. (a) _____ Rs. (b) _____ = Rs. _____

Fabrication _____ % Above Rs _____ Total Amount Rs _____

Marble / Tile _____ % Below Rs _____ Total Amount Rs _____

Total Rs. _____

Total (A) = a+b In words & figure _____

CONTRACTOR

DEPUTY CONSERVATOR WILDLIFE
HYDERABAD DIVISION