

## Schedule B (Civil)

**Name Of Work**      **Development of floating mound (16 Nos) infront of information centre @**

**Haleji Lake District Thatta**

Description	Quantity	Rate	Unit	Amount
01. Providing floating mound of size 15' x 15', having lower frame made out of pan wood strips 3"x9" @ 4' c/c and top made of deodar wood strips 12"x1", fixed on 6 PVC barrels of required size with stainless steel nut bolts etc complete as per drawing & directions of Engineer Incharge. The rate include all type of material, labour & carriage to site of work. (M.R)	16.0	No.	Rs.	60000.00
			Each	Rs. <b>960000.00</b>

**Total S.I**      **Rs.      0.00**

**Total N.S.I**      **Rs.      960000.00**

**G.Total**      **Rs.      960000.00**

\_\_\_\_\_ % Above / Below on the Rates of CSR      Amount to be added / deducted on

basis of premium quoted Total (b)

Total a + b Rs. (a) \_\_\_\_\_ Rs. (b) \_\_\_\_\_ = Rs. \_\_\_\_\_

Fabrication \_\_\_\_\_ % Above Rs \_\_\_\_\_ Total Amount Rs \_\_\_\_\_

Marble / Tile \_\_\_\_\_ % Below Rs \_\_\_\_\_ Total Amount Rs \_\_\_\_\_

**Total Rs. \_\_\_\_\_**

Total (A) = a+b In words & figure \_\_\_\_\_

**CONTRACTOR**

**DEPUTY CONSERVATOR WILDLIFE  
HYDERABAD DIVISION**