

Schedule B (Civil)

Name Of Work **Repair & restoration of fire places (04 Nos) @ Haleji Lake District Thatta**

Description	Quantity	Rate	Unit	Amount
01. Excavation in foundation of building, bridges and other structure including dagbelling dressing, refilling around structure with excavated earth, watering and ramming. Lead upto 5 ft (b) In ordinary soil. (S.I.No. 18(b)/P-4)	316.00 Cft	Rs. 3176.25	%oCft	Rs. 1004.00
02. Cement concrete brick or stone ballast 1.5" to 2" gauge (b) Ratio 1:4:8. (S.I.No. 4(b)/P-15)	214.00 Cft	Rs. 9416.28	%Cft	Rs. 20151.00
03. Erection and removal of centering for Reinforced or Plain cement concrete works of partial wood (2nd class). (b) Vertical. (S.I.No. 19(b)/ii/P-18)	560.00 Sft	Rs. 3127.41	%Sft	Rs. 17513.00
04. Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate without shuttering) (f) Ratio 1:2:4 (S.I.No. 5(f)/P-16)	210.00 Cft	Rs. 14429.25	%Cft	Rs. 30301.00
05. Filling, watering and ramming earth in floors with surplus earth from foundation. Lead upto one chain and lift upto 5 ft. (S.I.No. 21/P-4)	211.00 Cft	Rs. 1512.50	%oCft	Rs. 319.00
06. Supplying and filling sand under floors and plugging in wells. (S.I.No. 29/P-26)	148.00 Cft	Rs. 1141.25	%Cft	Rs. 1689.00
07. Providing and lying 1:3:6 cement concrete solid block masonry wall 6" and below in thickness set in 1:6 cement sand mortar in ground floor super structure including raking out joints and curing etc complete. (S.I.No. 24/P-19)	129.00 Cft	Rs. 15771.01	%Cft	Rs. 20345.00
08. Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13(b)/P-52)	716.00 Sft	Rs. 2206.60	%Sft	Rs. 15799.00
09. Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11(a)/P-52)	716.00 Sft	Rs. 2197.52	%Sft	Rs. 15734.00
10. Providing and laying topping cement concrete 1:2:4 including surface finishing and dividing into panels (d) 3" thick. (S.I.No. 16(d)/P-42)	324.00 Sft	Rs. 4411.82	%Sft	Rs. 14294.00
11. Making and fixing grating in opening including fixing at site with flat iron 2"x3/8"and 3/4" square bars 4" c/c . (S.I.No. 25/P-92)	18.00 Sft	Rs. 293.15	P.Sft	Rs. 5277.00

Total S.I except Steel Work, Marble, G.Tiles, Alcop D&W, F.Door, W.Guaze & P.Block

Total Steel Work

Total Marble, G.Tiles, Alcop D&W, F.Door, W.Guaze & P.Block

Total N.S.I

G.Total

_____ % Above / Below on the Rates of CSR Amount to be added / deducted on basis of premium quoted Total (b)

Total a + b Rs. (a) _____ Rs. (b) _____ = Rs. _____

Fabrication _____ % Above Rs _____ Total Amount Rs _____

Marble / Tile _____ % Below Rs _____ Total Amount Rs _____

Total Rs. _____

Total (A) = a+b In words & figure _____

CONTRACTOR

DEPUTY CONSERVATOR WILDLIFE
HYDERABAD DIVISION