

Schedule B (Civil)

Name Of Work **Development of floating mound (12 Nos) in surrounding area of pelican island**

@ Haleji Lake District Thatta

Description	Quantity	Rate	Unit	Amount
01. Providing floating mound of size 15' x 15', having lower frame made out of pan wood strips 3"x9" @ 4' c/c and top made of deodar wood strips 12"x1", fixed on 6 PVC barrels of required size with stainless steel nut bolts etc complete as per drawing & directions of Engineer Incharge. The rate include all type of material, labour & carriage to site of work. (M.R)	12.0	No.	Rs.	60000.00
			Each	Rs. 720000.00

Total S.I **Rs. 0.00**

Total N.S.I **Rs. 720000.00**

G.Total **Rs. 720000.00**

_____ % Above / Below on the Rates of CSR Amount to be added / deducted on
basis of premium quoted Total (b)

Total a + b Rs. (a) _____ Rs. (b) _____ = Rs. _____

Fabrication _____ % Above Rs _____ Total Amount Rs _____

Marble / Tile _____ % Below Rs _____ Total Amount Rs _____

Total Rs. _____

Total (A) = a+b In words & figure _____

CONTRACTOR

**DEPUTY CONSERVATOR WILDLIFE
HYDERABAD DIVISION**