

## Schedule B (Civil)

### Name Of Work      Repair & restoration of lavatories (02 Seated) @ Haleji Lake District Thatta

Description	Quantity	Rate	Unit	Amount
01. Excavation in foundation of building, bridges and other structure including dagbelling dressing, refilling around structure with excavated earth, watering and ramming. Lead upto 5 ft (b) In ordinary soil. (S.I.No. 18(b)/P-4)	153.00    Cft	Rs.    3176.25	%oCft	Rs.    486.00
02. Cement concrete brick or stone ballast 1.5" to 2" gauge (b) Ratio 1:4:8. (S.I.No. 4(b)/P-15)	67.00    Cft	Rs.    9416.28	%Cft	Rs.    6309.00
03. Providing and lying 1:3:6 cement concrete solid block masonry set in 1:6 cement sand mortar in plinth & foundation including raking out joints and curing etc complete. (S.I.No. 23/P-19)	61.00    Cft	Rs.    14268.53	%Cft	Rs.    8704.00
04. Erection and removal of centering for Reinforced or Plain cement concrete works of partial wood (2nd class). (b) Vertical. (S.I.No. 19(b)/ii/P-18)	230.00    Sft	Rs.    3127.41	%Sft	Rs.    7193.00
05. Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate without shuttering) (f) Ratio 1:2:4 (S.I.No. 5(f)/P-16)	131.00    Cft	Rs.    14429.25	%Cft	Rs.    18902.00
06. R.C.C work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms, moulds, lifting, shuttering, curing, rendering and finishing the exposed surface (including screening and washing of shingle (a) R.C.C work in roof slab, beams, columns, rafts, lintels and other structural members laid in situ or precast laid in position. Complete in all respects (i) Ratio 1:2:4 90 lbs. (S.I.No. 6(a)/i/P-17)	72.00    Cft	Rs.    337.00	P.Cft	Rs.    24264.00
07. Fabrication of Tor steel reinforcement for cement concrete including cutting, bending, laying in position, making joints and fastening including cost of binding wire (also includes removal of rust from bars. (S.I.No. 8(b)/P-17)	3.00    Cwt	Rs.    5001.70	P.Cwt	Rs.    15005.00
08. Filling, watering and ramming earth in floors with surplus earth from foundation. Lead upto one chain and lift upto 5 ft. (S.I.No. 21/P-4)	102.00    Cft	Rs.    1512.50	%oCft	Rs.    154.00
09. Supplying and filling sand under floors and plugging in wells. (S.I.No. 29/P-26)	126.00    Cft	Rs.    1141.25	%Cft	Rs.    1438.00
10. Providing and lying 1:3:6 cement concrete solid block masonry wall above 6" in thickness set in 1:6 cement sand mortar in ground floor super structure including raking out joints and curing etc complete. (S.I.No. 23/P-19)	168.00    Cft	Rs.    14621.44	%Cft	Rs.    24564.00
11. Providing & fixing galvanized iron frames / chowkats of size 7"x 2" or 4.5"x3" for doors using 20 guage G.I sheet including welded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jams. The cost also include all carriage, tools and plants used in making & fixing. (S.I No. 29/P-93)	33.00    Rft	Rs.    228.90	P.Rft	Rs.    7554.00
12. Providing & fixing galvanized iron frames / chowkats of size 7"x 2" or 4.5"x3" for windows using 20 guage G.I sheet including welded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jams. The cost also include all carriage, tools and plants used in making & fixing. (S.I No. 28/P-93)	12.00    Rft	Rs.    240.50	P.Rft	Rs.    2886.00
13. Providing and fixing iron / steel grill using solid square bars of size 1/2"x1/2" placed at 4" c/c and frame of flat iron 3/4"x1/4" including circle shape at 1-0 apart equivalent fitted with screws or pins including painting 3 coats with 1st coat of red oxide paint etc. (S.I.No. 30/P-94)	4.00    Sft	Rs.    194.16	P.Sft	Rs.    777.00
14. Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13(b)/P-52)	556.00    Sft	Rs.    2206.60	%Sft	Rs.    12269.00
15. Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11(a)/P-52)	556.00    Sft	Rs.    2197.52	%Sft	Rs.    12218.00

16. Coloured glazed tiles 1/4" thick dodo jointed in white cement & pigment and laid over 1:2 cement sand mortar 3/4" thick including finishing. (S.I.No. 38/P-45)	200.00	Sft	Rs.	28299.30	%Sft	Rs.	56599.00
17. Laying floor of approved coloured glazed tiles 1/4" thick laid in white cement & pigment over a bed of 3/4" thick cement mortar 1:2. (S.I.No. 25/P-43)	96.00	Sft	Rs.	27747.06	%Sft	Rs.	26637.00
18. Providing and laying topping cement concrete 1:2:4 including surface finishing and dividing into panels (c) 2" thick. (S.I.No. 16(c)/P-42)	70.00	Sft	Rs.	3502.38	%Sft	Rs.	2452.00
19. First class deodar wood wrought, joinery in doors and windows etc, fixed in position including chowkats, hold fasts, hinges, iron tower bolts, chocks, cleats, handles and cords with hooks etc. Deodar panelled or panelled and glazed or fully glazed (b)1.75" thick . (S.I.No. 7(b) /P-58)	34.00	Sft	Rs.	1273.76	P.Sft	Rs.	30700.00
				902.93	Only Shutter		
20. Priming coat of chalk under distemper. (S.I.No. 23/P-54)	566.00	Sft	Rs.	442.75	%Sft	Rs.	2506.00
21. Distempering (c) 3 coats. (S.I.No. 24(c)/P-54)	566.00	Sft	Rs.	1079.65	%Sft	Rs.	6111.00
22. Painting new surfaces (c) Preparing surface and painting of doors and windows any type (including edges) (I&ii) 3 coats. (S.I.No. 5(c)/I&ii/P-70)	68.00	Sft	Rs.	2116.41	%Sft	Rs.	1439.00

Total S.I except Steel Work, Marble, G.Tiles, Alcop D&W, F.Door, W.Guaze & P.Block	Rs.	159709.00
Total Steel Work	Rs.	26222.00
Total Marble, G.Tiles, Alcop D&W, F.Door, W.Guaze & P.Block	Rs.	83236.00
Total N.S.I	Rs.	0.00
G.Total	Rs.	<u><u>269167.00</u></u>

\_\_\_\_\_ % Above / Below on the Rates of CSR      Amount to be added / deducted on basis of premium quoted Total (b)

Total a + b Rs. (a) \_\_\_\_\_ Rs. (b) \_\_\_\_\_ = Rs. \_\_\_\_\_

Fabrication \_\_\_\_\_ % Above Rs \_\_\_\_\_ Total Amount Rs \_\_\_\_\_

Marble / Tile \_\_\_\_\_ % Below Rs \_\_\_\_\_ Total Amount Rs \_\_\_\_\_

**Total Rs.** \_\_\_\_\_

Total (A) = a+b In words & figure \_\_\_\_\_

\_\_\_\_\_

CONTRACTOR

DEPUTY CONSERVATOR WILDLIFE  
HYDERABAD DIVISION

## Schedule B (WS & Sanitary)

**Name Of Work** Repair & restoration of lavatories (02 Seated) @ Haleji Lake District Thatta

Description	Quantity	Rate	Unit	Amount
01. Providing & fixing squatting type white Glazed Earthenware W.C Pan with front flush inlet & complete with including the cost of flushing cistern with internal fitting and flush pipe with bend and making requisite number of holes in walls, plinth and floor for pipe connections and making good in cement concrete 1:2:4 (B)(i) W.C of not less than 19" clear opening between flushing rims and 3 gallons flushing tank with 4" dia C.I trap & C.I thumble. (S.I.No. 1(B)/i/P-1)	2.0 No.	Rs. 4846.60	Each	Rs. 9693.00
02. Providing & fixing 24"x18" Lavatory Basin in white glazed earthenware complete with and including the cost of W.I or C.I cantilever brackets 6" built into walls, painted white in 2 coats after a primary coat of red lead paint, a pair of 1/2" dia chrome plated pillar taps, 1.5" rubber plugs and chrome plated brass chain, 1.25" brass waste of approved pattern, 1.25" dia malleable iron or C.P brass traps, malleable iron or brass unions and making requisite number of holes in walls, plinth and floor for pipe connection and making good in cement concrete 1:2:4 (Foreign Or Equivalent). (S.I.No. 10/P-3)	1.0 No.	Rs. 4928.00	Each	Rs. 4928.00
03. Providing G.I Pipes, specials and clamps etc including fixing, cutting and fitting complete with and including cost of breaking through walls and roof, making good etc, painting 2 coats after cleaning the pipes etc with white zink paint with pigment to match the colour of the building and testing with water to pressure head of 200 ft and handling. (i) 1/2" dia. (S.I.No.1(i)/P-12)	40.0 Rft	Rs. 73.21	P.Rft	Rs. 2928.00
04. Supplying & fixing Long Bib Cock of superior quality with C.P head 1/2" dia. (S.I.No. 13(a)/P-19)	2.0 No.	Rs. 1109.46	Each	Rs. 2219.00
05. Supplying & fixing concealed Tee Stop Cock of superior quality with C.P head 1/2" dia. (S.I.No. 12(a)/P-18)	3.0 No.	Rs. 843.92	Each	Rs. 2532.00
06. Supplying & fixing Swan Type Pillar Cock of superior quality with C.P head 1/2" dia. (S.I.No. 16(a)/P-19)	1.0 No.	Rs. 795.30	Each	Rs. 795.00
07. Providing laying uPVC Pipes of class D fixing in trench including cutting fitting and jointing with solvent cement including testing with water to a head of 400 ft. (PH S.I.No. 6/P-24) (i) 4" dia.	10.0 Rft	Rs. 226.00	P.Rft	Rs. 2260.00
<b>Total S.I except Pipe Work</b>				<b>Rs. 20167.00</b>
<b>Pipe Work (GI/RCC/Asbestos)</b>				<b>Rs. 5188.00</b>
<b>Total N.S.I</b>				<b>Rs. 0.00</b>
<b>G.Total</b>				<b>Rs. 25355.00</b>

\_\_\_\_\_ % Above / Below on the Rates of CSR

Amount to be added / deducted on basis of premium quoted Total (b)

Total a + b Rs. (a) \_\_\_\_\_ Rs. (b) \_\_\_\_\_ = Rs. \_\_\_\_\_

Cost of Pipe Work \_\_\_\_\_ % Above Rs \_\_\_\_\_ Total Amount Rs \_\_\_\_\_

**Total Rs. \_\_\_\_\_**

Total (A) = a+b In words & figure \_\_\_\_\_

**CONTRACTOR**

**DEPUTY CONSERVATOR WILDLIFE  
HYDERABAD DIVISION**