

**OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION-II,
GOVERNMENT OF SINDH, KARACHI**

Tender form issued to M/S. _____, Government Contractor,
and charged Rs. _____ Vide D.R. No. _____, Dated: _____


**EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION-II
KARACHI**

NAME OF WORK: REHABILITATION / IMPROVEMENT / RENOVATION & PROVISION OF MISSING FACILITIES IN EXISTING PRIMARY / ELEMENTARY SCHOOLS OF DISTRICT CENTRAL KARACHI (ADP NO. 191 OF 2016-2017) @ GBPS PIXYDALE NORTH NAZIMABAD KARACHI

I/We hereby tender for execution of the works of Government of Sindh (herein before / after) referred to as Government of Sindh, specified in the underwritten memorandum within the time modified in each memorandum at:

447. Part-A:	@ _____ (Above / Below),
448. Part-B:	@ _____ (Above / Below),
449. Part-C:	@ _____ (Above / Below),
450. Part-D:	@ _____ (Above / Below),
451. Part-E:	@ _____ (Above / Below),
452. Part-F:	@ _____ (Above / Below),
453. Part-G:	@ _____ (Above / Below),
454. Part-H:	@ _____ (Above / Below),

The estimate carried out & according to all respect with the specification design / drawing & instruction, in writing referred to rule-I here of the clause-12 of the annexed condition of the contract & agreement, that when material for the work are provided by the Government such materials & rates to paid for then shall be as provided in Schedule-B here to:

GENERAL DESCRIPTION:

i)	Estimated Cost	:-	Rs. 7,000,000/=
ii)	Earnest Money 5%	:-	Rs. 350,000/=
iii)	Security Deposit (5%) in/c Earnest Money (5%) Total (10%)	:-	Rs. 700,000/=
iv)	Income Tax (7.50%)	:-	Rs. 525,000/=
v)	Time allowed for completion of work	:-	24 Months

**EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION-II
KARACHI**

CONTRACTOR'S UNDERTAKING

I/We have offered that above rates after taking into consideration all the terms and conditions as per B-I, printed tender & this memorandum and shall be base to fill-up & completed the B-I, tender form co, as to complete the agreement. In case of failure, the Department will be at liable to take action against me/us.

cxv)	Schedule-A:	Nil
cxvi)	Schedule-B:	Attached herewith

(SIGNATURE OF CONTRACTOR)

SCHEDULE " B "

Name of Work:-Rehabilitation, Improvement / Renovation & Missing Facilities in Existing Primary / Elementary Schools District Karachi Central @ GBPS Paxdale No.1 North Nazimabad Karachi (SEMIS CODE 408120028) (ADP No:191 of 2016-2017)

S.No	Description of Item	Qty	Rate	Unit	Amount
------	---------------------	-----	------	------	--------

SCHEDULE ITEM

1	Excavation in foundation of building, bridges and other structure including dagbelling dressing, refilling around structure with excavated earth, watering and ramming. Lead upto 5 ft (b) In ordinary soil.(S.I.No:- 18(b)/C-1)	7996.00	3176.25	% 0Cft	25,397.00
2	Cement concrete bsick or stone ballast 1 1/2" To 2" Guage ratio1:4:8 (S.I.NO:4-B/P-15).	1900.00	9416.28	% Cft	178,909.00
3	Filling, watering and ramming earth in floors with surplus earth from foundation lead upto one chain and lift upto 5 feet. (S.I.N:21./P--5).	2665.33	1512.50	% 0Cft	4,031.00
4	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lead upto one chain and lift upto 5 feet.(S.I.N:22/P-5)	1065.67	3630.00	% 0Cft	3,868.00
5	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle.) (a) R.C work in roof slab, beams columns rafts, lintels and other structural members laid in situ or precast laid in position complete in all respects. (I) Ratio (1 : 2: 4) 90 Lbs.cement 2 Cft. Sand 4 Cft. Shingle 1/8" to 1/4" gauge. (S.I.N: 6 (A-I) /P- 16).	4340.00	337.00	P.Cft	1,462,580.00
6	Erection and removal of centering for R.C.C or plain cement concrete works of Deodar wood (2nd-Class)(S.I No 19(b)ii/P/18	1623.00	3127.41	% Sft	50,758.00
7	Cement concrete plain including placing compacting, finishing and curing, comlete (including screening and washing at stone aggregate without shuttering. (S,I No 5(H)/P.16)	598.00	12595.00	% Cft	75,318.00
8	Providing and laying 1 :3 : 6 Cement concrete solid Block masorany set in 1 :6 cement sand mortar in plinth and foundation in cluding raking out joints and curing etc. complete.(S.I.N:23 /P-18).	184.00	14268.53	% Cft	26,254.00
9	Providing and laying 1 :3 : 6 Cement concrete solid Block masorany wall 6" And Below in thickness set in 1 : 6 cement mortar in G.F ground floor superstructure including raking out joints & curing etc. complete. (S.I.NO:23/P-19).	2417.00	15771.01	% Cft	381,185.00
10	Providing and fixing G.I frames /Choukhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet I/c welded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage , tools and plants used in making and fixing.(S.I NO 29/P.93)	162.00	228.90	P.Rft	37,082.00
11	Providing and fixing G.I frames /Choukhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet I/c welded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage , tools and plants used in making and fixing.(S.I NO 29/P.93)	487.00	240.50	P.Rft	117,124.00

12	First Class deodar Wood Wrought Joinery in doors and windows fixed in position I/C Chowkats holds fasts hinges iron tower with hooks etc complete 1-3/4" Thick (Only Shutters) (S.I.NO,7/P-58)	303.00	902.93	P.Sft	273,588.00
13	Making Notice Board Made with Cement (S.I.N:1/-100)	200.00	58.11	P.Sft	11,622.00
14	Cement Plaster 1:4 3/4 Thick. (P-52/S.I.No:11©)	15978.00	3015.76	% Sft.	481,858.00
15	Providing and laying 1" thick topping cement concrete (1:2:4) including Surface finishing and dividing into panels: 3" Topping (S.I.N: 16(B)/P-42).	115.00	4411.40	% Sft	5,073.00
16	Providing and laying topping cement concrete 1:2:4 including surface finishing and dividing into panells 2" thick. (S.I.NO. 16 (A) / P-42)	1904.00	3275.50	% Sft	62,366.00
17	Two Coat of Bituman Laid hot using 34 lbs for % Sft ,over Roof and Blinded with sand at one Cft% Sft(S,I NO,13/P-35)	1904.00	1887.40	%Sft	35,936.00
18	Reinforced cement concrete spout including fixing in position 2 1/2" x 6" x 5".(S.I.No14.P.18)	10.00	261.25	Each	2,613.00
19	White Wash three Coats (S.I.N:15/P-62)	3482.00	829.95	%Sft	28,899.00
20	Primary Coats of Chalk Under distemper(S.I.N:23/P-59).	8455.00	442.75	%Sft	37,435.00
21	Distempering (c) 3 Coats (S.I.N.24©/P-54)	8455.00	1079.65	%Sft	91,284.00
22	Providing & fixing colour crete jto wall surface to provide, durable crust and aesthetics having thickness upto 3/4" with specified colour having water, fire and temite resistance (upto 20' -0 height). (P-56/S.I.N:44)	4792.00	6319.50	% Sft	302,830.00
23	Painting new surfaces:- (c) preparing surface and painting of doors and windows any type, (including edges).(S.I.N:5© / P-69).	1241.00	2116.41	% Sft	26,265.00
24	Providing and fixing with sunk iron screws wooden architrave approved design/ shape having width not less than 2- 1/2 inches as directed by Engineer incharge.(S.I.N.60 P.66)	390.00	49.97	P.Rft	19,488.00
				Total	3,741,763.00

_____ % Below / Above

Contractor Signature

NON-SCHEDULE ITEM

1	P/L procelence tile glazed and polished 16"x16"x5/16" on floor or wall facing in required colour abd patter in white cement sand pigment over a base of 1:2 grey cement mortar 3/4"thick in/c washing and filling or joints with slurry of white cement and pigment in desired shape with finishing cleaning and cost of wax polish etc complete in/c cutting tiles to proper profile(R.A.Approved)	3399.00	262.00	P.Sft	890,538.00
				Total	890,538.00

Contractor Signature