

9

**OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION-II,
GOVERNMENT OF SINDH, KARACHI**

Tender form issued to M/S. _____, Government Contractor,
and charged Rs. _____ Vide D.R. No. _____, Dated: _____


**EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION-II
KARACHI**

NAME OF WORK: REHABILITATION / RECONSTRUCTION OF EXISTING PRIMARY / SECONDARY
SCHOOLS (ADP NO. 361 OF 2016-2017) @ RAIS MORAND KHAN QAISRANI VILLAGE
SCHOOL GADAP TOWN KARACHI

I/We hereby tender for execution of the works of Government of Sindh (herein before / after) referred to as Government of Sindh, specified in the underwritten memorandum within the time modified in each memorandum at:

319. Part-A:	@ _____ (Above / Below),
320. Part-B:	@ _____ (Above / Below),
321. Part-C:	@ _____ (Above / Below),
322. Part-D:	@ _____ (Above / Below),
323. Part-E:	@ _____ (Above / Below),
324. Part-F:	@ _____ (Above / Below),
325. Part-G:	@ _____ (Above / Below),
326. Part-H:	@ _____ (Above / Below),

The estimate carried out & according to all respect with the specification design / drawing & instruction, in writing referred to rule-I here of the clause-12 of the annexed condition of the contract & agreement, that when material for the work are provided by the Government such materials & rates to paid for then shall be as provided in Schedule-B here to:

GENERAL DESCRIPTION:

i)	Estimated Cost	:-	Rs. 4,000,000/=
ii)	Earnest Money 5%	:-	Rs. 200,000/=
iii)	Security Deposit (5%) in/c Earnest Money (5%) Total (10%)	:-	Rs. 400,000/=
iv)	Income Tax (7.50%)	:-	Rs. 300,000/=
v)	Time allowed for completion of work	:-	24 Months

**EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION-II
KARACHI**

CONTRACTOR'S UNDERTAKING

I/We have offered that above rates after taking into consideration all the terms and conditions as per B-I, printed tender & this memorandum and shall be base to fill-up & completed the B-I, tender form co, as to complete the agreement. In case of failure, the Department will be at liable to take action against me/us.

lxxxiii) Schedule-A: Nil
lxxxiv) Schedule-B: Attached herewith

(SIGNATURE OF CONTRACTOR)

SCHEDULE - B


NAME OF WORK:-

**REHABILITATION / RECONSTRUCTION OF EXISTING PRIMARY /
SECONDARY SCHOOLS AT GADAP TOWN KARACHI (ADP. NO.361 2016-17)
AT RAIS MORAND KHAN QAISRANI VILLAGE KARACHI.**

S.No	Description of Item	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges and other structure in/c degebillng dressing, refilling around structure with excavated earth watering and ramming lead upto 5ft (b) in ordinary soil (S.I.No.18/P-4)	600.00	3176.25	%0Cft	Rs: 1906.00
2	Cement Concrete brick or stone ballast 1-1/2" to 2" guage ratio 1:4:8 (S.I.No.4b/P-15)	200.00	9416.28	%Cft	Rs: 18833.00
3	R.C.C work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms, moulds, lifting, shuttering, curing, rendering and finishing the exposed surface (including screening and washing of shingle (a) R.C.C work in roof slab, beams, columns, rafts, lintels and other structural members laid in situ or precast laid in position. Complete in all respects (i) Ratio 1:2:4 90 lbs. (S.I.No. 6(a)/i/C-4)	400.00	337.00	Peft	Rs: 134800.00
1	Reinforced cement concrete spout in/c fixing in position 2-1/2 x 6"x 5" (S.I.No.13 P-18)	10.00	261.25	Each	Rs: 2613.00
2	P/L 2"thick topping cement concrete 1:2:4 in/c surface finishing and dividing into pannels pannels (S.I.No.16c P-42)	1058.00	3275.50	%Sft	Rs: 34655.00
3	Two coats of bitumen laid hot using 34 lbs for % Sft over roof and blinded with sand @ 1 Cft per % Sft. (S.I.No. 13/P-7)	4849.00	1887.40	%Sft	Rs: 91520.00
6	Scraping ordinary distemper, oil bound distemper or paint on walls (S.I.No.54b P-15).	35071.00	108.96	%Sft	Rs: 38213.00
7	Distemping three coats (S.I.No.24© C-9)	17373.00	1079.65	%Sft	Rs: 187568.00
9	Painting new surface © preparing surface and painting of doors and windows any type (in/c edges and 3 coats (S.I.No.5©/I&iiC-11)	1040.00	2116.41	%Sft	Rs: 22011.00
8	Preparing the surface and painting with matt finish in/c rubbing the surface with bathy	17698.00	2717.00	%Sft	Rs: 480855.00
10	Preparing the surface and painting with weather coat in/c rubbing the surface with rubbing brick / sand paer filling the voids with chalk / plaster of paris and then painting with weather coat of approved make (S.I.No.38A P-56).	9940.00	2567.95	%Sft	Rs: 255254.00
13	Rubbing and Polishing Old Mosaic floor.(S.I.No.26 P-43)	6662.00	1228.92	%Sft	Rs: 81871.00
14	Painting new surface © preparing surface and painting guard bars gates of iron bars grating railing (in/c standard braccess etc) & similar opening work. (S.I.No.5d P-76)	4708.00	1228.92	%Sft	Rs: 57858.00
Total:-					1,407,957.00

_____ % Below / Above

Contractor Signature


EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION-II
EDUCATION & LITERACY DEPARTMENT
GOVT. OF SINDH KARACHI.

COMPOUND WALL

1	P/L 1:3:6 solid block masonry wall 6" below set in 1:6 cement mortar in ground floor super structure l/c raking out joints etc complete. (S.I.No: 23/Chapter-4)	1518.00	15771.01	%Cft	Rs:	239404.00
2	Cement plaster 1:4 upto 20 height (c) 3/4" thick. (S.I.No.11(c)/C-9)	5316.00	3191.76	%Sft	Rs:	169674.00
3	Primary coat of chalk under distemper. (S.I.No. 23/C-9)	5064.00	442.75	%Sft	Rs:	22421.00
4	Distemping 3 coats. (S.I.No. 24(c)/C-9)	15192.00	1079.65	%Sft	Rs:	164020.00
6	Painting new surface © preparing surface and painting guard bars gates of iron bars grating railing (in/c standard braccess etc) & similar opening work. (S.I.No.5d P-76)	192.00	1270.83	%Sft	Rs:	2440.00
Total:-					Rs:	579759.00

_____ % Below / Above

Contractor Signature

BORING

1	Boring for tube well in all water bearing soils from ground level to 10 ft. or 30.5 meter depth in/c sinking and with drawing of casing pipe (S.I.No.BHE 1 P-41) (200 mm 8" dia).	150.00	535.00	P.Rft	Rs:	80,250.00
2	Supplying and installing PVC strainers 'B' class of approved design quality and make in/c necessary socket etc complete. (S.I.No.9 BHE P-43).	140.00	554.05	P.Rft	Rs:	77,567.00
3	Supplying and installling PVC blind pipe 'B' class of approved design quality and make in/c necessary socket etc complete. (S.I.No. 12 BHE Page-44).	140.00	516.80	P.Rft	Rs:	72,352.00
4	Providing Laying uPVC pipes of Class 'B' fixing in trench in/c cutting fitting and jointing with solvent cement in/c testing with water to a head of 61 meter or 200 ft. (S.I.No.4 BHE Page -23).	140.00	90.00	P.Rft	Rs:	12,600.00
5	Shrouding with graded bagri (3/8" to 1/8" or 9 to 3 mm) in between bore and blind pipe for the following diameters of strainers. (S.I.No.13 BHE P-45) (200 mm 8" dia).	150.00	105.00	P.Rft	Rs:	15,750.00
6	Full hire charges of the pumping set per day in/c of wages of driver and assistant fuel or electric energy plate forms required for placing pumps etc at lower depth with suction and delivery pipes for pumping out water found at various depth from trench in/c the cost of erection and dismantling after completion of the job iii) Hire charges of pumping out water from 20ft. depth trench (PHS.I.No.23 iii) Page-53).	8.00	1500.00	P.Day	Rs:	12,000.00
7	Supplying and fixing centrifugal Pump Local made etc complete.	2.00	24000.00	Each	Rs:	48,000.00
Total:-					Rs:	318,519.00

_____ % Below / Above

Contractor Signature

CHECKED
DRAFTSMAN
 Education & Literacy Division-II

EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION-II
 EDUCATION & LITERACY DIVISION-II
 GOVT. OF SINDH KARACHI.

Non - Schedule Items

- 1 P/F floor for Marble tile of Botesina, Verona of Badal Block (12" x 12" x 3/4") fine dressed on the surface without winding in ground floor laid white cement 3/4" over 1" inch thick (Average) lime mortar 1:2 one lime two sand setting the tiles in/curring rubbing chemical polishing etc (R/A approved).

1936.00

301.00

P.Sft

Rs: 582736.00

Total:- 582,736.00

Contractor Signature

SCHEDULE ITEM 20% BELOW

- 1 P/F in position door & windows and ventilators of first class deodar wood frames and 1-3/4" thick commercial ply veneer shutters of first class deodar skelton (Hollow) and commercial ply wood (3 ply) on both Side (S.I.No.9 P-58)

231.00

856.53

P.Sft

Rs: 197858.00

- 2 First class deodar wood wrought joinery in doors and windows etc fixed in position in/c chowkhast hold fasts hinges, iron tower bolts chocks cleats handles and cords with hooks etc (S.I.No.7 P-58) Only shutters.

336.00

902.93

P.Sft

Rs: 303384.00

- 3 P/F 3/8" thick marble tiles of approved quality and colour and shade 8" x 4" or 6" x 4" in dado skirting and facing removal / tucking of existing plaster surface etc over 1/2" thick base of cement mortar 1:3 setting and washing the tiles with white cement slurry cement finishing cleaning and polishing etc complete for new work (S.I.No.68/P-55)

288.00

186.02

P.Sft

Rs: 53574.00

Total:- 554,816.00

_____ % Below / Above

Contractor Signature

SCHEDULE ITEM 10% ABOVE ON STEEL

- 1 Fabrication of Tor steel reinforcement for cement concrete including cutting, bending, laying in position, making joints and fastening including cost of binding wire (also includes removal of rust from bars. (S.I.No. 7(b)/C-4)

20.00

5001.70

P.cwt

Rs: 100034.00

- 2 Making & Fixing steel grated doors with 1/16" thick sheeting in/c angle iron frame 2" x 2" 3/8 and 3/4" square bars 4" centre to centre with locking arrangement (S.I.No.24 P-92)

96.00

726.72

P.Sft

Rs: 69765.00

Total:- 169,799.00

_____ % Below / Above

Contractor Signature

CHECKED

DRAFTSMAN
Education Division-II

EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION-II
EDUCATION & LITERACY DEPARTMENT
GOVT. OF SINDH KARACHI.