


**OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION-II,
GOVERNMENT OF SINDH, KARACHI**

Tender form issued to M/S. _____, Government Contractor,
and charged Rs. _____ Vide D.R. No. _____, Dated: _____


**EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION-II
KARACHI**

NAME OF WORK: REHABILITATION / IMPROVEMENT / RENOVATION & PROVISION OF MISSING FACILITIES IN EXISTING PRIMARY / ELEMENTARY SCHOOLS OF DISTRICT MALIR KARACHI (ADP NO. 188 OF 2016-2017) @ GBELS HAJI PATHAL GOTH SECTOR 7/A MAYMARABAD CADAP TOWN KARACHI

I/We hereby tender for execution of the works of Government of Sindh (herein before / after) referred to as Government of Sindh, specified in the underwritten memorandum within the time modified in each memorandum at:

455. Part-A:	@ _____ (Above / Below),
456. Part-B:	@ _____ (Above / Below),
457. Part-C:	@ _____ (Above / Below),
458. Part-D:	@ _____ (Above / Below),
459. Part-E:	@ _____ (Above / Below),
460. Part-F:	@ _____ (Above / Below),
461. Part-G:	@ _____ (Above / Below),
462. Part-H:	@ _____ (Above / Below),

The estimate carried out & according to all respect with the specification design / drawing & instruction, in writing referred to rule-I here of the clause-12 of the annexed condition of the contract & agreement, that when material for the work are provided by the Government such materials & rates to paid for then shall be as provided in Schedule-B here to:

GENERAL DESCRIPTION:

i)	Estimated Cost	:-	Rs. 9,000,000/=
ii)	Earnest Money 5%	:-	Rs. 450,000/=
iii)	Security Deposit (5%) in/c Earnest Money (5%) Total (10%)	:-	Rs. 900,000/=
iv)	Income Tax (7.50%)	:-	Rs. 675,000/=
v)	Time allowed for completion of work	:-	24 Months

**EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION-II
KARACHI**

CONTRACTOR'S UNDERTAKING

I/We have offered that above rates after taking into consideration all the terms and conditions as per B-I, printed tender & this memorandum and shall be base to fill-up & completed the B-I, tender form co, as to complete the agreement. In case of failure, the Department will be at liable to take action against me/us.

cxvii) Schedule-A: Nil
cxviii) Schedule-B: Attached herewith

(SIGNATURE OF CONTRACTOR)

SCHEDULE - B

NAME OF WORK:-

**REHABILITATION / IMPROVEMENT / RENOVATION & PROVISION OF
MISSING FACILITIES IN EXISTING PRIMARY / ELEMENTARY SCHOOLS
DISTRICT MALIR @ GBELS HAJI PATHAI GOTH SECTOR 7/A MAYMARABAD.**

S.No	Description of Item	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges and other structure in/c degebillng dressing, refilling around structure with excavated earth watering and ramming lead upto 5ft (b) in ordinary soil (S.I.No.18/P-4)	7500.00	3176.25	%0Cft	Rs: 23822.00
2	Cement Concrete brick or stone ballast 1-1/2" to 2" guage ratio 1:4:8 (S.I.No.4b/P-15)	775.00	9416.28	%Cft	Rs: 72976.00
3	R.C.C work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms, moulds, lifting, shuttering, curing, rendering and finishing the exposed surface (including screening and washing of shingle (a) R.C.C work in roof slab, beams, columns, rafts, lintels and other structural members laid in situ or precast laid in position. Complete in all respects (i) Ratio 1:2:4 90 lbs. (S.I.No. 6(a)/i/C-4)	3500.00	337.00	Pcft	Rs: 1179500.00
4	Erection and removal of centering for R.C.C or plain cement concrete work of deodar wood (2nd class) (S.I.NO.18-P-21) (vertical)	1000.00	3127.41	%Cft	Rs: 31274.00
5	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate without shuttering) (h) Ratio 1:3:6 (S.I.No. 5(h)/C-4)	750.00	12595.00	%Cft	Rs: 94463.00
6	P/L 1:3:6 solid block masonry wall 6" below set in 1:6 cement mortar in ground floor super structure 1/c raking out joints etc complete. S.I.No: 23/Chapter-4)	2000.00	15771.01	%Cft	Rs: 315420.00
7	Cement Plaster 1:4 upto 12' height 3/4" thick (S.No.11-C/P-52).	12000.00	3191.76	%sft	Rs: 383011.00
8	Dismantling cement concrete plain 1:2:4 (S.I.No.19c P/11).	799.00	1597.20	%Cft	Rs: 12762.00
9	Two coats of bitumen mastic coating 34 lbs for % Sft over roof and blinded with sand @ 1 Cft per % Sft (S.I.No. 53/P-7)	1550.00	1887.40	%Sft	Rs: 29255.00
10	Scraping ordinary distemper, oil bound distemper or paint on walls (S.I.No.54b P-15).	39536.00	108.96	%Sft	Rs: 43078.00
11	Primary Coat of chalk under distemper (S.I.No.23/C-9)	4220.00	442.75	%Sft	Rs: 18684.00
12	Distemping three coats (S.I.No.24 C-9)	4860.00	1079.65	%Sft	Rs: 52471.00
13	Painting new surface © Preparing surface and painting of doors and windows any type (in/c edges) (I&II) 3 coats (S.I.No.50/I&iiC-11)	3500.00	2116.41	%Sft	Rs: 74074.00

CHECKED
DRAFTSMAN
Education Division-II

14	Painting new surface © preparing surface and painting guard bars gates of iron bars grating railing (in/c standard braccess etc) & similar opening work. (S.I.No.5d P-76)	3658.00	1270.83	%Sft	Rs:	46487.00
15	Preparing the surface and painting with matt finish in/c rubbing the surface with bathy (silicon carbide rubbng brick) filling the voids with zink / chalk /plaster of paris mixture , applying first coat premix making the surface smooth and then painting 3 coats with matt finish of approved make etc complete (New surface)(S.I.No.36-A P-55)	40000.00	2717.00	%Sft	Rs:	1086800.00
16	Preparing the surface and painting with weather coat in/c rubbing the surface with rubbing brick / sand paer filling the voids with chalk / plaster of paris and then painting with weather coat of approved make (S.I.No.38A P-56).	12690.00	2567.95	%Sft	Rs:	325873.00
17	P/F Colour Create to wall surface to provide durable crust and aesthetics having thickness upto 3/4" with specified colour having water fire and termite resistance (upto 20' height) (S.I.No.44 P-56)	3000.00	6319.50	%Sft	Rs:	189585.00
					Total:-	3,979,535.00
_____ % Below / Above						

Contractor Signature

NON-SCHEDULE ITEM

1	P/F floor for Marble tile of China, Verona of Badal Block (12" x 12") fine dressed on the surface without winding in ground floor laid 1" thick (Average) lime mortar 1:2 one lime tow sand setting the tile with grey cement slurry in/c curring rubbing & polishing etc complete in/c the cost of mortar 1" thick (R/A approved).	4500.00	301.00	P.Sft	Rs:	1,354,500.00
					Total:-	1,354,500.00

Contractor Signature

SCHEDULE ITEM 20% BELOW

1	S/F in position Aluminium Channels framing for slidding windows & ventilators of Alcop made with 5mm thick tinted glass glazing (Belgium) & Aluminium fly screen in/c handles stopper & locking arrangement etc complete. B) Deluxe model (Bronze) (S.I.No.84/P-108).	408.00	1647.69	P.Sft	Rs:	672258.00
2	First class deodar wood wrought joinery in doors and windows etc fixed in position in/c chowkhast hold fasts hinges, iron tower bolts chocks cleats handles and cords with hooks etc (S.I.No.7 P-58) Only shutters.	600.00	902.93	P.Sft	Rs:	541758.00
3	Laying floor of approved with glazed tile 1/4" in white cement 1:2 over 3/4" thick cement mortar 1:2 complete (S.I.No.24/P-43)					

CHECKED
 DEPUTY MAN
 Education Division-II


	60.00	27678.86	%Sft	Rs:	16607.00
4	White glazed tiles 1/4" thick dado jointed in white cement and laid over 1:2 cement sand mortar 3/4" thick in/c finishing (S.I.NO.37/P-45)				
	325.00	28253.61	%Sft	Rs:	91824.00
Total:-					1,322,447.00
_____ % Below / Above					

Contractor Signature

SCHEDULE ITEM 10% ABOVE ON STEEL

1	Fabrication of Tor steel reinforcement for cement concrete including cutting, bending, laying in position, making joints and fastening including cost of binding (also includes removal of rust from bars. (S.I.No. 7(b)/C-4)				
	250.00	5001.70	P.cwt	Rs:	1250425.00
2	P/F G.I frames / Chowkats of size 7"x2" or 4-1/2" x 3" for doors using 20 gauge G.I. sheet i/c welded hinges and fixing at site with necessary hold fasts filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage tools and plants used making and fixing.(S.I.No: 29/P-93)				
	108.00	228.90	P.Rft	Rs:	24721.00
3	P/F G.I frames / Chowkats of size 7"x2" or 4-1/2" x 3" for windows & vent. using 20 gauge G.I. sheet i/c welded hinges and fixing at site with necessary hold fasts filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage tools and plants used making and fixing.(S.I.No: 28/P-93)				
	360.00	240.50	P.Rft	Rs:	86580.00
4	S/F in position iron / steel grill of 3/4" x 1/4" size flat iron of approved design in/c painting 3 coats etc complete (wt. not less than 3.7lbs of finishing grill) (S.I.NO.26 /P-93)				
	1303.00	180.50	P.Sft	Rs:	235192.00
Total:-					1,596,918.00
_____ % Below / Above					

Contractor Signature


EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION-II
 EDUCATION & LITERACY DEPARTMENT
 GOVT. OF SINDH KARACHI.