

4

**OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION-II,  
GOVERNMENT OF SINDH, KARACHI**

Tender form issued to M/S. \_\_\_\_\_, Government Contractor,  
and charged Rs. \_\_\_\_\_ Vide D.R. No. \_\_\_\_\_, Dated: \_\_\_\_\_

  
**EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION-II  
KARACHI**

**NAME OF WORK:** REHABILITATION / IMPROVEMENT / RENOVATION & PROVISION OF MISSING FACILITIES IN EXISTING PRIMARY / ELEMENTARY SCHOOLS OF DISTRICT CENTRAL KARACHI (ADP NO. 191 OF 2016-2017) @ GGPS NAZIMABAD NO. 1 FIRDOUS COLONY LIAQUATABAD KARACHI

I/We hereby tender for execution of the works of Government of Sindh (herein before / after) referred to as Government of Sindh, specified in the underwritten memorandum within the time modified in each memorandum at:

431. Part-A:	@ _____	(Above / Below),
432. Part-B:	@ _____	(Above / Below),
433. Part-C:	@ _____	(Above / Below),
434. Part-D:	@ _____	(Above / Below),
435. Part-E:	@ _____	(Above / Below),
436. Part-F:	@ _____	(Above / Below),
437. Part-G:	@ _____	(Above / Below),
438. Part-H:	@ _____	(Above / Below),

The estimate carried out & according to all respect with the specification design / drawing & instruction, in writing referred to rule-I here of the clause-12 of the annexed condition of the contract & agreement, that when material for the work are provided by the Government such materials & rates to paid for then shall be as provided in Schedule-B here to:

**GENERAL DESCRIPTION:**

i)	Estimated Cost	∴	Rs. 10,000,000/=
ii)	Earnest Money 5%	∴	Rs. 500,000/=
iii)	Security Deposit (5%) in/c Earnest Money (5%) Total (10%)	∴	Rs. 1,000,000/=
iv)	Income Tax (7.50%)	∴	Rs. 750,000/=
v)	Time allowed for completion of work	∴	24 Months

**EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION-II  
KARACHI**

**CONTRACTOR'S UNDERTAKING**

I/We have offered that above rates after taking into consideration all the terms and conditions as per B-I, printed tender & this memorandum and shall be base to fill-up & completed the B-I, tender form co, as to complete the agreement. In case of failure, the Department will be at liable to take action against me/us.

cxi) Schedule-A: Nil  
cxii) Schedule-B: Attached herewith

(SIGNATURE OF CONTRACTOR)

**Work:- Rehabilitation / Improvement / Renovation & Missing Facilities in Existing Primary/ Secondary Schools District Central Karachi @ G.G.P.S Al Zehra Nazimabad Firdous Colony Karachi**

**SCHEDULE - B**

S.No.	Description of items.	QTY	Rate	Unit	Amount
1	Dismantling First class Tile Roofing (p-11/22a)	2893.80	453.75	%Cft	13130.62
2	Dismantling cement block massonary (p-10/14)	3814.25	1134.38	%Sft	43268.09
3	P/L 1:3:6 c.c solid block masonry wall 6" Above set in 1:6 c.m in g.f super-Structure in/c rackin our and jointing and curring etc complete (P-19/24)	3321.33	14621.44	%Cft	485626.27
4	Cement plaster (1:4), 3/4"thick, 20' height.(p-52/11d)	13178.11	3015.76	%Sft	397420.17
5	Providing and fixing Alumnium sheet on doors pasted with glue as per requirement (P/73/61)	52.27	63.77	P.Sft	3333.26
6	Painting new surfaces (c) Preparing surface and painting of doors and windows any type (including edges) 2 coats. (P- 69/5c)	315.19	2116.41	%Sft	6670.71
7	Providing and fixing colour creat to wall surface to provide, durable crust and esthetics having thickness upto 3/4" with specified colour having water, fire and termite resistance upto 20'-0 height. (p-56/44)	4636.80	6319.50	%Sft	293022.58
8	Notice Board made with cement. (p-95/1)	235.20	58.11	P.Sft	13667.47
9	P/F with sunk iron screws wooden Architrave approved design/ shap having width not less than 2-1 as directed by Engineer Incharge	540.75	49.97	P.Sft	27021.28
10	Preparing the surface and painting with matt finish including rubbing the surface with Bathy (Silicon carbide rubbing brick) filling the voids with zink /chalk plaster of paris mixture applying firrst coats premix makaing the surface smooth and dhen panting 3 coats with matt finish of approved make etc complete (new Surface) (P/61/36)	13178.16	3444.38	%Sft	453905.91
11	Primary coat of chalk under distemper. (/P/54/23)	4085.68	442.75	%Sft	18089.35
12	Distempering (c) 3 coats.(P/54/2402)	4085.68	1079.65	%Sft	44111.04
13	Reinforced cement concrete spout including fixing in position 2.5"x6"x5". (P-18/14)	14.00	261.25	Each	3657.50
14	Providing and laying topping cement concrete 1:2:4 including surface finishing and dividing into panells (c) 2" thick. (S.I.No: 16/c/Chapter-8)	5145.00	3275.50	%Sft	168524.48
15	Two coats of bitumen laid hot using 34 lbs for % Sft over roof and blinded with sand @ 1 Cft per % Sft. (p-35/137)	5145.00	1887.40	%Sft	97106.73

**CHECKED**  
**DRAFTSMAN**  
**Division-II**

R.C.C work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms, moulds, lifting, shuttering, curing, rendering and finishing the exposed surface (including screening and washing of shingle) (a) R.C.C work in roof slab, beams, columns, rafts, lintels and other structural members laid in situ or precast laid in position. Complete in all respects (i) Ratio 1:2:4 90 lbs.

4285.79 337.00 P.Cft 1444311.23

Total 3512866.68

Add/ Less \_\_\_\_\_ Above / Below

Contractor Signature

- 1 Fabrication of Tor steel reinforcement for cement concrete including cutting, bending, laying in position, making joints and fastening including cost of binding wire (also includes removal of rust from bars.

286.99 5001.70 P.Cwt 1435437.88

- 2 Providing and fixing iron steel grill using solid square bars of size 1/2"x1/2" placed at 4" I/c and frame of flat iron gate of 3/4" x 3/4" I/c circle shape at apart equivalent fitted with screws are pins I/c painting 3 coats with 1st coat of red oxide painting

978.55 194.16 P.Sft 189995.27

- 3 G.I Expanded metal 1/2" to 3/4" mesh 16 gauge fixed to chowkts with 1 cover moulding and fixed screws including teak wood frame 2" x 2" (P/58/I/6)

470.40 334.24 P.Sft 157227.91

- 4 P/F G.I frames / Chowkats of size 7"x2" or 4-1/2" x 3" for Doors using 20 gauge G.I. sheet i/c welded hinges and fixing at site with necessary hold fasts filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also I/c all carriage tools and plants used making and fixing.(p-93/29)

137.55 228.90 P.Rft 31485.20

- 5 P/F G.I frames / Chowkats of size 7"x2" or 4-1/2" x 3" for Windows using 20 gauge G.I. sheet i/c welded hinges and fixing at site with necessary hold fasts filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also I/c all carriage tools and plants used making and fixing.(P-93/28)

254.40 240.50 P.Rft 61183.20

Total 1875329.45

Add/ Less \_\_\_\_\_ Above / Below

Contractor Signature

- 1 Providing and fixing 3/8" thick marble tiles of approved quality and shade size 8"x4"/6"x4" in dado skirting and facing removal/tucking of existing plaster surface etc over 1/2" thick base of cement mortar 1:3 setting of tiles in slurry of white cement over mortar base i/c filing the joint & washing the tiles & polishing (P-68/Chapter-8) (a) For new Work

451.26 186.04 P.Sft 83952.41



first class deodar wood wrought, joinery in doors and windows etc, fixed in position including chowkats, hold fasts, hinges, iron tower bolts, chocks, cleats, handles and cords with hooks etc. Deodar panelled or panelled and glazed or fully glazed (a) 2" thick . (p-58 7 b) (Only Shutters)

315.19 902.73 P.Sft 284531.47

Total 368483.88

Add/ Less \_\_\_\_\_ Above / Below

Contractor Signature

- 1 Providing and laying Floor for Marble Tiles of botesina, Verona or Badami (12"x12"x3/4) fine dressed on the surface without winding set in grey cement and over 3/4" thick bed of 1:2 grey cement slurry jointing and washing finishing tiles with slurry of white cement i/c pigment to match the colours of tiles i/c curring grinding rubbing and chemical polish polishing etc complete as directed by Engineer Incharge (R.A Approved)

5389.98

P.Sft

Contractor Signature

CHECKED  
DRAFTSMAN  
Education Division-II

EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION-II  
EDUCATION & LITERACY DEPARTMENT  
GOVT. OF SINDH KARACHI.