


**OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION-II,
GOVERNMENT OF SINDH, KARACHI**

Tender form issued to M/S. _____, Government Contractor,
and charged Rs. _____ Vide D.R. No. _____, Dated: _____


**EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION-II
KARACHI**

NAME OF WORK: M/R TO GOVERNMENT DEGREE COLLEGE FOR BOYS NEAR GARAM CHASHMA
MANGHOPIR GADAP KARACHI (ELECTRIFICATION WORK)

I/We hereby tender for execution of the works of Government of Sindh (herein before / after) referred to as Government of Sindh, specified in the underwritten memorandum within the time modified in each memorandum at:

1. Part-A: @ _____ (Above / Below),
2. Part-B: @ _____ (Above / Below),

The estimate carried out & according to all respect with the specification design / drawing & instruction, in writing referred to rule-I here of the clause-12 of the annexed condition of the contract & agreement, that when material for the work are provided by the Government such materials & rates to paid for then shall be as provided in Schedule-B here to:

GENERAL DESCRIPTION:

i)	Estimated Cost	:-	Rs. 800,000/=
ii)	Earnest Money 5%	:-	Rs. 40,000/=
iii)	Security Deposit (5%) in/c Earnest Money (5%) Total (10%)	:-	Rs. 80,000/=
iv)	Income Tax (7.50%)	:-	Rs. 60,000/=
v)	Time allowed for completion of work	:-	04 Months

**EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION-II
KARACHI**

CONTRACTOR'S UNDERTAKING

I/We have offered that above rates after taking into consideration all the terms and conditions as per B-I, printed tender & this memorandum and shall be base to fill-up & completed the B-I, tender form co, as to complete the agreement. In case of failure, the Department will be at liable to take action against me/us.

- i) Schedule-A: Nil
ii) Schedule-B: Attached herewith

(SIGNATURE OF CONTRACTOR)

NAME OF WORK : - GOVERNMENT DEGREE COLLEGE FOR BOYS NEAR GARAM CHISHMA MANGHOPIR KARACHI
(ELECTRIFICATION WORK) (PAK ARMY TROOPS DURING 6TH POPULATION & HOUSING CENSUS)

SCHEDULE OF PRICE

S.NO	ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
1	Wiring for light or fan point with 3/.029 PVC insulated wire in 20 mm (3/4") channel pati on surface as required. (S.I.NO: P-15/129).	80	Point	910.00	P.P	72800.00
2	Wiring for plug point with 1/1.13(3/.029)PVC insulated wire in 20 mm (3/4") channel pati on surface as required. (S.I.NO: P-15/130).	12	Nos	742.00	Each	8904.00
3	Providing & Laying (Main or Sub-Main) PVC insulated with size 2-7/.029 copper conductor in 3/4" dia PVC conduit on surface (S.I.No: P-1/3).	300.00	Mtr.	171.00	P.Mtr.	51300.00
4	Providing & Laying (Main or Sub-Main) PVC insulated with size 4-7/.044(6mm ²) copper conductor in 1-1/2" dia PVC conduit on surface. (S.No:P-5/33)	200.00	Mtr.	566.00	P.Mtr.	113200.00
5	Providing & Laying (Main or Sub-Main) PVC insulated with size 4-7/.064 (16mm ²) copper conductor in 1-1/2" dia PVC conduit on surface. (S.No:P-5/35)	106.00	Mtr.	1169.00	P.Mtr.	123914.00
6	P/F circuit breaker 6,10,15,20,30,40,50 & 63 amps SP (TB-5S) on prepared board as required. (S.NO:P-31/203)	50	Nos	916.00	Each	45800.00
7	P/F circuit breaker 3,5,10,15,20 & 30 amps TP (XS-30Ns (NB) on prepared board as required. (S.NO:P-31/205)	2	Nos.	5301.00	Each	10602.00
8	P/F circuit breaker 15,2,30,40,50 & 60 amps TP (XS-100 CS (CB) on prepared board as required. (S.NO:P-31/206)	2	Nos	5521.00	Each	11042.00
9	P/F Bakelite ceiling rose with two terminals (S.No:P-33/228)	80	Nos.	72.00	Each	5760.00

CHECKED
DRAFTSMAN
Education
Division-II

Add: % above / below

Total Rs: 443322.00

G.Total Rs:

NON-SCHEDULE ITEM.

1	P/F flush type fancy type switch 10 Amps i/c:plastic board imprinted made etc complete.	80	Nos		Each	
2	P/F flush type 2 pin plug socket 10 Amps with fancy type board and sheet i/c:necessary connection.	12	Nos		Each	
3	P/F flush type 3 pin plug socket 5 Amps with fancy type board and sheet i/c:necessary connection.	10	Nos		Each	

4	P/F flush type 3 pin plug socket 15 Amps with fancy type board and sheet i/c necessary connection.	2	Nos	Each
5	P/F fan dimmer fancy type imported .	20	Nos	Each
6	P/F ceiling FAN 56" Sweep imported make with necessary electric connection etc complete.	20	Nos	each
7	P/F distribution board 18" SWG double shutter for accommodate circuit breaker and busbar i/c painting with enamelled paint as approved by Engineer/ Incharge	8.00	Sft	P.Sft
8	P/F Pannel board with heavy duty guage metal sheet D.S to accommodate circuit breaker bus bars etc.	4.00	Sft	P.Sft
9	P/F L.E.D Tube light 18 watts (Light emitting Diod) classification with L.E.D driver complete plastic covered and base etc complete.	10	Nos	Each
10	P/F L.E.D light 8" square / circle shop (09) watts in plastic cover fancy type (china make).	50	Nos	Each
11	P/F Search light 400 watts imported quality i/c fixing on wall with necessary connection etc complete.	6	Nos	Each
12	P/F water pumping set 1 HP 2800 RPM single phase 220 volts 2" 0x1-1/2 section and delivery 60" head in clouding base plate & also making c.c 1:3:6 plate form required size & along with nuts & bolts complete in all respects as approved by Engineer/ Incharge .(RA).	1	Nos	Each

CHECKED
Chafiz
DRAFTSMAN
Education Works Division-II

Part-B Total Rs: _____

Part-A Total Rs: _____

G.Total Rs: _____

(CONTRACTOR SIGNATURE)

[Signature]
EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION-II
KARACHI
[Red Stamp]