

**OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION-II,  
GOVERNMENT OF SINDH, KARACHI**

Tender form issued to M/S. \_\_\_\_\_, Government Contractor,  
and charged Rs. \_\_\_\_\_ Vide D.R. No. \_\_\_\_\_, Dated: \_\_\_\_\_

EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION-II  
KARACHI

**NAME OF WORK:** M/R TO GBPS RAZA MUHAMMAD BROHI NEAR ABDUL REHMAN GABOL VILLAGE  
GADAP MALIR KARACHI

I/We hereby tender for execution of the works of Government of Sindh (herein before / after) referred to as Government of Sindh, specified in the underwritten memorandum within the time modified in each memorandum at:

1. Part-A: @ \_\_\_\_\_ (Above / Below),  
2. Part-B: @ \_\_\_\_\_ (Above / Below),

The estimate carried out & according to all respect with the specification design / drawing & instruction, in writing referred to rule-I here of the clause-12 of the annexed condition of the contract & agreement, that when material for the work are provided by the Government such materials & rates to paid for then shall be as provided in Schedule-B here to:

**GENERAL DESCRIPTION:**

i)	Estimated Cost	:-	Rs. 360,000/=
ii)	Earnest Money 5%	:-	Rs. 18,000/=
iii)	Security Deposit (5%) in/c Earnest Money (5%) Total (10%)	:-	Rs. 36,000/=
iv)	Income Tax (7.50%)	:-	Rs. 27,000/=
v)	Time allowed for completion of work	:-	04 Months

EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION-II  
KARACHI

**CONTRACTOR'S UNDERTAKING**

I/We have offered that above rates after taking into consideration all the terms and conditions as per B-I, printed tender & this memorandum and shall be base to fill-up & completed the B-I, tender form co, as to complete the agreement. In case of failure, the Department will be at liable to take action against me/us.

- i) Schedule-A: Nil  
ii) Schedule-B: Attached herewith

(SIGNATURE OF CONTRACTOR)

NAME OF WORK:- REPAIR OF ELECTRIC WORK AT GBPS RAZA MUHAMMAD BROHI NEAR  
ABDUL REHMAN GABOL VILAGE UNDER 6TH POPULATION & HOUSING  
CENSUS-2017 ( ELECTRIFICATION WORK)

SCHEDULE OF PRICE

S.NO.	ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
1	Wiring for light or fan point with 3/0.29 PVC insulated wire in 20 mm (3/4") channel pati on surface as required. (S.I.NO: P-15/129).	40	Point	910.00	P.P	36400.00
2	Wiring for plug point with 1/1.13(3/0.29)PVC insulated wire in 20 mm (3/4") channel pati on surface as required. (S.I.NO: P-15/130).	7	Nos	742.00	Each	5194.00
3	Providing & Laying ( Main or Sub-Main) PVC insulated with size 2-7/0.29 copper conductor in 3/4" dia PVC conduit on surface ( S.I.No: P-1/3 ).	250.00	Mtr.	171.00	P.Mtr.	42750.00
4	Providing & Laying ( Main or Sub-Main) PVC insulated with size 2-7/0.36 ( 4mm2) copper conductor in 3/4" dia PVC conduit on surface ( S.I.No: P-1/4 ).	80.00	Mtr.	200.00	P.Mtr.	16000.00
5	Providing & Laying ( Main or Sub-Main) PVC insulated with size 2-7/0.44( 6mm2) copper conductor in 3/4" dia PVC conduit on surface ( S.I.No: P-1/5 ).	90.00	Mtr.	305.00	P.Mtr.	27450.00
6	P/F circuit breaker 6,10,15,20,30,40,50 & 63 amps SP (TB-5S) on prepared board as required. (S.NO:P-31/203)	10	Nos	916.00	Each	9160.00
7	P/F circuit breaker 3,5,10,15,20 & 30 amps TP (XS 30NS) (NB) on prepared board as required. (S.NO:P-31/205)	2	Nos.	5301.00	Each	10602.00
8	P/F Bakelite ceiling rose with two terminals. (S.No:P-33/228)	40	Nos.	72.00	Each	2880.00

CHECKED  
DRAFTSMAN  
Education Division-II

Add; % above / below

G. Total Rs:

150436.00

GTotal Rs;

PART-B ( NON-SCHEDULE ITEM.)

1	P/F flush type fancy type switch 10 Amps i/c:plastic board impted made etc complete.	80	Nos		Each
2	P/F flush type 2 pin plug socket 10 Amps with fancy type board and sheet i/c:necessary connection.	15	Nos		Each
3	P/F flush type 3 pin plug socket 5 Amps with fancy type board and sheet i/c:necessary connection.	2	Nos		Each

O.	ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
4	P/F flush type 3 pin plug socket 15 Amps with fancy type board and sheet i/c:necessary connection.	2	Nos		Each	
5	P/F ceiling FAN 56" Sweep imported make with necessary electric connection etc complete.	10	Nos		each	
6	P/F fan dimmer fancy type imported .	10	Nos		Each	
7	P/F distribution board 18" SWG double shuter for accommodate circiut breaker and busbar i/c painting with enemelled paint as approved by Engineer/ Incharge	4.00	Sft		P.Sft	
8	P/F Pannel board with heavy duty guage metal sheet D.S to accommodate circiut breaker bus bars etc.	4.00	Sft		P.Sft	
9	P/F Energy Saver superior quality i/c:fixing on existing holder etc complete as a approved y Engineer/Incharge.	20	Nos		Each	
10	P/F wall / Ceiling mounted light , fancy type , superior quality i/c necessary electric connection , with holder without energy saver as approved by Engineer /	20	Nos		Each	
11	P/F L.E.D Tube light 18 watts ( Light emitting Diod) classification with L.E.D driver complete plastic covered and base etc complete.	10	Nos		Each	
12	P/F Search light 400 watts imported quality i/c fixing on wall with necessary connection etc complete.	5	Nos		Each	
13	P/F water pumping set 5 -1/2 2800 RPM Three phase 440 volts 2".0x1-1/2 section and delivery 12571 head in clouding base plate & also making c.c 1:3:6 plate form required size c along with nuts & bolts complete in all respect as a approved by Engineer/ Incharge (RA).	1	Nos		Each	

**CHECKED**  
**DRAFTSMAN**  
**Education Division-II**

Total Part-B Rs:

Total Part-A Rs:

G.Total Rs:

Say Rs:

( CONTRACTOR SIGNATURE )

**EXECUTIVE ENGINEER**  
**EDUCATION WORKS DIVISION-II**  
**KARACHI**