

# SCHEDULE -B

NAME OF WORK:- STRENGTHENING OF PROFESSIONAL DEVELOPMENT CENTRE B.ED  
COLLEGE DARSANO CHANNO GADAP TOWN KARACHI.

S.No.	Description	Qty	Rate	Unit	Amount.
-------	-------------	-----	------	------	---------

## SCHEDULE ITEM AT PAR

1	P/F in position door & windows and ventilators of first class deodar wood frames and 1-3/4" thick commercial ply vaneer shutters of first class deodar skelton (Hollow) and commercial ply wood (3 ply) on both Side (S.I.No.9 P-65)	224.00	856.53	P.sft	191,863.00
2	Painting new surface © Preparing surface and painting of doors and windows any type (in/c edges) (I&II) 3 coats (S.I.No.5©/I&iiC-11)	448.00	2116.41	%sft	9,482.00
3	S/F in position iron / steel grill of 3/4" x 1/4" size flate iron of approved design in/c painting 3 coats etc complete (wt. not less then 3.7lbs of finsihing grill) (S.I.NO.26 /P-97)	8130.00	180.50	P.sft	1,467,465.00
4	p/f WITH Jute felt paper of 60 lbs over roof in/c cleaning of roof with wire brush an removing dust applying bitumen coat at the 34lbs per %Sft as premix inter coats and then laying felt paper with 10% over laps then an d spreeding hill sand at the rate of 1Cft for 100 sft The coat also in/c necessary fire material kerosene oil wood etc. (S.I.No.42 P-39).	5640.00	106.73	P.sft	601,957.00
5	Providing anti termite treatment by spraying / sprinkling / spreading Neptachler 0.5% Emulsion as on overall pre-construction treatment in slab type construction along external foundation trenches of the building over complete premeter of the foundation trench ete as per direction of Engineer Incharge.	308.00	40.00	P.Rft	12,320.00
6	Providing Anti Termite Treatment by Spraying / Sprinkling / Spreading Neptachlar 05% Emulsion as on over all pre-construction treatment in slab and long attached perches or entrance etc. complete as per direction of Engineer Incharge.	5640.00	9.74	P.Sft	54,934.00
7	Supplying & Fixing false ceiling of plaster of paris in pannels in/c making frame work of deodar wood in/c painting with soligia paint. (S.I.No.52 P-64).	3200.00	25293.42	%Sft	809,389.00
8	Glazed tile dado 1/4" thick laid in pigment over 1:2 cement sand mortor 3/4" thick in/c finishing (S.I.No.38 P-45)	1461.00	28299.30	%Sft	413,453.00
9	Distempering Two Coats (S.I.No.24-C-9).	3887.10	1043.90	P.Sft	40,577.00
Total Rs:-					3,601,440.00

\_\_\_\_\_ % Below / Above

Contractor Signature

EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION-II  
EDUCATION & LITERACY DEPARTMENT  
GOVT. OF SINDH KARACHI.

S.No.	Description	Qty	Rate	Unit	Amount.
-------	-------------	-----	------	------	---------

**NON SCHEDULE ITEM**

- 1 Providing & Applying Grafitto (3/8 x 1/2") thick the product composed of material marble guard stone oxide detonium HSc natural colour, chips and pigments ammonia nitrogen jelicoal heated on high temperature on ultra violet mixed with acrylic resin anti bacterial & fungal addities and anti fumming against alkali, showing no blisering wrinlking or lifting after application resistant to accelerated weather change and rsistant to water head of 100 liter per 8 hours drying time haveing touch dry from etc complete (R.A approved).

**CHECKED**

2640.00 27.80 P.Sft 73,392.00

- 2 Providing & Fixing both Sides Laminated Lasan Kitchen cabinates 3/4" depth in/c boxing with back shelves shutters brass fitting etc complete (R.A).

**DRAFTSMAN**

**Education Division-II**

144.00 1649.00 P.Sft 237,456.00

**Total Rs:-**

**310,848.00**

**Contractor Signature**

**EXECUTIVE ENGINEER**  
**EDUCATION WORKS DIVISION-II**  
**EDUCATION & LITERACY DEPARTMENT**  
**GOVT. OF SINDH KARACHI.**