

SR No. 10

**BIDDING DATA**

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

(a). Name of Procuring Agency: **Executive Engineer Education Works Division N.Feroze**

(b). Brief Description of Works: MAINTENANCE & REPAIR OF GPS SHADI KHAN DHILLO TALUKA MORO.

(c). Procuring Agency's address: **Near DC House N.Feroze.**

(d). Estimated Cost:- 600000/-

(e). Amount of Bid Security:- **2%** (Fill in lump sum amount or in % age of bid amount /estimated cost, but not exceeding 5%)

(f). Period of Bid Validity (days):- **30 Days** (Not more than sixty days).

(g). Security Deposit :- ( including bid security): 10% (in % age of bid amount / estimated cost equal to 10%)

(h). Percentage, if any, to be deducted from bills:- 10.50%.

(i). Deadline for Submission of Bids along with time:- 12-04-2017 (2:00PM)

(j). Venue, Time, and Date of Bid Opening:- XEN Office dated: 12-04-2017 on 3:00 PM

(k). Time for Completion from written order of commence: - 03 Months

(L). Liquidity damages:- \_\_\_\_\_ (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).

(m). Deposit Receipt No: Date: Amount: (in words and figures)

(Executive Engineer/Authority issuing bidding document)

  
EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION  
NAUSHAHRO FEROZE

SCHEDULE B"

WORK: REPAIR TO GOVT: BOYS PRIMARY SCHOOL AT: SHADI KHAN  
DHILLO TAL: MORO

---

S.NO: Description Qty unit Rate Amount

---

1. Dismantling CC reinforcement separating reinf:  
from concrete cleaning and straighting the same  
(S.I.NO: 20 P.10)  
= 328 RS: 5445/- %sft RS: 17860/-  
(RS: five thousand four hundred forty five)
2. Dismantling CC plain 1:2:4 (S.I.NO: 19 P.10)  
= 498 RS: 3327/50 %sft RS: 16571/-  
(RS: three thousand three hundred twenty seven  
and ps: fifty)
3. Dismantling brick work in lime or mortar  
cement mortar (S.I.NO: 13 P.10)  
= 453 RS: 1285/63 %sft RS: 5824/-  
(RS: one thousand two hundred eighty five  
and ps: sixty three)
4. Removing cement or lime plaster  
(S.I.NO: 53 P.13)  
= -- RS: 121/- %sft RS: --  
(RS: one hundred twenty one)
5. Excavation in foundation of building bridges  
and other structure i/c degbelling dressing  
reinf: filling around the structure with excavated  
earth watering lead up to 5ft' (S.I.NO: 18 P.4)  
= -- RS: 3176/25 %ocft RS: --  
(RS: three thousand one hundred seventy six  
and ps: twenty five)
6. CC brick or stone ballst 1-1/2" to 2" guage  
ratio 1:5:10 (S.I.NO: 4 P.14)  
= 124 RS: 8694/95 %sft RS: 10782/-  
(RS: eight thousand six hundred ninty four  
and ps: ninty five)
7. Pacca brick work in foundation & plinth  
cement sand mortar 1:6 (S.I.NO: 4 P.19)  
= 1124 RS: 11948/36 %sft RS: 13426/-  
(RS: eleven thousand nine hundred forty eight  
and ps: thirty six)



