

**RECONDITIONING OF ROAD FROM INDUS HIGHWAY TO SHER SHAH SOORI
ROAD VIA LUTUF ALI BHAND, AALEE SHAH, KHASKHELY, THARO JAMALI
MILE 4/0-5/0 (I/C APPROACH ROAD)**

(SCHEDULE "B")

SR.NO.05

(PART-A)

Qty	Item of work	Rate	Unit	Amount
<p>1.Earth work for road embankment by bulldozers i/c ploughing, Mixing, clod breaking dressing and compacting with optimum moisture content lead up to 100Ft and lift up to 5-0 Ft in all types of soil except rock.</p> <p style="text-align: center;"><u>Compacting upto 85% Modified AASHO Density without lead</u></p>				
422100 Cft		Rs.3656/23	%0 CFT	Rs.1543295/-
<p>2.Laying bricks on end edging including supply of 9" 4 ½ " x 3" 1st Class burnt bricks excavation for laying edging with small side parallel to the road. Rate includes all cost of materials labour and carriage of 3 chains.</p>				
13600 RFT		Rs.2750/80	% RFT	Rs.374108/-
<p>3.Preparing base course including supplying and spreading stone metal of approved quality from approved quarry properly graded to maximum size of 1 ½" and required thickness to proper camber and grade including supplying and spreading 15 CFT screening and non plastic quarry fines, filling depressions with stone metal after initial rolling including watering and compacting modified AASHO specifications. (This includes providing and using templates, camber plates screen forms as directed). Rate I/Cs all costs of materials T and P and carriage upto 3 chains.</p>				
42400 CFT		Rs.8805/49	% CFT	Rs.3733528/-
<p>4.Providing 1st coats of surface dressing on new or existing surface with 30 lbs of bitumen of 80/100 penetration and 4 CFT crush Bajri of ¾ inch to ½ inch gauge including cleaning roads surface and rolling etc complete. Rate includes all coasts of materials T and P and carriage of three Chain.</p>				
81600 SFT		Rs.1619/24	% SFT	Rs.1321298/-
<p>5.Providing 1 " thick consolidated premixed carpet in proper camber and grade including supply of 10 Cft Bajri 4 CT hill sand of approved quality and gauge and bitumen 67lbs of 80/100 penetration including maxing in machnical mixer in required proportions including heating the materials and cleaning the road surface. Rate includes all costs of materials T and P carriage upto site of work.</p>				
81600 SFT		Rs.4516/40	%SFT	Rs.3685381/-

TOTAL Rs.10657609/-

Ded: diff: cost of bitumen 35.34 tons
@ Rs.27638/- P.ton

(-) Rs. 976727/-

NOTE:- Any error / omission if any, will be corrected.

CONTRACTOR


EXECUTIVE ENGINEER
PROVL:HIGHWAY DIVISION DADU

**CONSTRUCTION OF 3' SPAN CULVERT ALONG ROAD FROM INDUS HIGHWAY TO
SHER SHAH SOORI ROAD VIA LUTUF ALI BHAND, AALEE SHAH, KHASKHELY,
THARO JAMALI MILE 4/0-5/0**

**(SCHEDULE "B")
(PART-B)**

Qty	Item of work	Rate	Unit	Amount
	1. Excavation in foundation of bridges and other structures i/c deg belling dressing refilling around the structure with excavated earth watering remaining lead upto one chain and life upto 5'-0 (in ordinary soil).			
1056 CFT		@ 3176/25	P.%0 CFT	Rs.3354/-
	2.C.C Brick or stone ballast 1 ½" to 2" gauge Ratio 1:4:8			
224 CFT		@ Rs.9416/28	P.% CFT	Rs.21092/-
	3. Pacca Brick work in foundation cement sand mortor Ratio 1:4			
374 CFT		@ Rs.12501/41	P/% CFT	Rs.46755/-
	4. Errection and removal of centering for R.C.C or C.C Plain work vertical portal wood.			
109 SFT		@ Rs.3127/41	P % SFT	Rs. 3409/-
	5 Cement concrete plan including placing compacting finishing and curing, complete (including screening and washing of stone aggregate without shuttering).			
89 CFT		@ Rs.14429/25	P.% CFT	Rs.12842/-
	6. Fabrication of mild steel reinforcement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire (also includes removal of rust from bars.)			
5.67 CWT		@ Rs.5001/70	P.CWT	Rs.28360/-
	7. R.C.C work i/cs all labour and materials except the cost of steel reinforcement for cement concrete i/c bending binding which will be paid sepretly. This rate also i/c kind of forms mould lifting shuttering curring i/c screening and rendering the exposed surface R.C.C work roof slab beams lintels rafts columns and other structure member laid in situ laid in position in all respect.			
92 CFT		@ Rs.337/-	P % CFT	Rs.31004/-
	8. Cement Plaster ½" thick 20' height Ratio 1:3			
313 SFT		@ Rs.2283/93	P % SFT	Rs.7149/-
			TOTAL	Rs.153965/-

NOTE:- Any error / omission if any, will be corrected.

CONTRACTOR


EXECUTIVE ENGINEER
PROVL:HIGHWAY DIVISION DADU