

**CONSTRUCTION OF 3' SPAN CULVERTS & APPROACHES CULVERTS &  
BRIDGES RECONDITIONING OF ROAD FROM JOHI TO WAHI PANDHI ROAD  
MILE 0/0-10/2**

**(SCHEDULE "B")  
(PART-A)**

Qty	Item of work	Rate	Unit	Amount
1056 CFT	1. Excavation in foundation of bridges and other structures i/c deg belling dressing refilling around the structure with excavated earth watering remaining lead upto one chain and life upto 5'-0 (in ordinary soil). 2.C.C Brick or stone ballast 1 ½" to 2" gauge Ratio 1:4:8	@ 3176/25	P.%0 CFT	Rs.3354/-
883 CFT	3. Pacca Brick work in foundation cement sand mortor Ratio 1:4	@ Rs.9416/28	P.% CFT	Rs.83146/-
443 CFT	4. Errection and removal of centering for R.C.C or C.C Plain work vertical portal wood.	@ Rs.12501/41	P/% CFT	Rs.55381/-
109 SFT	5 Cement concrete plan including placing compacting finishing and curing, complete (including screening and washing of stone aggregate without shuttering).	@ Rs.3127/41	P % SFT	Rs. 3409/-
747 CFT	6. Fabrication of mild steel reinforcement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire (also includes removal of rust from bars.)	@ Rs.14429/25	P.% CFT	Rs.107786/-
5.60 CWT	7. R.C.C work i/cs all labour and materials except the cost of steel reinforcement for cement concrete i/c bending binding which will be paid sepretly. This rate also i/c kind of forms mould lifting shuttering curring i/c screening and rendering the exposed surface R.C.C work roof slab beams lintels rafts columns and other structure member laid in situ laid in position in all respect.	@ Rs.4820/20	P.CWT	Rs.26993/-
92 CFT	8. Pointing flash on stone work raised (Ratio 1:3)	@ Rs.337/-	P % CFT	Rs.31004/-
185 SFT		@ Rs.1758/08	P % SFT	<u>Rs.3252/-</u>
	<b>TOTAL</b>			<b>Rs.315299/-</b>

**NOTE:- Any error / omission if any, will be corrected.**

**CONTRACTOR**

  
EXECUTIVE ENGINEER  
PROVL:HIGHWAY DIVISION DADU