

**CONSTRUCTION OF 250RFT RETAINING WALL ALONG W/R OF ROAD JOHI TO  
BHAN ROAD AT MILE 0/5**

**(SCHEDULE "B")  
(PART-A)**

Qty	Item of work	Rate	Unit	Amount
	1. Excavation in foundation of bridges and other structures i/c deg belling dressing refilling around the structure with excavated earth watering remaining lead upto one chain and life upto 5'-0 (in ordinary soil).			
7500 CFT		@ 3176/25	P.%0 CFT	Rs.23822/-
	2.C.C Brick or stone ballast 1 ½" to 2" gauge Ratio 1:4:8			
1500 CFT		@ Rs.9416/28	P.% CFT	Rs.141244/-
	3. Errection and removal of centering for R.C.C or C.C Plain work vertical portal wood.			
3500 SFT		@ Rs.3127/41	P % SFT	Rs. 109459/-
	4 Cement concrete plan including placing compacting finishing and curing, complete (including screening and washing of stone aggregate without shuttering).			
6750 CFT		@ Rs.14429/25	P.% CFT	<u>Rs.973974/-</u>
NOTE:- Any error / omission if any, will be corrected.			<b>TOTAL</b>	<b>Rs.1248500/-</b>

CONTRACTOR

  
EXECUTIVE ENGINEER  
PROVL:HIGHWAY DIVISION DADU