

**IMPROVEMENT OF ROAD SUPER HIGHWAY BYE PASS HYDERABAD TO KOTRI
VIA KHANPUR MILE 0/5-2/7
(SCHEDULE "B")**


(PART-A)

SR. NO. 01

Qty	Item of work	Rate	Unit	Amount
	1.Preparing base course including supplying and spreading stone metal of approved quality from approved quarry properly graded to maximum size of 1 1/2" and required thickness to proper camber and grade including supplying and spreading 15 RFT screening and non plastic quarry fines, filling depressions with stone metal after initial rolling including watering and compacting modified AASHO specifications. (This includes providing and using templates, camber plates screen forms as directed). Rate I/Cs all costs of materials T and P and carriage upto 3 chains.			
21384 CFT		Rs.7316/52	% CFT	Rs.1564565/-
	2.Providing two coats of surface dressing on new or existing surface with 55 lbs of bitumen of 80/100 penetration and 6.75 Bajri of 1/2-3/4" inch gauge including cleaning roads surface and rolling etc complete. Rate includes all coasts of materials T and P and carriage of three Chain.			
106900 SFT		Rs.2836/24	% SFT	Rs.3031940/-
	3.Supply to laying proper line and grade plant mixed ASHALT concrete power finished hyderlic / electric control prepare to specified formula exceeding to fob of finishing to proper line and grade level and camber etc complete rate i/c take coats with bitumen 80/100 penetration and all cost of material from source of supply of plant to site of work 2" thick (132.5 lbs for mix plant 15 lbs of prime).			
220250 SFT		Rs.8690/89	%SFT	Rs.19141685/-
	4.Excavation in shingle gravel formation rock not requiring blasting underessed lead upto 100 ft			
	<u>Compacting upto 85% Modified AASHO Density</u>			
140500 Cft		Rs.7646/83	%0 CFT	Rs.1074380/-
	5. Payment marking in reflective Thermo Plastic paint for line of in 6" width >			
30591 RFT		Rs.41.24	P.RFT	Rs.1261573/-
	6. Providing & Fixing percast edge block 3750 PSI Industrial Made size 6 inches thick & 12" inches long x18" inches high including the cost of cartage, excavation form work for haunching 1450 PSI lean concrete, 2250 PSI concrete for haunching 1:4 cement sand mortor			
3080 RFT		Rs.297.01	P.RFT	Rs.914790/-
			TOTAL	Rs.26988933/-
	Ded: diff: cost of bitumen 251.66 tons @ Rs.18748/- P.ton			(-) Rs. 4718122/-

NOTE:- Any error / omission if any, will be corrected.

CONTRACTOR


EXECUTIVE ENGINEER
PROVL:HIGHWAY DIVISION DADU

**IMPROVEMENT OF 3' SPAN CULVERTS SUPER HIGHWAY BYE PASS
HYDERABAD TO KOTRI VIA KHANPUR MILE 0/5-2/7**

(SCHEDULE "B")


(PART-B)

Qty	Item of work	Rate	Unit	Amount
1308 CFT	1. Excavation in foundation of bridges and other structures i/c deg belling dressing refilling around the structure with excavated earth watering remaining lead upto one chain and life upto 5'-0 (in ordinary soil).	@ 3176/25	P.%0 CFT	Rs.4155/-
273 CFT	2.C.C Brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8	@ Rs.9416/28	P.% CFT	Rs.25706/-
444 CFT	3. Coursed Rubble Masonary including hammer dressed in cement sand mortor Ratio (1:4)	@ Rs.26475/-	P/% CFT	Rs.117549/-
211 SFT	4. Erection and removal of centering for R.C.C or C.C Plain cement concrete works of Deodar wood (2 nd class) for partial wood (Vertical).	@ 3127/41	P.% SFT	Rs.6599/-
218 CFT	5. Cement concrete plan including placing compacting finishing and curing, complete (including screening and washing of stone aggregate without shuttering).	@ Rs.14429/25	P.% CFT	Rs.31456/-
10.95 CWT	6. Fabrication of mild steel reinforcement concrete i/c cutting bending laying in position making joints and fastening i/c cost of binding wire (also includes removal of rust from bars.)	@ Rs.4820/20	P.CWT	Rs.52781/-
225 CFT	7. R.C.C work i/cs all labour and materials except the cost of steel reinforcement for cement concrete i/c bending binding which will be paid seprety. This rate also i/c kind of forms mould lifting shuttering curring i/c screening and rendering the exposed surface R.C.C work roof slab beams lintels rafts columns and other structure member laid in situ laid in position in all respect.	@ Rs.337/-	P % CFT	Rs.75825/-
216 SFT	8 Cement plaster upto 20' height 1/2" thick ratio (1:3)	@ Rs.1758/08	P % SFT	Rs.3797/-
	TOTAL			Rs.320128/-

Therefore, cost of 01 No. 320128x3=960384/-

NOTE:- Any error / omission if any, will be corrected.

CONTRACTOR


**EXECUTIVE ENGINEER
PROVL:HIGHWAY DIVISION DADU**